

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer, Division HPPWD Solan.

Email: [ee-sol-hp@nic.in](mailto:ee-sol-hp@nic.in) Land line NO:-Fax NO:-01792-223811

No.PW-SD/CB-Tender/-21-22-

9901-06

Dated:-

27-09-2021


To

✓ The Executive Engineer (IT Cell),  
Nigam Vihar, Nirman Bhawan,  
HPPWD, Shimla-2

Subject: - Publication of e-Tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19<sup>th</sup> June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

**Encl: - Schedule of quantities.**

  
Executive Engineer,  
Solan B & R Division,  
H.P.P.W.D, Solan.

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), H.P.P.W.D., Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3<sup>rd</sup> Circle, HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.

Executive Engineer,  
Solan B & R Division,  
H.P.P.W.D, Solan.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER  
(Exigency)**

Sealed item rate tenders are hereby invited on Form No.6 &8 by the Executive Engineer, Solan B&R Division, H.P. PWD. Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act.1968. The important dates of tender are as under:

Sr.No.	Tender Schedule		
1	The last date for receipt of application for tender form.	06.10.2021	Upto 4.00 P.M.
2	The last date sale of tender forms.	07.10.2021	Upto 4.00 P.M.
3	The date for receipt of tender forms.	08.10.2021	Upto 10.30 A.M.
4.	The date of opening of tenders	08.10.2021	At 11.00 A.M.

The tender shall be received upto **10.30 A.M. on 08.10.2021** and will be opened on the same day at **11.00 AM** in the presence of intending contractors or their authorized representatives who may like to be present. The tender form can be had from this office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/ Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs)	Time	Cost of Form
--------	--------------	-----------------------	--------------------	------	--------------

1.	"A/R & M/O of Chambaghat Kandaghat Via Salumna road Km.0/0 to 10/0(SH:-Dressing of berms/ shoulders, removal of slips/debries & jungle clearance etc in Km.2/0 to 6/0".	3,31,646/-	6,650/-	One Months	Rs. 350/-
2.	"A/R & M/O of Chambaghat Kandaghat Via Salumna road Km.0/0 to 10/0(SH:-Dressing of berms/ shoulders, removal of slips/debries & jungle clearance etc in Km.6/0 to 10/0".	3,29,044/-	6,600/-	One Months	Rs. 350/-
3.	"A/R & M/O of Salogra Ashwani Khad road Km.0/0 to 7/500(SH:-Dressing of berms/ shoulders, removal of slips/debries & jungle clearance etc in Km.0/0 to 3/0".	4,44,604/-	8,900/-	One Months	Rs. 350/-
4.	"A/R & M/O of Salogra Ashwani Khad road Km.0/0 to 7/500(SH:-Dressing of berms/ shoulders, removal of slips/debries & jungle clearance etc in Km.3/0 to 7/500".	4,65,051/-	9,350/-	One Months	Rs. 350/-

**TERMS & CONDITIONS: -**

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms. Application without earnest money will not be entertained.

## SCHEDULE OF QUANTITY

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
						331646.00
					Estimated Cost:-	6650.00
					Earnest Money:-	One month.
					Time Limit :-	

Job No. :- 1

Name of work: - Annual repair and maintenance of Chambaghat Kandaghat via Salumna road Km. 0/0 to 10/0 ( SH :- Dressing of berms/ shoulders, removal of slips/debries and jungle clearance etc. in Km. 2/0 to 6/0 )

1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto any height and all lead as per technical specification 302.3.5 and 1611 including carriage of all labour, equipments and materials to various location through all modes of transportation in all lead, lift and other incidental charges.	186.65	m3	Per cubic metre	
2	Maintenance of Earthen shoulder by Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC, as per drawings and Technical Specification Clause 1903 including carriage of all labour, equipments and materials to various location through all modes of transportation in all lead, lift and other incidental charges.	8000.00	m2	Per square metre	
3	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of all labour, equipments and materials to various location through all modes of transportation in all lead, lift and other incidental charges.	7200.00	m2	Per square metre	

Total in Words

T/S No. 123 for 2021-22

Sr. No. 181 for the year 2021-22.

Executive Engineer  
B&R Division, HP.PWD, Solan.

## SCHEDULE OF QUANTITY

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
						329044.00
					Estimated Cost:-	
					Earnest Money:-	6600.00
					Time Limit :-	One month.

Job No. :- 0

Name of work :- Annual repair and maintenance of Chambaghat Kandaghat via Salumna road Km. 0/0 to 10/0 ( SH :- Dressing of berms/ shoulders, removal of slips/debris and jungle clearance etc. in Km. 6/0 to 10/0 )

1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto any height and all lead as per technical specification 302.3.5 and 1611 including carriage of all labour, equipments and materials to various location through all modes of transportation in all lead, lift and other incidental charges.	287.21	m3	Per cubic metre		
2	Maintenance of Earthen shoulder by Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of all labour, equipments and materials to various location through all modes of transportation in all lead, lift and other incidental charges.	7200.00	m2	Per square metre		
3	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of all labour, equipments and materials to various location through all modes of transportation in all lead, lift and other incidental charges.	10800.00	m2	Per square metre		

**Total in Words**

T/S No. 125 for 2021-22

Sr. No. 180 for the year 2021-22.

Executive Engineer  
B&R Division, HP.PWD, Solan.

## SCHEDULE OF QUANTITY

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Words	Figures	
	Job No. :- 3			Estimated Cost:-		444604.00
				Earnest Money:-		8900.00
				Time Limit :-		One month.

Name of work: - Annual repair and maintenance of Salogra Ashwani Khad road Km. 0/0 to 7/500 ( SH :- Dressing of berms/ shoulders, removal of slips/debries and jungle clearance etc. in Km. 0/0 to 3/0)

1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of stops and disposal of cut material with in lift upto any height and all lead as per technical specification 302.3.5 and 1611 including carriage of all labour, equipments and materials to various location through all modes of transportation in all lead, lift and other incidental charges.	287.21	m3	Per cubic metre		
2	Maintenance of Earthen shoulder by Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of all labour, equipments and materials to various location through all modes of transportation in all lead, lift and other incidental charges.	10800.00	m2	Per square metre		
3	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of all labour, equipments and materials to various location through all modes of transportation in all lead, lift and other incidental charges.	7200.00	m2	Per square metre		

**Total in Words**

T/S No. 124 for 2021-22

**Sr. No. 178 for the year 2021-22.**

Executive Engineer  
B&R Division, HP, P.W.D. Solan.



### SCHEDULE OF QUANTITY

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
Job No. :- 4						
Name of work :- Annual repair and maintenance of Salogra Ashwani Khad road Km. 0/0 to 7/500 ( SH :- Dressing of berms/ shoulders, removal of slips/debris and jungle clearance etc. In Km. 3/0 to 7/500)						
				Estimated Cost:-		465051.00
				Earnest Money:-		9350.00
				Time Limit :-		One month.

1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto any height and all lead as per technical specification 302.3.5 and 1611 including carriage of all labour, equipments and materials to various location through all modes of transportation in all lead, lift and other incidental charges.	295.66	m3	Per cubic metre		
2	Maintenance of Earthen shoulder by Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC, as per drawings and Technical Specification Clause 1903 including carriage of all labour, equipments and materials to various location through all modes of transportation in all lead, lift and other incidental charges.	11400.00	m2	Per square metre		
3	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of all labour, equipments and materials to various location through all modes of transportation in all lead, lift and other incidental charges.	6600.00	m2	Per square metre		

**Total in Words**

T/S No. 126 for 2021-22

Sr. No. 179 for the year 2021-22.

Executive Engineer  
B&R Division, HP.PWD, Solan.

