

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed item rate tenders on form No. 6 and 8 are hereby invited by the undersigned on behalf of the Governor of Himachal Pradesh for the following works from approved and eligible contractors of appropriate class enlisted in H.P.PWD, so as to reach in this office on **06.12.2021 up to 11:00 AM** and shall be opened on the same day **11:30 AM** in the presence of intending contractors or their authorized representatives who may like to be present. The tender form can be had from this office against cash payment (Non-refundable) during the working hours on **04.11.2021 upto 10:30 AM**.

The earnest money in the shape of FDR/TDR, National Saving Certificate time Deposit/Account/Saving account in any of the Post Office/Nationalized Bank in H.P. duly pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Sarahan, Distt. Sirmour must accompany with each application/tender. Conditional tender and tender received without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The undersigned reserve the right to accept or reject the tenders without assigning any reason.

Sr. No	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs)	Time	Form No.	Cost of Form
1	C/o Rain Baru road Km 0/0 to 3/420 (SH:- formation cutting in Km 1/330 to 1/705) under MMGPY	394630/-	8,000/-	One Month	6&8	350/-
2	R/R damages on various roads under HPPWD; Sub Division Sarahan (SH:- Removal of slips on various roads)	2,00,200/-	4000/-	One Month	6&8	350/-
3	A/R & M/O Sarahan Chandigarh road Km 0/0 to 42/0 (SH:- C/o R/wall at RD 7/805 to 7/812)	86400/-	2000/-	One Month	6&8	350/-
4	A/R & M/O various roads under Sarahan Division (SH:- Supply and stacking of fuel wood)	240000/-	5000/-	One month	6&8	350/-
5	C/o Macher Jabiyana Wasni road Km 0/0 to 7/165 (SH:- C/o PCC R/wall in between RD 6/750 to 6/762) under MNP	415634/-	8500/-	One month	6&8	350/-
6	A/R & M/O to Sirmouri Mandir Bagthan road Km 0/0 to 10/375 (SH:- C/o unlined drain in between Km 4/00 to 8/00 and Removal of slips in various RD's)	167860/-	3500/-	One month	6&8	350/-

7	R/R Damages on Narag Wasni Dinger road Km 0/0 to 17/600 (SH:- C/o PCC R/wall at RD 1/900 to 1/912	348603/-	7000/-	One month	6&8	350/-
---	---	----------	--------	-----------	-----	-------

Certificate:- it is certified that the tenders of above work are exigency/emergent nature and in public interest

TERMS & CONDITIONS: -

1. The contractors/Bidders must submit their Permanent Income tax Account number/GST number on the tender along with copy of the same be attached with the application.
2. The contractors/Firms should attach copy of the Registration/renewal with the application.
3. The contractor/bidders should quote his rates both in figures and words, where there is any discrepancy between the rates in figures and words, the rates in words will be Governed.
4. The contractors/bidder must inspect the site to ascertain/familiar the site conditions, accessibility etc., before quoting the bid/tender.
5. Conditional and telegraphic tender shall not be accepted and rejected straightway. Tender received after due date and time will be rejected.
6. The contractor/Firms should have to produce the details of works in hand in HPPWD and its position thereof alongwith application.
7. The tender documents shall be issued to only those contractors who does not have more than two works in hand in any HPPWD circle/Division worth Rs 1.00 crore each.
8. The contractor shall have to establish testing laboratory at site for the day to day testing of material.
9. The offer shall remain valid up to 75 days
10. The provisions of guidelines issued vide the Principal Secretary (PW) to the Govt. of HP, Shimla vide notification No. PBW (B) A (3) 1/2020 dated Shimla-2 the 22th July, 2020 regarding adoption of CPWD works manual 2019 & other publication of CPWD in HPPWD shall also be applicable.
11. The tender form will not be issued to those contractors whose performance found unsatisfactory.
12. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reasons.

Executive Engineer,
Sarahan B&R Division,
HPPWD; Sarahan.

NO: - PW/ SRN/ Tender/2021-22-

1484-1505

Dated:- 30/11/2021

Copy forwarded to the following for information and necessary action to:-


1. The Deputy Commissioner, Nahan Distt. Sirmour (HP)
2. The Superintending Engineer, 12th Circle; HPPWD Nahan Distt. Sirmour for information please.
3. The Executive Engineer, (IT Cell), Nigam Vihar, HPPWD; Shimla-2 for uploaded of Notice Inviting Tender on Departmental website please.
4. All the Assistant Engineer working under this Division.
5. All the leading contractor working under Sarahan Division.
6. Copy to the notice board.

Executive Engineer,
Sarahan B&R Division,
HPPWD; Sarahan.

SCHEDULE OF QUANTITY
Name of work:- C/O Rain Baru road km 0/0 to 3/420 (Sit:- Formation cutting in km 1/330 to 1/705) under MMGPY

Job No.1

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, in conformit with the requirement of technical specification for Rural Road. clause 1603.1 and 1603.2 of General conditions for contract to achieve designed formation width including hauling and safe disposal of unsuitable cut materials upto all lead and lifts in specified manner i/c arrangement of dumping site trimming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer -in-Charge for smooth riding. The recovery for stones, whether useful or not, for 180.10 cum (one hundred eight point ten) in all cases, @ rupees 170/- only(Rupees one hundred seventy only) per cubic meter shall be effected on pro-rata basis. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall compensated by him in all cases.	3100.00	Per cubic metre.	5	6	7



Executive Engineer
Sarhan Division,
HP.PWD., Sarhan

SCHEDULE OF QUANTITY

Job No 2

Name of work:- R/R Damages on various roads under HP.PWD Sub Division Sarahan (Sft:- Removal of slips on various roads)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	2200.00	Per Cubic Metre			


Executive Engineer
Sarahan Division,
HP.PWD., Sarahan

Name of work:- A/R & M/O Sarahan Chandigarh Road km 0/0 to 42/0 (SH:- C/O R/Wall at Rd 7/805 to 7/812)

SCHEDULE OF QUANTITY

Job no. 3

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	5.25	Per Cubic Metre.			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203 (Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	19.64	Per Cubic Meter.			
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full width of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	14.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	6.30	Per Cubic Meter.			


Executive Engineer
Sarahan Division,
HP.PWD., Sarahan

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O to Various roads under Sarahan Division (Sh:- Supply and stacking of fuel wood)

Job no. 4

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Supply and stacking of dry mixed hard fuel wood of small size and stacked in proper stack of proper size as per HPPWD Specification and as per the direction of Engineer -in Charge including cartage of materials in all leads and lifts including all incidental charges	300.00	Per Qtl			


Executive Engineer
Sarahan Division,
HP.PWD., Sarahan

SCHEDULE OF QUANTITY

Name of work:- C/O Macher Jabyana Wasni road km 0/0 to 7/165 (SH:- C/O PCC R/wall in between Rd 6/750 to 6/762) under MNP

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause ThreeHundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling, in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	61.20	Per Cubic Metre.			
2	Providing and laying cement concrete 1:6:12 (One cement: Six sand: twelve graded crushed stone aggregate 40(Forty) millimeter nominal size) in open foundation and curing complete excluding cost of form work complete as per drawing and technical specification clause 802,803,1202 and 1203 including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge	5.76	Per cubic meter.			
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	95.40	Per Cubic Meter.			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	18.00	Each			
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	9.00	Per Cubic Meter.			

Executive Engineer
Sarahan Division,
HP.PWD., Sarahan

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O to Sirmouri Mandir Bagthan road km 0/0 to 10/375 (SH:- C/O unlined drain in between km 4/00 to 8/000 and Removal of slips in various Rd's)

Job no. 6

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	2	3	4	5	6	7
1	Construction of unlined surface drain of average cross-sectional area 0.2 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	3500.00	Per Running Metre			
2	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	560.00	Per Cubic Metre			

(Signature)
Executive Engineer
Sarhan Division,
HP.PWD., Sarhan

SCHEDULE OF QUANTITY

Job No. 7

Name of work:- R/R Damages on Narag Wasni Dinger road km 0/0 to 17/600 (SH:C/O PCC R/Wall at RD 1/900 to 1/912)

Sr. No	Description Items of work	Qty.	Unit	Rate		Amount
				in figures.	in words	
1	Earth work in excavations for structure as per drawing and technical specifications clause 305.1 (Clause Three Hundred Five point One) including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto a lead of 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	47.28	Per Cubic Metre.			
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications C- 802, 803, 1202 & 1203(Clause - Eight hundred Two, Eight hundred Three, One thousand Two hundred Two and One thousand Two hundred Three) 1:4:8. (One Cement : Four Sand : Eight graded stone) aggregate 25 mm nominal size and curing complete including the cost of form work and carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	4.32	Per Cubic Meter.			
3	Providing and laying Plain Cement Concrete 1:3:6(one cement: three sand: six graded hard stone aggregate 20mm(twenty) millimeter)nominal size} and curing complete including the cost of formwork for plain/reinforced concrete as per drawing and HP PWD technical specifications i/c carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge.	69.54	Per cubic meter.			
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm (One Hundred) dia AC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 (Clause - Six hundred Fourteen, Seven hundred Nine, One thousand Two hundred Four point Three point Seven),including hauling /carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in- Charge	9.00	Each			
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 in granular material and as per direction of the Engineer-in Charge, including carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction of the Engineer-in-Charge.	9.00	Per Cubic Meter.			

Executive Engineer
Sarahan Division,
HP.PWD., Sarahan