



HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer Barsar Division HPPWD Barsar

Web:- [www.hppwd.gov.in](http://www.hppwd.gov.in). Email:- [ee-bsr-hp@nic.in](mailto:ee-bsr-hp@nic.in)

Phone No:- 01972-288041

Fax No. 01972-288041

No:- PW-BSR-E-105/2023-2024- 17271-17321

Dated:- 22-02-2024

To


The Executive Engineer (IT Cell),  
Nigam Vihar, HP Shimla-2.

Subject:- Publication of Tender Notice.

Sir,


Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16<sup>th</sup> July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity  
And "A" Certificate.

  
Executive Engineer  
Barsar Division  
HPPWD Barsar

Copy forwarded with its enclosures for information to:-

1. The Superintending Engineer, 8<sup>th</sup> Circle, HPPWD, Hamirpur.
2. The Assistant Engineer, Sub Division, HPPWD Barsar and Dhaneta.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Supdt of C Branch in this office.
6. Notice Board.

  
Executive Engineer  
Barsar Division  
HPPWD Barsar.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Barsar Division HPPWD Barsar

Web:- [www.hppwd.gov.in](http://www.hppwd.gov.in) Email:- [ee-bar-hp@nic.in](mailto:ee-bar-hp@nic.in)

Phone No:- 01972-288041

**NOTICE INVITING TENDER.**

Scaled percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Barsar Division HPPWD Barsar on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **02-03-2024 up to 10.30 A.M.** and same will be opened on the same day at **11.00 A.M.** in presence of the interested contractors or their authorized representative. The application will be received in this office on dated **29-02-2024 upto 1:30 P.M.** The tender form can be had from the office of Executive Engineer Barsar Division HPPWD Barsar on cash payment (Non-refundable) on **01-03-2024 during office hours fro 12:00 P.M.** to onwards. The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Barsar Division HPPWD Barsar cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from, earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions.. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required along with latest returns, Copy of PAN Card, EPF along with latest returns failing which no tender form will be issued to him. All the required documents must be attached with the application.**

Sr. No.	Name of work	Estimated Cost	Earnest Money	Cost of Tender form	Time limit	Eligible Class
1	SDF-2023/630 (R/O) Restoration of rain damages on Salouni Bijhari Deotsidh road km 0/00 to 10/00 (SH:- C/O R/wall at Rd 2/900 to 2/906 & 5/700 to 5/715) D.C. deposit	4,64,320/-	9300/-	350/-	Two Month	C & D
2	SDF-2023/621 (R/O) Restoration of rain damages on Jalari Salouni Deotsidh road km 27/500 to 30/500 (SH:- C/O R/wall at Rd 28/650 to 28/660)	2,99,785/-	6000/-	350/-	Two Month	C & D
3	SDF-2023/619 (R/O) Restoration of rain damages on Salouni Bijhari Deotsidh road km 10/00 to 20/500 (SH:- C/O R/wall at Rd 19/405 to 19/423.50) D.C. deposit	4,49,059/-	9000/-	350/-	Two Month	C & D
4	SDF-2023/611 (R/O) Restoration of rain damages on Badaran Garli road km 13/500 to 22/500 (SH:- C/O R/wall at Rd 21/465 to 21/490) D.C. deposit	4,85,205/-	9800/-	350/-	Two Month	C & D
5	Restoration of rain damages on Chakmoh to Sathwin via Sakri Samella Holth Jangli road Km 0/00 to 10/660 (SH:- C/O R/wall at Rd 6/885 to 6/895 & C/O B/wall at Rd 6/860 to 6/875)	2,89,516/-	5,800/-	350/-	One Month	C & D
6	Restoration of rain damages on Bhota Bijhari via Ropari road Km 0/00 to 14/300 (SH:- C/O R/wall at Rd 10/200 to 10/208, 11/500 to 11/503 & 11/600 to 11/607)	3,64,510/-	7,300/-	350/-	One Month	C & D
7	Restoration of rain damages on Bumbloo bridge to Kathiana via Saman Kothi Km 0/00 to 7/900 (SH:- C/O E/wall at Rd 4/945 to 4/980 & P/L cement concrete pavement in Km 4/945 to 4/958)	4,35,268/-	8,800/-	350/-	Two Month	C & D

8	Restoration of rain damages on link road Dandwin to Dhangota via Kharal Km 0/00 to 5/315 (SH:- P/L cement concrete pavement at Rd 0/00 to 0/038)	4,85,421/-	9,800/-	350/-	Two Month	C & D
9	Levelling work of ground at Govt. Degree College Barsar District Hamirpur (SH:- P/L paver block in front of college )	3,42,745/-	6,900/-	350/-	Two Month	C & D
10	Restoration of rain damages on Bumbloo bridge to Kathiana via Saman Kothi Km 0/00 to 7/900 (SH:- C/O E/wall at Rd 4/980 to 5/015 & P/L cement concrete pavement in Km 4/960 to 4/973)	4,32,093/-	8,700/-	350/-	Two Month	C & D
11	Restoration of rain damage on Badaran Garli via Ghallian Jole Km. 0/0 to 2/500 ( Sh:- P/L Interlocking paver block pavement at rd. 15/696 to 5/766)	4,91,457/-	9,900/-	350/-	Two Month	C & D
12	Restoration of rain damage on Badaran Garli via Ghallian Jole Km. 0/0 to 2/500 ( Sh:- P/L Interlocking paver block pavement at rd. 17/640 to 17/810)	4,91,392/-	9,900/-	350/-	Two Month	C & D
13	Restoration of rain damages on link road Dandwin to Dhangota via Kharal Km 0/00 to 5/315 (SH:- P/L cement concrete pavement at Rd 0/039 to 0/077)	4,85,350/-	9,800/-	350/-	Two Month	C & D
14	C/O link road Mata Vaishno Devi Mandir to Harizan basti Suglani to Dhangota Km 0/00 to 3/500 (SH:- C/O R/wall at Rd 2/600 to 2/629 & Embankmen filling in Km 2/600 to 2/700) (under SCSP Head)	4,33,565/-	8,700/-	350/-	Two Month	C & D
15	Restoration of rain damages on Jamli Chaleli road Km 0/00 to 1/300 (SH:- P/L cement concrete pavement at Rd 0/240 to 0/345 & V-Shape drain at Rd 0/300 to 0/360 L/side & 0/340 to 0/400 R/side )	4,84,842/-	9,700/-	350/-	Two Month	C & D
16	Restoration of rain damages on Dhangota Sathwin Bara Tajyar road Km 0/00 to 6/00 (SH:- P/L cement concrete pavement at Rd 2/760 to 2/858 & 4/00 to 4/030 )	4,97,778/-	10,000/-	350/-	Two Month	C & D
17	Restoration of Rain damages on Bara Khalout Joreghat road Km 0/00 to 8/180 (SH:- C/O R/wall at Rd 4/010 to 4/020 & B/wall at Rd 4/200 to 4/216)	3,64,594/-	7,300/-	350/-	Two Month	C & D
18	Restoration of rain damages on Harizan Basti Sher Hardo to Tillu road Km 0/00 to 2/00 (SH:- C/O R/wall at Rd 0/220 to 0/239.40)	4,92,484/-	9,900/-	350/-	Two Month	C & D
19	C/O link road Mata Vaishno Devi Mandir chowk to Harizan basti Suglani to Dhangota Km 0/00 to 3/500 (SH:- C/O R/wall at Rd 2/630 to 2/655 & Embankmen filling in Km 2/700 to 2/850) (under SCSP Head)	4,39,515/-	8,800/-	350/-	Two Month	C & D
20	Restoration of rain damages on Sukkar Khad to Beri via Pahloo Khas road Km 0/00 to 5/540 (SH:- C/O wire crate R/Wall at Km 1/400 to 1/435 )	4,71,385/-	9,500/-	350/-	Two Month	C & D
21	C/O link road to Sawar Sath Ward No -3 (G.P Jajri) (SH:- C/O R/wall at Rd 0/180 to 0/190 & Cement concrete pavement at Rd 0/155 to 0/179)	1,59,546/-	4,000/-	350/-	One Month	C & D

22	Restoration of rain damages on Bara Khalaut Joreghat road Km 0/00 to 8/180 (SH:- P/F crash barrier at Km 6/200 to 6/300)	4,65,603/-	9,400/-	350/-	Two Month	C & D
23	Restoration of rain damages on Mehre Garli Bijhari road Km 0/00 to 12/00 (SH:- C/O R/wall at Rd 0/745 to 0/762.50)	4,51,406/-	9,100/-	350/-	Two Month	C & D
24	Restoration of rain damages on Bara Khalaut Joreghat road Km 0/00 to 8/180 (SH:- P/F crash barrier at Km 6/900 to 6/990)	4,18,810/-	8,400/-	350/-	Two Month	C & D
25	NDF/2023/13 R/O link road to village Kalohan Km 0/00 to 2/00 (SH:- C/O R/wall at Rd 0/055 to 0/071)	1,50,046/-	3,100/-	350/-	One Month	C & D
26	Restoration of rain damages on Salouni Bijhari Deotsidh road Km 0/00 to 10/00 (SH:- C/O R/wall at Rd 5/700 to 5/720)	4,06,831/-	8,200/-	350/-	Two Month	C & D
27	A/R & M/O on Barsar Shahtalai road Km 0/00 to 11/400 (SH:- Repair of pot holes in between Km 0/00 to 11/400)	4,79,451/-	9,600/-	350/-	Two Month	C & D
28	A/R & M/O on Una Aghar Mandi road Km 67/00 to 69/00 & Jhiralari Check Loader Meena Ka Dehra Km 0/00 to 6/00 (SH:- Repair of pot holes in between Km 67/00 to 69/00 & 0/00 to 6/00 respectively)	4,79,089/-	9,600/-	350/-	Two Month	C & D
29	C/O B/wall & P/L interlocking paver block at H.S.C Jajri (SH:- P/L 60mm thick interlocking paver block in Courtyard ) (Deposit work)	1,70,010/-	3,500/-	350/-	One Month	C & D
30	C/O R/wall, B/wall Courtyard at H.S.C building at Fagoti (SH:- P/L 60mm thick interlocking paver block in Courtyard , C/O Ramp, White washing in boundary wall) (Deposit work)	2,49,605/-	5,000/-	350/-	One Month	C & D
31	Restoration of rain damages on various road under HPPWD Sub Division Barsar (Section Bijhari) (SH:- Supply and stacking of Granular sub-base of various road at various Rds)	4,76,307/-	9,600/-	350/-	Two Month	C & D
32	A/R & M/O HPPWD Rest House at Deotsidh (SH:- Distempering , painting & Sanitary work etc. )	4,99,693/-	10,000/-	350/-	Two Month	C & D
33	Restoration of rain damages on Salouni Bijhari Deotsidh road Km 0/00 to 10/00 (SH:- C/O R/wall at Rd 6/800 to 6/818)	3,11,174/-	6,300/-	350/-	One Month	C & D
34	A/R & M/O HPPWD Rest House at Bijhari District Hamirpur P/L distempering work , plastering work, wood work , sanitary work etc. )	4,04,746/-	9,100/-	350/-	Two Month	C & D
35	SDF/2023/70 (R/O) Rain damages on village Karwin road Km 0/00 to 2/00 (G.P Bani) (SH:- C/O R/wall at Rd 0/00 to 0/006) (D.C Deposit)	1,48,817/-	3,000/-	350/-	One Month	C & D

36	Restoration of rain damages on link road Bhota Bihari via Ropari Km 0/00 to 14/00 (SH:- C/O wire crate R/Wall at Rd 3/520 to 3/533.50 )	4,92,646/-	9,900/-	350/-	Two Month	C & D
37	Restoration of rain damages on link road Bhota Bihari via Ropari Km 0/00 to 14/00 (SH:- C/O B/Wall at Rd 3/533 to 3/551.90 )	4,96,184/-	10,000/-	350/-	Two Month	C & D
38	Restoration of rain damages on link road Bhota Bihari via Ropri Km 0/00 to 14/00 (SH:- C/O R/wall at Rd 3/855 to 3/874.30)	4,87,354/-	9,800/-	350/-	Two Month	C & D
39	Restoration of rain damages on link road Janain Samtana road (SH:- C/O wire crate R/Wall at Rd 9/090 to 9/118.70)	4,88,820/-	9,900/-	350/-	Two Month	C & D
40	Restoration of rain damages on Kohla Ghumarwin road Km 0/00 to 1/495 (SH:- P/L 900mm dia RCC Hume pipe culvert at Rd 1/155 i/c wing wall & C/O R/wall at Rd 0/425 to 0/440 )	4,71,412/-	9,500/-	350/-	Two Month	C & D
41	SDF/2023/69 (R/O) Rain damages on Mehre Jabble Kheriyan road Km 0/00 to 5/565 (SH:- C/O B/wall at Rd 1/350 to 1/385) (D.C Deposit)	4,96,289/-	10,000/-	350/-	Two Month	C & D
42	SDF/2023/214 (R/O) Restoration of rain damages on GHS Karer Lahri Salan Km 0/00 to 2/00 (SH:- C/O wire crate R/Wall at Rd 0/375 to 0/383.50 & 0/705 to 0/725 ) (G.P Karer) (D.C Deposit)	4,93,232/-	9,900/-	350/-	Two Month	C & D
43	SDP/2023/59, SDP/2023/95 C/O link road village Saheli to Lower Saheli KM 0/00 to 1/00 (SH:- Formation cutting at Rd 0/00 to 0/570) (G.P Karsai) (D.C Deposit)	4,98,468/-	10,000/-	350/-	Two Month	C & D
44	A/R & M/O Judicial Court Complex building at Barsar (SH:- Distempering, painting, wood work etc.)	4,98,128/-	10,000/-	350/-	Two Month	C & D
45	Restoration of rain damages on Harsour to Garli road Km 0/00 to 6/00 (SH:- C/O Edge wall at Rd 5/100 to 5/135 & 5/600 to 5/615)	3,28,164/-	6,600/-	350/-	Two Month	C & D
46	Restoration of rain damages on Nara Shahtalai road Km 0/00 to 5/555 (SH:- C/O P/L Cement concrete pavement at Rd 2/300 to 2/423)	4,70,179/-	9,500/-	350/-	Two Month	C & D
47	SDF/2023/211 (R/O) Restoration of rain damages on GHS Karer to Harizan Basti Lahri Salan Km 0/00 to 2/00 (SH:- C/O R/Wall at Rd 1/140 to 1/145.15 & 1/154.15 to 1/159.93 ) (G.P Karer)	3,02,240/-	6,100/-	350/-	Two Month	C & D
48	NDF/2023/16 (R/O) Nara Rappar Shahtalai road Km 0/00 to 5/555 (SH:- C/O R/wall at Rd 3/850 to 3/857 & B/wall at Rd 2/800 to 2/825)DC Deposit	3,74,442/-	7500/-	350/-	One Month	C & D

49	NDF/2023/15 (R/O) Darkoti Shahtalai road Km 0/00 to 4/555 (SH:- C/O U-Shape drain at Rd 0/00 to 0/113) DC Deposit	2,99,916/-	6000/-	350/-	One Month	C & D
50	MPR/2023/66 C/O link road from Dalchera to Sarla Barsar Division Block Bijhari Distt. Hamirpur SH:- P/L cement concrete pavement at Rd 0/615 to 0/702 & 0/803 to 0/826 & C/O R/wall at Rd 0/762 to 0/765.50)	4,64,603/-	9300/-	350/-	Two Month	C & D
51	Restoration of rain damages on Badaran Garli via Galliyen Jole road Km 13/500 to 22/500 (SH:- C/O surface dressing , Unlined surface drain Km 13/500 to 15/500)	2,76,407/-	5600/-	350/-	One Month	C & D
52	A/R & M/O HPPWD Rest House at Bhota (SH:- Repairing of furniture)	1,54,850/-	3100/-	350/-	One Month	C & D
53	A/R & M/O HPPWD Rest House at Barsar (SH:- Repairing of furniture)	1,62,100/-	3300/-	350/-	One Month	C & D
54	SDF-2023/704 & SDF/2023/705 (R/O) Tehsil office building at Bijhari Tehsil Bijhari District Hamirpur (SH:- Painting distempering & C/O Boundary wall i/c gate) DC Deposit	4,00,612/-	8100/-	350/-	Two Month	C & D
55	C/O link road to village Chhatoli Brahmana Km 0/00 to 0/700 (SH:- C/O R/wall at Rd 0/300 to 0/315 & P/L 600mm dia RCC Hume pipe culvert at Rd 0/325 with wing wall) (under OTMNP Head)	4,99,720/-	10000/-	350/-	Two Month	C & D
56	Restoration of rain damages on Bijhari Chalsai Ambota Chakrala Ghangot road Km 0/00 to 7/900 SH:- C/O V-shape drain at Rd 0/670 to 0/810, R/wall at Rd 0/505 to 0/516 & P/L cement concrete pavement at Rd 0/610 to 0/660 & 0/770 to 0/810)	4,69,401/-	9400/-	350/-	Two Month	C & D
57	Restoration of rain damages on Bijhari Chalsai Ambota, Chakrala, Ghangot road Km 0/00 to 7/900 (SH:- P/L interlocking concrete block pavement at Rd 2/216 to 2/262 with edge wall & V-Shape drain at Rd 2/180 to 2/350 )	4,81,878/-	9700/-	350/-	Two Month	C & D
58	A/R & M/O various road under HPPWD Division Barsar (SH:- Supply and stacking reinforced cement concrete pipe NP2 900 mm , 450mm & 600mm dia with collar at Divisional store Barsar (under Stock Storage)	4,93,125/-	9900/-	350/-	One Month	C & D
59	Restoration of rain damages on link road to Harizan Basti Damyana SH:- C/O Edge wall at Rd 0/035 to 0/055 & U-Shape drain at various Rds ) (DC Deposit)	4,16,531/-	8400/-	350/-	Two Month	C & D
60	Stock Storage under HPPWD Divisional Store Barsar( Sh:- Supply and stacking informatory board) Under Stock Storage	4,13,000/-	8300/-	350/-	One Month	C & D

61	A/R & M/O various bridge under HPPWD Sub Division Barsar (Section Chakmoh) ( Sh:- Repair of railing and painting)	2,33,106/-	4500/-	350/-	One Month	C & D
62	A/R & M/O on Divisional office and Residential Quarter at Barsar( Sh:- Distempering, Painting, ceiling, Repair work etc.)	4,94,958/-	9900/-	350/-	Two Month	C & D
63	A/R & M/O on Residential Quarter at HPPWD colony Barsar( Sh:- Distempering, Painting, sanitary works )	4,98,614/-	10000/-	350/-	Two Month	C & D

Certified that the tenders for Job No. 1 to 63 are of urgent nature and in public interest.

HIM SUCHANA AVAM JAN SAMPARK

Executive Engineer  
Barsar Division  
HPPWD Barsar

On behalf of Governor of Himachal Pradesh

218

Job - 1

Job No:-  
Estimated Cost Rs:- 4,64,320.00  
Earnest Money Rs:- 93000.00  
Time Limit :- two month

DNIT  
Name of Work:- SBF-2023/630 (R/O) Restoration of rain damages on Satoumi Bijhari Deotsidh road km 0/00 to 10/00  
(S/N:- G/O: R/wall at Rd 2/900 to 2/906 & 5/700 to 5/715)  
(DC Deposit):

Sl. No.	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including clearing of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive of royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	35.13	Rupees Four Hundred Ninety Ninety Only	Per Cubic Metre	17526.00
2	Providing and laying cement concrete 1:5:10, mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive of royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	97.74	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	417184.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	18.50	Rupees One Thousand Two Hundred Nine And Paise Forty Only	Per Cubic Metre	22374.00



4	Providing, weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D. plast)/ Finelex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(N):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	18.00 Numbers	402.00 Rupees Four Hundred Two Only	Each	7236.00
Total:-					464320.00

DMMT approved for Rs/- 4,64,320/-

only

Executive Engineer  
Barrsar Division  
H&WD Barrsar

267

Job - 2


Job No:-  
Estimated Cost Rs:- 2,99,785.00  
Earnest Money Rs:-6000.00  
Time Limit :- Two month

DNIT  
Name of Work:- SDE-2023/621 (R/O) Restoration of rain damages on Jalari Saloumi Deotsidh road km 27/500 to 30/500  
(S/E)- C/O- RA/wall at Rd 28/650 to 28/660

Sl.No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out; construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated, suitable approved material to the original surface in layers not exceeding 150mm(one hundred-fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	16.20	Cubic metre	Per Cubic Metre	8082.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202 and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	65.70	Cubic metre	Per Cubic Metre	280427.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government.	6.00	Cubic metre	Per Cubic Metre	7256.00
		1209.40	Rupees One Thousand Two Hundred Nine And Paise Forty Only		

<p>Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D plus) / Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all loads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, GST on other taxes imposed by the Government.</p>	10.00	Numbers	402.00	Rupees Four Hundred Two Only	Lach	4020.00
Total:-						299785.00

DNIT approved Rs. 2,99,785/- only.

Executive Engineer  
Barsar Division  
  
Barsar

265

Sub-3

Job No:-  
 Estimated Cost Rs:- 4,49,059.00  
 Earnest Money Rs:-9000.00  
 Time Limit :- Two month

DNIT  
 Name of Work:- SDF-2023/619 (R/O) Restoration of rain damages on Salouni Bijhari Deotsidh road km 10/00 to 20/500  
 (SH- C/O R/wall at Rd 19/405 to 19/423-50)  
 (DC Deposit)

Sl.No	Description of Item	Rate inclusive all taxes % G.S.T	Figure	words	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rocks, hard rock, chiseling/wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	21.65	498.90	Rupees Four Hundred Ninety Nine Only	Per Cubic Metre	10801.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	97.79	4268.30	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	417397.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	11.10	1209.40	Rupees One Thousand Two Hundred Nine And Paise Forty Only	Per Cubic Metre	13424.00

4) Providing weep-holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D/plyst)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(N):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3:7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	18.50 Numbers	402.00 Rupees Four Hundred Two Only	Each	7437.00
			Total:-	449059.00

DNI approved for Rs. 4,49,059/- only.

Executive Engineer  
 Barsar Division  
 H.P.W.D. Barsar

257

Job-4

Job No:-  
Estimated Cost Rs:- 4,85,205.00  
Earnest Money Rs:-9800.00  
Time Limit :- Two month

Name of Work:- SDF-2023/611 (R/O) Restoration of rain damages on Badaran Garli road km 13/500 to 22500  
DNIT  
(SH:- C/O R/wall at Rd 21/465 to 21/490)

Sl.No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	25.68	Rupees Four Hundred Ninety Nine Only	Per Cubic Metre	12812.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	104.07	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	444202.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, , GST or other taxes imposed by the Government.	15.00	Rupees One Thousand Two Hundred Nine And Paise Forty Only	Per Cubic Metre	18141.00

<p>4) Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (Diploplast/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (four kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	25.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	10050.00
Total:-						485205.00

DNIT approved for Rs. 485,205/- only

Executive Engineer  
 Barsar Division  
 Barsar

150

Job No-  
 Estimated Cost Rs:- 2,89,516.00  
 Earnest Money Rs:-5800.00  
 Time Limit :- One month

Name of Work:- Restoration of rain damages on Chakmoh to Sathwin via Sakri Samella (with Jangli road Km 0/00 to 10/660 (SH)- C/O R/wall at Rd 6/885 to 6/895 & C/O B/wall at Rd 6/860 to 6/875)  
 DNIJ

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T			Unit	Amount
		Figure	words			
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	23.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Cubic metre	Per Cubic Metre	11924.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground; or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	60.65	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Cubic metre	Per Cubic Metre	258872.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, , GST or other taxes imposed by the Government.	6.00	Rupees One Thousand Four Hundred Forty Four And Paise Ninety Five Only	Cubic metre	Per Cubic Metre	8670.00



4	Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Holes/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	25.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	10050.00
Total:-							289516.00

DNIT approved for 121-2, 89, 516/-  
only)

Executive Engineer  
Barsar Division  
KDPWD Barsar

151

Job No- 16  
 Estimated Cost Rs:- 3,64,510.00  
 Earnest Money Rs:-7300.00  
 Time Limit :- One month

Name of Work:- Restoration of rain damages on Bhota Bijhari via Ropari road Km 0/00 to 14/300  
 (SH:- C/O R/wall at Rd 10/200 to 10/208, 11/500 to 11/503 & 11/600 to 11/607)  
 DNIT

Sr.N	Description of Item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	24.75	Cubic metre	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	12348.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	74.92	Cubic metre	4268.30	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	319781.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, , GST or other taxes imposed by the Government.	14.62	Cubic metre	1444.95	Rupees One Thousand Four Hundred Forty Four And Paise Ninety Five Only	Per Cubic Metre	21125.00

<p>4) Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plate) / Inlolex / Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other inclusions. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	28.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	11256.00
<b>Total:-</b>						<b>364510.00</b>

DNIT approved for Rs - 364,510/-  
only

Executive Engineer  
Bansar Division  
HPPWD Bansar

Schedule of quantity

Name of Work:- Restoration of rain damages on Bumbloo bridge to Kathiana via Saman Kothi Km 0/00 to 7/900  
(SH:- C/O E/wall at Rd 4/945 to 4/980 & P/L cement concrete pavement in Km 4/945 to 4/958)

Job No- 7

Estimated Cost Rs:- 4,35,268.00

Earnest Money Rs:-8800.00

Time Limit :- Two month

Sl. No	Description of Item	Quantity	Rate inclusive all taxes i/c G.S.T		Amount
			Figure	words	
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Lngineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	27.30	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	13620.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	51.45	5862.20	Rupees five Thousand Eight Hundred Sixty Two And Paise Twenty Only	301610.00
3	Providing and laying cement concrete 1:2 ½ :5 (one cement : Two and half Sand : five graded crushed stone ) aggregate 20mm (Twenty millimeter) nominal size for plain/reinforced cement concrete in substructure as per drawings and technical specification clause 802,804,805,806,807,1202 & 1204 including entire carriage of material in all leads and lifts. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	7.49	6183.40	Rupees Six Thousand One Hundred Eighty Three And Paise Forty Only	46314.00

4) Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (one cement : one and half coarse sand : three graded stone aggregate 20 mm (twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	3.27	Cubic metre	7113.40	Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre	23261.00
5) Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.10	Cubic metre	1409.40	Rupees One Thousand Four Hundred Nine And Paise Forty Only	Per Cubic Metre	42423.00
6) Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast) Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	8040.00
Rate rate quoted in words and figure					Total:-	435268.00

Executive Engineer  
Bansar Division  
HPWD Bansar

153

8

DNIT

Job No-  
 Estimated Cost Rs:- 4,85,421.00  
 Earnest Money Rs:-9800.00  
 Time Limit :- Two month

Name of Work:- Restoration of rain damages on link road Dandwin to Dhangota via Kharal Km 0/00 to 5/315  
 (SH:- P/L cement concrete pavement at Rd 0/00 to 0/038)

Sr.No	Description of Item	Rate inclusive all taxes % G.S.T			Unit	Amount
		Figure	words			
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surfacc and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	31.83	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	15880.00	
2	Construction of granular sub base by providing well graded material mixing in a mechanical mix plant at OMC carriage of mixed material to work site upto all leads spreading in uniform layers with motor grader on prepared surface and compacted with smooth wheel roller to achieve the desired density, complete as per technical Specification Clause 401. for grading -I material including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	12.73	Rupees Two Thousand Sixty Two And Paise Ten Only	per cubic metre	26251.00	
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	64.03	Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	Per Cubic Metre	375357.00	

Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, including the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (one cement : one and half coarse sand : three graded stone aggregate 20 mm (twenty millimetre) nominal size). In foundation including bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts; The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	9.55	Cubic metre	7113.40	Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre	67933.00
Total:-						485421.00

*DNIT approved for Rs- 4,85,421/- only*

Executive Engineer  
Barsar Division  
HOWD Barsar

154

Name of Work:- Levelling work of ground at Govt. Degree College Barsar District Hamirpur  
(SH:- P/L paver block in front of college) डेपॉजिट वर्क

DNIT

Job No- 19

Estimated Cost Rs:- 3,42,745.00

Earnest Money Rs:-6900.00

Time Limit :- Two month

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T	Unit	Amount	Rate inclusive all taxes i/c G.S.T	
					Figure	words
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise-out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	21.00	Cubic metre	10477.00	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only
2	Construction of granular sub base by providing well graded material mixing in a mechanical mix plant at OMC carriage of mixed material to work site upto all leads spreading in uniform layers with motor grader on prepared surface and compacted with smooth wheel roller to achieve the desired density, complete as per technical Specification Clause 401. for grading -I material including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	14.00	Cubic metre	28869.00	2062.10	Rupees Two Thousand Sixty Two And Paise Ten Only
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre, nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202.&1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	14.00	Cubic metre	82071.00	5862.20	Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 ( one cement : one and half coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	2.86	Cubic metre	20344.00	7113.40	Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only



<p>5 Providing and laying of inter locking concrete paver block vibro compacted upto M-30 (M-Thirty ) grade having thickness 60mm(sixty millimeter) including border or kerb block over sub base of sand as per drawing and technical specification Clause-1504 approved any make conforming to the Nitco, Modern, Gico, NTC/ BIS specification for interlocking paver blocks including entire carriage of material with in all leads and lifts and other incidentals .The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government</p>	140.00	square metre	1435.60	Rupees One Thousand Four Hundred Thirty Five And Paise Sixty Only	per square metre	200984.00
Total:-						342745.00

DNIT approved for Rs/- 3,42,745/-  
only

Executive Engineer  
Barsar Division  
HBPWD, Barsar

155

DNJJ

Name of Work:- Restoration of rain damages on Bumbloo bridge to Kathiana via Saman Kothi Km 0/00 to 7/900  
(SHI:- C/O E/wall at Rd 4/980 to 5/015 & P/L cement concrete pavement in Km. 4/960 to 4/973)

Job No- 10

Estimated Cost Rs:- 4,32,093.00  
Earnest Money Rs:-8700.00

Time Limit :- Two month

Sr.No	Description of Item	Rate inclusive all taxes 1/6 G.S.T	Rate inclusive all taxes 1/6 G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	27.30	Cubic metre	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre 13620.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	50.75	Cubic metre	5862.20	Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	Per Cubic Metre 297507.00
3	Providing and laying cement concrete 1:2 1/2 :5 (one cement : Two and half Sand : five graded crushed stone ) aggregate 20mm (Twenty millimeter) nominal size for plain/reinforced cement concrete in substructure as per drawings and technical specification clause 802,804,805,806,807,1202 & 1204 including entire carriage of material in all leads and lifts. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	6.99	cubic metre	6183.40	Rupees Six Thousand One Hundred Eighty Three And Paise Forty Only	Per Cubic Metre 43222.00
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 ( one cement : one and half coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government .	3.27	Cubic metre	7113.40	Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre 23261.00

5	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.10	Cubic metre	1409.40	Rupees One Thousand Four Hundred Nine And Paise Forty Only	Per Cubic Metre	42423.00	
6	Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-PIAST) / HINDLEX / SUPREME having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	12060.00	
							Total:-	432093.00

DNIT approved for Rs - 432,093/-  
only

Executive Engineer  
Bansar Division  
HAWD Bansar

156

Job No-  
 Estimated Cost Rs:- 4,91,157.00  
 Earnest Money Rs:-9900.00  
 Time Limit :- Two month

Name of Work:- Restoration of rain damages on Badaran Garli via Gallian Jole Km 0/00 to 22/500  
 (SH:- P/L Interlocking Paver Pavement at Rd 15/696 to 15/766)  
 DNIT

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T			Unit	Amount
		Figure	words	Per		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	11.20	Rupees Four Hundred Sixty Five And Paise Sixty Only	Per Cubic Metre	5215.00	
2	Stone soling properly hand packed filling interstices with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter ) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	4.16	Rupees One Thousand Four Hundred Sixty Nine And Paise Twenty Only	Per Cubic Metre	6112.00	
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) . on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	22.40	Rupees Five Thousand Eight Hundred Seventy Three Only	Per Cubic Metre	131555.00	
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 ( one cement : one and half coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government .	3.82	Rupees Seven Thousand One Hundred Ninety Five Only	Per Cubic Metre	27485.00	

<p>5) Providing and laying of inter locking concrete paver block vibro compacted upto M-30 (M-Thirty ) grade having thickness 60mm(sixty millimeter) including border or kerb block over sub base of sand as per drawing and technical specification Clause-1504 approved any make conforming to the Nitco, Modem, Gico, NTC/ BIS specification for interlocking paver blocks including entire carriage of material with in all leads and lifts and other incidentals .The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.</p>	224.00	square metre	1432.10	Rupees One Thousand Four Hundred Thirty Two And Paise Ten Only	per square metre	320790.00
					Total:-	491157.00

15/11/14  
 DMIT approved for Rs. 491,157/-

*only*

Executive Engineer  
 Barsar Division  
 M.P.W.D Barsar

157

Job No- 12  
 Estimated Cost Rs:- 4,91,392.00  
 Earnest Money Rs:- 9900.00  
 Time Limit :- Two month

Name of Work:- Restoration of rain damages on Badaran Garli via Gallian Jole Km 0/00 to 22/500  
 (SH:- P/L Interlocking Paver Block Pavement at Rd 17/640 to 17/810)  
 DNII

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T	Unit	Amount	Figure	words	
					Figure	words	
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	11.20	Cubic metre	465.60	Rupees Four Hundred Sixty Five And Paise Sixty Only	Per Cubic Metre	5215.00
2	Stone soling properly hand packed filling interstices with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter ) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	4.32	Cubic metre	1469.20	Rupees One Thousand Four Hundred Sixty Nine And Paise Twenty Only	Per Cubic Metre	6347.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	22.40	Cubic metre	5873.00	Rupees Five Thousand Eight Hundred Seventy Three Only	Per Cubic Metre	131555.00
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 ( one cement : one and half coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	3.82	Cubic metre	7195.00	Rupees Seven Thousand One Hundred Ninety Five Only	Per Cubic Metre	27485.00

5) Providing and laying of inter locking concrete paver block vibro compacted upto M-30 (M-Thirty) grade having thickness 60mm(sixty millimeter) including border or kerb block over sub base of sand as per drawing and technical specification Clause-1504 approved any make conforming to the Nitco, Modern, Gico, NTC/ HIS specification for interlocking paver blocks including entire carriage of material with in all leads and lifts and other incidentals .The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	224.00 square metre	1432.10	Rupees One Thousand Four Hundred Thirty Two And Paise Ten Only	per square metre	320790.00
Total:-					491392.00

DNIT approved for  
only) 24-4,91,392/-

Executive Engineer  
Barsar Division  
PWD Barsar

158

13

Job No- 13  
 Estimated Cost Rs:- 4,85,350.00  
 Earnest Money Rs:-9800.00  
 Time Limit :- Two month

Name of Work:- Restoration of rain damages on link road Dandwin to Dhangota via Kharal Km 0/00 to 5/315  
 (SH- P/L cement concrete pavement at Rd 0/039 to 0/077)

DNIT

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T	Unit		Amount
			Figure	words	
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	31.83	Cubic metre	Per Cubic Meire	15880.00
2	Construction of granular sub base by providing well graded material mixing in a mechanical mix plant at OMC carriage of mixed material to work site upto all leads spreading in uniform layers with motor grader on prepared surface and compacted with smooth wheel roller to achieve the desired density, complete as per technical Specification Clause 401. for grading -I material , including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	12.73	Cubic metre	per cubic metre	26251.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	64.03	Cubic metre	Per Cubic Meire	375357.00



<p>4) Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 ( one cement : one and half coarsc sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana , toll tax, GST or other taxes imposed by the Government .</p>	9.54 Cubic metre	7113.40 Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre 67862.00
Total:-			485350.00

DNIT approved for Rs-4,85,350/-  
only

Executive Engineer  
Bansar Division  
HWPWD Bansar

159

Job No- 14  
 Estimated Cost Rs:- 4,33,565.00  
 Earnest Money Rs:- 8700.00  
 Time Limit :- Two month

DNIT  
 Name of Work:- C/O Link road Mata Vaishno Devi Mandir to Harizan basti Suglani to Dhangota Km 0/00 to 3/500  
 (SI):- C/O R/wall at Rd 2/600 to 2/629 & Embankment filling in Km 2/600 to 2/700)

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words -		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness, including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	28.13	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	14034.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	74.24	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	316879.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, , GST or other taxes imposed by the Government.	24.94	Rupees One Thousand Four Hundred Forty Four And Paise Ninety Five Only	Per Cubic Metre	36037.00
4	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of tables 300.1 and 300.2 as per technical specification clause 301.5 and as per direction of the Engineer-in- Charge including entire carriage of material upto all leads and lifts and other incidental the rate includes octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	450.00	Rupees One Hundred Twenty Five And Paise Seventy Only	Per Cubic Metre	56565.00

<p>5) Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast) / P/holex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614. 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	25.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	10050.00
Total:-						433565.00

DNI T approved for Rs/- 4,33,565/-

only

Executive Engineer  
Bansar Division  
HDDWD Bansar

160

15

Job No-  
Estimated Cost Rs:- 4,84,842.00  
Earnest Money Rs:-9700.00  
Time Limit :- 100 months

Name of Work:- Restoration of rain damages on Jamli Chaleli road Km 0/00 to 1/300  
(SH:- P/L cement concrete pavement at Rd 0/240 to 0/345 & V-Shape drain at Rd 0/300 to 0/360 L/side & 0/340 to 0/400 R/side )

DNIT

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T	Figure	words	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	32.85	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	16389.00
2	Construction of granular sub base by providing well graded material mixing in a mechanical mix plant at OMC carriage of mixed material to work site upto all leads spreading in uniform layers with motor grader on prepared surfacc and compacted with smooth wheel roller to achtevc the desired density, complete as per technical Specification Clause 401. for grading -I material including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	10.51	2062.10	Rupees Two Thousand Sixty Two And Paise Ten Only	per cubic metre	21879.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregatc 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	45.60	5862.20	Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	Per Cubic Metre	267316.00

<p>1) Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level, up to floor five level, including the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (one cement : one and half coarse sand : three graded stone aggregate 20 mm (twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	25.20	Cubic metre	7113.40	Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre	179258.00
					Total:-	484842.00

DNIT approved for PS- 4, 84, 842/-  
(only)

Executive Engineer  
Barsar Division  
KPWD Barsar

161

Name of Work:- Restoration of rain damages on Dhangota Sathwin Bara Tajyar road Km 0/00 to 6/00  
 (SH)- P/L cement concrete pavement at Rd 2/760 to 2/858 & 4/00 to 4/030 )

Job No- 16  
 Estimated Cost Rs:- 4,97,778.00  
 Earnest Money Rs:- 100000.00  
 Time Limit :- Two month

DNIT

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T			Unit	Amount
		Figure	words	Unit		
1	Earth work in excavation for all type of road structure-such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	13.50	Cubic metre	498.90 Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	6735.00
2	Construction of granular sub base by providing well graded material mixing in a mechanical mix plant at OMC carriage of mixed material to work site upto all leads spreading in uniform layers with motor grader on prepared surface and compacted with smooth wheel roller to achieve the desired density, complete as per technical Specification Clause 401. for grading -I material including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	11.85	Cubic metre	2062.10 Rupees Two Thousand Sixty Two And Paise Ten Only	per cubic metre	24436.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals. . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	40.96	Cubic metre	5862.20 Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	Per Cubic Metre	240116.00

4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (one cement : one and half coarse sand : three graded stone aggregate 20 mm (twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	31.84	Cubic metre	7113.40	Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre	226491.00
						Total:-	497778.00

DNIT approved for Rs- 497,778/-  
only

Executive Engineer  
Barsar Division  
HAWD Barsar

162

17

Job No-  
Estimated Cost Rs:-3,64,594.00  
Earnest Money Rs:-7300.00  
Time Limit :- Two month

Name of Work:- Restoration of Rain damages on Bara Khalout Joreghat road Km 0/00 to 8/180  
(SIL:- C/O R/wall at Rd 4/010 to 4/020 & E/wall at Rd 4/200 to 4/216)  
DNIT

Sr.No	Description of Item	29.02	Cubic metre	Figure	Rate inclusive all taxes i/c G.S.T words	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	29.02	Cubic metre	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	14478.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	76.29	Cubic metre	4268.30	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	325629.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government	8.60	Cubic metre	1444.95	Rupees One Thousand Four Hundred Forty Four And Paise Ninety Five Only	Per Cubic Metre	12427.00



3	Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia. PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	30.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	12060.00
Total:-							364594.00

DNIT approved for Rs/- 3,64,594/-  
only)

Executive Engineer  
Barsar Division  
HDDWD Barsar

165

Job No- 18  
 Estimated Cost Rs:- 4,92,484.00  
 Earnest Money Rs:-9900.00  
 Time Limit :- Two month

Name of Work:- Restoration of rain damages on Harizan Basti Sher Hardo to Tillu road Km 0/00 to 2/00  
 (SIF:- C/O R/wall at Rd 0/220 to 0/239.40)  
 DNIT

Sr.N	Description of Item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	24.44	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	12193.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	103.98	4268.30	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	443818.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government.	21.60	1409.40	Rupees One Thousand Four Hundred Nine And Paise Forty Only	Per Cubic Metre	30443.00

4	Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast) / Finolex / Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkapa, toll tax, GST or other taxes imposed by the Government.	15.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	6030.00
Total:-							492484.00

ONIT approved for Rs. 4,92,484/-  
only

Executive Engineer  
Barsar Division  
HDPWD Barsar

167

Job No- 19

Estimated Cost Rs:- 4,39,515.00  
 Earnest Money Rs:- 8800.00  
 Time Limit :- Two month

Name of Work:- C/O Link road Mata Vaishno Devi Mandir chowk to Harizan basti Suglani to Dhangota Km 0/00 to 3/500  
 (SH:- C/O R/wall at Rd 2/630 to 2/655 & Embankment filling in Km 2/700 to 2/850)  
 (under SCSIP Head)

DNT

Sl.No	Description of Item	Rate inclusive all taxes i/c G.S.T	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	24.25	Cubic metre	12098.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	64.00	Cubic metre	273171.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government.	21.50	Cubic metre	31066.00
4	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of tables 300.1 and 300.2 as per technical specification clause 301.5 and as per direction of the Engineer-in-Charge including entire carriage of material upto all leads and lifts and other incidental the rate includes octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	900.00	cubic metre	113130.00

<p>5 Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-In-Charge including entire carriage of material within all leads and lifts and other incidents The rates are Inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.</p>	25.00	Numbers	402.00	Rupees Four Hundred Two Only	10050.00
Total:-					439515.00

DNIT approved for Rs-4,39,515/- only

Executive Engineer  
Bajsar Division  
PPWD Bajsar

168

Job No - 20  
 Estimated cost Rs:- 471385.00  
 Earnest money Rs:- 9500 .00  
 Time Limit :- Two Month

Name of work:- Restoration of rain damages on Sukkar Khad to Beri via Pahloo Khas road Km 0/00 to 5/540  
 (SH:- C/O wire cratic R/Wall at Km 1/400 to 1/435 )

DNIT

Sr.No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figures	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	57.79	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	28831.00
2	Providing and laying of boulder apron laid in wire creates with 4mm (four millimeter dia G.I wire conferring to I.S. 280 and IS-4826 in 100mmx100mm (one hundred millimeter into one hundred millimeter) mash WOVEN diagonally) including 10 percent extra for laps and joints laid with stone boulder weighting not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax , GST or other taxes imposed by the Government .	133.92	3122.40	Rupees Three Thousand One Hundred Twenty Two And Paise Forty Only	Per Cubic Metre	418152.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , , GST or other taxes imposed by the Government.	16.71	1460.30	Rupees One Thousand Four Hundred Sixty And Paise Thirty Only	Per Cubic Metre	24402.00
					Total:-	471385.00

DNIT approved for Rs. 4,71,385/- only

Executive Engineer  
 Barsar Division  
 PWD Barsar

170

21

Job No-  
Estimated Cost Rs:- 1,99,546.00  
Earnest Money Rs:- 4000.00  
Time Limit :- One month

Name of Work:- C/O link road to Sawar Sath Ward No -3 (G.P Jajri )  
(SH:- C/O R/wall at Rd 0/180 to 0/190 & Cement concrete pavement at Rd 0/155 to 0/179)  
DNIT  
(Deposit work)

Sr.N	Description of Item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	26.40	498.90	Rupces Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	13171.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	20.26	4268.30	Rupces Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	86476.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, , GST or other taxes imposed by the Government.	4.40	1409.40	Rupces One Thousand Four Hundred Nine And Paise Forty Only	Per Cubic Metre	6201.00

	4.00	Numbers	Rupees Four Hundred Two Only	Each	1608.00
<p>4 Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall , return wall , retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.</p>	7.20	Cubic metre	1593.10 Rupees One Thousand Five Hundred Ninety Three And Paise Ten Only	Per Cubic Metre	11470.00
<p>5 Stone soling properly hand packed filling interstices with spalls and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter ) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.</p>	7.20	Cubic metre	5862.20 Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	Per Cubic Metre	42208.00
<p>6 Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &amp; 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .</p>	5.40	Cubic metre	7113.40 Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre	38412.00
<p>7 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 ( one cement : one and half coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.</p>				Total:-	199546.00

DNIT approved for Rs. 1,99,546/-  
only

Executive Engineer  
Barsar Division  
HPWD Barsar



172

Name of Work:- Restoration of rain damages on Bara Khalaut Joreghat road Km 0/00 to 8/180  
(SH:- P/F crash barrier at Km 6/200 to 6/300)

DNJIT

Job No- 22  
Estimated Cost Rs:- 4,65,603.00  
Earnest Money Rs:-9400.00  
Time Limit :- Two month

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount		
		Figure	words				
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	9.03	Cubic metre	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	4505.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802.803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	9.03	Cubic metre	5800.95	Rupees Five Thousand Eight Hundred And Paise Ninety Five Only	Per Cubic Metre	52383.00
3	Providing and erecting a "W" metal beam crash barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam, guard , rail 70cm(seventy centimetre) above road/ ground level, fixed on ISMC series channel vertical post 150x75x5mm(one hundred fifty into seventy five into five millimetre) thick spaced 2 mtr (two metre) center to center 1.8mtr (one point eight metre ) high 1.1m(one point one meter) below ground/ road level all steel parts and fittings to be galvanized by hot dip process all fittings to conform to IS:1367 and IS 1364 metal beam, guard rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm(one hundred fifty into seventy five into five millimetre) 330mm (three hundred thirty millimetre) long complete as per clause 810. and as per standard drawing and as desired by the site Engineer-in Charge including carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	100.00	running metre	4087.15	Rupees Four Thousand Eighty Seven And Paise Fifteen Only	Per running Metre	408715.00
					Total:-		465603.00

DNJIT approved for Rs:- 4,65,603/-  
only

Executive Engineer  
Bajsar Division  
H.P.W.D. Bajsar

173

Job No- 23

Estimated Cost Rs:-4,51,406.00  
 Earnest Money Rs:-9100.00  
 Time Limit :- Two month

DNIT  
 Name of Work:-Restoration of rain damages on Mehre Garli Bijhari road Km 0/00 to 12/00  
 (SH)- C/O R/wall at Rd 0/745 to 0/762.50

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T			Unit	Amount
		Figure	words			
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	20.48	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	10217.00	
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	92.51	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	394860.00	
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, , GST or other taxes imposed by the Government	21.00	Rupees One Thousand Four Hundred Nine And Paise Forty Only	Per Cubic Metre	29597.00	

<p>Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall , return wall , retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.</p>	15.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	6030.00
<p>Construction of embankment with approved materials deposited at site from road way cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of tables 300.1 and 300.2 as per technical specification clause 301.5 and as per direction of the Engineer-in- Charge including entire carriage of material upto all leads and lifts and other incidental the rate includes octroi, royalty malkana , toll tax, GST or other taxes imposed by the Government .</p>	85.00	cubic metre	125.90	Rupees One Hundred Twenty Five And Paise Ninety Only	Per Cubic Metre	10702.00
Total:-						451406.00

UNIT approved for Rs = 4,51,406/-  
 only

Executive Engineer  
 Barsar Division  
 H.O. BARSAR

Name of Work:- Restoration of rain damages on Bara Khalaat Joreghat road Km 0/00 to 8/180  
(SH:- P/F crash barrier at Km 6/900 to 6/990)

DNIT

Job No- 24  
Estimated Cost Rs:- 4,18,810.00  
Earnest Money Rs:- 8400.00  
Time Limit :- Two month

174

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T	Unit	Amount
		Figure	words	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including scitting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	4036.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement:three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5800.95	Rupees Five Thousand Eight Hundred And Paise Ninety Five Only	46930.00
3	Providing and erecting a "W" metal beam crash barrier comprising of 3mm (three millimetre) thick corrugated sheet metal beam, guard, rail 70cm(seventy centimetre) above road/ ground level, fixed on ISMC series channel vertical post 150x75x5mm(one hundred fifty into seventy five into five millimetre) thick spaced 2 mtr (two metre) center to center 1.8mtr (one point eight metre) high 1.1m(one point one meter) below ground/ road level all steel parts and fittings to be galvanized by hot dip process all fittings to conform to IS:1367 and IS 1364 metal beam, guard rail to be fixed on the vertical post with a spacer of channel section 150x75x5mm(one hundred fifty into seventy five into five millimetre) 330mm (three hundred thirty millimetre) long complete as per clause 810. and as per standard drawing and as desired by the site Engineer-in-Charge including carriage of material with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4087.15	Rupees Four Thousand Eighty Seven And Paise Fifteen Only	367844.00
			Total:-	418810.00

DNIT approved for Rs:- 4,18,810/- only

Executive Engineer  
Bansar Division  
HQPWD Bansar

1776

Job No- 25

Estimated Cost Rs:- 1,50,046.00

Earnest Money Rs:- 3100.00

Time Limit :- One month

DNIJ

Name of Work:- NDF/2023/13 R/O link road to village Kalohan Km 0/00 to 2/00

(SIJ:- C/O R/wall at Rd 0/055 to 0/071)

(Deposit work)

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil : ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	7.36	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	3672.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	27.04	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	115415.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, , GST or other taxes imposed by the Government	19.20	Rupees One Thousand Four Hundred Forty Four And Paise Ninety Five Only	Per Cubic Metre	27743.00

<p>4 Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment ; wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.</p>	8.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	3216.00
Total:-						150046.00

*DNIT approved for Rs. 1,50,046/- only*

Executive Engineer  
 Barsar Division  
 PWD Barsar

177


Job No- 26  
 Estimated Cost Rs:-4,06,831.00  
 Earnest Money Rs:-8200.00  
 Time Limit :- Two month

DNJT  
 Name of Work:-Restoration of rain damages on Salouni Bihari Deotsidh road Km 0/00 to 10/00  
 (SHL- C/O R/wall at Rd 5/700 to 5/720)

Sl.No	Description of Item	Rate inclusive all taxes i/c G.S.T	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/ wedging out. of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	30.60	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	15266.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	83.80	4263.40	Rupees Four Thousand Two Hundred Sixty Three And Paise Forty Only	Per Cubic Metre	357273.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, , GST or other taxes imposed by the Government	17.20	1409.40	Rupees One Thousand Four Hundred Nine And Paise Forty Only	Per Cubic Metre	24242.00

<p>4 Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plasty)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.</p>	25.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	10050.00
Total:-						406831.00

DNIT approved for RSJ- 4,06,831/-  
only)

  
 Executive Engineer  
 Barsar Division  
 H.P.W.D. Barsar



182

27

Job No :- 27  
 Estimated Cost Rs:- 4,79,451.00  
 Earnest Money Rs:- 9600.00  
 Time Limit :- Two month

DNIT  
 Name of Work:- A/R & M/O on Barsar Shahatalai road Km 0/00 to 11/400  
 (SH:- Repair of pot holes in between Km 0/00 to 11/400)

Sr.No	Description of Item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Repair to pot holes and removal of loose material trimming of sides cleaning of surface by providing tack coat 20mm(twenty millimeter) thick premix carpet and seal coat type-B specification Clause 1904.2.503 & 508.1 including entire carriage of material in all leads and lifts as per the direction of Engineer-in- Charge, including entire carriage of material in all leads and lifts. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	1327.37	square metre	343.95	Rupees Three Hundred Forty Three And Paise Ninety Five Only	Per square metre	456549.00
2	Providing and laying spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100KN in stages to proper grade and camber applying and brooming with application of crushable stone screening/ binding materials to fill-up the interstices of coarse aggregate watering and compacting to the required density Grading -III 53mm to 22.4mm ( fifty three millimeter into twenty two point four millimeter )size stone aggregate as per Technical Specification Clause 405 including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	10.00	cubic metre	2290.20	Rupees Two Thousand Two Hundred Ninety And Paise Twenty Only	Per cubic metre	22902.00
Total:-							479451.00

DNIT approved for Rs:- 4,79,451/-  
*only*

Executive Engineer  
 Barsar Division  
 H.P.W.D. Barsar

183

28

Job No :- 28  
 Estimated Cost Rs:- 4,79,089.00  
 Earnest Money Rs:- 9600.00  
 Time Limit :- Two month

DNIT  
 Name of Work:- A/R & M/O on Una Aghar Mandi road Km 67/00 to 69/00 & Jhiralari Check Loader Meena Ka Dehra Km 0/00 to 6/00  
 (SH:- Repair of pot holes in between Km 67/00 to 69/00 & 0/00 to 6/00 respectively)

Sr.No	Description of Item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Repair to pot holes and removal of loose material trimming of sides cleaning of surface by providing tack coat 20mm(twenty millimeter) thick premix carpet and seal coat type-B specification Clause 1904.2.503 & 508.1 including entire carriage of material in all leads and lifts as per the direction of Engineer-in- Charge. including entire carriage of material in all leads and lifts. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	1346.05 square metre	343.95	Rupees Three Hundred Forty Three And Paise Ninety Five Only	Per square metre	462974.00
2	Providing and laying spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness hand packing rolling with smooth wheel roller 80-100KN in stages to proper grade and camber applying and brooming with application of crushable stone screening/ binding materials to fill-up the interstices of coarse aggregate watering and compacting to the required density Grading -III 53mm to 22.4mm ( fifty three millimeter into twenty two point four millimeter )size stone aggregate as per Technical Specification Clause 405 including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	7.00 cubic metre	2302.20	Rupees Two Thousand Three Hundred Two And Paise Twenty Only	Per cubic metre	16115.00
Total:-						479089.00

DNIT approved for Rs- 4,79,089/-  
 only

Executive Engineer  
 Barsar Division  
 H.P.W.D Barsar

184

Name of Work:- C/O B/wall & P/L interlocking paver block at H.S.C Jajri  
(SH)- P/L 60mm thick interlocking paver block in Courtyard)  
(Deposit work)

DNIT

Job No- 29  
Estimated Cost Rs:- 1,70,010.00  
Earnest Money Rs:- 3500.00  
Time Limit :- one month

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surfacc and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	56.88	Cubic metre	498.90 Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre 28377.00
2	Stone soling properly hand packed filling interstices with spalls and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter ) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	6.91	Cubic metre	1493.10 Rupees One Thousand Four Hundred Ninety Three And Paise Ten Only	Per Cubic Metre 10317.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	6.91	Cubic metre	5862.20 Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	Per Cubic Metre 40508.00
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 ( one cement : one and half coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	1.13	Cubic metre	7113.40 Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre 8038.00

<p>5) Providing and laying of interlocking concrete paver block vibro compacted upto M-30 (M-Thirty) grade having thickness 60mm (sixty millimeter) including border or kerb block over sub base of sand as per drawing and technical specification Clause-1504 approved any make conforming to the Nitco, Modern, Gico, NTC/ BIA specification for interlocking paver blocks including entire carriage of material with in all leads and lift and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	69.09	square metre	1198.00	Rupees One Thousand One Hundred Ninety Eight Only	per square metre	82770.00
Total:-						170010.00

DNIIT approved for Rs. 1,70,010/-

only

Executive Engineer  
Barsar Division  
P.W.D. Barsar

185

Job No- 30

DNIT

Name of Work:- C/O R/wall, B/wall Courtyard at H.S.C building at Jagoti (SH:- P/L 60mm thick interlocking paver block in Courtyard, C/O Ramp, White washing in boundary wall) (Deposit work)

Estimated Cost Rs:- 2,49,605.00  
Earnest Money Rs:-5000.00  
Time Limit :- one month

Sr.No	Description of Item	Rate inclusive all taxes & G.S.T		Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil : ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of stumps and other deleterious materials and disposal of materials upto any approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	5.67	Cubic metre	498.90 Rupees Four Hundred Ninety Eight And Paise Ninety Only	2829.00
2	Stone soling properly hand packed filling interstices with speels and consolidating with power road roller to the required gradient .and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter ) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	6.31	Cubic metre	1493.10 Rupees One Thousand Four Hundred Ninety Three And Paise Ten Only	9421.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	6.42	Cubic metre	5862.20 Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	37635.00
4	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 ( one cement : one and half coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government .	2.60	Cubic metre	7113.40 Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	18495.00

	124.35 square metre	1198.00	Rupees One Thousand One Hundred Ninety Eight Only	per square metre	148971.00
5) Providing and laying of inter locking concrete paver block vibro compacted upto M-30 (M-Thirty) grade having thickness 60mm (sixty millimeter) including border or kerb block over sub base of sand as per drawing and technical specification Clause-1504 approved to the Nitco, Modern, Gisco, NITV / BIS specification for interlocking paver blocks including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	281.52 square metre	75.50	Rupees Seventy Five And Paise Fifty Only	per square metre	21255.00
6) Finishing walls with water proofing cement paint of required shade for old work (one or more coats applied @ 2.20 kg/10 sqm (two point twenty kilogram per ten square metre) over priming coat of primer applied @ 0.80 litres/10 sqm (zeri point eighty liters per ten square metre) complete including cost of Priming coat including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	87.64 Kilogram	125.50	Rupees One Hundred Twenty Five And Paise Fifty Only	per kilogram	10999.00
7) Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.				Total:-	249605.00

D.N.I.T approved for Rs/- 2,49,605/-

*(Signature)*

Executive Engineer  
Bansar Division  
H.P. WD Bansar

187

Job No- 31

Estimated Cost Rs:-4,76,307.00  
Earnest Money Rs:-9600.00

Time Limit :- One Month

DNIT  
Name of work:- Restoration of rain damages on various road under HPPWD Sub Division Barsar (Section Bijhari)  
(SH:- Supply and stacking of Granular sub-base of various road at various Rds)

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T Figure	Unit	Amount
1	Supply and stacking of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts With material conforming to Grade-I (size range 75 mm (seventy five millimetre ) to 0.075 mm (zero point zero seven five) having CBR Value-30 (thirty) as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	390.00	Cubic metre	1221.30	Per Cubic Metre	476307.00
					Total:-	476307.00

DNIT approved for Rs. 4,76,307/-  
only

Executive Engineer  
Barsar Division  
HPPWD Barsar

188

32

DNIT

Name of work:- A/R & M/O HPPWD Rest House at Deotsidh  
 (SH:- Distemping, painting & Sanitary work etc.)

Estimated Cost Rs:- 4,99,693.00

Earnest Money Rs:- 10000.00

Time Limit :- Two Month

Sr No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Square metre	Figure	words	Figure		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government	374.42	15.40	Rupees Fifteen And Paise Forty Only	15.40	Per square metre	5,766.00
2	Providing and applying white cement based putty of average thickness 1mm(one millimetre) of approved brand and manufacture of over the plastered wall surface to prepare the surface even and smooth complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	374.42	106.10	Rupees One Hundred Six And Paise Ten Only	106.10	Per square metre	39,726.00
3	Applying priming coat with primer of approved brand and manufacture, having low VOC( Volatile Organic Compound) content with water thinnable cement primer on wall surface having VOC( Volatile Organic Compound) content less than 50grams /liter(fifty grams/litre) including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	374.42	49.90	Rupees Forty Nine And Paise Ninety Only	49.90	per square metre	18,684.00
4	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer as approved by Engineer-in-Charge including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	468.20	128.40	Rupees One Hundred Twenty Eight And Paise Forty Only	128.40	per square metre	60,117.00
5	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications for Painting wood work with Deluxe Multi Surface Paint to give an even shade two or more coat applied @ 0.90 ltr/ 10 sqm (zero point nine zero liter per ten square metre) over an under coat of primer applied @ 0.75 ltr/ 10 sqm(Zero point seventy five liter per ten square metre) of approved brand and manufacture including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	282.36	116.30	Rupees One Hundred Sixteen And Paise Thirty Only	116.30	Per square metre	32,838.00
6	Finishing walls with Acrylic Smooth exterior paint of required shade new work (Two or more coat applied @ 1.67 ltr/10 sqm (one point sixty seven liter / ten square metre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two point twenty kilogram/ ten square metre) including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	99.88	153.00	Rupees One Hundred Fifty Three Only	153.00	Per square metre	15,282.00



7	Painting Steel work with Deluxe Multi Surface Paint to give an even shade two or more coat applied @ 0.90 ltr/ 10 sqm (zero point nine zero liter/ ten square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm(zero point eight zero liter / ten square metre) of approved brand and manufacture including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	252.11	Square metre	118.50	Rupees One Hundred Eighteen And Paise Fifty Only	Per square metre	29,875.00
8	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, 35mm (thirty millimetre) thick shutters 2nd class teak wood excluding panelling which will be paid for separately, all complete as per direction of Engineer-in charge. (Note:- Butt hinges and necessary screws shall be paid separately) including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	5.13	square metre	3654.50	Rupees Three Thousand Six Hundred Fifty Four And Paise Fifty Only	per square metre	18748.00
9	Providing and fixing Swiss one piece toilet with Ezee close slim UF Seat cover-size (W.P.II) 380x720x705mm (three hundred eighty into seven hundred twenty into seven hundred five millimetre) S trap 220 mm (two hundred twenty millimetre) & 300 mm (three hundred millimetre) of approved quality including entire carriage of material in all leads and lifts The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government (Market Rate )	5.00	Numbers	19990.00	Rupees Nineteen Thousand Nine Hundred Ninety Only	Each	99950.00
10	Providing and fixing elite wash basin size (WxPxH) 620x500x 845mm (six hundred twenty into five hundred into eight hundred forty five millimetre) of approved quality including entire carriage of material in all leads and lifts The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government (Market Rate )	4.00	Numbers	5650.00	Rupees Five Thousand Six Hundred Fifty Only	Each	22600.00
11	Providing and fixing elite full pedestal for wash basin size 620x500x 845mm (six hundred twenty into five hundred into eight hundred forty five millimetre) of approved quality including entire carriage of material in all leads and lifts The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government (Market Rate )	4.00	Numbers	2340.00	Rupees Two Thousand Three Hundred Forty Only	Each	9360.00
12	Providing and fixing 600x450 mm (six hundred into four hundred fifty millimetre) beveled edge mirror of superior glass (of approved quality) complete with 6 mm (six millimetre) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	4.00	Numbers	1178.60	Rupees One Thousand One Hundred Seventy Eight And Paise Sixty Only	each	4714.00
13	Providing and fixing C.P Brass towel rod Catalogue No (27213016011) size 600mm ( six hundred millimetre) complete with brackets fixed to wooden cleats with CP Brass screws with coceated fittings arrangement of approved quality and colour heavy duty of Hindware/ Cera/ Jaguar make complete. including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government. (Market Rate )	4.00	Numbers	1780.00	Rupees One Thousand Seven Hundred Eighty Only	each	7120.00

16	Providing and fixing C.P Brass towel ring Catalogue No (272130160101) complete with brackets fixed to wooden cleats with CP Brass screws with concealed fittings arrangement of approved quality heavy duty of Hindware/ Cera/ Jaguar make complete. including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government. (Market Rate )	4.00	Numbers	1340.00	Rupees One Thousand Three Hundred Forty Only	each	5360.00
17	Providing and fixing C.P brass paper holder with flap Catalogue No (272130160071) of approved quality including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government. (Market Rate )	4.00	Numbers	1750.00	Rupees One Thousand Seven Hundred Fifty Only	each	7000.00
18	Providing and fixing Soap basket Catalogue No (272130160041 ) of approved quality make complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government. (Market Rate )	8.00	Numbers	1800.00	Rupees One Thousand Eight Hundred Only	each	14400.00
19	Providing and fixing C.P brass bib tap heavy duty 15mm (fifteen millimetre) dia of approved quality conforming to IS8931 catalogue No (272210330021) make . complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government. (Market Rate )	4.00	Numbers	1280.00	Rupees One Thousand Two Hundred Eighty Only	each	5120.00
20	Providing and fixing C.P brass long nose bib tap with capatan head (heavy duty) 15mm (fifteen millimetre) dia of approved quality conforming to IS8931 catalogue No (272210710031) make . complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government. (Market Rate )	8.00	Numbers	1360.00	Rupees One Thousand Three Hundred Sixty Only	each	10880.00
21	Providing and fixing 15mm (fifteen millimetre) dia C.P. brass stop cock for basin mixer and geyser points of approved quality conforming to IS:8931 catalogue No (272210440161) make complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government. (Market Rate )	42.00	Numbers	890.00	Rupees Eight Hundred Ninety Only	each	37380.00
22	Providing and fixing sink mixer with swinging spout of approved quality conforming to IS:8931 catalogue No (272200330061) make complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government. (Market Rate )	4.00	Numbers	5040.00	Rupees Five Thousand Forty Only	each	20160.00
23	Providing and fixing square rain shower in stainless steel with round shower arm with flange of approved quality conforming to IS:8931 catalogue No (272220420061) 250mm (two hundred fifty millimetre) make complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government. (Market Rate )	4.00	Numbers	6780.00	Rupees Six Thousand Seven Hundred Eighty Only	each	27120.00

<p>Providing and fixing G.I union in G.I pipe including cutting and threading the pipe and making long screws etc. complete (New work) 15mm (fifteen millimetre) nominal bore including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	8.00	Numbers	193.70	Rupees One Hundred Ninety Three And Paise Seventy Only	each	1550.00
<p>Providing and fixing 110mm ( one hundred ten millimetre ) dia nominal size high pressure made of Polyurethane, Hindware, Cera/finolex of following dia PVC spigot and socket waste and ventilating pipes ISI unknuck including fixing with approved adhesive etc. complete including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	14.50	Running metre	327.10	Rupees Three Hundred Twenty Seven And Paise Ten Only	Per running metre	4743.00
<p>Providing and fixing Tooth brush and tumbler holder catalogue No (272130150071) etc. complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government. (Market Rate)</p>	1.00	Numbers	1200.00	Rupees One Thousand Two Hundred Only	each	1200.00
					Total:-	499693.00

DNIT approved for Rs- 4,99,693/-  
only

Executive Engineer  
Barsar Division  
BPPWD Barsar

<p>providing and fixing G.I union in G.I pipe including cutting and threading the pipe and making long screws etc. complete (New work) 15mm (fifteen millimetre) nominal bore including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	8.00	Numbers	193.70	Rupees One Hundred Ninety Three And Paise Seventy Only	each	1550.00
<p>providing and fixing 110mm ( one hundred ten millimetre ) dia nominal size high pressure made of polyurethane, Hindware, Cera/finolex of following dia PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	14.50	Running metre	327.10	Rupees Three Hundred Twenty Seven And Paise Ten Only	Per running metre	4743.00
<p>Providing and fixing Tooth brush and tumbler holder catalogue No (272130150071) etc. complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government. (Market Rate)</p>	1.00	Numbers	1200.00	Rupees One Thousand Two Hundred Only	each	1200.00
Total:-						499693.00

DNIT approved for Rs- 4,99,693/- only

Executive Engineer  
Barsar Division  
RRPWD Barsar

DNIT

Name of Work:-Restoration of rain damages on Salouni Bijhari Deotsidh road Km 0/00 to 10/00  
(SIF:- C/O R/wall at Rd 6/800 to 6/818)

Job No- 33

Estimated Cost Rs:-3,11,174.00

Earnest Money Rs:-6300.00

Time Limit :- One month

189

Sl.No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	31.14	Rupees Four Hundred Ninety Nine Only	Per Cubic Metre	15536.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	63.00	Rupees Four Thousand Two Hundred Sixty Three And Paise Forty Only	Per Cubic Metre	268594.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government	15.48	Rupees One Thousand Four Hundred Nine And Paise Forty Only	Per Cubic Metre	21818.00

<p>Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast) / Pholox/ Supreme having working pressure not less than 4 kg per centimeter square (four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidents The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	13.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	5226.00
					Total:-	311174.00

*only*  
*ONBIT approved for Rs. 3,11,174/-*

Executive Engineer  
 Bajsar Division  
 H.P.W.D Bajsar

(190)

Name of Work:-A/R & M/O HPPWD Rest House at Bijhari District Hamirpur  
P/L distemping work , plastering work, wood work , sanitary work etc. )

DNIT

Job No- 34

Estimated Cost Rs:- 4,04,746.00

Earnest Money Rs:-9100.00

Time Limit :- Two month

Sr.N	Description of Item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
0							
1	Providing and fixing anodised aluminium work for door, window, ventilators and glazed partitions frames with extruded built up standard tubular and other sections of approved make conforming to IS 733 and IS 1285 anodised transparent or dyed to required shade according to IS 1868. (Minimum anodic coating of grade AC 15 (fifteen) fixed with raw/plugs and screws or with fixing clips, or with expansion hold fastners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rustfree, straight, mitred and jointed mechanically where ever required including cleast angle, aluminium, snap beading for glazing/panelling C.P. brass/stainless steel screws. All complete as per architectural drawings and the directions of Engineer-In-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	10.56	kilogramme	490.45	Rupees Four Hundred Ninety And Paise Forty Five Only	per kilogramme	5,179.00
2	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item) With float glass panes of 4 mm(four millimetre) thickness (weight not less than 10.00 kg/ sqm)(tene point zero kilogram square metre) including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	7.20	Square metre	1467.20	Rupees One Thousand Four Hundred Sixty Seven And Paise Twenty Only	Per Square Metre	10564.00

<p>3 Providing and fixing 19mm (Nineteen millimeter) thick IDHMR water proof termite resistant commercial board of Uniply/Greenply/K (ply of its equivalent ISI marked IS No 1659 cabinet size 1.00x0.675x0.45 mtrs (one point zero two zero point six hundred seventy five into zero point fourty five metre) deep with shutter and drawers having on shelves of 19mm (nineteen millimetre) thick board and all sides of the cabinet of 19 mm (nineteen millimetre) thick board back side and bottom of cabinet shall be 8mm (eight millimetre) ply. The table tops shall be of 25mm (twenty five millimetre) thick water proof Termite resistant commercial board. The vertical portion of the table towards corner side shall be finished with 4mm (four millimetre) thick teak ply to be matched with the shade of panelled as per data Architectural drawing. The table top and other visible portion of commercial board ISI marked IS No 1659 of green ply /K (ply equivalent towards sitting side shall be finished with 1mm (one millimetre) thick lamination of approved shade except leg space is toe polished. All visible portion of commercial board shall be finished 6/8mm (six /eight millimetre) thick hard wood adging /flipping polished with natural shade. The cabinet from all around shall be fixed with 19x6mm (nineteen into six millimetre) thick hard wood edging complete with Piano hinges. PTMT handles of prayag polymers of its equivalent with steel screws. Knobs, Magnetic cutchers and Mortice locks /godrej admirah type locks and necessary screws, nails and favicol etc. P/F 1mm thick colored of plain lamination sheet (Sunmica) on boards /ply wood sheet with approved adhesive as per direction of Engineer-in-Charge. including entire carriage of materials in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	40.22	square metre	3651.00	Rupees three thousand three hundred forty two and paise forty only.	per square metre	146843.00
<p>4 Providing and fixing 1.00mm (one point zero millimetre) thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc complete as per direction of Engineer-in-Charge. including entire carriage of materials in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	18.62	square metre	1129.85	Rupees three thousand three hundred forty two and paise forty only.	per square metre	21038.00
<p>5 Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm (one point four millimetre) in both directions with wire of dia 0.63 mm, (zero point six three millimetre) for doors, windows and clerestory windows with hinges and necessary screws 35 mm (Thirty five millimetre) thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size of Deodar 1st class wood as per drawings and technical specification as per the direction of Engineer-in-Charge. including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	7.38	Square metre	4800.00	Rupees Four Thousand Eight Hundred Only	Per square metre	35424.00
<p>6 Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete 300x16mm (three hundred into sixteen millimetre) including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	4.00	Numbers	252.85	Rupees Two Hundred Fifty Two And Paise Eighty Five Only	Each	1011.00



<p>Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete lifts (about two hundred fifty into ten millimetre) including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	28.00	Numbers	93.00	Rupees Ninety Three Only	Each	2,604.00
<p>Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete (one hundred millimetre) including entire carriage of material in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	28.00	Numbers	54.70	Rupees Fifty Four And Paise Seventy Only	Each	1,532.00
<p>Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in gratings framed guard bars, ladders, railing, brackets and similar works including entire carriage of material in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	1.15	Quintal	11592.86	Rupees Eleven Thousand Five Hundred Ninety Two And Paise Eighty Six Only	per Quintal	13332.00
<p>Applying priming coat with Ready mixed paint brushing with white lead for priming over new wood and wood based surfaces after and including prepping the surface by thoroughly cleaning oil, grease, dirt and other foreign matter sand papering and knotting including entire carriage of material in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	14.76	square metre	40.29	Rupees Forty And Paise Twenty Nine Only	per square metre	595.00
<p>Painting two coats (excluding priming coat) with white paint on new wood and wood based surfaces, with ready mixed paint, brushing to give an even shade including cleaning of all dirt, dust and other foreign matter sand papering and stopping including entire carriage of material in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	14.76	square metre	109.86	Rupees One Hundred Nine And Paise Eighty Six Only	per square metre	1622.00
<p>Providing and laying 15mm (fifteen millimeters) thick cement plaster in single coat on the rough side of brick concrete/stone walls for interior plastering upto all floor levels including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (Eighty millimeters) in girth and finished even and smooth in cement mortar 1:6 (One cement : Six sand) and curing complete as per entire satisfaction of the Engineer-in-charge including entire carriage of material in all leads and lifts. The rate including Royalty, Malkana, Octroi, Toll Tax, GST or any other taxes imposed by the Government.</p>	23.00	square metre	287.85	Rupees Two Hundred Eighty Seven And Paise Fifty Five Only	per square metre	6,621.00

356.38	square metre	11.60	Rupees Eleven And Paise Sixty Only	Per square metre	4134.00
250.00	Square metre	103.20	Rupees One Hundred Three And Paise Twenty Only	Per square metre	25,800.00
					404,746.00

D NIT approved for Rs. 4,04,746/-

(only)

Executive Engineer  
 Barsar Division  
 H.P.W.D. Barsar

201

35


Job No-  
Estimated Cost Rs:-1,48,817.00  
Earnest Money Rs:-3000.00  
Time Limit :- One month

DNIT  
Name of Work:- SDF/2023/70 (R/O) Rain damages on village Karwin road Km 0/00 to 2/00 (G.P Bani)  
(SII:- C/O R/wall at Rd 0/00 to 0/006)  
(D.C Deposit)

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T			Unit	Amount
		Figure	words			
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Cubic metre	Per Cubic Metre	3647.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	4268.30	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Cubic metre	Per Cubic Metre	132701.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government	1444.95	Rupees One Thousand Four Hundred Forty Four And Paise Ninety Five Only	Cubic metre	Per Cubic Metre	10057.00

4	Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-Plast) / Inotex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	6.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	2412.00
Total:-							148817.00

D.N.T. approved for Rs 1,48,817 only

  
 Executive Engineer  
 Barsar Division  
 H.P.W.D. Barsar

264

Name of work:- Restoration of rain damages on link road Bhotia Bijhari via Ropari Km 0/00 to 14/00  
(SH:- C/O wire crate R/Wall at Rd 3/520 to 3/533.50)

DNIT

Job No - 36  
Estimated cost Rs:- 4,92,646.00  
Earnest money Rs:- 9900 .00  
Time Limit :- Two Month

Sr.No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figures	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	21.87	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	10911.00
2	Providing and laying of boulder apron laid in wire creates with 4mm (four millimeter dia G.I wire conferring to I.S. 280 and IS-4826 in 100mmx100mm (one hundred millimeter into one hundred millimeter) mash WOVEN diagonally) including 10 percent extra for laps and joints laid with stone boulder weighing not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana toll tax , GST or other taxes imposed by the Government.	147.64	3122.40	Rupees Three Thousand One Hundred Twenty Two And Paise Forty Only	Per Cubic Metre	460991.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, , GST or other taxes imposed by the Government.	16.20	1280.50	Rupees One Thousand Two Hundred Eighty And Paise Fifty Only	Per Cubic Metre	20744.00
					Total:-	492646.00

DNIT approved for Rs 492,646 only

Executive Engineer  
Barsar Division  
H.P.W.D. Barsar

205

37

Job No -  
Estimated cost Rs:- 4,96,184.00  
Earnest money Rs:- 10000 .00  
Time Limit :- Two Month

Name of work:- Restoration of rain damages on link road Bhoja Bijhari via Ropari Km 0/00 to 14/00  
(SHI- C/O B/Wall at Rd 3/533 to 3/551.90 )

DNIT

Sr.No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figures	Words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom, and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	26.83	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	13385.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802.803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	111.70	4268.30	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	476769.00
3	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	15.00	402.00	Rupees Four Hundred Two Only	Each	6030.00
					Total:-	496184.00

DNIT, approved for Rs 4,96,184 only

Executive Engineer  
Barsar Division  
IPPCWD Barsar

256

38

Job No-  
Estimated Cost Rs:-4,87,354.00  
Earnest Money Rs:-9800.00  
Time Limit :- Two Month

Name of work- Restoration of rain damages on link road Bhota Bijhari via Ropri Km 0/00 to 14/00  
SH:- C/O R/wall at Rd 3/855 to 3/874.30)  
DNJT

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	24.32 cubic metre	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	12133.00
2	Providing and laying cement concrete 1:5:10 (one cement : five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	102.86 Cubic metre	4268.30	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	439037.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government	23.16 Cubic metre	1302.00	Rupees One Thousand Three Hundred Two Only	Per Cubic Metre	30154.00

<p>4) Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D- plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.</p>	15.00	Numbers	402.00	Rupees Four Hundred Two Only	Each 6030.00
Total:-					487354.00

D.NIT, approved for Rs 4,87,354 only

Executive Engineer  
Barsar Division  
HBBWD Barsar



267

39

Job No -  
Estimated cost Rs:- 4,88,820.00  
Earnest money Rs:- 99000.00  
Time Limit :- Two Month

DNIT  
Name of work:-Restoration of rain damages on link road Janain Samtana road  
(SH):- C/O wire crate R/Wall at Rd 9/090 to 9/118.70)

Sr.No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figures	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	46.49	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	23194.00
2	Providing and laying of boulder apron laid in wire creates with 4mm (four millimeter dia G.I wire conferring to I.S. 280 and IS-4826 in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh WOVEN diagonally) including 10 percent extra for laps and joints laid with stone boulder weighting not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax , GST or other taxes imposed by the Government.	134.53	3122.40	Rupees Three Thousand One Hundred Twenty Two And Paise Forty Only	Per Cubic Metre	420056.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government.	35.00	1302.00	Rupees One Thousand Three Hundred Two Only	Per Cubic Metre	45570.00
					Total:-	488820.00

DNIT approved for Rs 4,88,820 only

Executive/Engineer  
Barsar Division  
HDPWD Barsar

208

Job No - 40

Estimated cost Rs:- 4,71,412.00

Earnest money Rs:- 9500 .00

Time Limit :- Two Month

DNIT

Name of work:- Restoration of rain damages on Kohia Ghumarwin road K'm 0/60 to 1/495  
(Site- P/I. 900mm dia RCC Hume pipe culvert at Rd 1/155 i/c wing wall & C/O R/wall at Rd 0/425 to 0/440 )

Sr.No	Description of item	Quantity	Unit	Rate inclusive all taxes i/c G.S.T		Amount
				Figures	words	
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	72.43	Cubic metre	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	36135.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802, 803, 1202 and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	59.61	Cubic metre	4268.30	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	254433.00
	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight graded crushed/broken stone aggregate 40 mm (forty millimetre nominal size) mechanically mixed and vibrated on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work in open foundation complete as per drawing and technical specification clause 802,803,1202&1203 as per direction of Engineer-in- Charge including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	2.29	cubic metre	5063.40	Rupees Five Thousand Sixty Three And Paise Forty Only	11595.00
	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	11.05	Cubic metre	5862.20	Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	64777.00

3	Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolcs/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	35.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	14070.00
	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government.	15.66	Cubic metre	1280.50	Rupees One Thousand Two Hundred Eighty And Paise Fifty Only	Per Cubic Metre	20053.00
	Providing and Laying reinforced cement concrete pipe NP <sup>2</sup> 900mm(nine hundred millimetre ) dia for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1:2(one cement : two sand ) but excluding excavation protection work back filling concrete and masonry work in head walls and parapets Clause 1106, including entire carriage of material within all leads and lifts other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government.	5.00	Running metre	4309.10	Rupees Four Thousand Three Hundred Nine And Paise Ten Only	Per running metre	21546.00
	Providing and laying of boulder apron laid in wire creates with 4mm (four millimeter dia G.I wire conferring to I.S. 280 and IS-4826 in 100mmx100mm (one hundred millimeter into one hundred millimeter) mesh WOVEN diagonally) including 10 percent extra for laps and joints laid with stone boulder weighting not less than 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty, malkana ,toll tax , GST or other taxes imposed by the Government .	15.63	Cubic metre	3122.40	Rupees Three Thousand One Hundred Twenty Two And Paise Forty Only	Per Cubic Metre	48803.00
						Total:-	471412.00

D NIT, approved for Rs 4,71,412 only

Executive Engineer  
Barsar Division  
B.P.W.D. Barsar

209

41

Job No-  
Estimated Cost Rs:-4,96,289.00  
Earnest Money Rs:-100000.00  
Time Limit :- Two month

DNIT  
Name of Work:- SDF/2023/69 (R/O) Rain damages on Mehre Jabble Kheriyar road Km 0/00 to 5/565  
(SH:- C/O B/wall at Rd 1/350 to 1/385)  
(D.C Deposit)

Sr.No	Description of Item	Cubic metre	Figure	Rate inclusive all taxes i/c G.S.T		Amount
				Words	Unit	
		25.99	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	12966.00
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock, hard rock, chiseling/wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stamps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of materials which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	110.41	4268.30	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	471263.00
2	Providing and laying cement concrete 1.5:10 mechanically mixed (one cement : five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	30.00	402.00	Rupees Four Hundred Two Only	Each	12060.00
3	Providing weep holes in brick masonry / stone masonry /plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.					
Total:-						496289.00

DNIT approved for Rs 496,289 only

Executive Engineer  
Barsar Division  
KOPWD Barsar

210

42

Job No -  
Estimated cost Rs:- 4,93,232.00  
Earnest money Rs:- 99000.00  
Time Limit :- Two Month

DNIT  
Name of work:- SDF/2023/214 (R/O) Restoration of rain damages on GHS Karer Lahri Salan Km 0/00 to 2/00  
(SH:- C/O wire grate R/Wall at Rd 0/375 to 0/383.50 & 0/705 to 0/725) (G.P Karer)  
(D.C Deposit)

Sl.No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figures	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including sciffing out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	46.17	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	23034.00
2	Providing and laying of boulder apron laid in wire creates with 4mm (four millimeter dia G.I wire conferring to I.S. 280 and IS-4826 in 100mmx100mm (one hundred millimeter into one hundred millimeter) mash WOVEN diagonally) including 10 percent extra for laps and joints laid with stone boulder weighting not less then 25kg (twenty five kilogram) each as per drawing and technical specification clause 1301 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax , GST or other taxes imposed by the Government .	133.59	3122.40	Rupees Three Thousand One Hundred Twenty Two And Paise Forty Only	Per Cubic Metre	417121.00
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , GST or other taxes imposed by the Government.	37.10	1430.65	Rupees One Thousand Four Hundred Thirty And Paise Sixty Five Only	Per Cubic Metre	53077.00
					Total:-	493232.00

DNIT, approved for Rs 4,93,232 only

Executive Engineer  
Barsar Division  
PPWD Barsar

211

Name of Work:- SDP/2023/59, SDP/2023/95 C/O link road village Saheli to Lower Saheli KM 0/00 to 1/00  
(SI:- Formation cutting at Rd 0/00 to 0/570) (G.P Karsai)  
(D.C Deposit) )

DNTT

Job No- **43**  
Estimated Cost Rs:- 4,98,468.00  
Earnest Money Rs:- 10000.00  
Time Limit :- Two month

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount	
		Figure	words			
1	Excavation in hilly area in all heights and depths in all kind of soil by manual/ mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rocks chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D technical specification clause 1603.1 and 1603.2 and sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all un-useful surplus material to required width of the road or on approved dumping sites by Engineer-in- Charge through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and carriage of machineries, materials, tools equipment and safety measures and incidentals. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in- Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2685.71	cubic metre	185.60	Per Rupees One Hundred Eighty Five And Paise Sixty Only	498468.00
				Total:-	498468.00	

DNTT approved for Rs 498,468/- only.

Executive Engineer  
Barsar Division  
H.P.W.D. Barsar

212

44

Job No-11  
 Estimated Cost Rs:- 4,98,128.00  
 Earnest Money Rs:- 100000.00  
 Time Limit :- Two months

DNIT  
 Name of Work:- A/R & M/O Judicial Court Complex building at Barsar  
 SH:- Distemping, painting, wood work etc.)

Sr.No	Description of Item	Rate inclusive all taxes % G.S.T		Unit	Amount
		Figure	words		
1	Finishing walls with water proofing cement paint of required shade for old work (one or more coats applied @ 2.20 kg/10 sqm (Two point twenty Kilogramme/ Ten square metre) over priming coat of primer applied @ 0.80 liters/10 sqm (zero point eighty liters/ten square metre) complete including cost of Priming coat including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	418.00	square metre	Per square metre	31559.00
2	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer as approved by Engineer-in-Charge including entire carriage of material in all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	2254.88	Square metre	Per square metre	289,527.00
3	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 4.0 mm (four point zero millimetre) thick glass panes as approved by Engineer-in-Charge including entire carriage of material in all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	15.30	Square metre	Per square metre	13964.00
4	Providing and fixing 19mm ( Nineteen millimeter) thick HDIMR water proof anti termite resistant board confirming box including shelves and shutters, the back side of cup board / cabinet of 8mm (eight millimetre) thick ply and cut portions of shelves shall be finished with 6mm(six millimetre) hard board edging. The shutters from all the sides shall be finished with 12mm(twelve millimetre) thick hard wood edging. The shutters from out side shall be finished with 1mm (one millimetre) thick laminated sheet of approved shade to match with paneling including stainless steel piano hinges and magnetic catcher with all accessories as per direction of Engineer-in- Charge. including entire carriage of materials in all leads and lifts .The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	43.47	square metre	per square metre	163078.00
				Total:-	498128.00

DNIT approved for Rs 4,98,128 only

Executive Engineer  
 Barsar Division  
 PWD Barsar

Name of Work:- Restoration of rain damages on Harsour to Garli road Km 0/00 to 6/00  
 (SH:- C/O Edge wall at Rd 4/500 to 4/550 & 5/600 to 5/615)

DNIT

Job No- 45  
 Estimated Cost Rs:- 3,28,164.00  
 Earnest Money Rs:- 6600.00  
 Time Limit :- Two month

213

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T			Unit	Amount
		Figure	words	Unit		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil. ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	31.50	Cubic metre	Per Rupees Four Hundred Ninety Eight And Paise Ninety Only	15715.00	
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202 and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	50.50	Cubic metre	Per Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	215549.00	
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, , GST or other taxes imposed by the Government.	60.00	Cubic metre	Per Rupees One Thousand Three Hundred Eighty And Paise Fifty Only	82830.00	



<p>4 Providing wecp holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall ,return wall ,retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D- plast)/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.</p>	35.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	14070.00
Total:-						328164.00

DNIT, approved for Rs 328,164 only

Executive Engineer  
Barsar Division  
HQ DWD Barsar

214

Job No- 46

DNIT

Name of Work:- Restoration of rain damages on Nara Shahtalai road Km 0/00 to 5/555  
(SH:- C/O P/L Cement concrete pavement at Rd 2/300 to 2/423)

Estimated Cost Rs:- 4,70,179.00  
Earnest Money Rs:-9500.00  
Time Limit :- 1 two month

Sr.No	Description of Item	Cubic metre	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	59.04	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	29455.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	39.36	5862.20	Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	Per Cubic Metre	230736.00
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 ( one cement : one and half coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	29.52	7113.40	Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre	209988.00
					Total:-	470179.00

DNIT. approved for Rs 4,70,179 only

Executive Engineer  
Barsar Division  
W.P.W.D Barsar

215

Job No- 47

DNIT

Name of work:- SDF/2023/211 (R/O) Restoration of rain damages on GHS Karer to Harizan Basti Lahri Salan Km 0/00 to 2/00 (SUL:- C/O R/Wall at Rd 1/140 to 1/145.15 & 1/154.15 to 1/159.93 ) (G.P Karer)  
 Estimated Cost Rs:- 3,02,240.00  
 Earnest Money Rs:-6100.00  
 Time Limit :- Two month  
 (D.C Deposit)

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T	Rate		U/Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	13.77	Cubic metre	498.90	Per Cubic Metre Rupees Four Hundred Ninety Eight And Paise Ninety Only	6870.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded) crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	58.25	Cubic metre	4268.30	Per Cubic Metre Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	248628.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	5.40	Cubic metre	5862.20	Per Cubic Metre Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	31656.00

<p>4 Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	<p>6.56 Cubic metre</p>	<p>1380.50</p>	<p>Rupees One Thousand Three Hundred Eighty And Paise Fifty Only</p>	<p>Per Cubic Metre</p>	<p>9056.00</p>
<p>5 Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plus) / P/solex/ Supreme having working pressure not less than 4 kg per centimeter square (four kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	<p>15.00 Numbers</p>	<p>402.00</p>	<p>Rupees Four Hundred Two Only</p>	<p>Each</p>	<p>6030.00</p>
<p>Total:-</p>					<p>302240.00</p>

DNIT approved for Rs. 302,240 only

Executive Engineer  
Bajsar Division  
H.P.W.D. Bajsar

242

Job No- 48  
 Estimated Cost Rs:-3,74,442.00  
 Earnest Money Rs:-7500.00  
 Time Limit :- One month

Name of Work:- NDF/2023/16 (R/O) Nara Rappar Shahtalai road Km 0/00 to 5/555  
 (SH:- C/O R/wall at Rd 3/850 to 3/857 & B/wall at Rd 2/800 to 2/825)  
 (D.C Deposit)

DNIT

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T			Unit	Amount
		Figure	words	Unit		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiseling/wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.) technical specification, clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	16.45	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	8207.00	
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	77.90	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	332501.00	
3	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	15.00	Rupees One Thousand Four Hundred Forty Four And Paise Ninety Five Only	Per Cubic Metre	21674.00	

4) Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment , wing wall , return wall , retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plate) / Finolox/ Supreme having working pressure not less than 4 kg per centimeter square (Four kilogram per centimeter square ) extending through the full width of the structures with slope of 1:1 towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 etc per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	30.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	12060.00
Total:-						374442.00

DNIT approved for Rs- 3,74,442/-  
only

Executive Engineer  
Barsar Division  
HPPWD Barsar

241

49

Job No-  
Estimated Cost Rs:-2,99,916.00  
Earnest Money Rs:-6000.00  
Time Limit :- One month

DNIT  
Name of Work:- NDF/2023/15 (R/O) Darkoti Shahtalal road Km 0/00 to 4/555  
(SH:- C/O U-Shape drain at Rd 0/00 to 0/113)  
(D.C Deposit)

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chisling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	62.64	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	31251.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	45.83	Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	per cubic metre	268665.00
Total:-					299916.00

DNIT approved for Rs:- 2,99,916/-  
only

Executive Engineer  
Barsar Division  
HPPWD Barsar

247

50

Job No-  
Estimated Cost Rs:-4,64,603.00  
Earnest Money Rs:-9300.00  
Time Limit :- Two Month

Name of work:- MPR/2023/66 C/O link road from Dalchera to Sarla Barsar Division Block Bijhari Distt. Hamirpur  
Sht:- P/L cement concrete pavement at Rd 0/615 to 0/702 & 0/826 & C/O R/wall at Rd 0/762 to 0/765.50)  
D (Deposit) 30%

DNIT

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other detecrious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and purping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engincer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	70.04	Cubic metre	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	34943.00
2	Stone soling properly hand packed filling interstices with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter ) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	33.00	Cubic metre	1450.30	Rupees One Thousand Four Hundred Fifty And Paise Thirty Only	47860.00
3	Providing and laying cement concrete 1:5:10 (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	8.47	Cubic metre	4323.00	Rupees Four Thousand Three Hundred Twenty Three Only	36616.00



<p>4) Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement three Sand : six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802, 803, 1202 &amp; 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	33.00	Cubic metre	5062.20	Rupees Five Thousand Sixty Two And Paise Twenty Only	Per Cubic Metre	167053.00
<p>5) Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (one cement : one and half coarse sand : three graded stone aggregate 20 mm (twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	24.75	Cubic metre	7113.40	Rupees Seven Thousand One Hundred Thirteen And Paise forty Only	Per Cubic Metre	176057.00
<p>6) Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government</p>	1.05	Cubic metre	1209.40	Rupees One Thousand Two Hundred Nine And Paise Forty Only	Per Cubic Metre	1270.00
<p>7) Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D-plus) / Pinolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	2.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	804.00
					Total:-	464603.00

Executive Engineer  
Barsar Division  
HPPWD Barsar

293

Job No:- 51

Estimated cost Rs:- 2,76,407.00  
 Earnest money Rs:- 5600 .00  
 Time Limit :- One Month

Name of work:- Restoration of rain damages on Badaran Gari via Galliyar Jole road Km 13/500 to 22/500  
 (SH:- C/O surface dressing, Unlined surface drain Km 13/500 to 15/500)

DNIT

Sr.No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			figures	words		
1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm (fifteen centimetre) deep and disposal of rubbish, lead up to 50m (fifty metre) and lift upto 1.5m (one point five metre) including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	6834.00	14.90	Rupees Fourteen And Paise Ninety Only	Per square metre	101827.00
2	Surface drains in soil construction of unlined surface drains if average cross section area 0.40 square metre (zero point four zero) square metre in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3.0 metre (three metre) and lead of 50m (average lead 25m) as per technical specification clause No 307 mechanical means including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1400.00	124.70	Rupees One Hundred Twenty Four And Paise Seventy Only	Per running metre	174580.00
Total:-						276407.00

DNIT approved for Rs:- 2,76,407/-

Executive Engineer  
 Barsar Division  
 PWD Baysar

only

29.10

Job No:- 52

Estimated Cost Rs:- 1,54,850.00

Earnest Money Rs:- 3100.00

Time Limit :- one month

DNIU

Work:- A/R & M/O HPPWD Rest House at Bhota  
(SH:- Repairing of furniture)

No	Description of Item	Rate inclusive all taxes i/c G.S.T		Unit	Amount		
		Figure	words				
1	Upholstering reshifting of sofa set /seats/using 2 thick sleep weel (32density) with quality foam sheets and back fixing padding with cilia and latest with superior quality trans try clot in proper position including cost of stitching materials sets sheeps well 40 density size 500x55x100 including necessary prepair of wood polishing complete as per wood polishing complete as per wood polishing complete as per PwD specifications including carriage of materials with including all leads and lifts as othier incidents within all leads and lifts as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	12.00	Numbers	5200.00	Rupees Five Thousand Two Hundred Only	Each	62400.00
2	Upholstering reshifting of sofa sed/seats/ using 2 thick sleep well (32 density) with quality foam sheets and back fixing padding with caula and latest with superior quality trans try clot in proper position including cost of stitching material and sets sleep well 40 density size 500x55x100 including necessary repair of wood complete as per HP.PwD specification, including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in- Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	13.00	Numbers	2750.00	Rupees Two Thousand Seven Hundred Fifty Only	Each	35750.00
3	Upholstering sofa chair and back with making of lapsstry cloth cutting to shape stitching and fixing etc. including properly seuring speings in position with twins U hooks and cane stick etc. fixing padding with cor: and colto / latex foam rubber of approved quality in the seat and back all complete including the cost of material in all leads lifts and other incidentals as per direction of Engineer-in- Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	21.00	Numbers	2700.00	Rupees Two Thousand Seven Hundred Only	Each	56700.00
					Total:-		154850.00

DNIU approved for pay - 1,54,850/-

only

Executive Engineer  
Baysar Division  
HPPWD Baysar

29K

53

Job No:-  
Estimated Cost Rs:- 1,62,100.00  
Earnest Money Rs:-3300.00  
Time Limit :- one month

DNIT

Name of Work:- A/R & M/O HPPWD Rest House at Barsar  
(SH:- Repairing of furniture)

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T			Unit	Amount
		Figure	words			
1	Upholstering reshuffling of sofa set /seats/using 2 thick sleep well (32density) with quality from sleeves nad back fixing padding with ella and latest with superior quantity trans cloth in proper position including cost of stitching materials sets sheeps well 40 density size 500055 100 including necessary bropair of wood polishing complete as pc wood polishing complete as per wood polishing complete as per PwD specifications including carriage of materials with including all leads and lifts as otyher incidents within all leads and lifts as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	5200.00	Rupees Five Thousand Two Hundred Only	15.00	Each	78000.00
2	Upholstering reshuffling of sofa set/seats/ using 2 thick sleep well (32 dncisty) with quality foam sheets and back fixing padding with caula and latest with superior quality trans try cloti in proper position including cost of stitching material and sets sleep well 40 density size 500x55x100 including necessary repair of wood complete as per HP.PWD specification, including carriage of materials, within all leads lifts and other incidentals as per direction of Engineer-in- Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare sess royalty or any other tax, leavy or coss in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	2750.00	Rupees Two Thousand Seven Hundred Fifty Only	8.00	Each	22000.00
3	Upholstering sofa chair and back with making of lapestry cloth cutting to shape stitching and fixing etc. including properly seuring springs in position with twins U hooks and cane stick etc. fixing padding with coir and cotto / latex foam rubber of approved quality in the scat and back all complete including the cost of material in all leads lifts and other incidentals as per direction of Engineer-in- Charge. The rate includes, octroi, Malkhana, Toll tax, Goods Service Tax, building and other construction worker, welfare coss royalty or any other tax, leavy or coss in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	2700.00	Rupees Two Thousand Seven Hundred Only	23.00	Each	62100.00
Total:-						162100.00

DNIT approved  
only

for Ref-162/09

Executive Engineer  
Barsar Division  
HPPWD Barsar

296

54

Job No:-  
 Estimated Cost Rs:- 4,00,612.00  
 Earnest Money Rs:- 8100.00  
 Time Limit :- Two month

Name of Work:- SDF-2023/704 & SDF/2023/705 (R/O) Tehsil office building at Bijhari Tehsil Bijhari District Hamirpur (SH)- Painting distempering & C/O Boundary wall i/c gate)  
 DNNT

Sr.No	Description of Item	Rate inclusive all taxes i/c G.S.T			Unit	Amount
		Figure	words	Per square metre		
1	Providing and fixing 19mm (nineteen millimetre) thick terramite resistant water proof Commercial board ISI marked is No 1659 of unply / green ply/kiply of its equivalent cabinet size 1.00x0.675x0.45mtr (one point zero zero into zero point six hundred seventy five into zero point forty five metre) deep with shutter & drawers having on shelves of 19mm (nineteen millimetre) thick board and all sides of the cabinet of 19mm (nineteen millimetre) thick board, back side and bottom of cabinet shall be 8mm (eight millimetre) ply. The table of tops shall be 25 mm (twenty five millimetre) thick water proof terramite resistant commercial board. The vertical portion of the table towards court side shall be finished with 4mm (four millimetre) thick teak ply to be matched with the shade of panelled as per detail Architectural drawing. The table top & other visible portion of commercial board ISI marked IS NO 1659 of green ply/ Kiply or its equivalent towards sitting side shall be finished with 1mm (one millimetre) thick lamination of approved shade except leg space is toe polished. All visible cut portion of commercial board shall be finished 6/8mm (six/eight millimetre) thick hard wood edging/hipping polished with natural shade. The cabinet from all around shall be fixed with 19x6mm (nineteen /six millimeter) thick hard wood edging complete with piano hinges PTMT handles of prayag polymers of its equivalent with steel screws, knobs, magnetic catchers and mortice locks/ Godrej admirab type locks and necessary screws, nails and favicol etc. complete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.	50.12	1078.95	Rupes One Thousand Seventy Eight And Paise Ninety Five Only	Per square metre	54,077.00
2	Painting two coats (excluding priming coat) on new steel and other metal surface with enamel paint brushing to give an even shade including cleaning the surface all dirt, dust and other foreign matter with enamel paint other than white complete as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	565.38	80.65	Rupes Eighty Five Only	per square metre	45598.00
3	Distempering two coats with oil bound made of Nerolac, Berger, Asian paint washable distemper of approved brand and manufacture and of required shade on undecorated wall surface to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar dropping and other foreign matter and also including preparing the surface even and sand papered smooth complete as per entire satisfaction of Engineer-in-charge including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government	860.90	125.90	Rupes One Hundred Twenty Five And Paise Ninety Only	per square metre	108,387.00

4	Distemping with dry distemper with favicol mix of approved brand and manufacture(Two coats)and of required shade on undecorated wall surface to given an even shade over and including primer coat of whitening after thoroughly brushing the surface free from mortar droppings and other foreign matter including preparing the surface even and sand papered smooth as per entire satisfaction of the Engineer-in-charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	365.93	square metre	92.10	Rupees Ninety Two And Paise Ten Only	per square metre	33702.00
5	Painting two coats (excluding priming coat)on new wood and wood based surfaces,with ready mixed paint, brushing to give an even shade including cleaning of all dirt,dust and other foreign matter sand papering and stopping: With white paint including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	142.02	Square metre	118.05	Rupees One Hundred Eighteen And Paise Five Only	Per square metre	16,765.00
6	Excavation in foundations, trenches etc., in earth work, lift upto 1.50 (one point fifty) Metres stacking the excavated soil not more than 3 (three) metres clear from the edge of the excavation and then returning the stacked soil in 15cm (fifteen centimetre) layers, when required in to plinths sides of foundations etc., consolidating each deposited layer by ramming and watering and then disposing of all surplus excavated earth as directed with in a lead of 20 (twenty) metres as per entire satisfaction of the Engineer-in-charge including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	10.80	cubic metre	420.15	Rupees Four Hundred Twenty And Paise Fifteen Only	Per cubic Metre	4538.00
7	Providing and laying cement concrete 1:6:12 (one cement: six sand : twelve graded stone aggregate 40 mm (fourty millimetre) nominal size) and curing complete excluding cost of centring and shuttering in foundation and plinth as per entire satisfaction of the Engineer-in-charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	5.40	cubic metre	4000.00	Rupees Four Thousand Only	Per cubic Metre	21600.00
8	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (one cement : six coarse sand : twelve graded stone aggregate 20 mm(twenty millimetre) nominal size) in cement mortar 1:6(one cement six coarse san) including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	5.00	cubic metre	5002.35	Rupees Five Thousand Two And Paise Thirty Five Only	per cubic metre	25,012.00
9	Half brick masonry work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in Cement mortar 1:4 (one cement : four coarse sand) in super structure above plinth level up to all floors level including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	42.00	square metre	982.00	Rupees Nine Hundred Eighty Two Only	Per square metre	41,244.00

10) Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint of approved steel primer all complete in trusses and trussed purlins in buildings as per entire satisfaction of the Engineer-in-charge including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, (GST) or other taxes imposed by the Government	2.00	Quintal	10500.00	Rupees Ten Thousand Five Hundred Only	Per quintal	21,000.00
11) Providing and laying cement concrete 1:2:4 (one cement: two sand : four graded stone aggregate 40mm (fourty millimetre) nominal size) and curing complete excluding cost of form work in foundation and plinth as per entire satisfaction of the Engineer-in-charge including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government	0.52	cubic metre	6586.30	Rupees Six Thousand Five Hundred Eighty Six And Paise Thirty Only	per cubic metre	3,425.00
12) 15mm (fifteen millimeters) thick cement plaster in single coat on the rough side of brick concrete/stone walls for interior plastering upto floor all level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm (Eighty millimeters) in girth and finished even and smooth in cement mortar 1:6 (One cement : Six sand) and curing complete as per entire satisfaction of the Engineer-in-charge including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, sale tax or other taxes imposed by the Government.	66.00	square metre	256.90	Rupees Two Hundred Fifty Six And Paise Ninety Only	per square metre	16955.00
13) Distemping two coats with oil bound made of Nerolac, Berger, Asian paint washable distemper of approved brand and manufacture and of required shade on undecorated wall surface to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free form mortar dropping and other foreign matter and also including preparing the surface even and sand papercd smooth complete as per entire satisfaction of the Engineer-in-charge including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	66.00	square metre	125.90	Rupees One Hundred Twenty Five And Paise Ninety Only	per square metre	8,309.00
					Total:-	400,612.00

DNIT approved for Rs/- 4,00,612/-

*only*

Executive Engineer  
Barsar Division  
HAWAB Barsar

251

Job No- 55  
 Estimated Cost Rs:-4,99,720.00  
 Earnest Money Rs:-10000.00  
 Time Limit :- Two month

DNIT  
 Name of Work:- C/O link road to village Chhatoli Brahmana Km 0/00 to 0/700  
 (S/L- C/O R/wall at Rd 0/300 to 0/315 & P/L 600mm dia RCC Hume pipe culvert at Rd 0/325 with wing wall)  
 (under OTMNP Head)

Sr.No	Description of Item	Rate inclusive all taxes i/e G.S.T		Unit	Amount
		Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	66.06	Cubic metre	465.60 Rupees Four Hundred Sixty Five And Paise Sixty Only	30758.00
2	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	67.11	Cubic metre	4258.90 Rupees Four Thousand Two Hundred Fifty Eight And Paise Ninety Only	285815.00
3	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight graded crushed/broken stone aggregate 40 mm (forty millimetre nominal size) mechanically mixed and vibrated on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work in open foundation complete as per drawing and technical specification clause 802,803,1202&1203 as per direction of Engineer-in- Charge . including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	2.88	cubic metre	4599.30 Rupees Four Thousand Five Hundred Ninety Nine And Paise Thirty Only	13246.00



4)	Providing and laying mechanically mixed and vibrated cement concrete nominal mix PCC Grade M-10 (M-10) on ground or under water and curing complete including pumping or bailing out water, desludging removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802, 803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	14.40	Cubic metre	5100.60	Rupees Five Thousand One Hundred And Paise Sixty Only	Per Cubic Metre	73449.00
5)	Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.20	Cubic metre	1236.30	Rupees One Thousand Two Hundred Thirty Six And Paise Thirty Only	Per Cubic Metre	20028.00
6)	Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (D. 110mm) / Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	25.00	Numbers	400.90	Rupees Four Hundred And Paise Ninety Only	Each	10023.00
7)	Providing and Laying reinforced cement concrete pipe NP <sup>2</sup> 900mm (nine hundred millimetre) dia for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation protection work back filling concrete and masonry work in head walls and parapets Clause 1106, including entire carriage of material within all leads and lifts other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.00	Running metre	4095.80	Rupees Four Thousand Ninety Five And Paise Eighty Only	Per running metre	20479.00
8)	Providing and Laying reinforced cement concrete pipe NP <sup>2</sup> 600mm (six hundred millimetre) dia for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation protection work back filling concrete and masonry work in head walls and parapets Clause 1106, including entire carriage of material within all leads and lifts other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	5.00	Running metre	2727.70	Rupees Two Thousand Seven Hundred Twenty Seven And Paise Seventy Only	Per running metre	13639.00

Job No-  
Estimated Cost Rs:-4,99,720.00  
Rs:-10000.00

<p>9) Construction of embankment with approved materials deposited at site from road way cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of tables 300.1 and 300.2 as per technical specification clause. 301.5 and as per direction of the Engineer-in-Charge including entire carriage of material upto all leads and lifts and other incidental the rate includes octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	<p>255.00 cubic metre</p>	<p>126.60</p>	<p>Ruppes One Hundred Twenty Six And Paise Sixty Only</p>	<p>Per Cubic Metre 32283.00</p>
<p>Total:-</p>				<p>499720.00</p>

DNIT approved for Rs. 4,99,720/- only.

Executive Engineer  
Barsar Division  
PPWD Barsar

259

56

DNIT

Job No-

Name of work:- Restoration of rain damages on Bijhari Chalsai Ambota Chakrala Ghangot road Km 0/00 to 7/900  
SHI- C/O V-shape drain at Rd 0/670 to 0/810, R/wall at Rd 0/505 to 0/516 & P/L cement concrete pavement at Rd 0/610 to 0/660 & 0/770 to 0/810)

Estimated Cost Rs:-4,69,401.00

Earnest Money Rs:-9400.00

Time Limit :- Two Month

Sr. No	Description of item	Quantity	Rate inclusive all taxes 1/6 G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	57.89 cubic metre	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	28881.00
2	Stone soling properly hand packed filling interstices with spalls and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter ) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	7.79 Cubic metre	1333.85	Rupees One Thousand Three Hundred Thirty Three And Paise Eighty Five Only	Per Cubic Metre	10391.00

<p>3 Providing and laying cement concrete 1:5:10 (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .</p>	59.28	Cubic metre	4268.30	Rupees Four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	253025.00
<p>4 Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. in open foundations / substructure complete as per drawing and technical specification clause 802,803, 1202 &amp;1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .</p>	20.67	Cubic metre	5862.20	Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	Per Cubic Metre	121172.00
<p>5 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 ( one cement : one and half coarse sand : three graded stone aggregate 20 mm(twenty millimetre) nominal size). In foundation footing bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty ,mulkana ,toll tax, GST or other taxes imposed by the Government .</p>	3.70	Cubic metre	7113.40	Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre	26320.00
<p>6 Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax , ,GST or other taxes imposed by the Government</p>	16.34	Cubic metre	1380.50	Rupees One Thousand Three Hundred Eighty And Paise Fifty Only	Per Cubic Metre	22557.00

<p>7) Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall, return wall, retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (1)-plus/ Finolex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.</p>	15.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	6030.00
<p>8) Construction of embankment with approved materials deposited at site from road way cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of tables 300.1 and 300.2 as per technical specification clause 301.5 and as per direction of the Engineer-in- Charge including entire carriage of material upto all leads and lifts and other incidental the rate includes octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	8.14	cubic metre	125.90	Rupees One Hundred Twenty Five And Paise Ninety Only	Per Cubic Metre	1025.00
					Total:-	469401.00

DNIT approved Rs. 4,69,401/- only.

1021  
 Executive Engineer  
 Barsar Division  
 HPPWD Barsar

250

57

DNIT

Job No-

Name of work:- Restoration of rain damages on Bijhari Chalsai Ambola Chakrala Ghangot road Km 0/00 to 7/900

Estimated Cost Rs:-4,81,878.00

SHT:- P/L interlocking concrete block pavement at Rd 2/216 to 2/262 with edge wall &amp; V-shape drain at Rd 2/180 to 2/350)

Earnest Money Rs:-9700.00

Time Limit :- Two Month

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (wherc blasting is prohibited ) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	9.56	cubic metre	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	4769.00
2	Stone soling properly hand packed filling interstices with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter ) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rate inclusive of Octroi, Toll Tax , GST or any other taxes imposed by the Government.	8.64	Cubic metre	1593.10	Rupees One Thousand Five Hundred Ninety Three And Paise Ten Only	Per Cubic Metre	13764.00
3	Providing and laying cement concrete 1:5:10 (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	9.18	Cubic metre	4423.00	Rupees Four Thousand Four Hundred Twenty Three Only	Per Cubic Metre	40603.00

<p>5) Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one part cement : three parts sand : six parts crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete etc. all heights and depths including cost of form work for plain concrete in drain and channel etc. in open foundations / substructure complete as per drawing and technical specification clause 802, 803, 1202 &amp; 1203 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.</p>	26.62	Cubic metre	5862.20	Rupees Five Thousand Eight Hundred Sixty Two And Paise Twenty Only	Per Cubic Metre	156052.00
<p>6) Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 ( one part cement : one and half coarse sand : three graded stone aggregate 20 mm (twenty millimetre) nominal size). In foundation footing, bases of columns and the like and mass concrete including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.</p>	3.68	Cubic metre	7113.40	Rupees Seven Thousand One Hundred Thirteen And Paise Forty Only	Per Cubic Metre	26177.00
<p>6) Providing and laying of inter locking concrete paver block vibro compacted upto M-30 (M-Thirty) grade having thickness 80mm (eighty millimeter) including border or kerb block over sub base of sand as per drawing and technical specification Clause-1504 approved any make conforming to the Nitco, Modern, Gico, NTC/ BIS specification for interlocking paver blocks including entire carriage of material with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government</p>	144.00	square metre	1435.60	Rupees One Thousand Four Hundred Thirty Five And Paise Sixty Only	per square metre	206726.00
<p>7) Back filling behind abutment wing wall and return wall with granular material complete as per drawing and technical specification clause 1204.3.8 including carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government</p>	21.12	Cubic metre	1409.40	Rupees One Thousand Four Hundred Nine And Paise Forty Only	Per Cubic Metre	29767.00

232

58

DNIT

Name of Work:- A/R & M/O various road under IPPWD Division Barsar

(SI):- Supply and stacking reinforced cement concrete pipe NP2 900 mm , 450mm & 600mm dia with collar at Divisional store Barsar (under Stock Storage)

Job No-

Estimated Cost Rs:- 4,93,125.00

Earnest Money Rs:-9,900.00

Time Limit :- one month

Sr.No	Description of Item	Running Metre	Rate inclusive all taxes i/e G.S.T		Unit	Amount
			Figure	words		
1	Supply and stacking reinforced cement concrete pipe NP2 900 mm (Ninc hundred millimetre) dia with collar at site complete as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rates arc inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	37.50	3700.00	Rupees Three Thousand Seven Hundred Only	Per Running Metre	138750.00
2	Supply and stacking reinforced cement concrete pipe NP2 450 mm (four hundred fifty millimetre) dia with collar at site complete as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	150.00	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Running Metre	202500.00
3	Supply and stacking reinforced cement concrete pipe NP2 600 mm (six hundred millimetre) dia with collar at site complete as per the direction of the Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rates arc inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	67.50	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per Running Metre	151875.00
					Total:-	493125.00

DNIT approved for Rs/- 493,125/-

only

Executive Engineer  
Barsar Division  
IPPWD Barsar



298

59

DNET

Name of work:- Restoration of rain damages on link road to Harizan Basti Daryana  
 SH:- C/O Edge wall at Rd 0/035 to 0/055 & U-Shape drain at various Rds )  
 (DC Deposit)

Job No-  
 Estimated Cost Rs:-4,16,531.00  
 Earnest Money Rs:-8400.00  
 Time Limit :- Two Month

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T.		Unit	Amount
				Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chisling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water ( surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	78.40	cubic metre	498.90	Rupees Four Hundred Ninety Eight And Paise Ninety Only	Per Cubic Metre	39114.00
2	Providing and laying cement concrete 1:5:10 (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	29.80	Cubic metre	4268.30	Rupees four Thousand Two Hundred Sixty Eight And Paise Thirty Only	Per Cubic Metre	127195.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government .	48.00	Cubic metre	5062.20	Rupees Five Thousand Sixty Two And Paise Twenty Only	Per Cubic Metre	242986.00

<p>Providing weep holes in brick masonry / stone masonry / plain and reinforced concrete abutment, wing wall return wall retaining and breast wall with 110mm (one hundred ten millimetre) dia PVC pipe (12-1444) / Finalex/ Supreme having working pressure not less than 4 kg per centimeter square (Four Kilogram per centimeter square ) extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 as per direction of Engineer-in- Charge including entire carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.</p>	18.00	Numbers	402.00	Rupees Four Hundred Two Only	Each	7236.00
Total:-						416531.00

*DNIT approved for Pst- 4,16,531/- only*

Executive Engineer  
 Barsar Division  
 HPPWD Barsar

303

DNIT

Name of work:- Stock storage under HPPWD Divisional Store Barsar  
(SII:- Supplying and stacking infomatory board ) (under stock storage)

Job No  
**60**

Estimated cost Rs:- 413000.00

Earnest money Rs:- 83000.00

Time Limit :- One Month

Sr.No	Description of item	Quantity		Rate inclusive all taxes /c G.S.T		Unit	Amount
		Numbers	Figures	Words	Amount		
1	Providing infomatory board with as per specification and drawing MS sheet of 2mm (two millimetre) thick duly welded with MS flat iron 32mmx 5mm (thirty two millimetre into five millimetre) size on edges MS sheet tube post of size 48.3 (fourty eight point three ) outer dia complete welded with MS sheet as per drawing all section of framed post and MS tube will be primer painted and as per direction of Engineer in charge 900x1200 mm (nine hundred into one thousand two hundred millimetre) size including entire carriage of material with in all leads , lifts and other incidentals. The rates are inclusive octroi , royalty , Malkana, toll tax, GST or other taxes imposed by the Government.	50.00	8260.00	Rupees Eight Thousand Two Hundred Sixty Only	Each	413000.00	
				Total:-		413000.00	

DNIT approved for Rs. 4,13,000/- only.

*[Signature]*  
Executive Engineer  
Barsar Division  
HPPWD Barsar

309

61

Job No -  
Estimated cost Rs:- 2,23,106.00  
Earnest money Rs:- 4500 .00  
Time Limit :- One Month

DNIT  
Name of work:- A/R & M/O various bridge under HPPWD Sub Division Barsar (Section Chakmoh)  
(SIH- Repair of railing & painting )

Sr.No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T		Unit	Amount
			Figures	words		
1	Finishing walls with Acrylic Smooth exterior paint of required shade new work (Two or more coat applied @ 1.67 ltr/10 sqm (one point sixty seven litre per ten square metre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two point twenty kilogram per ten square metre including entire carriage of material in all leads and lifts . The rates are inclusive-of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	929.08	153.00	Rupees One Hundred Fifty Three Only	Per square metre	142149.00
2	Repairs to plaster of thickness 12 mm to 20 mm (twelve millimetre to twenty millimetre ) in patches of area 2.5 sq.meters (two point five square metre) and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete With cement mortar 1:4 (one cement : four finesand including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in Chargeincluding entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	101.96	310.60	Rupees Three Hundred Ten And Paise Sixty Only	per square metre	31,669.00
3	Providing and applying white cement based putty of average thickness 1mm(one millimetre) of approved brand and manufacture of over the plastered wall surface to prepare the surface even and smooth complete including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	464.54	106.10	Rupees One Hundred Six And Paise Ten Only	Per square metre	49,288.00
					Total:-	223106.00

DNIT approved for Rs:- 2,23,106/-  
only

Executive Engineer  
Barsar Division  
HPPWD Barsar

62

Job No-  
Estimated Cost Rs:- 494958.00  
Earliest Money Rs:- 9900.00  
Time Limit :- Two month

DNIT  
Name of Work:- A/R & M/O on Divisional office & Residential quarter at Barsar  
(SH:- Distemping, Painting, ceiling, repair work etc.)

Sr. No	Description of item	Quantity		Rate inclusive all taxes i/c G.S.T		Unit	Amount
				Figure	words		
1	Renewing glass panes , with putty and nails wherever necessary including racking out the old putty Float glass panes of nominal thickness 4 mm (four millimetre) (weight not less than 10kg/sqm (ten kilogram per square metre) with satisfaction Engineer-in Charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	10.70	Square metre	828.44	Rupees Eight Hundred Twenty Eight And Paise Forty Four Only	Per square metre	8864.00
2	Providing and fixing plain multipurpose cement board(Hight pressure steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid seprately) 6 mm six millimetre) thick Cement fiber board as per IS:14862 with satisfaction Engineer-in Charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	13.32	Square metre	656.60	Rupees Six Hundred Fifty Six And Paise Sixty Only	Per square metre	8,746.00
3	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per direction of Engineer.in.Charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	2142.36	Square metre	12.20	Rupees Twelve And Paise Twenty Only	Per square metre	26,137.00
4	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer as per the direction of Engineer.in.Chief including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	2142.36	Square metre	128.40	Rupees One Hundred Twenty Eight And Paise Forty Only	Per square metre	275,079.00
5	Providing and applying white cement based putty of average thickness 1mm(one millimetre) of approved brand and manufacture of over the plastered wall surface to prepare the surface even and smooth complete as per the direction of Engineer.in.Chief including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	856.90	Square metre	106.10	Rupees One Hundred Six And Paise Ten Only	Per square metre	90,917.00
6	Painting wood work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (zero point nine zero liter/ ten square metre) over an under coat of primer applied @ 0.75 ltr/ 10 sqm(zero point seven five liter / ten square metre) of approved brand and manufacture as per the direction of Engineer.in.Chief including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	258.08	Square metre	100.30	Rupees One Hundred And Paise Thirty Only	Per square metre	25,885.00

<p>Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture as per the direction of Engineer.in.Chief including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	<p>41.90</p>	<p>Square metre</p>	<p>118.50</p>	<p>Rupees One Hundred Eighteen And Paise Fifty Only</p>	<p>Per square metre</p>	<p>4,965.00</p>
<p>Providing and fixing white vitreous china pedestal type water closet (European type) W.C. pan with ISI marked white solid plastic with seat and lid, 10 (ten litre) low level white vitreous china flushing cistern &amp; C.P. flush bend with fittings &amp; C.I. brackets, 40 mm (fourty millimetre) flush bend, overflow arrangement with specialia of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required as per the direction of Engineer.in.Chief including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government.</p>	<p>4.00</p>	<p>Numbers</p>	<p>6025.30</p>	<p>Rupees Six Thousand Twenty Five And Paise Thirty Only</p>	<p>Each</p>	<p>24101.00</p>
<p>Providing and laying matt finished vitrified tile made of Kajaria/ Nitco first class quality of size 300x300 x 9.8mm(three hundred into three hundred into nine point eight millimetre) having with water absorption less than 0.3%(zero point five percent) and conforming to IS: 15622 of approved make in all colours and shades in for outdoor floors such as footpath, court yard, multi modals location etc., laid on 20mm (twenty millimetre) thick base of cement mortar 1:4 ( one cement : four coarse sand) in all shapes &amp; patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge-including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government</p>	<p>18.40</p>	<p>Square metre</p>	<p>1142.40</p>	<p>Rupees One Thousand One Hundred Forty Two And Paise Forty Only</p>	<p>Per square metre</p>	<p>21020.00</p>
<p>French spirit polishing two or more coats on new works including a coat of wood filler including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty malkana, toll tax, GST or other taxes imposed by the Government</p>	<p>41.60</p>	<p>Square metre</p>	<p>222.20</p>	<p>Rupees Two Hundred Twenty Two And Paise Twenty Only</p>	<p>Per square metre</p>	<p>9,244.00</p>
<p>Total</p>						<p>494958.00</p>

*0206/ schedule of quantity approved  
for Rs - 494958/-*

Executive Engineer  
Barsar Division  
PWD Barsar

63

Job No-  
Estimated Cost Rs:- 498614.00  
Earnest Money Rs:- 10000.00  
Time Limit :- Two month

DNIT  
Name of Work:- A/R & M/O on Residential quarter HPPWD Colony Barsar  
(SH:- Distempering, Painting, Sanitary works)

Sr. No	Description of item	Quantity	Rate inclusive all taxes i/c G.S.T Figure	words	Unit	Amount
1	Renewing glass panes , with putty and nails wherever necessary including racking out the old putty float glass panes of nominal thickness 4 mm (four millimetre) (weight not less than 10kg/sqm (ten kilogram per square metre) with satisfaction Engineer-in Charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	3.50	828.44	Rupees Eight Hundred Twenty Eight And Paise Forty Four Only	Per square metre	2900.00
2	Providing and fixing insulating board ceiling of approved quality with necessary nails etc. complete (frame work to be paid separately) natural colour insulating board 12mm thick (twelve millimetre) as per direction of Engineer.in.Charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	106.00	698.00	Rupees Six Hundred Ninety Eight Only	Per square metre	73,988.00
3	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per direction of Engineer.in.Charge including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	2443.87	12.20	Rupees Twelve And Paise Twenty Only	Per square metre	29,815.00
4	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer as per the direction of Engineer.in.Chief including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	2443.87	128.40	Rupees One Hundred Twenty Eight And Paise Forty Only	Per square metre	313,793.00
5	Providing and applying white cement based putty of average thickness 1mm(one millimetre) of approved brand and manufacture of over the plastered wall surface to prepare the surface even and smooth complete as per the direction of Engineer.in.Chief including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	488.80	106.10	Rupees One Hundred Six And Paise Ten Only	Per square metre	51,862.00
6	Painting wood work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (zero point nine zero liter/ ten square metre) over an under coat of primer applied @ 0.75 ltr/ 10 sqm(zero point seven five liter / ten square metre) of approved brand and manufacture as per the direction of Engineer.in.Chief including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	122.00	100.30	Rupees One Hundred And Paise Thirty Only	Per square metre	12,237.00

7	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture as per the direction of Engineer.in.Chief including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	25.00	Square metre	118.50	Rupees One Hundred Eighteen And Paise Fifty Only	Per square metre	2,963.00
8	Providing and fixing 600x450 mm (six hundred into four hundred fifty millimetre) beveled edge mirror of superior glass (of approved quality) complete with 6 mm (six millimetre) thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. as per the direction of Engineer.in.Chief including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	4.00	Numbers	1094.80	Rupees one thousand one hundred thirty four and paise eighty eight only.	Each	4379.00
9	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 15 mm(fifteen millimetre) nominal bore as per the direction of Engineer.in.Chief including entire carriage of material in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	4.00	Numbers	445.50	Rupees Four Hundred Forty Five And Paise Fifty Only	Each	1782.00
10	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 810 gms.(eight hundred ten grams) 15 mm(fifteen millimetre) nominal bore as per the direction of Engineer.in.Chief including entire carriage of material in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government.	4.00	Numbers	638.00	Rupees Six Hundred Fifty Eight Only	Each	2632.00
11	Providing and fixing C.P brass angle valve for basin mixer and geyser points of approved quality conforming to IS8931 as per the direction of Engineer.in.Chief including entire carriage of material in all leads and lifts . The rates are inclusive of octroi, royalty malkana ,toll tax, GST or other taxes imposed by the Government	4.00	Numbers	565.70	Rupees one thousand seven hundred thirty three and paise ninety seven only.	Each	2263.00
					Total		498614.06

*Draft schedule of quantity approved for Rs-498614/-*

Executive Engineer  
Barsar Division  
H.P.W.D Barsar