



E-Mail id - ee-bil2-hp@nic.in
Phone No. 01978-222551

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

"NOTICE INVITING TENDERS"

Sealed items rates tender for the following works are hereby invited by the Executive Engineer Bilaspur Division No. II HPPWD Bilaspur (H.P.) from the eligible contractors of the appropriate class registered in HPPWD, as per revised enlistment rules so as to reach in the office undersigned on 27/02/2024 up to 10:30 AM and will be opened on the same day at 11:00 AM in the presence of intending contractors. The tender application will be received in this office against cash payment on 26/02/2024 up to 10:00 AM to 02:00 PM and tender form can be had from this office on same day from 03:00 PM to 05:00 PM. The earnest money as shown against each in the shape of FDR of any bank in Himachal Pradesh duly pledged in the name of undersigned must accompany with each tender. The tender form will be issued on contractor giving proof of enlistment, GST, PAN No. etc. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.


The draft NIT and other specifications and conditions of the tender can be seen by the contractors on the office of the undersigned on any working day during the office hours.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of form	Time limit
1	Restoration of Ran damages on Thatch Sikroha Neri Jukhala road Km. 0/0 to 18/690 (SH:- C/o R/wall at RD 0/325 to 0/336)	Rs 3,43,807/-	Rs. 6,900/-	Rs. 350/-	Three Month
2	Construction of Balance work of 317.50 meter span pre-stressed concrete bridge at Bagchhal over Govind Sagar Reservoir in Distt. Bilaspur (C/o Approach road to Bagchhal Bridge toward Marotan side at RD 0/0 to 0/030)	Rs 2,54,313/-	Rs. 5,100/-	Rs. 350/-	Three Month
3	Restoration of Road damages on Kutehla Kariyan Bagchhal road Km. 0/0 to 10/815 (SH:- Road widening from RD 10/787.50 to 10/791.25 on Swarghat side approach of Bagchhal Bridge) Deposit work	Rs 4,95,963/-	Rs. 10,000/-	Rs. 350/-	Three Month
4	C/o Neri to Ashamajari road Km. 0/ o 1/600 (SH:- C/o R/wall at RD 0/918 to 0/930)	Rs 2,99,649/-	Rs. 6,000/-	Rs. 350/-	Three Month
5	C/o Neri to Ashamajari road Km. 0/ o 1/600 (SH:- C/o R/wall at RD 0/933 to 0/945)	Rs 3,00,050/-	Rs. 6,000/-	Rs. 350/-	Three Month
6	Construction of Balance work of 317.50 meter span pre-stressed concrete bridge at Bagchhal over Govind Sagar Reservoir in Distt. Bilaspur (C/o Approach road to Bagchhal Bridge toward Marotan side at RD 0/030 to 0/270)	Rs 4,99,477/-	Rs. 10,000/-	Rs. 350/-	Three Month

Certified that tender of above works are being called of emergent nature in exigency of Public interest.

Terms and Conditions:-

1. The contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/firm shall have his registration and GST No., the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Bilaspur Division No. II HPPWD Bilaspur and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be similarly rejected.
5. The contractor/firms are requested to insert the rate of each item in words as in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.
6. The tender shall be issued to those contractors who have not more than two works in hand.



Executive Engineer,
Bilaspur Divn.No.II,
HP.PWD., Bilaspur.

Dated:- 19-2-2024

No.PW/NBT/CB/Tender-State/EA-1/2023- 14441-46

Copy forwarded to the following for information and necessary action:-

1. The Engineer-In-Chief HPPWD Nirman Bhawan Nigam Vihar Shimla-2.
2. The Chief Engineer (HZ) HPPWD Hamirpur
3. The Superintending Engineers, 10th Circle, HPPWD Bilaspur.
4. The Executive Engineer (IT) O/o Engineer-in-Chief HPPWD Shimla through email- eeict-pwd-shi@hp.gov.in & cc-pwd-hp@nic.in for uploading the same on HPPWD web portal.
5. All the Assistant Engineers working under this Division.
6. Drawing Branch in this office/Notice Board.


Executive Engineer,
Bilaspur Divn.No.II.

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.3,43,807/-Only.
Earnest Money :- Rs.6,900/-
Time:- Three Months.

NAME OF WORK:- Restoration of Rain Damages on Thatch Sikroha Neri Jukhala road km 0/00 to 18/690 (SH:- C/o R/wall at RD 0/325 to 0/336)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		Figure.	Words.	Figure.	Words.		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All Kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	33.55	cubic metre	4	5	6 Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	72.27	Cubic metre			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204, 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malikhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.52	Cubic metre.			Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v); 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty, Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	27.00	Nos.			Each	
Total:-							


 Executive Engineer,
 Bilaspur Division No. 2,
 H.P. P.W.D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,54,313-Only.

Earnest Money :- Rs.5,100/-

Time:- Three Months.

NAME OF WORK:- Construction of Balance Work of 317.50 mtr span pre-stressed concrete bridge at Bagchhal over Govind Sagar Reservoir in Distt. Bilaspur (C/O Approach road to Bagchhal Bridge toward Marottan Side at RD 0/000 to 0/030)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount	
		3	4	Figure.	Words.			
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300,1603.1,1603.2. & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un -useful material for filling in road way, camber ,embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of jumper work in all cases failing which recovery shall be effeced on the prevailing market rates.Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, royalty, Malkana, toll tax sale tax or other taxes imposed by the Government.	596.21	Cubic metres.	4	5	6	7	
Total								

Executive Engineer,
Bilaspur Division No. 2,
H.P. P.W.D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.

Estimated cost:- Rs.4,95,963/-Only.
 Earnest Money :- Rs. 10,000/- only
 Time:- Three Months.

AME OF WORK:- Restoration of Road damages on Kutehla Kariyan Bagghhal Road Km 0/0 to 10/815 (SH:- Road widening from RD 10/787.50 to 10/791.25 on swarghat side approach of Bagghhal Bridge) (Deposit Work).

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		Figure.	Words.	Figure.	Words.		
1	2	3	4	5	6	7	
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, graded width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification, 2014 Clause 300, 302.3.5 & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of material for filling in road way, camber ,embankments for grade improvements and disposal of all useful /surplus materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machines, materials tools equipments and execution shall be absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases as per direction of Engineer-in-Charges including carriage of materials within all leads and lifts.The rate including octroi,royalty , Malkana , toll tax, sale tax,Goods services tax or other taxes imposed by the Govt. A recovery of useful stone for 197.56 Cum (one hundred Ninety Seven point Fifty Six) Cubic metre at the rate of Rs.300/- (Rs. Three hundred) only shall be done on pro-rate basis in each running bill for this item including carriage of materials in all leads lifts as per the direction of the Engineer-in-Charge.	592.69	Cubic Metre			Per Cubic Metre	
Total:-							


 Executive Engineer,
 Bhagalpur Division No. 2,
 H.S.P.O., Bhagalpur (H.P.)


SCHEDULE OF QUANTITY.

Estimated cost:- Rs.2,99,649/-Only.
Earnest Money :- Rs.6,000/-
Time:- Three Months.

NAME OF WORK:- Construction of Neri to Ashamajhari road km 0/00 to 1/600 (SH:- C/o R/wall at RD 0/918 to 0/930)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		Figure.	Words.	Figure.	Words.		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All Kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3 27.48	cubic metre	4	5	6 Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.48	Cubic metre			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.44	Cubic metre.			Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v): 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Nos.			Each	
Total:-							

Executive Engineer,
Bilaspur Division No. 2,
P.W.D., Bilaspur (H.P.)

SCHEDULE OF QUANTITY.


Estimated cost:- Rs.3,00,050/-Only.

Earnest Money :- Rs.6,000/-

Time:- Three Months.

NAME OF WORK:- Construction of Neri to Ashamajhari road km 0/00 to 1/600 (SH:- C/o R/wall at RD 0/933 to 0/945)

Sr No.	Description of items.	Quantity		Rates in		Unit	Amount
		Figure.	Words.	Figure.	Words.		
1	2 Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm (thirty centimeter) in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m (fifty meter) and lift upto 1.5 m, as directed by Engineer-in-charge. All Kind of Soil including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	28.20	cubic metre	4	5	6 Per cubic metre	7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering as per drawing and technical specification in C.C 1:5:10 (one Cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimeter) nominal size) including carriage of materials , within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction work, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	63.48	Cubic metre			Per Cubic metre	
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204. 3.8 of MORD specification, 1200 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess, royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.68	Cubic metre.			Per Cubic Metre	
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment wing wall, return wall with 100mm (one hundred millimetre) dia PVC pipes extending through the full width of the structures with slope of 1 (v); 20 (H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of material with in all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rates includes octroi,royalty ,Malkana toll tax goods and service tax ,building and other construction work, welfare cess, royalty of any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Nos.			Each	
Total:-							

Executive Engineer,
 Bilaspur Division No. 2,
 Jt. PWD, Bilaspur (H.P.)


SCHEDULE OF QUANTITY.

Estimated cost:- Rs.4,99,477/-Only.
 Earnest Money :- Rs.10,000/-
 Time:- Three Months.

NAME OF WORK:- Construction of Balance Work of 317.50 mtr span pre-stressed concrete bridge at Bagghal over Govind Sagar Reservoir in Distt. Bilaspur (C/O Approach road to Bagghal Bridge toward Marottan Side at RD 0/030 to 0/270)

Sr No.	Description of items.	Quantity	Rates in		Unit	Amount	
			Figure.	Words.			
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification Clause 300,1603.1,1603.2, & sorting out useful material and stacking the same in all leads and lifts in acquired width of the road and transportation of un -useful material for filling in road way, camber ,embankments for grade improvements and disposal of all surplus un-useful materials to required width of the road or on approved dumping sites, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. All useful materials such as stone, shingles, aggregates, sand and slates shall be sorted out and stacked along road side which shall not be less than 1/3 (One third) for blasting work hard rock 1/6th(One sixth) of jumper work in all cases failing which recovery shall be effeced on the prevailing market rates.Any loss to the public/private property during the course of execution shall be the absolute responsibility of all the Contractor which shall have to be duly compensated by him in all cases as per direction of the Engineer-in-Charge including carriage of material within all leads and lifts. The rate includes octroi, royalty, Malkana,toll tax sale tax or other taxes imposed by the Government. A recovery of useful stones for 95.14 (Ninety Five point Fourteen) cubic metre @ Rs.300/- (three hundred) Per cubic metre shall be done on pro-rata basis in each running bill for this item	3	4	5	6	7	
	s	1902.77			Per Cubic metre		
Total							


 Executive Engineer,
 Bilaspur Division No. 2,
 J.P.W.D., Bilaspur (H.P.)
