

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWCB/CB-GA/Tender/2023-24-

17891-17990

Dated:- 6-3-2024

To

The Executive Engineer (IT Cell),
Nigam Bihar, Himachal Pradesh Shimla-2.
cc-pwd-hp@nic.in

Subject: - Publication of Tender Notice

Sir,

Enclosed please find herewith notice of various work as given in the tender inviting tender for uploading on departmental website as per notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021 as the works mentioned in the tender Notice are urgent nature and public interest.

Your's Faithfully,

Executive Engineer,
Bharmour Division,
HP.PWD, Bharmour

DA/As above.

Copy forwarded to the following for information please :-

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, Kangra Zone, HP.PWD.Dharamshala.
3. Deputy Commissioner Chamba District Chamba.
4. All the Superintending Engineers/Executive Engineer in HPPWD
5. All the Assistant Engineer under Bharmour Division.
6. Additional Deputy Commissioner Bharmour.
7. The Superintendent of Police Chamba.
8. Labour Officer Chamba.
9. Notice Board of this office

Executive Engineer,
Bharmour Division,
HP.PWD, Bharmour

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
SHORT TERM NOTICE INVITING TENDERS**

Sealed percentage rate tenders on from 6 & 8 are hereby invited by the Executive Engineer, Bharmour Division, HP.PWD. Bharmour on behalf of the Governor of H.P. for the following works from the approved and eligible contractors enlisted with HPPWD under revised rules:-

Tender Schedule:-

Date and time of receipt of application for tender form- 12.03.2024 up to 1.00 PM

Date and time of issue/Sale of tender form- 12.03.2024 2:00 PM to 04:30 PM

Date and time of receipt of tender form-13.03.2024 up to 11:30 AM

Date and time of opening tender form-13.03.2024 at 3:30 PM

The tender form can be had from the office of the Executive Engineer against Cash (Non-refundable). The earnest money should be in the shape of Fixed Deposit duly pledged in favour of the Executive Engineer Bharmour Division HPPWD Bharmour must accompany each tender. Conditional tender and the tender received without earnest money will summarily be reject. The offer will be kept open for 75 days. The Executive Engineer reserves the right to reject one or all tenders without assigning any reason.

Sr. No.	Name of work	Estimat ed cost	EMD	Cost of Tender	Time Allowed	Class of Contrac tor
1.	2	3	4	5	6	7
1.	Restoration of rain damage on Dunali Brehi road Km 0/00 to 6/00 (SH:- C/O R/wall at RD 2/734 to 2/746	337813	6756	Rs. 350/-	03 Month	Class C & D only
2.	Restoration of rain damage on Dunali Brehi road Km 0/00 to 6/00 (SH:- C/O R/wall at Rd 2/588 to 2/599.10	415097	8500	Rs. 350/-	03 Month	Class C & D only
3.	Restoration of rain damage on Sarehi Baloth road Km 0/00 to 4/00 (SH:- C/O Wire crate from RD 0/470 to 0/501.25	498526	10000	Rs. 350/-	03 Month	Class C & D only
4.	Restoration of rain damage on Sarehi Baloth road Km 0/00 to 4/00 (SH:- C/O Wire crate from RD 0/532.50 to 0/563.75	498526	10000	Rs. 350/-	03 Month	Class C & D only
5.	Restoration of rain damage on Handora Annanehar road (SH:- C/O R/wall at RD 0/202 to 0/211.90.	441368	8827	Rs. 350/-	03 Month	Class C & D only
6.	A/R & M/O rain damage on Cho to Gehra road (SH:- C/O B/wall at RD 0/720 to 0/750.	263682	5300	Rs. 350/-	03 Month	Class C & D only
7.	C/O Ghun to Uleni road (SH:- F/C at RD 0/172 to 0/225.	489813	9796	Rs. 350/-	03 Month	Class C & D only
8.	C/O Ghun to Uleni road (SH:- F/C at RD 0/00 to 0/172	499590	10000	Rs. 350/-	03 Month	Class C & D only
9.	C/O Batot to Almi road (portion Batot) to ga;:u Kasrodi) (SH:-C/O PCC R/wall at RD 1/005 to 1/015.	322757	6500	Rs. 350/-	03 Month	Class C & D only
10.	C/O link road to village Kalmala (SH:- F/C at RD 0/960 to 1/165	493933	9879	Rs. 350/-	03 Month	Class C & D only
11.	Restoration of rain damage on Dunali to Batot road Km 0/00 to 6/320 (SH:- C/O R/wall at RD 3/834 to 3/849	406251	8125	Rs. 350/-	03 Month	Class C & D only

12.	Restoration of rain damage on Dunali to Batot road Km 0/00 to 6/320 (SH:- C/O R/wall at RD 5/867 to 5/881	487502	9750	Rs. 350/-	03 Month	Class C & D only
13.	C/O Batot to Ahlmi portion Gallu to Kasrodi (SH:- C/O R/wall at Rd 0/075 to 0/095.	451754	9035	Rs. 350/-	03 Month	Class C & D only
14.	C/O Khanna to Pallan road (SH:- F/C at RD 0/950 to 1/030.	499705	9994	Rs. 350/-	03 Month	Class C & D only
15.	Restoration of rain damage on Lylh Groundi Ahlmi via Preena road Km 0/00 to 5/00 (SH:- C/O R/wall at RD 2/450 to 2/459.50.	499940	10000	Rs. 350/-	03 Month	Class C & D only
16.	C/O J/able Link road from Panehrue Janni to Sanahan (SH:- F/C at RD 1/430 to 1/520	454928	9099	Rs. 350/-	03 Month	Class C & D only
17.	C/O J/able Link road from Panehrue Janni to Sanahan (SH:- F/C at RD 1/520 to 1/650.	499038	10000	Rs. 350/-	03 Month	Class C & D only
18.	Restoration of rain damage on various road under Lylh section (SH:- Hiring for removal of slips at various Rds	309960	6200	Rs. 350/-	03 Month	Class C & D only
19.	A/R & M/O various road under Rakh and Gehra Section (SH:- Removal of slips at various Rds	488775	10000	Rs. 350/-	03 Month	Class C & D only
20.	C/O Khanna to Preena road (SH:- F/C at RD 0/00 to 0/570.	494497	9890	Rs. 350/-	03 Month	Class C & D only
21.	C/O Khanna to Preena road (SH:- F/C at RD 0/570 to 0/825.	492444	9849	Rs. 350/-	03 Month	Class C & D only
22.	C/O Khanna to Preena road (SH:- F/C at RD 0/825 to 1/020.	479572	9591	Rs. 350/-	03 Month	Class C & D only
23.	C/o Khanna to Pallan road (SH:- F/C at Rd 1/030 to 1/120.	499931	10000	Rs. 350/-	03 Month	Class C & D only
24.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O R/wall at RD 10/695 to 10/705	341022	6820	Rs. 350/-	03 Month	Class C & D only
25.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O R/wall at RD 10/860 to 10/878.	331730	6635	Rs. 350/-	03 Month	Class C & D only
26.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O R/wall at RD 10/685 to 10/695	265173	5303	Rs. 350/-	03 Month	Class C & D only
27.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O R/wall at RD 11/210 to 11/228	496590	9932	Rs. 350/-	03 Month	Class C & D only
28.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O R/wall at RD 10/900 to 10/915.	474732	9495	Rs. 350/-	03 Month	Class C & D only
29.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O R/wall at RD 11/170 to 11/190.	376049	7521	Rs. 350/-	03 Month	Class C & D only
30.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O R/wall at RD 10/915 to 10/930	474732	9495	Rs. 350/-	03 Month	Class C & D only
31.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O R/wall at RD 10/960 to 10/968 & 11/265 to 11/280	380288	7606	Rs. 350/-	03 Month	Class C & D only
32.	Improvement of KSPA road Km 0/00 to 13/00 (SH:- C/O R/wall at RD 10/655 to 10/675.	439577	8792	Rs. 350/-	03 Month	Class C & D only
33.	C/O Khani Bakroth road Km 0/00 to 1/170 (SH:- C/O P.C.C R/wall at RD 0/800 to 0/809.50.	491090	10000	Rs. 350/-	03 Month	Class C & D only
34.	Restoration of rain damage on Lylh Groundi Almi via Preena road Km 0/00 to 5/00 (SH:- PCC R/Wall at Rd 1/480 to 1/498.	474303	9500	Rs. 350/-	03 Month	Class C & D only
35.	Restoration of rain damage on Dunali to Batot road Km 0/000 to 6/320 (SH:- PCC R/Wall at Rd 0/900 to 0/914	389548	7791	Rs. 350/-	03 Month	Class C & D only
36.	C/O Play ground for High School Building at Chobia (Deposit work) (SH:- C/O PCC at RD 0/000 to 0/006.	414701	8294	Rs. 350/-	03 Month	Class C & D only
37.	Beautification of Shidh Baba Mandir at Raittan (Deposit work) (SH:- 15mm cement plaster, &	491525	9831	Rs.	03	Class C

	6mm ceiling plaster, P/F white glazed tiles 6mm, wood work, 2mm thick putty, Finishing walls with 100% Premium acrylic emulsion paint etc.)			350/-	Month	& D only
38	Beautification of Jiura Mata Mander at Jiura (Deposit work) (SH:- Dismantling old plaster, 15 mm cement plaster, Paint, P/F white glazed tiles 6mm. steel work etc).	487222	9744	Rs. 350/-	03 Month	Class C & D only
39	Beautification of Nag Mandhir Sarai Sulakhar (Deposit Work) (SH:- 15mm thick plaster & painting wood work with Deluxe Multi Surface Paint, Finishing with wall Duluxe Multi Surface Paint etc.	394834	7897	Rs. 350/-	03 Month	Class C & D only
40	Beautification of Sanhola Miyari Minder at Siur (Depost work) 15mm cement plaster & putty 2mm thickness, Finishing walls with 100% premium acylic emulsion paint, Painting wood work with Deluxe MultiSurface paint etc.	152678	3054	Rs. 350/-	03 Month	Class C & D only
41	C/o Bharmour to Badgram road Km 0/00 to 26/00 (SH:- C/O PCC B/wall at RD 24/470 to 24/490.	334913	6700	Rs. 350/-	03 Month	Class C & D only
42	Restoration of rain damage on various road under Lylh section (SH:- Removal of slips at various Rds	498750	10000	Rs. 350/-	03 Month	Class C & D only
43	Restoration of rain damage on KSPA road Km 13/000 to 40/000 (SH:- C/O R/wall at Rd 26/900 to 26/905 and 26/885 to 26/895.	327712	6554	Rs. 350/-	03 Month	Class C & D only
44	Restoration of rain damage on KSPA road Km 13/000 to 40/000 (SH:-C/O R/wall in wire crate at RD 37/910 to 37/930.	499848	9997	Rs. 350/-	03 Month	Class C & D only
45	Restoration of rain damage on KSPA road Km 13/000 to 40/000 (SH:- C/O R/wall at Rd 38/860 to 38/877	394699	7894	Rs. 350/-	03 Month	Class C & D only
46	Restoration of rain damage on KSPA road Km 13/000 to 40/000 (SH:-C/O R/wall in wire crate at RD32/105 to 32/050.	489274	9785	Rs. 350/-	03 Month	Class C & D only
47	C/O J/able to M/able road from Dadima to Grima road (SH:- C/O PCC R/Wall at Rd 1/390 to 1/400.	378815	7576	Rs. 350/-	03 Month	Class C & D only
48	C/O Patti to Khund road Km 0/00 to 3/300 (SH:- C/O PCC R/wall at Rd 0/372 to 0/381	497281	9946	Rs. 350/-	03 Month	Class C & D only
49	C/O Mehla Ukla road Km 0/000 to 4/000 (SH:- F/C at RD 0/480 to 0/570	242720	4854	Rs. 350/-	03 Month	Class C & D only
50	Improvement of Black spot on Choli to Lamu road Km 0/00 to 4/000 (SH:- C/O R/wall Due to Narrow width of road from Rd 0/200 to 0/268.	489715	9794	Rs. 350/-	03 Month	Class C & D only
51	Restoration of rain damage on Mehla Lakra Bandla road Km 0/00 to 4/100 (SH:- C/O wire crate from RD 2/070 to 2/100.	498766	9975	Rs. 350/-	03 Month	Class C & D only
52	A/R & M/O J.E. Residence at Durgethi HPPWD Garola (SH:- Putty 2mm thickness, Finishing wall with 100% premium acrylic emulsion pint, painting wood work Deluxe Multi surface Paint etc.	58892	1200	Rs. 350/-	03 Month	Class C & D only
53	Restoration of rain damage on various road under Bharmour Sub Division (SH:- Removal of slips at various Rds.	496146	10000	Rs. 350/-	03 Month	Class C & D only
54	C/O Hadsar Chobia road Km 0/00 to 7/500 (SH:- C/O PCC R/wall at RD 2/233 to 2/242.	495922	10000	Rs. 350/-	03 Month	Class C & D only
55	Rain damage on under Rakh Sub Division (SH:- Removal of slips and boulder at various RDs.	192836	3857	Rs. 350/-	03 Month	Class C & D only
56	Geotechnical investigation for construction of	304000	6100	Rs.	03	Class C

	136.950 Mtrs Apan Steel Bridge over Ravi River at RD 0/0/020 on Tiyari Kalah road			350/-	Month	& D only
57	Geotechnical investigation for construction of 40.00 Mtrs span Bridge over Serkaw (Behl Nallah) on Hadsar Chobia road at RD 5/200	304000	6100	Rs. 350/-	03 Month	Class C & D only
58	Geotechnical investigation for construction of Bridge over Kuthar Nallah on Bharmour Badgram road at RD 22/900.	304000	6100	Rs. 350/-	03 Month	Class C & D only
59	Geotechnical investigation for construction of 33.528 Mtrs valley Bridge Holi Nallah on Holi to Tatapani upto Andralagram	304000	6100	Rs. 350/-	03 Month	Class C & D only
60	Improvement of Naygram to Bajol road Km 0/000 to 7.595 Kms (SH:- Preparation of Detailed Project Report.	205065	4200	Rs. 350/-	03 Month	Class C & D only
61	Hydraulic data of 25.00 mtr span Bridge over Kuthar Nallah RD 22/960 on Bharmour Badgram road (SH:- Preparation of Hydraulic data	62500	1300	Rs. 350/-	03 Month	Class C & D only
62	Hydraulic data of 19.75 mtr span Bridge over Batot Khat at RD 0/500 on link road Batot to Almi road (SH:- Preparation of Hydraulic data	49375	1300	Rs. 350/-	03 Month	Class C & D only
63	C/O link road from Hadsar to Serkaw i/c Bridge over Bhel Nallah 4/000 to 8/200 (SH:- Preparation of Detailed Project Report.	113400	4200	Rs. 350/-	03 Month	Class C & D only
64	C/O link road from Kandi to Kuthar Samara Km 0/000 to 12/500 Km (SH:- Preparation of Detailed Project Report.	337500	6800	Rs. 350/-	03 Month	Class C & D only
65	C/O Hadsar Chobia road Km 0/00 to 7/800 (C/O R/wall at Rd 4/320 to 4/327.	432548	8651	Rs. 350/-	03 Month	Class C & D only
66	Restoration of rain damage on Bharmour Badgram road Km 0/000 to 26/000 (SH:- C/O PCC R/wall at RD 16/075 to 16/090.	466393	9328	Rs. 350/-	03 Month	Class C & D only
67	C/O Panjsei to Seri road Km 0/00 to 2/00 (SH:- Providing crate work R/Wall at RD 1/930 to 1/945.	404776	8100	Rs. 350/-	03 Month	Class C & D only
68	C/O J/able from Bharmour to Badgram road Km 0/00 to 26/00 (SH:- F/C at RD 22/050 to 22/150.	343533	6871	Rs. 350/-	03 Month	Class C & D only
69	Improvement of KSPA road Km 0/00 to 13/00 (C/O R/Wall at RD 3/252.20 to 3/255.35.	486596	9732	Rs. 350/-	03 Month	Class C & D only
70	Special repair of nos type II quarter at Dadima (SH:- Special Repair	170732	3415	Rs. 350/-	03 Month	Class C & D only
71	Restoration of rain damage on Choori Lyh Km 0/00 to 4/00 (SH:- C/O PCC R/wall at RD 1/150 to 1/157.50	364727	7300	Rs. 350/-	03 Month	Class C & D only
72	Protection work of Village Bantoo (SH:- C/O R/wall at RD 26/120 to 26/135.	492656	9853	Rs. 350/-	03 Month	Class C & D only
73	Restoration of rain damage on Dadima to Bharmani via Gharadu road Km 0/00 to 4/500 (SH:- C/O PCC R/wall at RD 3/325 to 3/340.	441430	8800	Rs. 350/-	03 Month	Class C & D only
74	Restoration of rain damage on Dhakog to Badgram road Km 0/00 to 7/00 (SH:- C/O R/wall at RD 3/260 to 3/269.	476848	9537	Rs. 350/-	03 Month	Class C & D only
75	Restoration of rain damage on Dhakog to Badgram road Km 0/00 to 7/00 (SH:- C/O R/wall at RD3/269 to 3/275.	317794	6356	Rs. 350/-	03 Month	Class C & D only
76	C/O Hadsar to Chobia road Km 0/00 to 7/500 (SH:- F/C at RD 5/630 to 5/665.	449871	8997	Rs. 350/-	03 Month	Class C & D only
77	Restoration of rain damage Bharmour Hadsar road Km 0/00 to 12/00 (SH:- C/O PCC R/wall at RD 11/495 to 11/506.	423725	8475	Rs. 350/-	03 Month	Class C & D only
78	C/O M/able road from Dayoki to Kardotha via	499010	10000	Rs.	03	Class C

	Badai road Km 0/00 to 3/00 (SH:- C/O PCC B/wall at RD 0/780 to 0/810.			350/-	Month	& D only
79	C/O J/able road from Kharamukh to Open road Km 0/00 to 3/000 (SH:- F/C at RD 0/871 to 0/940.	480606	9612	Rs. 350/-	03 Month	Class C & D only
80	C/O Hadsar to Chobia road Km 0/000 to 7/500 (SH:- Providing crate work at Serkaw Nallah at RD 5/490 to 5/502.50 (Chobia Side)	499778	10000	Rs. 350/-	03 Month	Class C & D only
81	A/R & M/O HPPWD Rest House Bharmour (SH:- C/O PCC B/wall at RD 0/00 to 0/017	493556	9871	Rs. 350/-	03 Month	Class C & D only
82	C/O Patti to Khund road Km 0/000 to 3/300 (SH:- p[roviding crate work R/Wall at RD 0/485 to 0/500.	497269	9945	Rs. 350/-	03 Month	Class C & D only
83	Improvement of Black spot on Bharmour Badgram road Km 0/000 to 26/000 (SH:- Improvement of Black spot at RD 16/800 to 16/860	441467	8829	Rs. 350/-	03 Month	Class C & D only
84	C/O Hadsar to Chobia road Km 0/000 to 7/500 (SH:- C/O PCC R/wall at RD 5/133 to 5/139.	391228	7825	Rs. 350/-	03 Month	Class C & D only
85	C/O Hadsar to Chobia road Km 0/000 to 7/500 (SH:- C/O PCC R/wall at RD 5/185 to 5/193.50	475422	9600	Rs. 350/-	03 Month	Class C & D only
86	C/O Hadsar to Chobia road Km 0/000 to 7/500 (SH:- C/O PCC R/wall at RD 5/193.50 to 5/202.	475441	9600	Rs. 350/-	03 Month	Class C & D only
87	Restoration of rain damage under Garola Sub Division at various road (SH:- Removal of slips at various Rds	498750	10000	Rs. 350/-	03 Month	Class C & D only
88	C/o KSPA road Km 0/00 to 40/00 (SH:- C/O R/Wall in PCC 1:4:8 at RD 17/957 to 17/970	488075	9800	Rs. 350/-	03 Month	Class C & D only

Certificate: - It is certified that the tenders of above works are exigency /emergent nature and in public interest.

Terms and conditions:-

1. The contractors shall produce their latest registration/ renewal of their registration/ Acknowledgement of up to date filed GST Return along with Certificate of GST Registration as per Condition No. 16(iii)/ EPF No. and earnest money should be accompanied with application. Application without earnest money will not be entertained.
2. Ambiguous/ telegraphic/Conditional tenders or tender by fax/ E- mail shall not be entertained/ considered and will summarily be rejected. Tender received after due date and time will be rejected. 3. The offer shall remain valid up to 75 days.
4. The contractor should not have more than two contracts within Division at a time tender. If the contractor has already two works in hand then the tender not excepted at the time of opening of tender and the same will be rejected technical evaluations.
5. If the contractors found lowest more than two works during the opened of bid then two works awarded to contractor at the one time and then opportunity will be given to next lowest bidder.
6. The contractor/bidder should quoted in percentage in words as well as in figures failing which XEN reserves the right to accept/ reject any or all tenders.
7. The contractor /bidders must inspect the site to ascertain /familiar the site conditions, accessibility etc. before quoting the bid/tender.


8. The tender documents shall be issued to only those contractors who does not have more the two works in hand in any HPPWD Circle/Division worth Rs. 1.00 Crore each.

9. That all your rates are inclusive of GST as such you will pay whole of it and you would not claim anything extra on this account from the Department.

10. The provisions of notification issued vide Additional Chief Secretary (PW) to the Govt. of HP. Shimla notification No. PBW (B) A (3)1/2018 dated 13.04.2021 shall also be applicable.

Provisions of the Addl. Chief Secretary (PW) to the Govt. of HP letter No. PBW(B)C(17)2/2012 dated 07.08.2018 are applicable.

The bidders are requested to submit their bid as per Notification issued by the Principal secretary PW to the Govt. of HP vide No.PBW(B)A(3)1/2020 dated 22.07.2020 & Govt. of HP vide No. PBW(B)A(3)1/2020-I dated 07.10.2021 and Engineer-in-Chief HPPWD Shimla-2 letter No. PW/CTR/32-20/Genl. Inst. CPWD/2020-37996- 38095 dated 13.03.2023.



Executive Engineer,
Bharmour Division,
HP.PWD; Bharmour

Dated:-

NO/PW/CB/GA /Tender/23-24-

Copy forwarded for information & necessary action to:-

1. Engineer-in-Chief, HP.PWD, Shimla.
2. Chief Engineer, Kangra Zone, HP.PWD.Dharamshala.
3. Deputy Commissioner Chamba District Chamba.
4. All the Superintending Engineers/Executive Engineer in HPPWD
5. All the Assistant Engineer under Bharmour Division.
6. Additional Deputy Commissioner Bharmour..
7. The Superintendent of Police Chamba.
8. Labour Officer Chamba.
9. Notice Board of this office



Executive Engineer,
Bharmour Division,
HP.PWD, Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 337813.00
 EARNEST MONEY :- Rs 6756
 TIME LIMIT THREE MONTHS

NAME OF WORK : Restoration of rain Damage on Dunali Brehri Road KM 0/00 to 6/00
SUB-HEAD : Construction of R/wall at RD 2/734 to 2/746

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603.4 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantam of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental.	41.40	487.30	Rupees Four Hundred Eighty Seven And Paise Thirty Only	Per cubic metre	20174.00
3	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	82.56	3660.30	Rupees Three Thousand Six Hundred Sixty And Paise Thirty Only	Per cubic metre	302194.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	17.28	893.80	Rupees Eight Hundred Ninety Three And Paise Eighty Only	Per cubic metre	15445.00
Total :-						337813.00


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 415097.00
 EARNEST MONEY :- Rs 8500
 TIME LIMIT THREE MONTHS

NAME OF WORK : Restoration of rain damage on Dunali Brehri Road Km 0/00 to 6/00
SUB-HEAD : - Construction of R/wall at RD 2/588 to 2/599.10

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603.4 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is inclusive, toll taxes, GST and any other taxes imposed by the Government.	17.00 Cubic metres	487.30	Rupees Four Hundred Eighty Seven And Paise Thirty Only	Per cubic metre	8284.00
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:5:10 (1 cement : 5 coarse sand) : 10 graded stone aggregate 40 mm nominal size). as per the directions of the Engineer-in-Charge The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	78.30 Cubic metres	4687.30	Rupees Four Thousand Six Hundred Eighty Seven And Paise Thirty Only	Per cubic metre	367016.00
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing walls, return walls with 100 mm dia. PVC pipe extended through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.37 within all leads, lifts of materials and other incidentals, as per the directions of the Engineer-in-Charge The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.00 Each	310.50	Rupees Three Hundred Ten And Paise Fifty Only	Each	6210.00

4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in-charge including carriage of materials within all leads and lifts and other incidental . The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	25.31 Cubic metres	893.80	Rupees Eight Hundred Ninety Three And Paise Eighty Only	Per cubic metre	22622.00
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level Mild steel and Medium Tensile steel bars The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	#### Kilogram	75.40	Rupees Seventy Five And Paise Forty Only	Per Kilogram	10965.00
Total :-						415097.00

Executive Engineer,
Bharmour Division,
HPPYD Bharmour

SCHEDULE OF QUANTITY

Name of Work :- Restoration of rain damage on Sarehi Baloth road km 0/00-4/00

S.No.		Description of Item	Quantity.	RATES			Unit	Amount (Rs.)
				Rate in Figure	Rate in Words	Rate in Words		
1		Earthwork in excavation for structures as per drawing and technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material, and disposal upto any lead dressing of sides and bottom and backfilling in tranches with excavated suitable material as per the directions of the Engineer-In-Charge. The rate is including octroi ,royalty,Malkana,toll tax ,GST and any other taxes imposed by the Government	47.81	487.30	Rupees four hundred eighty seven and paise thirty only	Per Cubic Metres	23298.00	
2		Providing and laying of boulder apron laid in wire crates with 4mm (fourmilli metre) dia GI Wire conforming to IS: 280 and IS: 4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (Woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighting not less than 25kg each as per drawing and MORD technical specifications clause 1301, including carriage of material, all leads and lifts and other incidental.the rate is including octroi ,royalty,Malkana,toll tax ,GST and any other taxes imposed by the Government	195.31	2433.20	Rupees two thousand four hundred thirty three and paise twenty only	Per Cubic Metres	475228.00	
TOTAL AMOUNT=							498526.00	

E/COST:-498526/-
E/MONEY:-10000/-
TIME LIMIT:-3 MONTH


 Executive Engineer
 Bharmour Division
 HPPWD, Bharmour

SCHEDULE OF QUANTITY

Name of Work :- Restoration of rain damage on Sarehi Baloth road km 0/00-4/00

S.No.		Description of Item	Quantity.	RATES			Unit	Amount (Rs.)
				Rate in Figure	Rate in Words	Rate in Words		
				E/COST:-498526/-				
				E/MONEY:-10000/-				
				TIME LIMIT:-3 MONTH				
1		Earthwork in excavation for structures as per drawing and technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material, and disposal upto any lead dressing of sides and bottom and backfilling in tranches with excavated suitable material as per the directions of the Engineer-In-Charge. The rate is including octroi ,royalty,Malkana,toll tax ,GST and any other taxes imposed by the Government	47.81	487.30	Rupees four hundred eighty seven and paise thirty only	Per Cubic Metres	23298.00	
2		Providing and laying of boulder apron laid in wire crates with 4mm (fourmilli metre) dia GI Wire conforming to IS: 280 and IS: 4826 in 100mmX100mm (one hundred millimetre into one hundred millimetre) mesh (Woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighting not less than 25kg each as per drawing and MORD technical specifications clause 1301, including carriage of material, all leads and lifts and other incidental.rhe rate is including octroi ,royalty,Malkana,toll tax ,GST and any other taxes imposed by the Government	195.31	2433.20	Rupees two thousand four hundred thirty three and paise twenty only	Per Cubic Metres	475228.00	
TOTAL AMOUNT=							498526.00	


 Executive Engineer
 Bharmour Division
 HPPWD, Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 441368.00
 EARNEST MONEY : Rs 8827.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK Restoration of Rain damage on Handora Annanehar road
SUB-HEAD :- Construction of retaining wall at RD 0/202 to 0/211.90

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.	16.73 Cubic metres	487.30	Rupees Four Hundred Eighty Seven And Paise Thirty Only	Per cubic metre	8153.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:6:12 (One cement : Six sand : Twelve graded/crushed stone aggregate 40mm (Forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	14.26 Cubic metres	4482.60	Rupees Four Thousand Four Hundred Eighty Two And Paise Sixty Only	Per cubic metre	63922.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 25mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	3.96 Cubic metres	4986.30	Rupees Four Thousand Nine Hundred Eighty Six And Paise Thirty Only	Per cubic metre	19746.00
4	Random Rubble Masonry work in cement mortar 1:6 (one cement isto six sand) in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	29.48 Cubic metres	4914.30	Rupees Four Thousand Nine Hundred Fourteen And Paise Thirty Only	Per cubic metre	144874.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer in-Charge including carriage of materials within all leads, lifts and other incidental.	52.00 Cubic metres	3660.30	Rupees Three Thousand Six Hundred Sixty And Paise Thirty Only	Per cubic metre	190336.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental.	16.04 Cubic metres	893.80	Rupees Eight Hundred Ninety Three And Paise Eighty Only	Per cubic metre	14337.00
	Total					441368.00

Executive Engineer,
 Bhammur Division,
 HPPWD Bhammur


SCHEDULE OF QUANTITY

Name of Work: **A/R & M/O of Rain Damage on Cho to Gehra road**

Sh. :- C/o B/Wall from Rd 0/735-0/750

E/COST:-263682/ E/MONEY:-5300/		TIME LIMIT:-3 MONTH				
S.N	Description of Item	Qty.	Rate in Figure	Rate in Words	Unit	Amount (Rs.)
1	Earthwork in excavation for structures as per drawing and technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material, and disposal upto any lead dressing of sides and bottom and backfilling in tranches with excavated suitable material with in all leads, lifts of materials and other incidentals, as per approved drawing, dressing and as directed by the Engineer-In-Charge.	31.00	487.30	Rupees four hundred eighty seven and paise thirty only	P/Cum	15105.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25 mm (twenty five millimetres) nominal size in road work as per the direction of the Engineer-In-charge including carriage of materials with in all leads, lifts and other incidental.	3.00	5011.20	Rupees five thousand eleven and paise twenty only	P/Cum	15034.00
3	Random rubble masonry work in cement mortar 1:6 (one cement isto six sand) in foundation complete as per drawing & technical specification Clauses 702, 704, 1202 and 1203as per direction of Engineer-In -Charge including carriage of material with in all leads, lifts and other incidental.	30.33	4920.70	Rupees four thousand nine hundred twenty and paise seventy only	P/Cum	149245.00
4	Construction of dry rubble masonry for retaining walls, breast walls, reventment wall and parapets etc. for sub structure and super structure as per drawing and technical specifications as per Clause 704.60 & 1302.50 as per the direction of Engineer-In-Charge including carriage of materials with in all leads and lifts and other incidental.	23.03	3660.30	Rupees three thousand six hundred sixty and paise thirty only	P/Cum	84297.00
TOTAL AMOUNT=						263682.00


 Assistant Engineer,
 Rakh Sub Division
HPPWD RAKH


 Executive Engineer
 Bhamour Division
HPPWD, Bhamour



DRAFT NOTICE INVITING TENDER

ESTIMATED COST : Rs 489813.00
 EARNEST MONEY : Rs 9796.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK : : Construction of Ghun to Uleri Road

SH- Formation Cutting from Rd 0/172 to 0/225

Sl No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-In-Charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shungle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Recovery of stone to the tune of 150 cum quantity at the rate of 300/- (Rupees Three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government	1694.56	289.05	Rupees Two Hundred Eighty Nine And Paise Five Only	Per Cubic metres	489813.00
Total						489813.00


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour


DRAFT NOTICE INVITING TENDER

ESTIMATED COST : Rs 499590.00 1227
 EARNEST MONEY : Rs 9992.00 64
 TIME LIMIT : THREE MONTHS MO

NAME OF WORK :- Construction of Ghun to Uleni Road

SH:- Formation Cutting from Rd 0/00 to 0/172

Sl. No.	Description of work	Quantity	RATES		Unit	Amount	
			Fig	Words			
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-In-Charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shungle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Recovery of stone to the tune of 150 cum quantity at the rate of 300/- (Rupees Three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government	2179.71	Cubic metres	229.20	Rupees Two Hundred Twenty Nine And Paise Twenty Only	Per Cubic metres	499590.00
Total							499590.00


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

9

DRAFT NOTICE INVITING TENDER

ESTIMATED COST : Rs 322757.00
 EARNEST MONEY : Rs 6455.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK Construction of Batot to Almi road (Portion Batot to Gailu Kasrodi)
SUB-HEAD :- Construction of PCC R/wall at RD 1/005 to 1/015

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.	22.20	389.80	Rupees Three Hundred Eighty Nine And Paise Eighty Only	Per cubic metre	8654.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical specifications section 800, 900 & 1200 1:4:8 (One cement : Four sand : Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) in road work and as per the instructions of Engineer-in-charge within all leads, lifts of materials and other incidentals.	52.50	5553.30	Rupees Five Thousand Five Hundred Fifty Three And Paise Thirty Only	Per Cubic Metre	291548.00
3	Providing and laying 100mm (Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope (V):20(H)(One vertical : Twenty Horizontal) towards drainage face complete as per drawing and MORD technical specification Clause 614, 709, 1204.3.7 and as per direction of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government	27.00	378.30	Rupees Three Hundred Seventy Eight And Paise Thirty Only	Number	10214.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in-charge including carriage of materials within all leads and lifts and other incidental .	15.30	806.60	Rupees Eight Hundred Six And Paise Sixty Only	Per cubic metre	12341.00
Total						322757.00

(Signature)
 Executive Engineer,
 Bhamour Division,
 HPPWD Bhamour


DRAFT NOTICE INVITING TENDER

NAME OF WORK :- Construction of Link Road to Village Kalmala

ESTIMATED COST :- Rs 493933.00
EARNEST MONEY :- Rs 9879.00
TIME LIMIT :- THREE MONTHS

SH:- Formation Cutting from Rd 0/960 to 1/165

Sl. No.	Description of work	Quantity	RATES		Unit	Amount	
			Fig	Words			
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-In-Charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shingle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Recovery of stone to the tune of 100 cum quantity at the rate of 300/- (Rupees Three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government	2848.52	Cubic metres	173.40	Rupees One Hundred Seventy Three And Paise Forty Only	Per Cubic metres	493933.00
Total							493933.00


Executive Engineer,
Bharmour Division,
HPPWD Bharmour

DRAFT NOTICE INVITING TENDER

ESTIMATED COST Rs 406251.00
 EARNEST MONEY Rs 8125.00
 TIME LIMIT THREE MONTHS

NAME OF WORK Restoration of rain damage on Dunali Batot Road Km 0/00 to 6/320
SH: C/O R/wall at RD 3/834 to 3/849

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the directions of the Engineer-in-Charge. The rate including octroi, royalty, Malhana, toll tax, GST or other taxes imposed by the Government.	31.35	487.30	Rupees Four Hundred Eighty Seven And Paise Thirty Only	Per Cubic metres	15277.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:6.12 (One cement : Six sand Twelve graded/crushed stone aggregate 40mm (Forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental	8.25	4531.20	Rupees Four Thousand Five Hundred Thirty One And Paise Twenty Only	Per Cubic metres	37382.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4.8 (One cement : four sand : eight graded/crushed stone aggregate 25mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental	5.25	5038.10	Rupees Five Thousand Thirty Six And Paise Ten Only	Per Cubic metres	26440.00
4	Random Rubble Masonry work in cement mortar 1:6 (one cement : six sand) in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	34.11	4927.00	Rupees Four Thousand Nine Hundred Twenty Seven Only	Per Cubic metres	168050.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	38.08	3660.30	Rupees Three Thousand Six Hundred Sixty And Paise Thirty Only	Per Cubic metres	139384.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and section 300 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malhana, toll tax, side tax or other taxes imposed by the Government.	22.05	893.80	Rupees Eight Hundred Ninety Three And Paise Eighty Only	Per Cubic metres	19708.00
Total						406251.00


 Executive Engineer,
 Bharpour Division,
 Jharkhand Bharmour

DRAFT NOTICE INVITING TENDER

NAME OF WORK :- Restoration of rain damage on Dunsail Batot Road Km 000 to 6/320
SI No. :- C/O R/wall at RD 3/834 to 3/849

ESTIMATED COST :- Rs 408251.00
EARNEST MONEY :- Rs 8125.00
TIME LIMIT :- THREE MONTHS

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the directions of the Engineer-in-Charge The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	31.35	487.30	Rupees Four Hundred Eighty Seven And Paise Thirty Only	Per Cubic metres	15277.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:6:12 (One cement : Six sand : Twelve graded/crushed stone aggregate 40mm (Forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	8.25	4531.20	Rupees Four Thousand Five Hundred Thirty One And Paise Twenty Only	Per Cubic metres	37382.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement into four sand into eight graded/crushed stone aggregate 25mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	5.25	5036.10	Rupees Five Thousand Thirty Six And Paise Ten Only	Per Cubic metres	26440.00
4	Random Rubble Masonry work in cement mortar 1:6 (one cement into six sand) in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	34.11	4927.00	Rupees Four Thousand Nine Hundred Twenty Seven Only	Per Cubic metres	168060.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1202.5 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	38.08	3660.30	Rupees Three Thousand Six Hundred Sixty And Paise Thirty Only	Per Cubic metres	138384.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and section 300 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	22.05	893.80	Rupees Eight Hundred Ninety Three And Paise Eighty Only	Per Cubic metres	19708.00
Total						408251.00


 Executive Engineer,
 Bhagamour Division,
 BPPWD Bharamour

DRAFT NOTICE INVITING TENDER.

ESTIMATED COST Rs 487502.00
 EARNEST MONEY Rs 9750.00
 TIME LIMIT THREE MONTHS

NAME OF WORK Restoration of rain damage on Dunali Batot Road Km 000 to 6/320

SH:- C/O R/wall at RD 5/867 to 5/881

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the directions of the Engineer-in-Charge The rate including octroi, royalty, Malkama, toll tax, GST or other taxes imposed by the Government.	32.06 Cubic metres	487.30	Rupees Four Hundred Eighty Seven And Paise Thirty Only	Per Cubic metres	15623.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 25mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	31.78 Cubic metres	5060.90	Rupees Five Thousand Sixty And Paise Ninety Only	Per Cubic metres	160835.00
4	Random Rubble Masonry work in cement mortar 1:6 (one cement isto six sand) in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	32.64 Cubic metres	4933.30	Rupees Four Thousand Nine Hundred Thirty Three And Paise Thirty Only	Per Cubic metres	161023.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	34.73 Cubic metres	3660.30	Rupees Three Thousand Six Hundred Sixty And Paise Thirty Only	Per Cubic metres	127122.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and section 300 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkama, toll tax, sale tax or other taxes imposed by the Government.	25.62 Cubic metres	893.80	Rupees Eight Hundred Ninety Three And Paise Eighty Only	Per Cubic metres	22899.00
Total						487502.00



 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT NOTICE INVITING TENDER

NAME OF WORK : Restoration of rain damage on Dunali Batot Road Km 0/00 to 6/320
SI: G/O R/wall at RD 5/867 to 5/881

ESTIMATED COST Rs 487502.00
EARNEST MONEY Rs 9750.00
TIME LIMIT THREE MONTHS

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the directions of the Engineer-in-Charge The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	32.08	487.30	Rupees Four Hundred Eighty Seven And Paise Thirty Only	Per Cubic metres	15623.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1-4-8 (One cement isto four sand isto eight graded/crushed stone aggregate 25mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	31.78	5060.90	Rupees Five Thousand Sixty And Paise Ninety Only	Per Cubic metres	160835.00
4	Random Rubble Masonry work in cement mortar 1:6 (one cement isto six sand) in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	32.64	4933.30	Rupees Four Thousand Nine Hundred Thirty Three And Paise Thirty Only	Per Cubic metres	161023.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	34.73	3660.30	Rupees Three Thousand Six Hundred Sixty And Paise Thirty Only	Per Cubic metres	127122.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and section 300 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	25.62	893.80	Rupees Eight Hundred Ninety Three And Paise Eighty Only	Per Cubic metres	22899.00
Total						487502.00


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour


DRAFT NOTICE INVITING TENDER

NAME OF WORK : Construction of Batot to Ahimi Portion Gallu Kasrodi

SH:- C/O R/wall at RD 0/075 to 0/095

ESTIMATED COST : Rs 451754.00
EARNEST MONEY : Rs 9035.00
TIME LIMIT : THREE MONTHS

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the directions of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	26.30 Cubic metres	389.80	Rupees Three Hundred Eighty Nine And Paise Eighty Only	Per Cubic metres	10252.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 40mm (forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	73.60 Cubic metres	5540.80	Rupees Five Thousand Five Hundred Forty And Paise Eighty Only	Per Cubic metres	407803.00
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing walls, return walls with 100 mm dia. PVC pipe extended through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614.709,1204.37 within all leads, lifts of materials and other incidentals. as per the directions of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government	36.00 Each	378.20	Rupees Three Hundred Seventy Eight And Paise Twenty Only	Each	13615.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and section 300 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	24.90 Cubic metres	806.60	Rupees Eight Hundred Six And Paise Sixty Only	Per Cubic metres	20084.00
Total						451754.00


 Executive Engineer,
 Bharmour Division,
 H.P.W.D. Bharmour


DRAFT NOTICE INVITING TENDER

ESTIMATED COST :- Rs 499705.00
 EARNEST MONEY :- Rs 9994.00
 TIME LIMIT THREE MONTHS

NAME OF WORK :- Construction of Khanna to Pallan road

SH:- Formation Cutting from Rd 0/950 to 1/030

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-In-Charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shungle, aggregate and slates ectetra shall be sorted out and stacked in proper stack. Recovery of stone to the tune of 120 cum quantity at the rate of 300/- (Rupees Three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government	1628.50	306.85	Rupees Three Hundred Six And Paise Eighty Five Only	Per Cubic metres	499705.00
Total						499705.00


 Executive Engineer,
 Bharpour Division,
 HPPWD Bharmour

DRAFT NOTICE INVITING TENDER

ESTIMATED COST : Rs 499940.00
 EARNEST MONEY : Rs 9999.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Restoration of rain damage on Lyth Groundl Ahimi Via Preena Road KM 0/00 to 6/00

SI:- C/O R/wall at RD 2/450 to 2/459.50

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the directions of the Engineer-in-Charge The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	23.75 Cubic metres	487.30	Rupees Four Hundred Eighty Seven And Paise Thirty Only	Per Cubic metres	11573.00
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, buttresses, string or facing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing. 1:5:10 (1 cement : 5 coarse sand) : 10 graded stone aggregate 40 mm nominal size), as per the directions of the Engineer-in-Charge The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	68.40 Cubic metres	4490.50	Rupees Four Thousand Four Hundred Ninety And Paise Fifty Only	Per Cubic metres	307150.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical MORD specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 25mm (twenty five millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	1.43 Cubic metres	4998.80	Rupees Four Thousand Nine Hundred Ninety Eight And Paise Eighty Only	Per Cubic metres	7148.00
4	Random Rubble Masonry work in cement mortar 1:6 (one cement isto six sand) in foundation complete as per drawing and technical specifications Clauses 702, 704, 1202 & 1203 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	14.30 Cubic metres	4917.50	Rupees Four Thousand Nine Hundred Seventeen And Paise Fifty Only	Per Cubic metres	70320.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	21.80 Cubic metres	3660.30	Rupees Three Thousand Six Hundred Sixty And Paise Thirty Only	Per Cubic metres	79795.00
6	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and section 300 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	26.80 Cubic metres	893.80	Rupees Eight Hundred Ninety Three And Paise Eighty Only	Per Cubic metres	23954.00
Total						499940.00


 Executive Engineer,
 Bhagnour Division,
 HPPWD Bhammour

DRAFT NOTICE INVITING TENDER

ESTIMATED COST :- Rs 454928.00 499038.00 197.00
 EARNEST MONEY :- Rs 9099.00 9981.00 190.00
 TIME LIMIT THREE MONTHS E MONTHS NTHS

NAME OF WORK :- C/O J/able Link Road From Panehrue Janni To Sanahan

SH:- Formation Cutting from Rd 1/430 to 1/520

Sl. No.	Description of work	Quantity	RATES		Unit	Amount	Amount
			Fig	Words			
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-In-Charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shingle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Recovery of stone to the tune of 150 cum quantity at the rate of 300/-(Rupees Three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government	1168.88	389.20	Rupees Three Hundred Eighty Nine And Paise Twenty Only	Per Cubic metres	454928.00	497.00
Total						454928.00	4497.00


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT NOTICE INVITING TENDER

ESTIMATED COST : Rs 494497.00
 EARNEST MONEY : Rs 9890.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK :- Construction of Khanna to Preena road

SH:- Formation Cutting from Rd 0/00 to 0/570

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-Charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shingle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Recovery of stone to the tune of 120 cum quantity at the rate of 300/- (Rupees Three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government	2276.69	217.20	Rupees Two Hundred Seventeen And Paise Twenty Only	Per Cubic metres	494497.00
Total						494497.00

Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT NOTICE INVITING TENDER

NAME OF WORK :- Construction of Khanna to Preena road

SH:- Formation Cutting from Rd 0/570 to 0/825

ESTIMATED COST :- Rs 492444.00
 EARNEST MONEY :- Rs 9849.00
 TIME LIMIT THREE MONTHS

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-In-Charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shingle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Recovery of stone to the tune of 120 cum quantity at the rate of 300/-(Rupees Three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government	2377.81	207.10	Rupees Two Hundred Seven And Paise Ten Only	Per Cubic metres	492444.00
Total						492444.00

Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour


DRAFT NOTICE INVITING TENDER

ESTIMATED COST :- Rs 479572.00
 EARNEST MONEY :- Rs 9591.00
 TIME LIMIT THREE MONTHS

NAME OF WORK :- Construction of Khanna to Preena road

SH:- Formation Cutting from Rd 0/825 to 1/020

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil. soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil. setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-In-Charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shungic, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Recovery of stone to the tune of 100 cum quantity at the rate of 300/- (Rupees Three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government	2765.70	173.40	Rupees One Hundred Seventy Three And Paise Forty Only	Per Cubic metres	479572.00
Total						479572.00


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT NOTICE INVITING TENDER

ESTIMATED COST :- Rs 499931.00
 EARNEST MONEY :- Rs 9999.00
 TIME LIMIT THREE MONTHS

NAME OF WORK :- Construction of Khanna to Pallan road

SH:- Formation Cutting from Rd 1/030 to 1/120

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-In-Charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. All useful material such as stones shungle, aggregate and slates etcetra shall be sorted out and stacked in proper stack. Recovery of stone to the tune of 120 cum quantity at the rate of 300/- (Rupees Three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private / property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materails within all leads and lifts and other incidentals The rate is including octroi, royalty, Malkhana, toll tax, GST and any other taxes imposed by the Government	1523.25	328.20	Rupees Three Hundred Twenty Eight And Paise Twenty Only	Per Cubic metres	499931.00
Total						499931.00


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT NOTICE INVITING TENDER

NAME OF WORK : Improvement of KSPA Road KM 0/00 to 13/00
SH:- C/O R/wall at RD 10/655 to 10/675

ESTIMATED COST : Rs 439577.00
 EARNEST MONEY : Rs 8792.00
 TIME LIMIT : THREE MONTHS

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per the directions of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	15.20	610.10	Rupees Six Hundred Ten And Paise Ten Only	Per Cubic metres	9274.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 1:4:8 (One cement isto four sand isto eight graded/crushed stone aggregate 40mm (forty millimetres) nominal size) in road work as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	67.56	5332.00	Rupees Five Thousand Three Hundred Thirty Two Only	Per Cubic metres	360230.00
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing walls, return walls with 100 mm dia PVC pipe extended through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.37 within all leads, lifts of materials and other incidentals as per the directions of the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	51.00	314.40	Rupees Three Hundred Fourteen And Paise Forty Only	Each	16034.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and section 300 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	14.40	1172.20	Rupees One Thousand One Hundred Seventy Two And Paise Twenty Only	Per Cubic metres	16980.00
5	Supplying, fitting and placing HYSD bar reinforcement in sub-structure complete as per drawing and technical specification Section 1002,1010 and 1202 as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	0.41	90632.00	Rupees Ninety Thousand Six Hundred Thirty Two Only	Per Metric tonne	37159.00
	Total					439577.00



 Executive Engineer,
 Bharmour Division,
 H.P.P.W.D. Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 491090.00
 EARNEST MONEY :- Rs 10000.00
 TIME LIMIT THREE MONTHS

NAME OF SUB-HEAD Construction of Khani Bakroth Road Km 0/00 to 1/170
 Construction of P.C.C R/Wall at RD 0/800 to 0/809.50

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603.4 and as per direction of the Engineer- In - Charge	37.90 Cubic metres	235.00	Rupees Two Hundred Thirty Five Only	Per cubic metre	8907.00
2	Providing and laying mechanically concrete in retaining walls, wall (any Thickness) including attached pilasters, columns, pipes, abutments, pillars, posts, struts, buttresses, string of lacing courses, parapets coping, bed blocks, anchor blocks, plains window sills, fillets, sunken floor etc. up to floor level, excluding the cost of centering shuttering and finishing 1:5:10 (Cement : 5 Coarse sand) 10 graded stone aggregate 40mm nominal.	85.31 Cubic metres	5300.00	Rupees Five Thousand Three Hundred Only	Per cubic metre	452143.00
3	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing walls, return walls with 100 mm dia. PVC pipe extended through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.37 within all leads, lifts of materials and other incidentals.	26.00 Nos	426.00	Rupees Four Hundred Twenty Six Only	Nos	11076.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge	17.10 Cubic metres	1109.00	Rupees One Thousand One Hundred Nine Only	Per cubic metre	18964.00
					Total :-	491090.00


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST Rs 327712.00
 EARNEST MONEY Rs 6554.00
 TIME LIMIT THREE MONTHS

NAME OF WORK Restoration of Rain Damage on KSPA road km 13/000 to 40/000
SUB-HEAD :- Construction of Retaining wall at RD 26/900 to 26/905 and 26/885 to 26/895

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge. The rate including octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	11.20 Cubic metres	333.90	Rupees Three Hundred Thirty Three And Paise Ninety Only	Per cubic metre	3740.00
2	Providing mild /tor steel reinforcement for RCC work including bnding, winding and positioning complete in all respect as per direction of Engineer- in- Charge. including carriage of materials within all leads and lifts and other incidentals. The rate including octroi , royalty, Malkana ,toll tax , sale tax or other taxes imposed by the Government.	132.69 Per kg	90.00	Rupees Ninety Only	Per kg	11942.00
3	Providing and laying cement concrete 1:2:4 (one cement isto two Sand isto four graded stone aggregate 20mm (twenty millimetre nomnal size) and curing complete excluding cost of form work in Foundation and plinth as directed by the Engineer-in-Charge, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rates inclusive of octroi, royalty, Malkhana, toll taxes, GST and any other taxes imposed by the Government.	22.50 Cubic metre	8000.00	Rupees Eight Thousand Only	Per cubic metre	180000.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub structure and super structure complete as per drawing and technical specification clauses 704.6 and 1302.5 as per the direction of Engineer-in-Charge and carriage of materials, within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	67.80 Cubic metres	1650.00	Rupees One Thousand Six Hundred Fifty Only	Per cubic metre	111870.00
5	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental.	28.80 Cubic metres	700.00	Rupees Seven Hundred Only	Per cubic metre	20160.00
Total						327712.00



 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 499848.00
 EARNEST MONEY : Rs 9997.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK Restoration of Rain Damage on KSPA road km 13/000 to 40/00
SUB-HEAD :- Construction of R/wall in wire crate at RD 37/910 to 37/930

Sl. No.	Description of work	Quantity		RATES		Unit	Amount
				Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.	14.40	Cubic metres	333.90	Rupees Three Hundred Thirty Three And Paise Ninety Only	Per cubic metre	4808.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10 (ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogramme) each as per drawing and technical specifications Clause 1301 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	172.80	Cubic metres	2800.00	Rupees two thousand three hundred thirty seven and paise twenty only	Per cubic metre	483840.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental.	14.00	Cubic metres	800.00	Rupees Eight Hundred Only	Per cubic metre	11200.00
							499848.00


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT NOTICE INVITING TENDER

ESTIMATED COST : Rs 489715.00
 EARNEST MONEY : Rs 9794.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK Improvement of black spot on Choli to Lamu road km 0/000 to 4/000
SUB-HEAD :- Construction of R/wall Due to narrow width of road from RD 0/200 to 0/268

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.	83.64	333.90	Rupees Three Hundred Thirty Three And Paise Ninety Only	Per cubic metre	27927.00
2	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification clauses 704.6 & 1302.5 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	233.24	1700.00	Rupees One Thousand Seven Hundred Only	Per cubic metre	396508.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental.	81.60	800.00	Rupees Eight Hundred Only	Per cubic metre	65280.00
Total						489715.00


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour


DNIT

NAME OF WORK :- IMPROVEMENT OF NAYAGRAM TO BAJOL ROAD 0.000 TO 7.595 KMS

ESTIMATED COST:-	205065.00
EARNEST MONEY:-	4200.00
TIME LIMIT :-	SIX MONTHS

SUB-HEAD :- Preparation of Detailed Project Report

Sr. No.	Description of Items	Quantity	Unit	RATES		Amount
				In Fig	In Words	
1	2	3	4	4	5	7
	<p>1) Preparation of Detailed Project Report in shape of manuscript along with drawing which include the following provision as given below :- and drawing complete in all respect in manuscript from and submission of the same to higher office for approval. If any correction / amendment has desired by the head office. The same may be corrected as desired and directed by the Engineer - In - Charge complete in all respect. After approval , the same should be submitted in two no. set of fair DPR and Drawing again if any correction / amendment as desired by Head offices. .</p> <p>a) Topography Survey by Digital total station with two second accuracy, showing all offsets such as Trees, Culverts, Bridge, Electric poles, Hand Pump Schools, Habitants Villages etc.</p> <p>b) Draw Cross Section at 15 m (Fifteen Meter) intervals, L- Section & calculate the quantity of earth work in standard format of Auto CAD showing all layers of pavement components.</p> <p>c) Preparation of Survey Plan showing all provision and preparation of detailed project report as per HPPWD specification and NABARD Guidelines.</p>	7.595	Per Kilometre	27,000.00	TWENTY SEVEN THOUSAND ONLY/-	2,05,065.00
TOTAL						2,05,065.00


EXECUTIVE ENGINEER
BHARMOUR DIVISION
HPPWD BHARMOUR


DNIT

NAME OF WORK :- HYDRAULIC DATA OF 25.00 MTR SPAN BRIDGE OVER KUTHAR NALLAH AT RD :-22/960 ON BHARMOUR BADAGRAM ROAD .

ESTIMATED COST:- 62500.00
EARNEST MONEY:- 1300.00
TIME LIMIT Two Months

SUB-HEAD :- Preparation of Hydraulic Data

Sr. No.	Description of Items	Quantity	Unit	In Fig	RATES		Amount
					In Words	Amount	
1	2 Preparation of Detailed Project Report of Bridge in shape of manuscript along with drawing which include the following provision as given below :- and drawing complete in all respect in manuscript from and submission of the same to higher office for approval. If any correction / amendment has desired by the head office. The same may be corrected as desired and directed by the Engineer - In - Charge complete in all respect. After approval , the same should be submitted in two no. set of fair DPR and Drawing again if any correction / amendment as desired by Head offices.	3	4 Per Job	4 62,500.00	5 SIXTY TWO THOUSAND FIVE HUNDRED ONLY/-	7 62,500.00	
					TOTAL		62,500.00


EXECUTIVE ENGINEER
BHARMOUR DIVISION
HPPWD BHARMOUR

DNIT

NAME OF WORK :- C/O LINK ROAD FROM HADSAR TO SERKAW I/C BRIDGE OVER BHEL NALLAH 4/000 TO 8/200 KM.

ESTIMATED COST:- 113400.00

EARNEST MONEY:- 4200.00

TIME LIMIT :- SIX MONTHS

SUB-HEAD :- Preparation of Detailed Project Report

Sr. No.	Description of Items	Quantity	Unit	RATES		Amount
				In Fig	In Words	
1	2 Preparation of Detailed Project Report in shape of manuscript along with drawing which include the following provision as given below :- and drawing complete in all respect in manuscript from and submission of the same to higher office for approval. If any correction / amendment has desired by the head office. The same may be corrected as desired and directed by the Engineer - In - Charge complete in all respect. After approval , the same should be submitted in two no. set of fair DPR and Drawing again if any correction / amendment as desired by Head offices. .	3 4.200	4 Per Kilometre	4 27,000.00	5 TWENTY SEVEN THOUSAND ONLY/-	7 1,13,400.00
a)	Topography Survey by Digital total station with two second accuracy, showing all offsets such as Trees, Culverts, Bridge, Electric poles, Hand Pump Schools, Habitants Villages etc.					
b)	Draw Cross Section at 15 m (Fifteen Meter) intervals, L- Section & calculate the quantity of earth work in standard format of Auto CAD showing all layers of pavement components.					
c)	Preparation of Survey Plan showing all provision and preparation of detailed project report as per HPPWD specification and NABARD Guidelines.					
TOTAL						1,13,400.00


EXECUTIVE ENGINEER
BHARMOUR DIVISION
HPPWD BHARMOUR


DNIT

NAME OF WORK :-C/O LINK ROAD FROM KANDI TO KUTHER SAMARA 0.000 TO 12.500 KM

ESTIMATED COST:-	337500.00
EARNEST MONEY:-	6800.00
TIME LIMIT :-	SIX MONTHS

SUB-HEAD :- Preparation of Detailed Project Report

Sr. No.	Description of Items	Quantity	Unit	RATES		Amount
				In Fig	In Words	
1	2	3	4	4	5	7
	1) Preparation of Detailed Project Report in shape of manuscript along with drawing which include the following provision as given below :- and drawing complete in all respect in manuscript from and submission of the same to higher office for approval. If any correction / amendment has desired by the head office. The same may be corrected as desired and directed by the Engineer - In - Charge complete in all respect. After approval , the same should be submitted in two no. set of fair DPR and Drawing again if any correction / amendment as desired by Head offices. .	12.500	Per Kilometre	27,000.00	TWENTY SEVEN THOUSAND ONLY/-	3,37,500.00
	a) Topography Survey by Digital total station with two second accuracy, showing all offsets such as Trees, Culverts, Bridge, Electric poles, Hand Pump Schools, Habitants Villages etc.					
	b) Draw Cross Section at 15 m (Fifteen Meter) intervals, L- Section & calculate the quantity of earth work in standard format of Auto CAD showing all layers of pavement components.					
	c) Preparation of Survey Plan showing all provision and preparation of detailed project report as per HPPWD specification and NABARD Guidelines.					
TOTAL						3,37,500.00


EXECUTIVE ENGINEER
BHARMOUR DIVISION
HPPWD BHARMOUR

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST Rs 476848.00
 EARNEST MONEY Rs 9537.00
 TIME LIMIT THREE MONTHS

NAME OF WORK Restoration of rain damages on Dhakog to Badgram road km 0/000 to 7/000
SUB-HEAD :- Construction of R/wall at RD 3/260 to 3/269

Sl. No.	Description of work	Quantity	Fig	RATES		Unit	Amount
				Words			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305 and 1603.4 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge Including carriage of materials within all leads, lifts and other incidental.	45.72 Cubic metres	610.10	Rupees Six Hundred Ten And Paise Ten Only	Per cubic metre	27894.00	
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical specifications section 800, 900 & 1200 1:4:8 (One cement is to Four sand is to Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size in or under water in open foundation for all type of structures etcetera including pumping or bailing out water, dewatering (surface and sub soil water) including removal of slush which may arise at the time of laying under water for all height/ depths and any quantum of water . including the cost of form work and curing complete for 14 (fourteen) days complete as per drawing and M.O.R.D technical specification clauses 800, 900, & 1200 and as per the direction of Engineer-in- Charge including carriage of material within all leads and lift and other incidentals.	79.11 Cubic metres	5332.00	Rupees Five Thousand Three Hundred Thirty Two Only	Per Cubic Metre	421815.00	
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental .	12.96 Cubic metres	1172.20	Rupees One Thousand One Hundred Seventy Two And Paise Twenty Only	Per cubic metre	15192.00	
4	Providing and Laying 100mm (Hundred millimetre) dia P.V.C. pipe weep holes masonry / stone masonry , Plain reinforced concrete , Abutment , Wing walls , Retaining wall /breast wall extended through the full width of the structure with slop 1 (V) :20(H) (One vertical in to twenty Horizontal) towards drainage complete as per drawing and MORD technical specification clause 619, 709 & 1206.6 and as per the direction of Engineer -in- Charge. The rate is including carriage of material within all leads and lift and other incidentals	38.00 Number	314.40	Rupees Three Hundred Fourteen And Paise Forty Only	Number	11947.00	
	Total					476848.00	


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST Rs 317794.00
 EARNEST MONEY Rs 6356.00
 TIME LIMIT THREE MONTHS

NAME OF WORK Restoration of rain damages on Dhakog to Badgram road km 0/000 to 7/000
SUB-HEAD :- Construction of R/wall at RD 3/269 to 3/275

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603.4 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental	30.48	610.10	Rupees Six Hundred Ten And Paise Ten Only	Per cubic metre	18596.00
2	Providing and Laying mechanically mixed and vibrated plain cement concrete in open foundations complete as per drawings and technical specifications section 800, 900 & 1200 1:4:8 (One cement is to Four sand is to Eight graded/crushed stone aggregate) 40mm (Forty millimetres) nominal size) in or under water in open foundation for all type of structures etcetera including pumping or bailing out water, dewatering (surface and sub soil water) including removal of slush which may arise at the time of laying under water for all height/ depths and any quantum of water , including the cost of form work and curing complete for 14 (fourteen) days complete as per drawing and M.O.R.D technical specification clauses 800, 900, & 1200 and as per the direction of Engineer-in- Charge including carriage of material within all leads and lift and other incidentals.	52.74	5332.00	Rupees Five Thousand Three Hundred Thirty Two Only	Per Cubic Metre	281210.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental .	8.64	1172.20	Rupees One Thousand One Hundred Seventy Two And Paise Twenty Only	Per cubic metre	10128.00
4	Providing and Laying 100mm (Hundred millimetre) dia P.V.C. pipe weep holes masonry / stone masonry , Plain reinforced concrete , Abutment , Wing walls , Retaining wall /breast wall extended through the full width of the structure with slope 1 (V) :20(H) (One vertical in to twenty Horizontal) towards drainingface complete as per drawing and MORD technical specification clause 619, 709 & 1206.6 and as per the direction of Engineer-in- Charge. The rate is includingcarriage of material within all leads and lift and other incidentals	25.00	314.40	Rupees Three Hundred Fourteen And Paise Forty Only	Number	7860.00
	Total					317794.00


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST : Rs 499778.00
 EARNEST MONEY : Rs 9996.00
 TIME LIMIT THREE MONTHS

NAME OF WORK Construction of Hadsar to Chobia road km 0/000 to 7/500
SUB-HEAD - Providing crate work at Serkaw Nallah at RD 5/490 to 5/502.50 Chobia Side.

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.	40.63 Cubic metres	235.05	Rupees Two Hundred Thirty Five And Paise Five Only	Per cubic metre	9550.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10 (ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogramme) each as per drawing and technical specifications Clause 1301 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	195.31 Cubic metres	2510.00	Rupees Two Thousand Five Hundred Ten Only	Per cubic metre	490228.00
						499778.00

Executive Engineer,
 Bhamour Division,
 HPPWD Bhamour

DRAFT NOTICE INVITING TENDER

NAME OF WORK Construction of Patti to Khund road km 0/000 to 3/300

SUB-HEAD :- Providing crate work R/wall at Rd 0/485 to 0/500

ESTIMATED COST Rs 497269.00
EARNEST MONEY Rs 9945.00
TIME LIMIT THREE MONTHS

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.	21.30 Cubic metres	235.05	Rupees Two Hundred Thirty Five And Paise Five Only	Per cubic metre	5007.00
2	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand) : 10 graded stone aggregate 40 mm nominal size) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing in road work and as per the instructions of Engineer-in-charge within all leads, lifts of materials and other incidentals.	27.00 Cubic metres	5836.00	Rupees Five Thousand Eight Hundred Thirty Six Only	Per Cubic Metre	157572.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10 (ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogramme) each as per drawing and technical specifications Clause 1301 as per the directions of the Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental.	140.62 Cubic metres	2380.10	Rupees Two Thousand Three Hundred Eighty And Paise Ten Only	Per cubic metre	334650.00
Total						497269.00

Executive Engineer,
Bharmour Division,
HPPWD Bharmour

DRAFT NOTICE INVITING TENDER

13

ESTIMATED COST Rs 441467.00
 EARNEST MONEY Rs 8829.00
 TIME LIMIT THREE MONTHS

NAME OF WORK Improvement of Black spot on Bharmour Badgram road km 0/000 to 26/000
SUB-HEAD :- Improvement of Black spot at RD 16/800 to 16/860

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Excavation in hilly area in all heights and depths and in all kind of soil by mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiseling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by engineer-in-charge at site according to the MORD technical specification clause 302, 304 and 1603 and sorting out useful materials and stacking the same in all leads, lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour if required. Recovery of stone to the tune of 335.00 cubic metres quantity at the rate of 300/- (Rupees Three hundred) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases including carriage of materials within all leads, lifts and other incidentals The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1060.20	416.40	Rupees Four Hundred Sixteen And Paise Forty Only	Per cubic metre	441467.00
	Total					441467.00

Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT NOTICE INVITING TENDER

NAME OF WORK Construction of Hadsar to Chobia road km 0/000 to 7/800
SUB-HEAD :- Construction of PCC R/wall at RD 5/133 to 5/139

ESTIMATED COST Rs 391228.00
 EARNEST MONEY Rs 7825.00
 TIME LIMIT THREE MONTHS

Sl. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material, within all leads, lifts of materials and other incidentals, as per approved drawing, design and as directed by the Engineer-in-Charge.	25.20 Cubic metres	235.05	Rupees Two Hundred Thirty Five And Paise Five Only	Per cubic metre	5923.00
2	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand) : 10 graded stone aggregate 40 mm nominal size) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing in road work and as per the instructions of Engineer-in-charge within all leads, lifts of materials and other incidentals.	62.34 Cubic metres	5836.00	Rupees Five Thousand Eight Hundred Thirty Six Only	Per Cubic Metre	363816.00
3	Providing and Laying 100mm (Hundred millimetre) dia P.V.C. pipe weep holes masonry / stone masnory , Plain reinforced concrete , Abutment , Wing walls , Retaining wall /breast wall extended thought the full width of the structure with slop 1 (V) :20(H) (One vertical in to twenty Horizontal) towards drainingface complete as per drawing and MORD technical specification clause 619, 709 & 1206.6	19.00 Nos	426.70	Rupees Four Hundred Twenty Six And Paise Seventy Only	Each	8107.00
4	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1604.7 and section 300 and as per direction of Engineer - In- Charge including carriage of materials within all leads and lifts and other incidental.	12.06 Cubic metres	1109.60	Rupees One Thousand One Hundred Nine And Paise Sixty Only	Per cubic metre	13382.00
Total						391228.00

Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

6

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST Rs 475441.00
 EARNEST MONEY Rs 9600.00
 TIME LIMIT THREE MONTHS

MA Construction of Hadsar Chobia road KM 0/00 to 7/500
 SU Construction PCC R/wall at RD. 5/193.50 to 5/202

Sr. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305 and 1603.4 and as per direction of the Engineer-In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal 50m of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetres) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantam of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental.	6.38	235.05	Rupees Two Hundred Thirty Five And Paise Five Only	Per cubic metre	1500.00
2	Providing Mild Steel/Tor Steel Reinforcement for R.C.C work including bending, binding and palcing in position complete upto pinth level. Mild steel and medium tensile steel bars	80.85	75.40	Rupees Seventy Five And Paise Forty Only	Kg	6096.00
3	Providing and Laying mechanically Concrete in retaining walls, return walls, walls (any Thickness) Including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string of lacing courses, parapets Coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc. up to floor five level, excluding the cost of centering shuttering and finishing 1:5:10 (Cemnet: 5 couarse sand): 10 graded stone aggregate 40mm nominal	75.74	5836.00	Rupees Five Thousand Eight Hundred Thirty Six Only	Per cubic metre	442019.00
4	Providing and Laying 100mm dia P.V.C. pipe weep holes masonry / stone masonry, Plain reinforced concrete, Abutment, Wing walls, Retaining wall /breast wall extended thought the full width of the structure with slop 1 (V) ;20(H) (One vertical in to twenty Horizontal) towards drainingface complete as per drawing and MORD technical specification clause 619, 709 & 1206.6	34.00	426.70	Rupees Four Hundred Twenty Six And Paise Seventy Only	Nos	14508.00
5	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete in road structure as per drawing and M.O.R.D. technical specifications clause 1204.3.8 and section 300	10.20	1109.60	Rupees One Thousand One Hundred Nine And Paise Sixty Only	Per cubic metre	11318.00
Total						475441.00

Dr. J. K. Schedule of Qty approved for Rs 475441/- only

Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs 498750.00
 EARNEST MONEY :- Rs 10000
 TIME LIMIT :- THREE MONTHS

NAME OF WORK :- Restoration of rain Damage Under Garola sub Division at Various Road
SUB-HEAD :- Removal of slips at Various rds

Sr. No.	Description of work	Quantity	RATES		Unit	Amount
			Fig	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611.1 as per the direction of Engineer - in - Charge The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4750.00	105.00	Rupees One Hundred Five Only	Per cubic metre	498750.00
				Total		498750.00


 Executive Engineer,
 Bharmour Division,
 HPPWD Bharmour