



Himachal Pradesh  
Public Works Department  
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083  
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

**SHORT TERM NOTICE INVITING TENDERS**

Scaled item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before 12/03/2024 up to 11.00 AM. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 11/03/2024 up to 4.00 P.M and the application for issue of tender form shall be received on 07/03/2024 up to 12.00 noon.


The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	C/o Dehan Arth Malag road Km. 0/0 to 10/0 (SW:- C/o Retaining wall at Rd 9/900 to 9/913)	4,85,843/-	9700	Two Months	350/-
2	Restoration of rain damages on various roads under Sub Division Thural (SW:- Painting of boards & writing letters, Kms Stone etc).	1,11,692/-	2200/-	Three Months	350/-
3	C/o Rud Panyali Kolru Galuhi Kaluna road (SW:- Soling & Wearing in Km, 2/005 to 2/065)	66,240/-	2000/-	Three Months	350/-
4	Restoration of rain damages on various roads under Bhawarna & Thural Sub Division (SW:- Supplying and stacking CC2001002000 Quick lime in Bhawarna & Thural Sub Division)	4,00,000/-	8000/-	One Month	350/-

**Terms & Conditions:-**

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm have to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.
5. The contractor will have to submit affidavit along with application for issue of tender that he has not more than two works in hand.
6. Next tender will be issued only after completion of previous works in hand.

HIM SUCHANA AVM JAN SAMPARK

  
Executive Engineer  
Bhawarna Division  
HPPWD Bhawarna  
(On behalf of Governor of Himachal Pradesh)

Dated:- 4/3/2024

No. PWD/BWD/Tender/NIT/2023-24/- 17705-64  
Copy to following for information and necessary action:-

1. The Principal Secy.(PW) to the Govt. of H.P. Shimla.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (KZ),HPPWD, Dharamshala.
4. The Director, Information & Publications Department, HP Shimla.
5. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
6. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD, Palampur.
7. The Deputy Commissioner, Kangra at Dharamshala.
8. The Sub-Divisional Officer( Civil ) Palampur.
9. All the S.E.s/E.E.s under Kangra Zone.
10. All the Assistant Engineers under this Division.
11. The Drawing /Accounts Branch in this office.
12. Notice Board.

Executive Engineer  
Bhawarna Division  
HPPWD Bhawarna

## Schedule of Quantity

Name of Work:- Construction of Dehan Arth Malag road Km 0/0 to 10/0. (SH):- Construction of Retaining wall at RD 9/900 to 9/13).

Estimated Cost :- Rs. 4,85,843/-  
Earnest Money :- Rs. 9700/-  
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	56.81			Per Cubic metre	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, malkana,toll tax, GST or other taxes imposed by the Government.	114.66			Per Cubic metre	
3	Providing and laying 100mm dia ( One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	52			Each	
<b>Total :-</b>						

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

### Schedule of quantity

**Name of Work :-** Restoration of rain damages on various roads under Sub-Division Thural various section (SH:- Painting of boards & writing letters, Kms stone etc.)

**Estimate Cost :-** 1,11,692/-  
**Earnest Money :-** 2200/-

**Time Limit :-** Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete, as per direction of Engineer-in-charge. The rate is including octroi, royalty, Malkana toll tax, GST or other taxes imposed by the Government.	400.00			Per Square metre	
2	Applying priming coat on new concrete/ masonry/ asbestos cement plastered surfaces after and including preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand appearing as required with ready mixed primer complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	15.00			Per Square metre	
3	Painting two coats(excluding priming costs) on new steel and other metal surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll-tax, GST and any other taxes imposed by the government.	43.70			Per Square metre	
4	Painting two coats (excluding priming coats) on new concrete masonry/ asbestos cement/plaster surfaces with ready mixed synthetic enamel paint of approved brand other than white paint brushing to give an any shade including cleaning the surface of all dirt, dust and other foreign matters and sand papering and stopping within all leads lifts and other incidentals as per the direction of Engineer-in-Charge.	200.00			Per Square metre	

5	Writing letters on figures on any surface with black japan-paint (stops, comas, hyphens and the like not to be measured and paid separately) as per the direction of Engineer-in-Charge.															
5.01	Block letters/figures		20000.00													
5.02	Indian (letters/figures)		25000.00													

  
 Executive Engineer  
 Bhawarna  
 Division  
 HP PWD Bhawarna

## Schedule of Quantity

Name of work:- C/o Rud Panyaili Kolru Galuhi Kaluna road (SH:- P/L Soling & Wearing in Km 2/005 to 2/065)

Estimate Cost :- Rs. 66,240/-  
Earnest Money :- 2000/-  
Time Limit :- One Month

S/No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Preparation of sub grade by dressing to camber ( Earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	211.05			Per Square metre	
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub- grade completed as per HP.PWD specifications as per directions of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	211.05			Per Square metre	
3	Providing, laying, Soling 90 to 45mm ( Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clasue 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	21.11			Per Cubic metre	
4	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 K.N. static Road roller in stages to proper grade and camber, applying and brooming, stone, screening type-B of size 11.2mm (eleven point two millimetre) nominal size at the rate of 0.20 cum. (Zero point two zero cubic metre) per ten square metre and binding materials at the rate of 0.06 cum. (Zero point zero six cubic metre) per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -II, 63mm to 45mm ( sixty three millimeters to forty five millimeters)size, 75mm ( seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer -in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	14.42			Per Cubic metre	
<b>Total:-</b>						

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna

## chedule of Quantity

Name of work:- Restoration of rain damages on various roads under Bhawarna & Thural Sub Division (SH:- Supplying and stacking CC2001002000 Quick lime in Bhawarna & Thural Sub Division)

Estimate Cost :- Rs. 4,00,000/-  
Earnest Money :- 8000/-  
Time Limit :- One Month

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Supplying and stacking CC2001002000 Quick lime corresponding to class A as per specifications 712 as amended in polythene based gunny bags of 50 kg (Fifty kilogram) containing total calcium Magnesium oxide 70% (seventy percent) for construction works (25 kg (Twenty five kilogram) pack each bag complete as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octrai, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	20000.00			Per Kilogram	
<b>Total:-</b>						

Note:- Bhawarna Sub-Division =10 tonne & Thural Sub-Division = 10 tonne

  
 Executive Engineer  
 Bhawarna Division  
 HP PWD Bhawarna