



Telephone No: 01782-233214

E-mail: [eenh-ram-hp@nic.in](mailto:eenh-ram-hp@nic.in)

No. PW/EE/NH/RMP-CB-Tender /2023-24-  
To

14504


Dated:- 05/03/2024

The Executive Engineer, (IT)  
Nigam Vihar Shimla-2.

Subject: - Publication of tender notice

Enclosed, please find herewith copy of tender notice in respect of tenders invited vide this office NIT No. PW/EE/NH/RMP/CB-Tender Notice/ 2023-24-14493-14503 dated 05/03/2024 for uploading the same on department website for wide publicity.

DA:- Copy of NIT

  
Executive Engineer,  
NH Division HPPWD,  
Rampur Bushahr.

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER

Sealed item rate tender(s) on PWD form No.6 &8 are hereby invited by the Executive Engineer, NH- Division, HP.PWD, Rampur Distt. Shimla (H.P) on behalf of the Governor of H.P for the following works from the registered contractors in HP.PWD in appropriate class to reach in this office on 12.03.2024 up to 10.30 A.M. and will be opened on the same day at 11.00A.M. in the presence of Contractors or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on 11.03.2024 i.e. 11.00 AM to 1.00 PM and the tender form can be had from this office against this cash payment (Non-refundable) on the same day from 2.00P.M. to 5.00 P.M. No application shall be entertained without earnest money or through FAX.

Earnest money shall be in shape of NSC/FDR duly pledged in favour of Executive Engineer NH-Division HP.PWD Rampur Bushahr Distt. Shimla H.P. Ambiguous /Telegraphically/conditional tenders or tender through FAX shall not be entertained/ considered in any case.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time	Form No.	Cost of form
1	A/R & M/O on NH-305 KM. 0/0 to 97/000 ( SH:- Preparation of Hydraulic Data of bridge at km 13/425,17/900,20/820,21/055,22/197 and 25/100)	480000/-	9600/-	Three months	6&8	350/-
2	A/R & M/O on NH-305 KM. 0/0 to 97/000 ( SH:- C/O PCC R/wall at RD 22/150 to 22/155.50)	496742/-	10000/-	One month	6&8	350/-
3	A/R & M/O on NH-305 KM. 0/0 to 97/000 ( SH:- C/O PCC B/wall at RD 17/235 to 17/251.20)	497277/-	10000/-	One month	6&8	350/-
4	A/R & M/O on NH-305 KM. 0/0 to 97/000 ( SH:- C/O PCC R/wall at RD 22/156 to 22/161.50)	492237/-	9900/-	One month	6&8	350/-
5	A/R & M/O on NH-305 KM. 0/0 to 97/000 ( SH:- C/O PCC R/wall at RD 16/300 to 16/311.40)	494341/-	9900/-	One month	6&8	350/-

**SPECIAL CONDITIONS**


1. The material shall be arranged by the contractor himself.
2. The detail of documents to be attached with the application is given below.
  - i Latest copy of renewal enlistment.
  - ii Copy of Pan Card.
  - iii Copy of GST No.
3. The offer of the tender shall be kept open for 90 days
4. Tender received after the specified time/date shall not be opened.
5. Executive Engineer NH-division HP.PWD Rampur Distt. Shimla H.P. reserves the right to reject any or all tender/s without assigning any reasons.
6. If due to any unforeseen reasons the office of the Executive Engineer NH-Division HP.PWD Rampur remain closed on the notified date of sale and receipt of tender, tender will be sold and received/opened the next working day of same specified time.
7. Tenderers may contact the Executive Engineer for any further information they may require during the working day/ office hours.
8. The contractors are requested to insert the rate of each in words as well as in figures failing which Executive Engineer reserves the right to reject any or all tenders.
9. The labourcess shall allow/ deduction @ 2% TDS amount of GST (1% CGST and 1% SGST).
10. The labour cess @ 1% will be deducted from the gross amount of the bill
11. All the works are of urgent nature hence the contractor already having two works are not eligible to participate for the tendering.
12. A contractors enlisted in a particular class shall be eligible to tender for his own class and one step below as per Govt. notification No.PBW (B) 22-1/2002 dated 26-05-2015.
13. The Contractor will have to submit the proof of registration under Employees Provident Funds & Miscellaneous Provision Act. 1952 before award of work.
14. Cement should be purchased from H.P. State Civil Supply Corporation
15. GST will be deducted from each bill as per latest instruction of the Government

Executive Engineer,  
NH Division, H.P.PWD,  
Rampur Bushahr.

No.PW/EE/NH/RMP/CB-Tender Notice/2023-24- 14493-14503  
Copy forwarded for information to the:-


1. Engineer-in-Chief, HP.PWD, Shimla
2. Chief Engineer (NH) HP.PWD, Shimla-1
3. Superintending Engineer, NH-Circle, HP.PWD, Shimla
4. All the Assistant Engineer working under this division
5. A/B & D/B in this office.
6. Notice board of this office.

Dated:- 05/03/2024

  
Executive Engineer,  
NH Division, H.P.PWD,  
Rampur Bushahr


Certificate

Certified that the tenders of the works invited vide this office NIT No. PW/EE/NH/RMP/CB-tender/ 2023-24-14493-14503 dated 05/03/2024 is of urgent nature in exigency of public interest.

  
Executive Engineer  
NH Division HPPWD,  
Rampur Bushahr.

### Schedule of Quantity

Name of work:- A/R & M/O on NH-305 KM. 0/0 TO 97/000 ( SH:- Preparation of Hydraulic Data of bridge at km 13/425,17/900,20/820,21/055,22/197 and 25/100)		Estimated cost		Units		Amount	
		Earnest Money	Time	Rs 480000/-	Rs 9600/-	Three months	
Sr. No.	Descriptions	Quantity	Rate		Per Job	Amount	
			In figure	In words			
1	Preparation of Hydraulic data i.e Topography survey by total station equipment for preparation of survey plan, cross section at bridge site, 50 m, 150 m, 300 m, upstream and down stream of river, L-section of road and river.	6					
<b>Total</b>							

  
 Executive Engineer  
 NH Division HPPWD  
 Rampur Bushahr


**Schedule of Quantity**

Name of work:- A/R & M/O on BH-305 Sainj Luri Jalori banjar Aut Road Km. 0/00 to 97/00) ( Sub Head:- C/O PCC R/wall at RD.22/150 to 22/155.50)

Estimated Cost:-	496742.00
Earnest Money:-	10000.00
Time:-	One month

S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	38.35			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant, including all incidental charges, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	74.93			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ Return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	16.65			Per running meter.	

<p>4 Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.</p>	<p>21.09</p>			<p>Per cubic meter.</p>	
<p><b>Total Rs:-</b></p>					

  
 Executive Engineer,  
 N.H.Division, HP.PWD,  
 Rampur Bsr.

**Schedule of Quantity**

Name of work:- A/R & M/O on BH-305 Sainj Luri Jalori banjar Aut Road Km. 0/00 to 97/00) ( Sub Head:- C/O PCC B/wall at RD.17/235 to 17/251.20)

Estimated Cost:-	497277.00
Earnest Money:-	10000.00
Time:-	One month

S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	61.72			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	76.63			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	40.50			Per running meter.	
<b>Total Rs:-</b>						

  
 Executive Engineer,  
 N.H. Division, HP, PWD,  
 Rampur Bsr.

**Schedule of Quantity**

Name of work:- A/R & M/O on BH-305 Saini Luri Jalori banjar Aut Road Km. 0/00 to 97/00) ( Sub Head:- C/O PCC R/wall at RD.22/156 to 22/161.50)

Estimated Cost:- 492237.00

Earnest Money:- 9900.00

Time:- One month

S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious mater, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	38.01			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant, including all incidental charges, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	74.25			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V :20H towards drawing face. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	16.50			Per running meter.	



<p>4 Back-filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.</p>	20.90			Per cubic meter.	
<b>Total Rs:-</b>					

  
 Executive Engineer,  
 N.H. Division, HP. PWD,  
 Rampur Bsr.

**Schedule of Quantity**


Name of work:- A/R & M/O on BH-305 Sainji Luri Jalori banjar Aut Road Km. 0/00 to 97/00) ( Sub Head:- C/O PCC R/wall at RD.16/300 to 16/311.40)

Estimated Cost:- 494341.00  
Earnest Money:- 9900.00

Time:- One month

S. No.	Descriptions	Qty.	Rate		Unit	Amount
			In figure	In words.		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	46.28			Per cubic meter.	
2	Providing concrete for plain/reinforced cement concrete in sub structure complete as per drawings and technical specifications. PCC Grade M15 using Batching plant , including all incidental charges. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	73.74			Per cubic meter.	
3	Providing weep holes in Brick masonry/Plain/ Reinforced concrete abutment, wing wall/ return wall with 100 mm dia AC pipe, extending through the full width of the structure with slope of 1V:20H towards drawing force. Complete as per drawing and Technical Specifications including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.	27.36			Per running meter.	

<p>4 Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specification. including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts, including all incidental charges. Any loss of public/private property during the course of execution shall be the sole responsibility of contractor which shall have to be duly compensated by him at his own cost.</p>	21.32			Per cubic meter.	
<b>Total Rs:-</b>					

  
 Executive Engineer,  
 N.H. Division, HP. PWD,  
 Rampur Bsr.