

REGISTERED

Office of the Executive Engineer, B&R Division, HP PWD Kalpa District Kinnaur (HP)

Web:- [www.hppwd.gov.in](http://www.hppwd.gov.in) E mail:- [hp-kin@nic.in](mailto:hp-kin@nic.in)

Phone No:- 01786-226027 Fax:- 01786-226027.

No:- PW/KNR-E-Tender/2022-  
To

11054-55

Dated:- 29/7/2024


The Executive Engineer (IT Cell),  
HP.PWD. Shimla-2.

**Subject:-**

**Publication of Tender Notice (OFFLINE)**


Enclosed please find herewith the Tender of works costing below 1.00 Lac as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) 1/2020 dated 16-07-2021. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity  
& Certificate.

  
Executive Engineer,  
Kalpa Division,  
HP.PWD. Kalpa.

**Copy forwarded for information to:-**

1. The Superintending Engineer, 11<sup>th</sup> Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.

  
Executive Engineer,  
Kalpa Division,  
HP. PWD, Kalpa

## HP.P.W.D. TENDER NOTICE.(offline)

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer, Kalpa Division, HP, PWD. Kalpa for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **07-03-2024 up to 10.30 A.M.** and shall be opened on the same day at **11:00 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on any working day during the office hours upto **4:00 P.M.** on **06-03-2024**. No application for issue of tender forms will be received on **06-03-2024** after **4:00 PM**. If the office happens to be closed on the above mentioned dates, the tenders will be sold/ opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R,s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The offer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No.	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	S/R to HPPWD Rests House at Reckong Peo in District Kinnaur (HP) (SH:- Providing furniture for varius suits)	4,48,400/-	9000/-	One Month	350/-	D Class
2	C/O NGO Mess at Police line at Reckong Peo in District Kinnaur HP (SH:- Providing furniture for various suits)	4,01,200/-	8500/-	One Month	350/-	D Class
3	S/R to District Level Conference Bhawan at Reckong Peo in District Kinnaur HP (SH:- Providing furniture)	3,72,700/-	7500/-	One Month	350/-	D Class
4	Additional Alteration for the Rest House at Moorang in District Kinnaur HP (SH:- Providing furniture for various suits)	3,80,550/-	8000/-	One Month	350/-	D Class
5	A/R & M/O link road from NH-22 to Ropa Khas Km. 0/00 to 15/850 (SH:- P/L of hot applied thermoplastic road marking paint on edge line both side from RD. 0/00 to 2/00)	4,65,200/-	9500/-	One Month	350/-	D Class
6	A/R & M/O Peo Karchham Shilti road Km. 0/00 to 11/635 (SH:- P/L of hot applied thermoplastic road marking paint on edge line valley side from RD. 5/720 to 8/580)	4,98,927/-	10,000/-	One Month	350/-	D Class
7	A/R & M/O Peo Karchham Shilti road Km. 0/00 to 11/635 (SH:- P/L of hot applied thermoplastic road marking paint on edge line valley side from RD. 8/580 to 11/440)	4,98,927/-	10,000/-	One Month	350/-	D Class
8	C/O Primary School at Kalpa in Distt. Kinnaur (H.P.) (SH:-Geotechnical investigation of soil/strata).	2,49,150/-	5000/-	Three Months	350/-	D" Class
9	C/O A.E. office cum residence at Moorang (SH:- Geotchnical Investigation of soil/strata)	2,49,150/-	5000/-	Three Months	350/-	D" Class
10	A/R & M /O Span Tokto to Rimbur at Asrang in Distt. Kinnaur HP (SH:- C/O R/wall in PCC 1:3:6 left side of the span)	4,98,638/-	10,000/-	Three Months	350/-	D Class




**Terms and conditions:-**

**Following documents should accompany the application for tenders:-**


1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts No allotted by the Provident Fund Commissioner Shimla and copy of PAN No.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not be entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in hand.

No.PW/KNR-E-Tender/NIT/2023- 10960-69  
Copy forwarded for information to:-

1. 1 The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11<sup>th</sup> Circle, HP.PWD. Rampur Bushahr.
5. The Block development officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.

  
Executive Engineer,  
Kalpa Division,  
HP. PWD. Kalpa.


Dated:-

  
28/3/2024

\_\_\_\_\_  
Executive Engineer,  
Kalpa Division,  
HP. PWD. Kalpa.

## CERTIFICATE

Certified that the Tender for works called vide this office Letter No. PW/KNR/E-Tender/2023- 10960-69 dated 28-02-2024. from Sr. No. 1 to 10 are of urgent nature and public interest.

  
Executive Engineer,  
Kalpa Division,  
HP.PWD. Kalpa.




SCHEDULE OF QUANTITY

Name of work:- Special repair to HPPWD Rest House at R/Peo in Distt. Kinnaur (H.P.)  
(SH:- Providing furniture for various suits).

Estimated Cost :- 4,48,400/-  
Earnest Money :- 9,000/-  
Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Supplying and stacking of VIP Double bed, with superior quality of wood, cloth, polishing with bed table, including all necessary fitting as per the direction of Engineer-in-Charge, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.00			Each	
2	Supplying and stacking Center table with superior quality of wood, including all necessary fitting as per the direction of Engineer-in-Charge, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	4.00			Each	
3	Supplying and stacking cushion chair. with superior quality of wood, foam, imitation leather & cloth including all necessary fitting as per the direction of Engineer-in-Charge, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	20.00			Each	
	<b>Total:-</b>					

  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.



SCHEDULE OF QUANTITY

Name of work:- C/O NGOs Mess at Police Line at Reckong Peo in Distt. Kinnaur (H.P.)  
(SH:- Providing furniture for various suits).

Estimated Cost :- 4,01,200/-  
Earnest Money :- 8,500/-  
Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Supplying and stacking sofa set of different seater with superior quality of foam, imitation leather & cloth including all necessary fitting as per the direction of Engineer-in-Charge, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	28.00			Per Seater	
2	Supplying and stacking center table wrappe with foam and superior cloth with glass top, including all necessary fitting as per the direction of Engineer-in-Charge, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	3.00			Each	
3	Repair of cushion chair with foam and superior cloth, including all necessary fitting as per the direction of Engineer-in-Charge, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	40.00			Each	
	<b>Total:-</b>					

Executive Engineer,  
Kalpa Division (B&R),  
HP, PWD, Kalpa.

(8)

### SCHEDULE OF QUANTITY

Estimated Cost :- 3,72,700/-  
Earnest Money :- 7,500/-  
Time :- One Month

Name of work:- Special repair to District level conference Bhawan at Reckong Peo in Distt. Kinnaur (H.P.)  
(SH:- Providing furniture).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Supplying and stacking sofa set of different seater with superior quality of foam, imitation leather & cloth including all necessary fitting as per the direction of Engineer-in-Charge, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	14.00			Per Seater	
2	Supplying and stacking center table wrappe with foam and superior cloth with glass top, including all necessary fitting as per the direction of Engineer-in-Charge, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.00			Each	
3	Supplying and stacking of cusion of size (22 inch x 20 inch) with superior cloth, including all necessary fitting as per the direction of Engineer-in-Charge, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	60.00			Each	
4	Supplying and stacking 6 (Six) seater Dining table with chairs with superior quality of wood, including all necessary fitting as per the direction of Engineer-in-Charge, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.00			Each	
	<b>Total:-</b>					

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.



**SCHEDULE OF QUANTITY**

**Name of work:-** Add. Alteration for the Rest House at Moorang in Distt. Kinnaur at in Distt. Kinnaur (H.P.)  
**(SH:-** Providing furniture for various suits).

Estimated Cost :- 3,80,550/-  
 Earnest Money :- 8,000/-  
 Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Supplying and stacking sofa set of different seater with superior quality of foam, imitation leather & cloth including all necessary fitting as per the direction of Engineer-in-Charge, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	23.00			Per Seater	
2	Supplying and stacking center table wrappe with foam and superior cloth with glass top, including all necessary fitting as per the direction of Engineer-in-Charge, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1.00			Each	
3	Supplying and fitting LED Pannel of size (7 feet x 6.5 feet) with superior quality of wood, polishing, including all necessary fitting as per the direction of Engineer-in-Charge, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.00			Each	
	<b>Total:-</b>					

Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD; Kalpa.



SCHEDULE OF QUANTITY

**Name of work:-** A/R & M/O on Link road from NH-22 to Ropa Khas Km 0/00 to 15/850


**(SH):-** Prividng and laying of hot applied thermoplastic road marking paint on edge line both side from RD 0/00 to 2/00).

Estimated Cost :: 4,65,200/-

Earnest Money :: 9,500/-

Time :: One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete with applicable specifications including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	400.00			Per Square meter	
	<b>Total:-</b>					₹ 0.00

  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

6

### SCHEDULE OF QUANTITY

Estimated Cost :- 4,98,927/-  
Earnest Money :- 10,000/-  
Time :- One Month

**Name of work:-** A/R & M/O Peo Karcham Shilti road Km 0/00 to 11/635

(SH:- Prividing and laying of hot applied thermoplastic road marking paint on edge line valley side from RD 5/720 to 8/580).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete with applicable specifications, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	429.00			Per Square meter	
<b>Total:-</b>						

Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.



7


### SCHEDULE OF QUANTITY

Estimated Cost :- 4,98,927/-  
Earnest Money :- 10,000/-  
Time :- One Month

Name of work:- A/R & M/O Peo Karcham Shiliti road Km 0/00 to 11/635

(SH:- Prividing and laying of hot applied thermoplastic road marking paint on edge line valley side from RD 8/580 to 11/440).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete with applicable specifications, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	429.00			Per Square meter	
<b>Total:-</b>						

  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa.

8

### SCHEDULE OF QUANTITY

Estimated Cost :- 2,49,150/-  
Earnest Money :- 5,000/-  
Time :- Three months

**Name of work:-** C/O Primary School at Kalpa in Distt. Kinnaur (H.P.)  
(SH:- Geotechnical investigation of soil/strata).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Sub-Soil investigation of all type soil/starta by drilling bore hole of NX size 75mm (Seventy five millimeter diameter) ranging from 10 meter or above in depth for investigation of soil/rock conditions at site of work i/c mobilization and demobilization fro drilling, shifting of machinery to bore site, make platform and water arrangement for drilling, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	33.00			Each	
					<b>Total:-</b>	

  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD; Kalpa



9

**SCHEDULE OF QUANTITY**

Estimated Cost :- 2,49,150/-  
Earnest Money :- 5,000/-  
Time :- Three Months

**Name of work:-** Construction of AE office cum residence at Moorang  
(SH:- Geotechnical investigation of soil/strata).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Sub-Soil investigation of all type of soil/starta by drilling bore hole of NX size (75 (seventy five millimeter diameter) ranging from 10 meter or above in depth for investigation of soil/rock conditions at site of work i/c mobilization and demobilization for drilling, shifting of machinery to bore site, make platform and water arrangement for drilling, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge.	33.00			Per Running meter	
					<b>Total:-</b>	

  
Executive Engineer,  
Kalpa Division (B&R),  
HP.PWD, Kalpa

Estimated Cost :- 4,98,638/-  
 Earnest Money :- 10,000/-  
 Time :- Three Months

**SCHEDULE OF QUANTITY**


**Name of work:-** A/R & M/O Span Tokto to Rimbur at Asrang in Distt. Kinnaur H.P.

(SH:- C/O R/wall in PCC 1:3:6 left side of the span)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with all lead and lift as per drawing and technical specification Clause 1603.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	39.10			Per Cubic meter	
2	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth, including carriage of material within all leads and lifts, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	24.020			Per Cubic meter	
3	Providing and laying cement concrete 1:6:12 (One Cement: Six Sand: Twelve graded stone aggregate 40mm (Forty millimeter nominal size) and curing complete excluding cost of centering and shuttering in: -Foundation and plinth, as directed by Engineer-in-Charge, including carriage of materials with in all leads and lifts, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	9.250			Per Cubic meter	
4	Providing and laying cement concrete 1:3:6 (One Cement: Three Sand: Six graded stone aggregate 20mm (Twenty millimeter nominal size) and curing complete excluding cost of centering and shuttering in: -Foundation and plinth, as directed by Engineer-in-Charge, including carriage of materials with in all leads and lifts, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	68.836			Per Cubic meter	
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(one millimeter) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	15.00			Each	



6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	5.07		Per Cubic meter	
<b>Total:-</b>					

  
 Executive Engineer,  
 Kalpa Division (B&R),  
 HP.PWD, Kalpa.