

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"

Sealed **Percentage rates** tender in emergent condition on form 6 & 7 are invited on behalf of Governor of Himachal Pradesh for the following work covered under emergent/inescapable nature from the approved and eligible contractors enlisted in H.P.PWD so as to reach in this office on or **06.02.2025 Up to 11.30 A.M.** and will be opened on the same day at 3.30 P.M. in the presence of interesting contractors or their authorized representatives who may like to be present. If it happens to be holiday on the schedule date of opening of tender, the same will be opened on next working day. The application for obtaining the tender form will be received upto **01.00 PM** & without EMD tender form will not be accepted, moreover the tender form can be had from this office against cash payment (Nonrefundable) up to 5.00 P.M. on **05.02.2025**.


The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Xen Mandi Division No. II must accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr No	Name of work	Estt. cost	E/Money	Cost of tender form	Time limit
1.	Construction of Indoor Stadium at Paddal Mandi District Mandi (H.P) (SH:- Submission of Structural design and approval of competent authority.	Rs 98,000	Rs 2,000	Rs. 350	One Month
2.	Construction of Indoor Stadium at Paddal Mandi District Mandi H.P (SH:- Submission of Structural of drawing and approval of competent authority.	Rs 98,000	Rs 2,000	Rs. 350	One Month
3.	Construction of Indoor Stadium at Paddal Mandi District Mandi H.P (SH:- Submission of working drawings and approval of competent authority.	Rs 98,000	Rs 2,000	Rs. 350	One Month
4.	Construction of Indoor Stadium at Paddal Mandi District Mandi H.P. (SH:- Vetting of structural design/drawings and approval of competent authority.	Rs 98,000	Rs 2,000	Rs. 350	One Month
5.	A/R & M/O Ner Chowk Pandoh bypass road (Portion of NH-21) road from km. 198/145 to 203/500). (SH:- Hiring of J.C.B for excavation of Katcha drain & removal of slips and dressing of berms etc.	Rs 99,000	Rs 2,000	Rs. 350	Two Months
6.	A/R & M/O Ner Chowk Pandoh bypass road (Portion of NH-21) road from km. 198/145 to 203/500). (SH:- Hiring of Tipper for carriage of debries/muck at RD 198/145 to 203/500) Job No.2	Rs 99,000	Rs 2,000	Rs. 350	45 Days
7.	A/R & M/O Nerchowk Pandoh bypass road (Portion of NH-21) road from km. 198/145 to 203/500).(SH:- Hiring of Tipper for carriage of debries/ muck at RD 198/145 TO 203/500) Job No.1	Rs 99,000	Rs 2,000	Rs. 350	45 Days
8.	RRD on various roads under Mandi Sub Division No-IV HPPWD Mandi (Randhara Section) (SH:- Hiring of JCB for removal of slips, cleaning of debries, drain and dressing of berms etc).	Rs 93,500	Rs 2,000	Rs. 350	One Month
9.	RRD on various roads under Mandi Sub Division No-IV HPPWD Mandi (Randhara Section) (SH:- Hiring of JCB for removal of slips, cleaning of debries, drain and dressing of berms etc).	Rs 99,000	Rs 2,000	Rs. 350	One Month
10.	RRD on Ganpati Kun Ka Tar road km 0/00 to 21/5600 (SH:- (Supplying and stacking at the site stone aggregate 53mm to 22.5mm size)	Rs 37,125	Rs 800	Rs. 350	One Month

11.	Annual repair and maintenance of old Mandi Shimla road km. 0/00 to 0/630. (SH:- Providing and applying 2.5mm thick road marking strips at RD 0/00 to 0/630. Skodhi Chowk and Bus School bazar works etcetera.(Job No.II)	Rs 62,013	Rs 1,300	Rs. 350	One Month
12.	Annual repair and maintenance of Residential and non residential building HPPWD Department Jail road Mandi (H.P) (SH:- Providing and fixing float valve, wheel and hydraulic door closer work etcetera.	Rs 49,467	Rs 1,000	Rs. 350	One Month
13.	Special repair of Session house, Judge Residence at Tarna Mandi, Distt, Mandi (H.P) (SH:- Providing cement concrete flooring, painting and plaster work etcetera.	Rs 75,623	Rs 1,500	Rs. 350	One Month
14.	Annual repair and maintenance of Old Mandi Shimla road km. 0/00 to 0/630. (SH:- Providing and applying 2.5mm thick road marking strips at RD 0/00 TO 0/630, Skodhi Chowk and Bus stop at School bazar works etcetera. (Job No. II)	Rs 58,418	Rs 1,200	Rs. 350	One Month
15.	Annual repair and maintenance of A.D J-II residence at Bhiuli Distt Mandi (H.P) (SH:- Providing and fixing cupboards, shelves etcetera(Job No.I)	Rs 98,471	Rs 2,000	Rs. 350	One Month
16.	Annual repair and maintenance of A.D J-II residence at Bhiuli Distt. Mandi (H.P) (SH:- Providing and fixing cupboards, shelves etcetera (Job No.2)	Rs 95,612	Rs 2,000	Rs. 350	One Month
17.	Annual repair and maintenance of Nerchowk Pandoh bypass road (section of NH-21)KM. 198/145 TO 203/500. (SH:- Clearing of shrubs and bushes.	Rs 85,015	Rs 1,700	Rs. 350	One Month
18.	Annual repair and maintenance of Nerchowk Pandoh bypass road (Section of NH-21)km. 198/145 to 203/500. (SH:- White washing and painting work.	Rs 98,731	Rs 2,000	Rs. 350	One Month
19.	RRD on Ratti Pul to Janed Panchyat Ghar road km. 0/00 to 2/900. (SH:- Repair of 3.00 mtr span culvert at Rd 2/325).	Rs 51,046	Rs 1,100	Rs. 350	One Month
20.	Annual repair and maintenance of Non residential building PWD Department Jail road Mandi (H.P) (SH:- Providing and fixing seat cover, sanitary pad machine , long body tab & other works etc. in Chief Engineer office & PVC cistern, soap tray in Division office Mandi-II	Rs 72,694	Rs 1,500	Rs. 350	One Month
21.	C/O Veterinary Hospital (Jaral) Pandoh Tehsil Sadar Distt. Mandi (H.P) (SH:- P/L marble work in room shelves).	Rs 88,152	Rs 1,800	Rs. 350	One Month
22.	C/O Manthala Rachwana Gaterbag road km.0/00 to 3/500. (SH:- Balance work of 3.00 mtrs span RCC slab culvert wing walls LHS U/S (Job no-I).	Rs 90,790	Rs 2,000	Rs. 350	One Month
23.	C/O Manthala Rachwana Gaterbag road km.0/00 to 3/500. (SH:- Balance work of 3.00 mtrs span RCC slab culvert wing walls LHS D/S (Job No.2)	Rs 91,336	Rs 2,000	Rs. 350	One Month
24.	RRD on under Mandi Sub Division No-IV HPPWD Mandi. (Bir Section) (SH:- Hiring of JCB for removal of slips, clearing of debries, drain and dressing of berms etc)	Rs 99,000	Rs 2,000	Rs. 350	One Month
25.	Special repair of Chanani Stairs near Seri Manch Mandi. (SH:- Dismantling Kota stone tiles& providing and laying granite in stairs.	Rs 97,793	Rs 2,000	Rs. 350	One Month
26.	Special repair of old laparoscopy building of Zonal Hospital Mandi at Raghunath ka Padhar Tehsil Sadar Distt. Mandi (H.P.) Sub Head: - Construction of concrete work in Boundary wall, etc. (Job No.1)	Rs 99,374	Rs 2,000	Rs. 350	One Month
27.	Special repair of old laparoscopy building of Zonal Hospital Mandi at Raghunath ka Padhar Tehsil Sadar Distt. Mandi (H.P.) Sub Head: - Construction of concrete and Brick work in Boundary wall, etc. (Job No.II)	Rs 98,800	Rs 2,000	Rs. 350	One Month
28.	Special repair of old laparoscopy building of Zonal Hospital Mandi at Raghunath ka Padhar Tehsil Sadar Distt. Mandi (H.P.) Sub Head: - Construction of Brick work in Boundary wall, etc. (Job No.III)	Rs 99,920	Rs 2,000	Rs. 350	One Month

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest. The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.


1. The valid enlistment/Registration of contractor in Appropriate Class.
2. Permanent account No. (PAN NO), G.S.T No.
3. Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Mandi Division No-II HPPWD Mandi.
4. The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
5. The officer of the tender shall remain valid up to 75 days after the opening of tender.
6. Ambiguous/telephonic/conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
7. Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.
8. If the date given above happens to be holiday the same shall be processed on next working day.
9. The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
10. The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
11. Work should be completed by the contractor within stipulated period.
12. The tender form will not be issued to those contractors whose past performance is not good and those who have many works in hand.
13. The bidders bidding for works at Sr. No. 1 to 4 must possess degree in Architecture & he/she should be member of council of architecture strict proof of same be produced.


Executive Engineer
Mandi Division No.II
HP.PWD Mandi
Dated: 28/01/2025

No.PW-MDII-CB NIT (off line) /2024-

Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-chief, HPPWD: Shimla.
2. The Deputy Commissioner Mandi Distt. Mandi HP
3. The Sub Divisional officer (Civil) Sadar Mandi Distt. Mandi HP
4. The Chief Engineer, (MZ)HPPWD: Mandi.
5. The Superintending Engineer, 1st Circle, HPPWD: Mandi.
6. The Distt. Panchyat officer Mandi Distt. Mandi HP
7. The Commissioner Nagar Nigam Mandi Distt. Mandi HP
8. All A. E, S under this division.
9. The President of Contractor's Association.
10. Notice Board/Accounts Branch/Drawing Branch/Supdt. With spare copies


Executive Engineer
Mandi Division No.II
HP.PWD Mandi

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 98000.00
 Earnest Money:- Rs. 2000.00
 Time:- One Month

Name of work:- Construction of Indoor Stadium at Paddal Mandi District Mandi HP.
 Sub Head:- Submission of Structural design and approval of competent authority

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Submission of Structural Design and its approval thereafter from competent authority of department as per direction of Engineer-in-charge.	1.00 No.	98000.00	Rupees, ninety eight thousand and paise nil only	Per Job	98000.00
				Total:-		98000.00


 Executive Engineer,
 Mandi Division No II,
 PWD Mandi

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 98000.00
Earnest Money:- Rs. 2000.00
Time:- One Month

Name of work:- Construction of Indoor Stadium at Paddal Mandi District Mandi HP
Sub Head:- Submission of Structural drawing and approval of competent authority.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Submission of Structural drawing and its approval thereafter from competent authority of department as per direction of Engineer-in-charge.	1.00 No.	98000.00	Rupees ninety eight thousand and paise nil only	Per Job	98000.00
				Total:-		98000.00


Executive Engineer,
 Mandi Division No. II,
 AHP EWD. Mandi.

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 98000.00
 Earnest Money:- Rs. 2000.00
 Time:- One Month

Name of work:- Construction of Indoor Stadium at Paddal Mandi District Mandi HP.
Sub Head:- Submission of working drawings and approval of competent authority.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Submission of working drawing and its approval thereafter from competent authority of department as per direction of Engineer-in-charge	1.00 No	98000.00	Rupees ninety eight thousand and paise nil only	Per Job	98000.00
	Total:-					98000.00


 Executive Engineer,
 Mandi Division No II,
 H.P. PWD Mandi

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 98000.00

Earnest Money:- Rs. 2000.00

Time:- One Month

Name of work:- Construction of Indoor Stadium at Paddal Mandi District Mandi HP
Sub Head:- Vetting of structural design/drawings and approval of competent authority

Sr. No.	Description of Item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Vetting of structural design/drawings from NIT/IIIT or PEC Chandigarh and its approval thereafter from competent authority of department as per direction of Engineer-in-charge	1.00 No	98000.00	Rupees ninety eight thousand and paise nil only	Per Job	98000.00
				Total:-		98000.00



Executive Engineer,
 Mandi Division No.II,
 HP.PWD Mandi.

%AGE OF SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Ner Chowk- Pandoh bypass road (Portion of NH-21) road from Km. 198/145 to 203/500).
(SH :- Hiring of J.C.B for excavation of Katcha drain & removal of slips and dressing of berms etc.
at various RD's.)

Estimated Cost Rs. 99,000/-
Earnest Money Rs. 2,000/
Time :- Two Months.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of J.C.B. one cum bucket capacity for removal of slips, clearing of debris, drains, dressing of berms etc. from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	90.00	1100.00	Ruppes One Thousand One Hundred Only	Per Hour	99,000.00
					Total	99,000.00


Executive Engineer
Mandi Division No.-II
H.P.P.W.D. Mandi

592

DRAFT SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Net Chowk Pandoh bypass road (Portion of NH-21) road from km. 198/145 to 203/500)
 (SH:- Hiring of Tipper for carriage of debris/muck at RD 198/145 to 203/500) Job No. 2

Estimated Cost Rs 99,000/
 Earnest Money Rs. 2,000/-
 Time : forty five days.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8 00 hours (Eight hours) from 9.00 A.M. to 5.00 P.M. daily. Any loss to the public/ private property of any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him all cases. The fuel of the tipper driver, repair work shall have to be born by the contractor/ owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in-charge.	33 00	3000.00	Rupees Three Thousand Only	Per day	99,000.00
Total						99,000.00

Pls
~~NOT checked and approved for Rs. 99,000/-~~

Assistant Engineer
 Sub Divn. No. - III
 H.P.W.D. Mandi.

9
 DMT approved for Rs. 99000/-

Executive Engineer
 Mandi Division No.-II
 H.P.W.D. Mandi

593

DRAFT SCHEDULE OF QUANTITY

Name of work :- A/R & M/O Net Chowk- Pandoh bypass road (Portion of NH 21) road from Km. 198/145 to 203/500).
(SH:- Hiring of Tipper for carriage of debris/muck at KU 198/145 to 203/500) Job No. 1

Estimated Cost Rs. 99,000/-
Earnest Money Rs. 2,000/-
Time :- forty five days.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8.00 hours (Eight hours) from 9.00 A.M. to 5.00 P.M. daily. Any loss to the public/ private property of any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him all cases. The fuel of the tipper driver, repair work shall have to be born by the contractor/ owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in-charge.	33.00	3000.00	Rupees Three Thousand Only	Per day	99,000.00
Total						99,000.00

the

Assistant Engineer
Sub Divn. No. - III
H.P.W.D. Mandi.

Draft checked and approved for Rs. 99,000/- only

Draft approved for Rs. 99,000/-


Executive Engineer
Mandi Division No.-II
H.P.P.W.D. Mandi

Name of work :- RRD on various roads under Mandi Sub Division No-IV HP PWD Mandi (Radhara Section)
 (SH:- Hiring of JCB for removal of slips, cleaning of debris, drain and dressing of berms etc)

Estimated Cost Rs. 93,500/-only
 Earnest Money Rs. 2,000/-only
 Time :- One month.

Percentage Rate Schedule of quantity

Sr. No.	Description of items.	Qty.	Rates In:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB for removal of slips, cleaning of debris, drain and dressing of berms etc in all kind of soil and trimming of side slopes and disposing of excavated earth up to any lead from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	85.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	93,500.00
					Total	93,500.00


 Executive Engineer,
 Mandi Division No-II,
 HP.PWD. Mandi.

Name of work : RRD on various roads under Mandi Sub Division No-IV HP PWD Mandi (Radhara Section)
(Sft. Hiring of JCB for removal of slips, cleaning of debris, drain and dressing of berms etc)

Estimated Cost Rs. 99,000/- only
Earnest Money Rs. 2,000/- only
Time : One month.

Percentage Rate Schedule of quantity

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB for removal of slips, cleaning of debris, drain and dressing of berms etc in all kind of soil and trimming of side slopes and disposing of excavated earth up to any lead from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	90.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99,000.00
					Total	99,000.00


Executive Engineer,
Mandi Division No-II,
HP.PWD. Mandi.

Name of work :- RRD on Ganpat Kun Ka Tar road km 0/00 to 21/5000 SH:- (Supplying and stacking at the site stone aggregate 53 mm to 22.5 mm size)

ESTIMATED COST :- 37125.00
 Earnest money :- 800.00
 TIME:- One month

Percentage Rate Schedule of Quantity

Sr.No.	Description of item	Quantity	Unit	Rate		Amount
				In fig	In Words	
1	Supplying and stacking of crushed stone aggregate 53 mm to 22.5mm(fourty five totwenty two point five millimeter) nominal size free form dirt dust, disintegrated pieces, deleterious and organic matter including loading at crusher site and unloading at site of work in proper stack as per PWD specification and as direction of the Engineer-in-charge including cartage of material with in all leads and lifts complete in all respect.	22.50	Per Cum	1650.00	Rupees Two thousand seven () only	37125.00
	Total					37125.00

Terms and conditions :- (1) The materials should be free from dirt, duct day leaves or any other organic matter soft and deck eyed, if the material is found below specification the same shall be rejected and nothing for the same shall be paid to the contractor.
 2.) The payment shall be made after deduction of voids as per norms.


 Assistant Engineer,
 Sub-Div No IV
 H.P.P.W.D. Mandi


 Executive Engineer
 Mandi Division No-II
 H.P.P.W.D. Mandi

Estimated Cost:-	Rs. 62013 00
Earnest Money:-	Rs. 1300 00
Time:-	One Month

Sub Head:- Providing and applying 2 5mm thick road marking strips at RD 0/0 to 0/630, Skodhi Chowk and Bus stop at School bazar works etcetera.(Job No.1)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	Providing and applying 2.5 mm (two point five millimetre) thick road marking strips (retro-reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi-automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etcetera complete in all respect including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	82.80	748 95	Rupees Seven Hundred Forty Eight square and Paise Ninety Five metre Only	Per square metre	62013.00
				Total:-		62013.00

Executive Engineer,
Mandi Division No II,
H.P. P.W.D. Mandi

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 49467.00
Earnest Money:- Rs. 1000.00
Time:- One Month

Name of work:- Annual repair and maintenance of Residential and non residential building HP PWD Department Jail road Mandi (H P)
Sub Head:- Providing and fixing float valve, wheel and hydraulic door closer work etcetera

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	Providing and fixing 20mm (twenty millimetre) nominal bore ball valve (brass) of approved quality. High or low pressure with plastic floats complete within all leads. lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge	16.00	716.75	Rupees Seven Hundred Sixteen and Paise Seventy Five Only	Each	11468.00
2	Providing and fixing 20mm (twenty millimetre) nominal bore gun metal gate valve with C.I wheel of approved quality (screwed end) complete within all leads. lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge	16.00	560.50	Rupees Five Hundred Sixty and Paise Fifty Only	Each	8968.00
3	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI IS 3564, embossed on the body door weight upto 35 kg (thirty five kilogram) and door width upto 700 mm(seven hundred millimetre). with necessary accessories and screws etcetera complete within all leads. lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge	15.00	1614.50	Rupees One Thousand Six Hundred Fourteen and Paise Fifty Only	Each	24218.00
4	Providing and fixing 20mm diameter (twenty millimetre) nominal bore G.I pipes complete with G.I fittings including trenching and refilling etc complete within all leads. lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge	17.10	281.45	Rupees Two Hundred Eighty One and Paise Forty Five Only	Per running metre	4813.00
	Total:-					49467.00


 Executive Engineer,
 Mandi Division No. II,
 HP PWD, Mandi

Percentage Rate Schedule of Quantity

Estimated Cost:-Rs. 75623.00
 Earnest Money:-Rs. 1500.00
 Time:- One Month

Name of work:- Special repair of Session house, Judge Residence at Tama Mandi, Distt. Mandi (HP).
 Sub Head:- Providing cement concrete flooring, painting and plaster work etcetera

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	40 mm (Forty millimetre) thick cement concrete flooring 1 2 4 (One cement two coarse sand four graded stone aggregate 20mm (Twenty millimetre) nominal size) finished with a floating coat of neat cement including cement slurry but excluding the cost of nosing of steps etc. including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge	75.75	468.40	Rupees Four Hundred Sixty Eight and Paise Forty Only	Per square metre	35481.00
2	Applying priming coat with readymixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge	45.69	56.05	Rupees Fifty Six and Paise Five Only	Per square metre	2561.00
3	Painting two or more coats on new work with synthetic enamel paint of approved brand and manufacture to give an even shade including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge	45.69	145.90	Rupees Hundred Forty Five and Paise Ninety Only	Per square metre	6666.00
4	15 mm (Fifteen millimetre) cement plaster in 1 3 (one cement three coarse sand) finished with a floating coat of neat cement on the rough side of single or half brick wall including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge	63.63	358.35	Rupees Hundred Fifty Eight and Paise Thirty Five Only	Per square metre	22802.00
5	Constructing masonry Chamber 30x30x50cm (thirty into thirty into fifty centimetre) inside, in brick work in cement mortar 1 4 (one cement four coarse sand) for stop cock with C 1 surface box 100x100 x75 mm (one hundred into one hundred into seventy five millimetre) (inside) with hinged cover fixed in cement concrete slab 1 2 4 mix (one cement two coarse sand four graded stone aggregate 20 mm (twenty millimetre) nominal size) including necessary excavation, foundation concrete 1 5 10 (one cement five fine sand ten graded stone aggregate 40mm (forty millimetre) nominal size) and inside plastering with cement mortar 1 3 (one cement three coarse sand) 12mm (twelve millimetre) thick, finished with a floating coat of neat cement complete as per standard design including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge	2.00	1688.00	Rupees Thousand Hundred Eighty Only	Each	3376.00
6	Finishing walls with water proofing cement paint of required shade on new work (Two or more coats applied @ (at the rate of) 3.84 kg/10 sqm (three point eight four kilogram per ten squaremetre) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge	40.80	116.10	Rupees One Hundred Sixteen and Paise Ten Only	Per square metre	4737.00
Total:-						75623.00

Engineer,
 Mandi Division No. 8,
 HP PWD Mandi

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 58418.00


Earnest Money:- Rs. 1200.00

Time:- One Month

Name of work:- Annual repair and maintenance of old Mandi Shimla road Km 0/0 to 0/630.

Sub Head :- Providing and applying 2.5mm thick road marking strips at RD 0/0 to 0/630, Skodhi Chowk and Bus stop at School bazar works etcetera (Job No.II)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	Providing and applying 2.5 mm (two point five millimetre) thick road marking strips (retro-reflective) of specified shade/ colour using hot thermoplastic material by fully/semiautomatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etcetera complete in all respect including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge	78.00	748.95	Rupees Seven Hundred Forty Eight and Paise Ninety Five Only	Per square metre	58418.00
	Total:-					58418.00


Executive Engineer,
 Mandi Division No II,
 HP PWD Mandi

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 98471.00
Earnest Money:- Rs. 2000.00
Time:- One Month

Name of work:- Annual repair and maintenance of A D J-II residence at Bhuli, Distt. Mandi (H P)
Sub Head:- Providing and fixing cupboards, shelves etcetera (Job No.I)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	Providing and fixing 18mm (eighteen millimetre) thick HDMR both side prelaminated board in Shutter/shelves/cup board with butt joints complete with all accessories including carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge	30.60	3218.00	Rupees Thousand Two Hundred Eighteen Only	Three Per square metre	98471.00
	Total:-					98471.00


 Executive Engineer
 Mandi Division No II
 MP PWD Mandi

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 95612.00
 Earnest Money:- Rs. 2000.00
 Time:- One Month

Name of work:- Annual repair and maintenance of A D J-II residence at Bhuli, Distt. Mandi (H P)
 Sub Head:- Providing and fixing cupboards, shelves etcetera. (Job No.2)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2 Providing and fixing 18mm (eighteen millimetre) thick HDMR both side prelaminated board in Shutter/shelves/cup board with butt joints complete with all accessories including carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge	3 13.26	4 3218.00	5 Rupees Three Thousand Two Hundred Eighteen Only	6 Per square metre	7 42671.00
2	Providing and fixing 6mm (six millimetre) thick HDMR both side prelaminated board in partition of cup board with butt joints complete with all accessories including carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge	19.01	1888.55	Rupees One Thousand Eight Hundred Eighty Five Only	Per square metre	35898.00
3	Providing and Fixing decorative high pressure 15mm(one point five millimetre) thick laminated sheet of plain / wood grain in gloss / matt/ suede finish with high density protective surface layer and reverse side of adhesive bonding quality conforming to IS 2046 Type S, including cost of adhesive of approved quality complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge	8.64	1972.55	Rupees One Thousand Nine Hundred Seventy Two and Paise Fifty Five Only	Per square metre	17043.00
				Total:-		95612.00


 Executive Engineer,
 Mandi Division No II,
 PWD Mandi

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 25015.00.

Earnest Money:- Rs. 1700.00

Time:- One Month

Name of work:- Annual repair and maintenance of Nerchowk Pandoh bypass road (section of NH-21) Km 198/145 to 203/500

Sub Head:- Clearing of shrubs and bushes.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge	10249.00	4 65	Rupees Four and Paise Sixty Five Only	Per square metre	47658.00
2	Cutting of shrubs from the road way or with in R.O.W and disposal of shrubs to suitable locations as per technical specifications Clause 1914 complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	467.00	14 00	Rupees Fourteen Only	Each	6538.00
3	Cutting of branches of trees and shrubs from the road way or with in R.O.W including disposal of wood and leaves to suitable location as per technical specification Clause 1914 complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	147.00	209.65	Rupees Two Hundred Nine and Paise Sixty Five Only	Each	30813.00
	Total:-					85015.00

Executive Engineer,
Mandi Division No.II,
RHP PWD, Mandi

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 98731.00
Earnest Money:- Rs. 2000.00
Time:- One Month

Name of work:- Annual repair and maintenance of Nerchowk Pandoh bypass road (section of NH-21) Km 198/145 to 203/500.

Sub Head:- White washing and painting work

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge	1005.00	25.65	Rupees Twenty Five and Paise Sixty Five Only	Per square metre	25778.00
2	Painting Steel work with Deluxe Multi Surface Paint to give an even shade Two or more coat applied @ (at the rate of) 0.90 ltr/10 sqm (zero point nine zero litre per ten square metre) over an under coat of primer applied @ (at the rate of) 0.80 ltr/10 sqm (zero point eight zero litre per ten square metre) of approved brand and manufacture complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	323.06	136.05	Rupees One Hundred Thirty Six and Paise Five Only	Per square metre	43952.00
3	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge	46.80	54.25	Rupees Fifty Four and Paise Twenty Five Only	Per square metre	2539.00
4	Wall painting two or more coats on new work with acrylic emulsion paint of approved brand and manufacture to give an even shade complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	222.93	118.70	Rupees One Hundred Eighteen and Paise Seventy Only	Per square metre	26462.00
	Total:-					98731.00

15



Executive Engineer,
Mandi Division No. II,
HP PWD, Mandi.

Percentage Rate SCHEDULE OF QUANTITY

Name of work :- RRI) on Ratu Pul to Jaland Panchayat Char road Km 0/00 to 2/900.
(SH: Repair of 3.00 mtr span culvert at Rd 2/325)

Estimated Cost Rs. 51,046/-
Earnest Money Rs. 1,100/-
Tender: One month.

Sr. No.	Description of items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation for structure as per drawing and technical specifications Clause 305.1 for retaining wall, breast wall, toe wall, abutments etc. in all kind of soil such as pick work, jumper work, pick jumper, pick jumper blasting work, blasting work in soft and hard rock, conglomerate rock or saturated soil and its intermediate classification of soil including chiseling/ wedging out of rock (where blasting is prohibited) including pumping or bailing out of watering /dewatering by all means upto any depth including setting out, construction of shoring, bracing, removal of slush and other deleterious material upto any lead and lift by all means of transportation dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge.	3.60	524.10	Rupees Five Hundred Twenty Four and Paise Ten Only	Per Cubic Metre	1,887.00
2	Providing and laying 1:3:6 (One cement : three sand : four graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	6.75	6318.75	Rupees Six Thousand Three Hundred Eighteen and Paise Seventy Five Only	Per Cubic Metre	42,652.00
3	Providing and laying flooring laid over cement concrete bedding complete as per drawing and technical specification Clause 1303 Rubble stone laid in cement mortar 1:3 (One cement : three sand) (Earth work in excavation and cement concrete for bedding to be measured and paid for separately) including carriage of materials with in all leads, lifts and other incidentals.	1.35	4820.10	Rupees Four Thousand Eight Hundred Twenty and Paise Ten Only	Per Cubic Metre	6,507.00
	Total					51,046.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

10

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 72694.00

Earnest Money:- Rs. 1500.00

Time:- One Month

Name of work:- Annual repair and maintenance of Non residential building PWD department Jail road Mandi (H.P.)

Sub Head:- Providing and fixing seat cover, sanitary pad machine, long body tab & other works etc. in Chief Engineer office & PVC cistern, soap tray in Division office Mandi II.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	Providing and fixing vitreous China (CERA) EWC(P) seat cover, hinges, accessories of superior quality as per direction complete within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	1.00 No.	1941.50	Rupees One Thousand Nine Hundred Forty One and Paise Fifty Only	Each	1942.00
2	Providing and fixing Sanitary pad disposal machine of superior quality complete within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	3.00 No.	13422.15	Rupees Thirteen Thousand Four Hundred Twenty Two and Paise Fifteen Only	Each	40266.00
3	Providing and fixing Long body tab of superior quality complete within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	3.00 No.	1581.95	Rupees One Thousand Five Hundred Eighty One and Paise Ninety Five Only	Each	4746.00
4	Providing and fixing Toilet paper holder of superior quality complete within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	6.00 No.	1439.70	Rupees One Thousand Four Hundred Thirty Nine and Paise Seventy Only	Each	8638.00
5	Providing and fixing 35mm (thirty millimetre) thick 2nd (second) class teak wood panelled or panelled and glazed shutters for doors windows and clerestory windows fixed with ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, excluding paneling which will be paid for separately all complete within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	2.85 Sqm	4921.10	Rupees Four Thousand Nine Hundred Twenty One and Paise Ten Only	Per Square metre	14025.00
6	Providing and fixing 10 (ten) litre P V C low level flushing cistern with manually controlled device (handle lever) conforming to IS 7231, with all fittings and fixtures complete within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	1.00 No.	2772.80	Rupees Two Thousand Seven Hundred Seventy Two and Paise Eighty Only	Each	2773.00
7	Providing and fixing PTMT soap Dish Holder having length of 138mm (one hundred thirty eight millimetre), breadth 102mm (one hundred two millimetre), height of 75mm (seventy five millimetre) with concealed fitting arrangements, weighing not less than 106 gms (one hundred six grams) complete within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	1.00 No.	303.75	Rupees Three Hundred Three and Paise Seventy Five Only	Each	304.00
	Total:-					72694.00


 Executive Engineer,
 Mandi Division No II,
 HP PWD Mandi.

Percentage Rate SCHEDULE OF QUANTITY

Name of work :- C/O Veterinary Hospital (Jaraal) Pandoh Tehsil Sadar Distt. Mandi (HP)
(Sh:- P/L marble work in room shelves)

Estimated Cost Rs. 88,152
Earnest Money Rs. 1,800/-
Time:- One month

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Earth work in excavation by mechanical means (hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge.	45.00	170.90	Rupees One Hundred Seventy and Paise Ninety Only	Per Cubic Metre	7,691.00
2	Providing and laying 40mm (forty millimetre) thick cement concrete flooring 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetre) nominal size) laid in one layer finished with a floating coat neat cement. in all floors including carriage of materials with in all leads, lifts and other incidentals.	17.63	496.65	Rupees Four Hundred Ninety Six and Paise Sixty Five Only	Per square Metre	8,756.00
3	Providing and fixing 16 mm (sixteen millimetre) thick gang saw cut, mirror polished, premoulded and polished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge.	19.10	3732.95	Rupees Three Thousand Seven Hundred Thirty Two and Paise Ninety Five Only	Per square Metre	71,299.00
4	Hacking of CC flooring including cleaning for surface etc. including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge.	27.49	2.30	Rupees Two and Paise Thirty Only	Per square Metre	63.00
5	Renewing 5.00 mm (five millimetre) glass panes weight not less than 12.50 Kg/sqm. (Twelve point fifty kilogramme) with wooden fillets including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer in-charge.	0.32	1072.40	Rupees One Thousand Seventy Two and Paise Forty Only	Per square Metre	343.00
	Total					88,152.00



Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

% age rate of SCHEDULE OF QUANTITY

Name of work :- C/O Manthala Rachwana Gatebag rod Km 0/00 to 3/500 (SH:- Balance work of 3.00 mtrs span RCC slab
Culvert wing walls. LHS U/S (Job no-II).

Estimated Cost Rs.90,790/-
Earnest Money Rs.2,000/-
Time:- One month.

Sr. No.	Description of items.	Quantity	Figure	Rates		Unit	Amount
				Words			
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 Pick Jumper work including carriage of materials with in all leads, lifts and other incidentals.	3.05	190.00	Rupees One Hundred Ninety Only		Per Cubic Metre	580.00
2	Earth work in excavation for structure as per drawing and technical specifications Clause 305.1 for retaining wall, breast wall, toe wall, abutments etc. in all kind of soil such as pick work, jumper work, pick jumper, pick jumper blasting work, blasting work in soft and hard rock, conglomerate rock or saturated soil and its intermediate classification of soil including chiseling/ wedging out of rock (where blasting is prohibited) including pumping or bailing out of watering /dewatering by all means upto any depth including setting out, construction of shoring, bracing, removal of slush and other deleterious material upto any lead and lift by all means of transportation dressing of sides and bottom and back filling in tranches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge	3.19	609.90	Rupees Six Hundred Nine and Paise Ninety Only		Per Cubic Metre	1946.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals.	15.00	5541.50	Rupees Five Thousand Five Hundred Forty One and Paise Fifty Only		Per Cubic Metre	83123.00
4	Providing wecp holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	5.00	388.20	Rupees Three Hundred Eighty Eight and Paise Twenty Only		Each	1941.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	1.91	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only		Per Cubic Metre	3200.00
	Total						90790.00


Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

Name of work :- C/O Manthala Rachwana Gaterbag rod Km 0/00 to 3/500 (SH:- Balance work of 3.00 mtr's span RCC slab Culvert wing walls, LHS D/S (job no-2).

Estimated Cost Rs.91,336/-
Earliest Money Rs.2,000/-
Time:- One month.

Percentage Rate SCHEDULE OF QUANTITY

Sr. No.	Description of Items.	Quantity	Rates		Unit	Amount
			Figure	Words		
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 Pick Jumper work including carriage of materials with in all leads, lifts and other incidentals.	3.07	190.00	Rupees One Hundred Ninety Only	Per Cubic Metre	583.00
2	Earth work in excavation for structure as per drawing and technical specifications Clause 305.1 for retaining wall, breast wall, toe wall, abutments etc. in all kind of soil such as pick work, jumper work, pick jumper, pick jumper blasting work, blasting work in soft and hard rock, conglomerate rock or saturated soil and its intermediate classification of soil including chiseling/ wedging out of rock (where blasting is prohibited) including pumping or bailing out of watering /dewatering by all means upto any depth including setting out, construction of shoring, bracing, removal of slush and other deleterious material upto any lead and lift by all means of transportation dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals or as per the direction of Engineer-in-charge	3.19	609.90	Rupees Six Hundred Nine and Paise Ninety Only	Per Cubic Metre	1946.00
3	Providing and laying 1:5:10 (One cement : five sand : ten graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain concrete in open foundations complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials	15.08	5541.50	Rupees Five Thousand Five Hundred Forty One and Paise Fifty Only	Per Cubic Metre	8356.00
4	Providing weep holes in block masonry/ stone masonry/ plain reinforced concrete abutments wing wall, return wall with 100mm PVC pipe extending through the full width of the structure with slope of 1 (V) : 20 (H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1203.3.7 including carriage of materials with in all leads, lifts and other incidentals.	5.00	388.20	Rupees Three Hundred Eighty Eight and Paise Twenty Only	Each	1941.00
5	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8. Granular material including carriage of materials with in all leads, lifts and other incidentals.	1.97	1675.15	Rupees One Thousand Six Hundred Seventy Five and Paise Fifteen Only	Per Cubic Metre	3300.00
	Total					91336.00

Executive Engineer,
Mandi Division No-II,
HP. PWD, Mandi.

Percentage Rate Schedule of quantity

Name of work :- RRD on under Mandi Sub Division no-IV HPPWD Mandi.(Bir Section)

(SH:- Hiring of JCB for removal of slips, cleaning of debris, drain and dressing of berms etc)

Estimated Cost Rs. 99,000/-only
Earnest Money Rs. 2000/-only
Time :- One month.

Sr. No.	Description of items.	Qty.	Rates in:		Unit.	Amount.
			Figure.	Words.		
1	Hiring of JCB for removal of slips, cleaning of debris, drain and dressing of berms etc in all kind of soil and trimming of side slopes and disposing of excavated earth up to any lead from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	90.00	1100.00	Rupees One Thousand One Hundred Only	Per Hour	99,000.00
					Total	99,000.00


 Executive Engineer,
 Mandi Division No-1,
 H.P.PWD. Mandi.

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 97793.00
Earnest Money:- Rs. 2000.00
Time:- One Month

Name of work:- Special repair of Chanam Stairs near Serl Manch Mandi.
Sub Head:- Dismantling Kota stone tiles & providing and laying granite in stairs.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	Dismantling tile work with any thickness in floors and roofs laid in cement mortar including stacking material complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge	11.09	47.20	Rupees Forty Seven and Paise Twenty Only	Per square metre	523.00
2	Providing and laying in position reinforced cement concrete 1:2:4 (one cement two coarse sand four graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) including curing complete excluding the cost of centering, shuttering, in all works up to all floor level complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge	1.92	6469.85	Rupees Six Thousand Four Hundred Sixty Nine and Paise Eighty Five Only	Per cubic metre	12422.00
3	Providing and fixing 18 mm (eighteen millimetre) thick gang saw cut, mirror polished, premoulded and prepolished, machine cut granite stone of required size and shape of approved shade, colour and texture in footpath, flooring in road side plazas and similar locations, laid over 20 mm (twenty millimetre) thick base cement mortar 1:4 (one cement : four coarse sand), including grouting the joints with white cement mixed with matching pigment, epoxy touch ups etcetera with granite stone of area less than 0.50 sqm (zero point five zero squaremetre) at all levels complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge	18.45	4598.80	Rupees Four Thousand Five Hundred Ninety Eight and Paise Eighty Only	Per square metre	84848.00
	Total:-					97793.00


Executive Engineer,
Mandi Division No.II,
AMPWD, Mandi.

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 99374.00
 Earnest Money:- Rs. 2000.00
 Time:- One Month

Name of work:- Special repair of old laproscopy building of Zonal Hospital Mandi at Raghunath ka Padhar Tehsil Sadar Dist Mandi (H P)
Sub Head:- Construction of concrete work in Boundary wall, etc. (Job No.1)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	Earth work in excavation in all kinds of soil by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten squaremetre) on plan), including dressing of sides and ramming of bottoms, upto any lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, upto any lead including carriage of material within all leads, lifts and other incidental charges complete in all respect as per direction and satisfaction of Engineer-in-Charge.	20.25	180.95	Rupees One Hundred Eighty and Paise Ninety Five Only	Per cubic metre	3664.00
2	Providing centering and shuttering including strutting,propping etcetera and removal of form for Retaining walls, return walls, walls (any thickness) including attached pilasters buttresses, plinth and string courses fillets, kerbs and steps etcetera complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge	60.00	437.30	Rupees Four Hundred Thirty Seven and Paise Thirty Only	Per square metre	26238.00
3	Providing and laying cement concrete 1.5:10 (one cement five coarse sand ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping bed blocks, anchor blocks, plain window sills, fillets, sunken floor etcetera up to floor all level, excluding the cost of centering, shuttering and finishing including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge	13.50	5146.05	Rupees Five Thousand One Hundred Forty Six and Paise Five Only	Per cubic metre	69472.00
Total:-						99374.00


 Executive Engineer,
 Mandi, Division No.II,
 HP PWD, Mandi.

Estimated Cost:- Rs.	98800 00
Earnest Money:- Rs.	2000 00
Time:-	One Month

One Month

Executive Engineer,
Mandi Division No. II,
MP PWD Mandi

Percentage Rate Schedule of Quantity

Estimated Cost:- Rs. 99920.00
 Earnest Money:- Rs. 2000.00
 Time:- One Month

Name of work:- Special repair of old laproscopy building of Zonal Hospital Mandi at Raghunath ka Padhar Tehsil Sadar Distt Mandi (H.P.)
 Sub Head:- Construction of Brick work in Boundary wall (Job No III)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	Brick work with common burnt clay F.P.S (non modular) bricks of class designation 7.5 in foundation and plinth in cement mortar 1:4 (one cement four sand) complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer in-Charge	9.98	10012.00	Rupees Ten Thousand Twelve Only	Per cubic metre	99920.00
	Total:-					99920.00


 Executive Engineer
 Mandi Division No II,
 HP PWD Mandi