

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No:-PW-NCD-E-Tender-NIT/2024-25- 9765-72

Dated:- 11.2.2025

To


The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject: - Publishing of tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Pncipal Secretary (PW), to the Govt. of H.P. letter No.PBW(B) A(3)1/2024 dated Shimla-2 the 03-01- 2024 as the works mentioned in the tender notice are urgent in nature and in public interest.


DA: - Notice Inviting Tender.
(31 Nos. Works)


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Copy forwarded to for information:-

Copy forwarded to the Superintending Engineer, 1st Circle, HP.PWD.,
Mandi for information please.

Copy to all the Assistant Engineers, working under this Division.
Copy to Account Branch in this office.
Copy to Drawing Branch in this office.
Notice Board.


Executive Engineer
Nerchowk Division
HPPWD Nerchowk.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER"

Sealed **Percentage rate** tenders on form "688" are invited by the Executive Engineer, Nerchowk, HPPWD Nerchowk for the following works from the approved and eligible contractors enlisted in H.P.P.W.D. so as to reach in this office on or before **25.02.2025 upto 01.30 PM** and will be opened on the same day at **3.00 PM** in the presence of interested contractors or their authorized representatives who may like to be present. If it happen to be holiday on the tender will be open on next working day. The application for obtaining the tender form will be received up to **11:30 AM on 22.02.2025** and tender form will be issued on dated **25.02.2025 upto 11:30 AM**. The EMD should be attached during the submission of application for obtaining the tender form. The application will not be accepted without Earnest Money & Cost of tender form.

The earnest money in the shape of FDR National Saving Certificate/Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany with each tender. The conditional tenders and the tenders received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for **75 days**. The Executive Engineer reserves the right to reject the tender's without assigning any reason:-

Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of Tender From (Rs.)	Time limit	Appropriate Class of Contractor
1	Restoration of rain damages on Manjhyali Ghour Sardhwar Kothigehri Batahan road km 0/000 to 13/000. (SH:- Construction of Breast wall at RD 2/322 to 2/330).	88188	1800	350	One Month	"D"
2	Construction of link road from Jakdohal Balahi to Batahan Gram Panchayat Kothi Gehri. (SH:- Construction of Retaining wall at RD 0/102 to 0/105). Under SCDP.	51332	1100	350	One Month	"D"
3	A/R & M/O on various roads under Rewalsar Sub Division HPPWD Rewalsar. (SH:- Hiring of Tipper for carriage of muck and patch work materials and other various works). Sardhwar Section.	94550	1900	350	Two Months	"D"
4	A/R & M/O Chandigarh Mandi Manali road (Old NH-21) KM 184/600 to 198/050 (SH: C/o PCC drain in 1:3:6 at RD 188/245 to 188/281).	98386	2000	350	Two Months	"D"
5	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Gagal Section) (SH: Supplying and stacking at site ordinary stone in various roads) Job No.I.	99400	2000	350	15 days	"D"
6	A/R & M/O on various roads under Sub-Division Nerchowk HPPWD Nerchowk. (SH:- Preparation of forest cases under FRA2006). 1. C/O link road from Double Lane road to the sites of National Disaster Response Force (NDRF) km 0/0 to 2/300.	95000	2000	350	12 Months	"D"
7	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Gagal Section) (SH:- Hiring of Tractor with trolley for carriage of muck/ debris and shifting of material etc).	99000	2000	350	Two Months	"D"
8	A/R & M/O various Bridges under Sub Division Rewalsar HPPWD Rewalsar. (SH:- Painting on various bridges). Leda Section.	92430	2000	350	One Month	"D"
9	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (SH: Hiring of Tipper for carriage of muck & Patch work material) (Gagal Section).	97600	2000	350	Two Months	"D"
10	C/o Type-III Qtr (One No.) Horticulture Department at Bhangrotu Tehsil Balh Distt. Mandi (HP) (SH: Prov. And fixing cup-board).	95532	2000	350	One Month	"D"
11	A/R & M/O Chandigarh Mandi Manali road (Old NH-21) KM 184/600 to 198/050 (SH: C/o PCC drain in 1:3:6 at RD 188/210 to 188/245).	95654	2000	350	Two Months	"D"

12	Restoration of rain damages on Chandyal to Chatru via Sishal Trambi road Km 0/0 to 6/0 (SH: Providing and filling selected soil in road stretch at RD 0/023 to 0/039)	98389	2000	350	Two Months	"D"
13	A/R & M/O Shri Lal Bahadur Shastri Govt. Medical College & Hospital Nerchowk, Distt. Mandi (HP) (SH: Preparation of working estimate for the painting and distempering etc. in non residential buildings)	99800	2000	350	One Month	"D"
14	RRD on various roads under Chakkar Sub Division, HPPWD Nerchowk (Nerchowk Sec.) (SH: Hiring of Tractor trolly for carriage of muck/ debris and shifting of materials etc.)	99000	2000	350	Two Months	"D"
15	C/o of Govt. High School Buildign at Sarkidhar, Sub Tehsil Rewalsar, Distt. Mandi (HP) (SH: Preparation of working estimate for C/o building portion with WS&SI, Septic Tank, RWHS and development of site etc.)	99500	2000	350	One Month	"D"
16	Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD Rewalsar, (Sardhwar Section). (SH:- Hiring of Earth cutting/ Excavating Machine for removal of slips, clearing of debris, drains and dressing of berms etecetra).	94550	1900	350	One Month	"D"
17	C/o Tanda Kohla Tikri Kawalkot- Sidhkothei (Via Baba BalakNath Mandir) Thapla Gabhol Galu road Km 0/0 to 5/150 (Portion KM 0/0 to 1/300) under NABARD Distt. Mandi (HP) (SH: Preparation of working estimate)	99500	2000	350	One Month	"D"
18	A/R & M/O Reur to Durgapur road km 0/0 to 4/0. (SH:- C/O Breast wall at RD 1/525 to 1/531.50).	96564	2000	350	Two Months	"D"
19	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Gagal Section) (SH: Supplying and stacking at site ordinary stone in various roads) Job No.II.	98000	2000	350	15 days	"D"
20	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Ratti Section) (SH: Hiring of JCB clearing of debris drains and dressing of berms etc.).	99750	2000	350	One Month	"D"
21	A/R & M/O Guest House Building SLBS Govt. Medical College & Hospital at Nerchowk. (SH:- Providing and Fixing curtain rods).	98274	2000	350	Two Months	"D"
22	C/o 45 mtr long PSC Box Girder Bridge over Ratti Khad at Chhuhata village at RD 1/650 (SH: Preparation of detailed estimate)	98000	2000	350	One Month	"D"
23	RRD on Samlon Manjhyali Chalehar Safru road KM 0/0 to 9/945 (SH: Removal of slips in various reaches , dressing of berms and clearing of drain in Km 0/0 to 5/0)	95325	2000	350	One Month	"D"
24	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk (Ratti Section) (SH: Hiring of JCB clearing of debris drains and dressing of berms etc.).	99750	2000	350	One Month	"D"
25	Restoration of rain damages on Ratti to Randhara road KM 0/0 to 9/0 (SH: C/o Retaining wall at RD 7/250 to 7/258).	95393	2000	350	Two Months	"D"
26	Restoration of rain damages on Tawan Kummi Bhiura Sakroha road KM 0/0 to 10/300 (SH: C/o Breast wall in P.C.C. 1:5:10 at RD 9/095 to 9/105).	94967	2000	350	Two Months	"D"
27	Restoration of rain damages on Chandyal to Chatru via Sishal Trambi road Km 0/0 to 6/0 (SH: Providing and filling selected soil in road stretch at RD 0/039 to 0/055)	95346	2000	350	Two Months	"D"
28	A/R & M/O Reur to Durgapur road km 0/0 to 4/0. (SH:- C/O Breast wall at RD 1/531.50 to 1/538).	96564	2000	350	Two Months	"D"

29	Restoration of rain damages on Rewalsar Galoo to Serla Khabu via Gehri road km 0/0 to 2/0. (SH:- Removal of Slip, dressing of berm, clearance of drain etc. in various reaches in km 0/0 to 0/975). Under OTMNP.	44292	1000	350	One Month	"D"
30	Addition & Alteration work in SLBS Govt. Medical College & Hospital at Nerchowk. (SH:- Providing and fixing Rolling shutters in ESS-1).	60815	1300	350	Two Months	"D"
31	Addition & Alteration work in the campus of SLBS Govt. Medical College & Hospital at Nerchowk. (SH:- C/O Aluminium partition in Admin Block outside of M.S. Office in first floor).	49563	1000	350	One Month	"D"

Note:- The Contractors/Firms should possess the following documents (Photo copy to be attached).

1. The Contractor/Firm should be enlisted with the HP.PWD. & Registration/Renewal copy attached.
2. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
3. The list of similar type of work executed and work done performance certificate issued by the concerned Executive Engineer required to be produced by the contractor along with application.
4. **Only two tenders shall be issued to each contractor.**
5. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking/affidavit alongwith application that he is not having more than two works in hand in HP.PWD for execution failing which the application for issuing the tender forms shall not be accepted.
6. The contractor/firm shall be issued tenders on the production of valid GST/income tax clearance certificate.
7. As per Govt. Notification No.PBW (B)A(3)1/2020-I dated 07.10.2021, in case the tendered amount of the lowest bidder comes more than 5% in 1st call the negotiation can be conducted with him but the negotiated amount should remain within 5% of the amount put to tender (on market rate) and vide Govt notification No.PBW (B)A(3)1/2020-I dated 10.05.2023 tendered amount below 30% of the estimated cost will be accepted.


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DNIT No. 55 FOR THE YEAR 2024-25

Sub No. 1

Draft Schedule of Quantity

Estimated Cost:- Rs. 88188.00
Earnest Money:- Rs. 1800.00
Time:- One Month

Name of work:- Restoration of rain damages on Manjhyali Ghour Sardhwar Kothigehr Batahan road Km. 0/000 to 13/000.
Sub Head:- Construction of Breast wall at R. D. 2/322 to 2/330.

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Excavation in soil in hilly area by mechanical means for all kinds of soil including cutting and trimming of side slopes and disposing of excavated earth with in all leads and lifts as per technical specification clause 1603.1. including carriage of material and other incidental charges complete in all respect as per direction of Engineer-in-Charge.	10.96 Cum.	172.00	Rupees one hundred seventy two and paise nil only	Per cubic metre	1885.00
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	16.80 Cum.	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	4822.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702,704,1202 & 1204 Random rubble masonry in cement mortar 1:6 (one cement : six sand) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	14.05 Cum.	3650.00	Rupees three thousand six hundred fifty and paise nil only	Per cubic metre	51283.00
4	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub structure and super structure complete as per Drawing and technical specifications clauses 704.6 & 1302.5 complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	14.38 Cum.	2100.00	Rupees two thousand one hundred and paise nil only	Per cubic metre	30198.00
					Total	88188.00

Draft schedule of quantity approved for Rs. 88,188/- only.

Executive Engineer,
H.P.W.D. Division,
Muzbawar

DNIT No. 52 FOR THE YEAR 2024-25

Job No. 2.

Draft Schedule of Quantity

Estimated Cost:- Rs 51332.00
Earnest Money:- Rs 1100.00
Time:- One Month

Name of work:- Construction of link road from Jakdohal Balahi to Batahan Gram Panchayat Kothi Gehri
Sub Head:- Construction of Retaining wall at R.D. 0/102 to 0/105 Under SCDP

Sr. No.	Description of item	Qty	Rate with all taxes including GST		Unit	Amount
			In Figure	In Rs. P. In words		
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	5.18 Cum	287.00	Rupees two hundred eighty seven and paise nil only	Per cubic metre	1487.00
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (one cement : six sand : twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	1.47 Cum	3090.00	Rupees three thousand ninety and paise nil only	Per cubic metre	4542.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clauses 702,704,1202 & 1204 Random rubble masonry in cement mortar 1:6 (one cement : six sand) curing complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	7.76 Cum	3650.00	Rupees three thousand six hundred fifty and paise nil only	Per cubic metre	28324.00
5	Construction of dry rubble masonry for retaining walls, breast walls, revetment walls and parapets etc for sub structure and super structure complete as per Drawing and technical specifications clauses 704.6 & 1302.5 complete within all leads, lifts carriage of material and other incidentals.	7.02 Cum	2100.00	Rupees two thousand one hundred and paise nil only	Per cubic metre	14742.00
6	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	2.13 Cum	1050.00	Rupees one thousand fifty and paise nil only	Per cubic metre	2237.00
	Total					51332.00

Draft schedule of quantity approved for Rs. 51,332/- only.

Executive Engineer,
H.P.W.D. Division,
Meerut.

DNIT NO. 135 FOR THE YEAR 2024-25

Job No. 3.

Draft Schedule of Quantity

Estimated Cost:- 94550.00
Earnest Money:- 1900.00
Time:- Two months

Name of work:- A/R & M/O on various roads under Rewalsar Sub-Division HP.PWD. Rewalsar.
Sub Head:- Hiring of Tipper for carriage of muck and patch work materials and other various works. (Sardhwar Section)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different site of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8.00(Eight hours) from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in charge.	31.00 days	3050.00	Rupees thousand fifty and paise nil only	Per day	94550.00
					Total:-	94550.00

*Draft schedule of quantity approved for Rs. 94,550/-
(Rupees Ninety four thousand Five Hundred fifty) only*

[Signature]
Executive Engineer,
Nerchowk Division,
HP.PWD. Merchak.

DIT No 326 for the year 2024-25

7/11/24

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Chandigarh Mandi Manali road (Old NH-21) Km. 184/600 to 198/050.
(SH:- Construction of P.C.C drain in 1:3:6 at RD. 188/245 to 188/281)

Estimated Cost:- 98386.00
Earnest Money :- 2000.00
Time :- Two Month

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. In figure	P. In word		
1	Earth work in excavation of foundation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	31.68	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	9092.00
2	Providing and laying plain/reinforced cement concrete in substructure as per drawing and technical specification clause 802,803,1202 and 1203 P.C.C nominal mix 1:3:6 (One cement: three sand:six graded stone aggregate) including carriage of material with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	18.72	4770.00	Rupees Four thousand seven hundred seventy and paise zero only.	Per Cubic Metre	89294.00
					Total	98386.00

Draft Schedule of quantity checked & approved for 98386/-
C Rupees Ninety Eight Thousand Three Hundred Eighty Six Only

Executive Engineer,
HPBWD Division,
HPBWD Nethowk

D.M.T No. (214) for the year 2024-25

Part No. 5

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Gagal Section)(SH:- Supplying and stacking at site ordinary stone in various roads) Job No. 1

Estimated Cost:- 99400.00
Earnest Money :- 2000.00
Time : 15 days

S.N	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
			In figure		In word	
1	Supplying and stacking of ordinary stone approved quality including loading at quarries site and unloading at site of work and stacking in proper stack along the road side as per direction of Engineer-in-charge with in all leads, lifts and carriage of materials and other incidentals.	71.00	1400.00		Rupees One thousand four hundred and paise nil only.	Per cubic Metre
						99400.00
					Total	99400.00

Draft Schedule of quantity checked & approved for Rs = 99,400/-
(Rupees ninety nine thousand four hundred) only

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

DRAFT SCHEDULE OF QUANTITY

Estimated Cost: 95000.00
 Earnes Money: 2000
 Time: 12 months

Name of work:- A/R and M/O on Various roads under Sub Division Nerchowk, H.P.P.W.D. Nerchowk (SH:-Preparation of forest cases under F.R.A. 2005)
 1.C/O Link Road From Double Lane Road To The Sites Of National Disaster Response Force (NDRF) Km. 0/0 To 2/300

Sr.No.	Description	Qty In Km.	Rate In		Unit	Amount
			Figure	Words		
1	Preparation of FRA case under forest conservation Act, 2006 including preparation of Digital Map of land falling in the Proposed Site and collection of other field data. All relevant documents/format mandatory required should be attached with the case as per latest requirement, of Ministry of Environment Govt. of India after getting the joint inspection/site etc. including computer typing one copy, binding complete and getting it through from HPPWD, Sub Division Nerchowk at HPPWD Nerchowk, Office of D.F.O. Mandi. The case including attending all observations, if raised, at any time by any office and prepare the same in all respect as per direction and complete satisfaction of public works department & forest department.	1 Job	95000	Ninety five thousand only	Per Job	95000
Total :-						95000.00

Draft Schedule of quantity checked & approved for Rs. = 95000/- only

(Rajeev Nigdyt five thousand) only

Assistant Engineer,
 Chakkar Sub-Division
 H.P.P.W.D. Ner Chowk

Executive Engineer
 Division Nerchowk
 HPPWD Nerchowk

Name of work: - A/R & M/O various roads under Chakkar Sub Division, H.P.PWD, Nerchowk (Gagal Section)

(SH:- Hiring of Tractor with trolley for carriage of muck/debris and shifting of material etc.

Estimated Cost Rs.99000/-
Earnest Money Rs.2000/-
Time:-Two Month

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of tractor with trolley with hydraulic lift system for carriage of material to different sites of work with in all leads & lifts and to the entire satisfaction of the Engineer-in-Charge. The tractor should work minimum 8 hours from 9 AM to 5 PM daily, any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the tractor owner which shall have to be fully compensated by him in all cases. The expenditure for fuel, lubricants, driver and repair work shall have to be borne by the tractor owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in Charge.	60 days	1650.00	Rupees one thousand Six Hundred Fifty only	Per Days	99000.00
Total -						99000.00

Assistant Engineer,
~~Chakkar Sub-Division,~~
HPPWD Nerchowk.

~~Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.~~

Draft Schedule of quantity checked & approved for US - 99000 only
(Rabeer Kingly nine thousand) *over*
[Signature]
Executive Engineer

DNIT NO. (124) FOR THE YEAR 2024-25

Mat No. 8

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various Bridges under Sub Division Rewalasaar HPPWD Rewalasaar. (SH:- Painting on various bridges) Leda Section

Estimated Cost:- 92430.00
Earnest Money :- 2000.00

Time :- One Month

S N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			In figure	In word		
1	Finishing walls with 100% (One hundred percent) Premium acrylic emulsion paint having VOC less than 50 gm/litre (Fifty gramme per litre) and UV resistance as per IS 15489:2004. Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm (one point four three litre per ten square metre) over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm (Zero point nine zero litre per ten square metre) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	479.76	125.20	Rupees One hundred twenty five and paise twenty only.	Per Square Metre	60066.00
2	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (Zero point nine zero litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (Zero point eight zero litre per ten square metre) of approved brand and manufacture including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	360.00	89.90	Rupees Eighty nine and paise ninety only.	Per square metre	32364.00
		Total				92430.00

Right schedule of quantity approved for Rs. 92,430-
(Rupees Ninety Two Thousand Four Hundred thirty-
Only.

Executive Engineer,
HPPWD Division
Nerchowk

DMIT S.No (215) for the Year 2024-25

DRAFT SCHEDULE OF QUANTITY

Name of work: - A/R & M/O various roads under Chakkar Sub Division H.P.PWD Nerchowk
(SH:- Hiring of Tipper for carriage of muck & Patch work material) (Gagal Section)

Estimated Cost 97600/-
Earnest Money Rs.2000/-
Time:- Two Month

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of Tipper 5.5 cum capacity having lift system for carriage of material to different sites of work with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 6 hours from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the tipper owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in charge.	32 Days	3050.00	Rupees Three thousand Fifty only	Per Days	97600.00
Total -						97600.00

[Signature]

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Draft Schedule of quantity and approved for Rs 97600/- Rupees Ninety Seven thousand Six Hundred only.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk

For the Year 2024-25

Job No. 11

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Chandigarh Mandi Manali road (Old NH-21) Km. 184/600 to 198/050.
(SH:- Construction of P.C.C drain in 1:3:6 at RD. 188/210 to 188/245)

Estimated Cost:- 95654.00
Earnest Money :- 2000.00
Time :- Two Month

S.N o	Description of Item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.	In figure	In word	
1	Earth work in excavation of foundation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	30.80	287.00		Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre 8240.00
2	Providing and laying plain/reinforced cement concrete in substructure as per drawing and technical specification clause 802,803,1202 and 1203 P.C.C nominal mix 1:3:6 (One cement: three sand:six graded stone aggregate) including carriage of material with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	18.20	4770.00		Rupees Four thousand seven hundred seventy and paise zero only.	Per Cubic Metre 86314.00
					Total	95654.00

Draft Schedule of Quantity checked & approved for Rs 95654/-
Rupees Ninety Five Thousand Six Hundred Fifty Four Only,

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

D.N.I.T No. (233) for the year 2024-25

Job No. 12

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Chandyal to Chatru via Sisai Trambi road 0/0 to 6/00. (SH:- Providing and filling selected soil in road stretch at RD. 0/023 to 0/039)

Estimated Cost:- 98389.00
Earnest Money :- 2000.00
Time :- One Month

S.N	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P	In word		
1	Construction of embankment with material obtained from borrow pits construction of embankment with appoeved pits with a lift to 1.5 metre transporting to site, spreading, grading to required slope and compacting to meet required slope and compacting to meet requirement of table 300.01 and 300.02 with a lead upto 5000 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	240.56	409.00	Rupees four hundred nine and paise zero only.	Per Cubic Metre	98389.00
					Total	98389.00

Draft Schedule of Quantity checked & approved for Rs. 98389/-
(Rupees Ninety eight thousand three hundred eighty nine) only.

Executive Engineer,
HPPWD Division,
HPPWD Noida

DNT No 9 FOR THE YEAR 2024-25

Page No. 13

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Shri Lal Bahadur Shastri Government Medical College & Hospital Nerchowk, Distt.

Estimated Cost:- 99800.00
Earnest Money :- 2000.00
Time :- One Month

Mandi H.P. (Sub Head:- Preparation of working estimate for the Painting and distemper etc. in non residential buildings)

S.N	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Preparation of working estimate for Painting and distemping of following non residential buildings i.e. PRA Building, Medical College, Guest House Building & RDH Building. The job shall include preparation of detailed estimate after measuring inner and outer dimentions of the building very precisely. The estimate should based on HPSR 2020/ market rates for non scheduled items. The job work shall include supplying of estimate as per directions of Engineer-in-Charge.	1	99800.00	Rupees Ninety nine thousand eight hundred and paise zero only.	Per Job	99800.00
					Total	99800.00

Draft schedule of quantity approved for Rs. 99,800/-
(Rupees Ninety nine thousand eight hundred) only.

Executive Engineer,
HPPWD Division,
Nerchowk.

DWP S.No. 78 for the year 2024-25
 Date No. 14

DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on various roads under Chakkar Sub Division, HPPWD Nerchowk. (Nerchowk Section) (SH:- Hiring of Tractor with trolly for carriage of muck/ debris and shifting of materials etc.)

Estimated Cost:-	99000.00
Earnest money:-	2000.00
Time:- Two Month	

S. No.	Description of item	Qty.	Rate in		Unit	Amount
			Figure	Words		
1	Hiring of tractor with trolley with hydraulic lift system for carriage of material to different sites of work with in all leads & lifts and to the entire satisfaction of the Engineer-in-Charge. The tractor should work minimum 8 hours from 9 AM to 5 PM daily. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the tractor owner which shall have to be fully compensated by him in all cases. The expenditure for fuel, lubricants, driver and repair work shall have to be borne by the tractor owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in Charge.	60.00	1650.00	Rupees One thousand six hundred fifty only.	Per day	99000.00
Total:-						99000.00

Draft schedule of quantity approved for 2,99,000/-

Executive Engineer
 HPPWD Division
 Nerchowk.

15

DNIT No. (32) FOR THE YEAR 2024-25

Part No. 15

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Govt. High School Building at Sarkidhar, Sub Tehsil Rewalsar, Tehsil Balh, Distt. Mandi (H.P.). (SH:- Preparation of working estimate for C/O building portion with W.S. & S.I., Septic Tank, Rain water harvesting system and Development of Site etc.)

Estimated Cost:- 99500.00
Earnest Money :- 2000.00
Time :- One Month

S.N	Description of item	Quantity	Rate with all taxes excluding GST in		Unit	Amount
			Rs. P.	In word		
1	Preparation of Working estimate of whole project as per Architectural Drawing for the Construction of Govt. High School Building at Sarkidhar, Sub Tehsil Rewalsar, Tehsil Balh, Distt. Mandi (H.P.) including Building portion with W.S. & S.I., Septic Tank, RWHT & Site Development etc.. The Job shall also include supplying detailed estimate as per analysis of rates on based on HPSR 2020/market rates for all the items appearing in the estimate. The work shall also include supplying the estimate in triplicate and approval of the same in divisional office/Circle office/CE office (MZ) Mandi complete as per directions of Engineer-in-charge.	1	99500.00	Rupees Ninety Nine Thousand Five Hundred and Paise Zero Only	Per Job	99500.00
Total						99500.00

Draft schedule of quantity approved for Rs. 99,500/-
(Rupees Ninety Nine thousand Five hundred only.)

Executive Engineer,
HPPWD Division
Nerchowk

DNIT NO 033 FOR THE YEAR 2024-25

Lab No. 16

Draft Schedule of Quantity

Estimated Cost:- 94500.00
Earnest Money:-Rs. 1900.00
Time:- One month

Name of work:- Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD Rewalsar. (Sardhwar Section)
Sub Head:- Hiring of Earth cutting / Excavating machine for removal of silps, clearing of debris, drains and dressing of berms etcetra.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer in-charge.	90.00 Hours	1050.00	Rupees thousand fifty and paise nil only	one Per hour	94500.00
Total:-						94500.00

Conditions:-
Contractor should have his own machinery or he should have an agreement with the owner of the machinery.

draft schedule of quantity approved for Rs. 94,500/- (Rupees Ninety four thousand Five Hundred) only

Executive Engineer,
Nerchowk Division,
H.P. PWD, Nerchowk.

DNIT No 211 for the Year 2024-25

2024 No. 17

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Tanda-Kohla-Tikrri-Kawalkot-Sidhkothei (Via Baba Balaknath Mandir)- Thapla-Gabhu; Galu road Km. 0/0 to 5/150 (Portion km. 0/0 to 1/300) under NABARD Distt. Mandi HP. (SH:- Preparation of working estimate)

Estimated Cost:- 99500.00
Earnest Money :- 2000.00
Time :- One Month

S.N	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Surveying and preparation of working estimate of construction of Tanda-Kohla-Tikrri-Kawalkot-Sidhkothei (Via Baba Balaknath Mandir)- Thapla-Gabhu Galu road Km. 0/0 to 5/150 (Portion km. 0/0 to 1/300) i.e. R.O.F.D., Cross-drainage work, Retaining Walls, Breast Walls & other necessary provision taken in the estimate, preparation of working estimate in duly approved from the higher office, if any correction/ amendments has disired by the head office, the same may be corrected as desired and complete as per directions of Engineer in charge.	1	99500.00	Rupees Ninety Nine Thousand Five Hundred and paise zero only.	Per Job	99500.00
Total						99500.00

Draft Schedule of quantity approved for
Rs 99500.00 (Rupees Ninety Nine thousand Five
Hundred) only.

Assistant Engineer,
Chakkar Sub-Division
HPWD, Mor Chowk

Executive Engineer,
HPWD Division
Nerchowk

DRAFT NO. (140) FOR THE YEAR 2024-25

Job No. 18

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Reur to Durgapur road km. 0/0 to 4/0. (SH:- C/O Breast wall at RD. 1/525 to 1/531.50)

Estimated Cost:- 96564.00
Earnest Money :- 2000.00

Time :- Two months

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P. In figure	In word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth up to any lead and lift as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	11.05	172.00	Rupees One hundred seventy two and paise zero only.	Per Cubic Metre	1901.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	5.32	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	1527.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 in cement concrete 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	21.56	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	91414.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material and other incidentals as per the direction of the Engineer-in-Charge.	6.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	1722.00
					Total	96564.00

Draft schedule of quantity approved for Rs. 46,564/- (Rupees five hundred sixty four) only

Executive Engineer,
HPPWD Division,
HPPWD Nerchowk

D.N.I.T. No. (218) for the year 2019-20

Chak No. 19

DRAFT SCHEDULE OF QUANTITY

A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (Gagal section) (SH:-Supply and staking at site at site Ordinary stone in various roads) Job No-2.

Estimated Cost:- 98000.00
Earnest Money :- 2000.00
Time :- 15 days

Sr.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Supplying and stacking of ordinary stone approved quality including loading at quarries site and unloading at site of work and stacking in proper stack along the road side as per direction of Engineer-in-charge with in all leads, lifts and carriage of materials and other incidentals.	70.00	1400.00	Rs. One Thousand Four Hundred only	Per cubic Metre	98000.00
Total						98000.00

*Draft schedule of quantity checked & approved for M. = 98000/- only
(Rupees Ninety eight thousand) only*

Executive Engineer,
HPPWD Division,
HPPWD-Nerchowk

DN/T S.No 213 for the year 2024-25

Lab No. 20

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O on various roads under Chakkar Sub Division HPPWD Nerchowk (Ratti section)

Estimated Cost Rs. 99750/-
Earnest Money Rs. 2000/-
Time: - One Month.

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	95 hours	1050.00	Rupees one Thousand fifty only	Per hours	99750.00
					Total:-	99750.00

Draft Schedule of quantity approved for Rs 99750.00/
Chakkar Ninety Nine thousand Seven Hundred Fifty Only.Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

DNIT NO (12) FOR THE YEAR 2024-25

Lab No. 21

Draft Schedule of Quantity

Estimated Cost:-Rs. 98274.00
Earnest Money:-Rs. 2000.00
Time:- Two Months

Name of work:- AVR & M/O Guest House Building SLBS Govt. Medical College & Hospital at Nerchowk

Sub Head:- Providing and fixing curtain rods

Sr. No.	Description of item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Providing and fixing 25 mm dia curtain rods of 1.25 mm thick chromium plated brass plate, with two chromium plated brass brackets fixed with C.P. brass screws and wooden plugs, etc., wherever necessary complete as per direction of Engineer-in-Charge:	130.00 Rmt	615.40	Rupees six hundred fifteen and paise forty only	Per Rmt	80002.00
2	Providing and fixing chromium plated brass curtain rod knob/end cap of ornamental design for 25mm dia pipes with CP screws etc complete as per direction of Engineer-in-Charge:	80.00 No.	228.40	Rupees two hundred twenty eight and paise forty only	Each	18272.00
Total:-						98274.00

Draft schedule of quantity approved for Rs. 98,274/-
(Rupees Ninety eight thousand Two Hundred Seventy four)

Executive Engineer,
HP.PWD.Division,
Nerchowk

DNT No. 219 for the year 2024-25

Job No. 22


DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of 45 mtr. long PSC Box Girder Bridge over Ratti Khad at Chhuhata Village at RD. 1/650 (Sub Head :- Preparation of Detailed estimate)

Estimated Cost:- 98000.00
Earnest Money :- 2000.00
Time :- One Month

S.N	Description of item	Quantity	Rate		Unit	Amount
			In figure	In word		
1	Preparation of detailed estimate for C/O 45 M LONG PSC BOX GIRDER BRIDGE OVER RATTI KHAD AT CHHUHATA VILLAGE AT RD 1/650. The job work also include supplying detail estimate based on HPSR with presently market rates duly supported with analysis of rate market rate. Detailed estimate duly approved from the Circle Office & Chief office. (three sets of detailed estimate and soft copy) as per direction of Engineer-in - charge.	1	98000.00	Rupees Ninety eight thousand and paise zero only.	Per Job	98000.00
					Total	98000.00

Draft Schedule of quantity checked & approved for
Rs 98000/- (Rupees Ninety Eight Thousand) only


Executive Engineer,
HPPWB Division
Nerchowki

DNT No (127) for the year 2024-025

Job No. 23

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :- RRD on Samloun Manjivai Chahar Saphru Road K. m. 0/0 to 9/945 (SH- Removal of slips in various reaches , dressing of berms & cleaning of drain in k.m 0/0 to 5/0

Estimated Cost :- 95325.00

Earnest Money :- 1890.00

Time :- One Month

Sr.No	Description of item	Quantity	Rate with all taxes including GST in Rs. P.		Unit	Total amount with all taxes including GST in Rs. P.
			In Figure	In words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material as per technical specification 302.3.5 and 1611 complete in all lead and lifts and as per direction of Engineer in charge.	650.00	99.80	Ruppes ninety nine and paise eighty only	Per cum	64870.00
2	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. complete in all lead and lifts and as per direction of Engineer in charge.	2300.00	3.35	Ruppes three and paise thirty five only	Per Running Metre	7705.00
3	Maintenance of Earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete in all lead and lifts and as per direction of Engineer in charge.	1625.00	14.00	Ruppes fourteen and paise zero only	Per Square meter	22750.00
						95325.00

Draft schedule of quantity approved for Rs. 95,325/- only (Ruppes Ninety five thousand Three hundred twenty five) only

Assistant Engineer,
Rewalsart Sub-division,
H.P.P.W.D. Nerchowk.

Executive Engineer,
HPPWD Division
Nerchowk

DMIT S.No 216 for the Year 2024-25

Sub No. 24

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O on various roads under Chakkar Sub Division HPPWD Nerchowk (Ratti section)

Estimated Cost Rs. 99750/-
Earnest Money Rs. 2000/-
Time:- One Month.

(SH:- Hiring of JCB clearing of debris drains and dressing of berms etc.)

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	95 hours	1050.00	Rupees one Thousand fifty only	Per hours	99750.00
Total:-						99750.00

*Draft schedule of quantity approved for Rs. 99750/-
(Rupees Ninety Nine Thousand Seven Hundred Fifty Only).*

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

Job No-25

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Ratti to Randhara road km. 0/0 to 9/0. (SH:- Construction of Retaining wall at RD. 7/250 to 7/258)

Estimated Cost:- 95393.00
Earnest Money :- 2000.00
Time :- Two Months

S. N	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P	In figure	In word	
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	9.68	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	2778.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : Ten graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	20.08	4240.00	Rupees Four thousand two hundred forty and paise only.	Per Cubic Metre	85139.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	3.84	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	4032.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge	12.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	3444.00
Total						95393.00

*Draft Schedule of quantity checked & approved for Rs 95393/-
Rupees Ninety Five thousand Three hundred and Ninety Three only.*

Executive Engineer,
HPPWD Division,
MPPWD Nerchowda

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Tawan Kumni Bhiura Sakroha road km. 0/0 to 10/300. (SH:- C/O Breast wall in P.C.C. 1:5:10 at RD. 9/995 to 9/105)

Estimated Cost:- 94967.00
Earnest Money :- 2000.00
Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.	In word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth up to any lead and lift as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	11.27	172.00	Rupees One hundred seventy two and paise zero only.	Per Cubic Metre	1932.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	7.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	2009.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 in cement concrete 1:5:10 (one cement, five sand : ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	20.79	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	88150.00
4	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material and other incidentals as per the direction of the Engineer-in-Charge.	10.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	2870.00
		Total				94967.00

Draft Schedule of quantity checked & approved for Rs. 94967/-

(Rupees Ninety four thousand Nine hundred eighty seven) only

Executive Engineer,
HPWD Division,
HPWD Nerchowky

D.N.J. Mr. (236) for the year 2021-22

Job No. 27


DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Chandyal to Chatru via Sishal Trambh road 0/0 to 6/00. (SH:- Providing and filling selected soil in road stretch at RD. 0/039 to 0/055)

Estimated Cost:- 95346.00
Earnest Money :- 2000.00
Time :- One Month

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P In figure	In word		
1	Construction of embankment with material obtained from borrow pits construction of embankment with approved pits with a lift to 1.5 metre transporting to site, spreading, grading to required slope and compacting to meet required slope and compacting to meet requirement of table 300.01 and 300.02 with a lead upto 5000 metre including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	233.12	409.00	Rupees four hundred nine and paise zero only.	Per Cubic Metre	95346.00
					Total	95346.00

*Draft Schedule of Quantity checked & approved for Rs. 95346/- only
(Rupees Ninety five thousand three hundred forty six) only*


Executive Engineer,
HPWD Division,
HPPWD Nerchowk

DRAFT NO. (143) FOR THE YEAR 2024-25

Job No. 28

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Reur to Durgapur road km. 0/0 to 4/0. (SH:- C/O Breast wall at RD. 1/531.50 to 1/538)

Estimated Cost:- 96564.00
Earnest Money :- 2000.00
Time :- Two Months

S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.	In word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth up to any lead and lift as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	11.05	172.00	Rupees One hundred seventy two and paise zero only.	Per Cubic Metre	1901.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	5.32	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	1527.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803.1202 and 1203 in cement concrete 1:5:10 (one cement: five sand: ten graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	21.56	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	91414.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material and other incidentals as per the direction of the Engineer-in-Charge.	6.00	287.00	Rupees Two hundred eighty seven and paise zero only.	Each	1722.00
					Total	96564.00

Executive Engineer
HPPWD Division,
CHPPWD Nercio

Job No. 29

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Rewalsar galoo to Seria Khabu via Gehri road km. 0/0 to 2/0. (SH:- Removal of slip, dressing of berm, clearance of drain etc. in various reaches in km. 0/0 to 0/275) Under OTMNP					Estimated Cost:- 44292.00	
					Earnest Money : 1200.00	
					Time :- One Month	
S.N o	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P In figure	In word		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	301.75	99.75	Rupees Ninety nine and paise seventy five only.	Per Cubic Metre	30100.00
2	Maintenance of Earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	804.38	14.00	Rupees Fourteen and paise zero only.	Per square Metre	11261.00
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 as per the entire satisfaction and direction of Engineer-in-Charge.	875.00	3.35	Rupees Three and paise thirty five only.	Per Running Metre	2931.00
					Total	44292.00

Draft schedule of quantity approved for
Rs. 44,292/- (Rupees Forty four thousand
Two Hundred Ninety two) only.


 Executive Engineer
 HPBWD Division,
 HPBWD Narchok

DNR No. (13) FOR THE YEAR 2024-25

Sl. No. 30

Draft Schedule of Quantity

Estimated Cost:-Rs. 60815.00
 Earnest Money:- Rs. 1300.00
 Time:- Two Months

Name of work:- Addition & alteration work in SLBS Govt. Medical College & Hospital at Nerchowk
 Sub Head:- Providing and fixing Rolling shutters in ESS-1

Sr. No.	Description of item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
1	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters complete as per direction of Engineer-in-Charge.	13.32 Rmt	3983.10	Rupees Three Thousand Eight Hundred Eighty Three and paise ten only	Per Rmt	53055.00
2	Providing and fixing ball bearing for rolling shutters complete as per direction of Engineer-in-Charge	2.00 No.	446.45	Rupees Four hundred Forty Six and paise forty five only	Each	893.00
3	Extra for providing mechanical device chain and crank operation for operating rolling shutters exceeding 10.00 sq.m and upto 16.80 sq.m area of door complete as per direction of Engineer-in-Charge.	1.00 No.	6867.10	Rupees Six Thousand Eight Hundred Sixty Seven and paise ten only	Each	6867.00
TOTAL						60815.00

Draft schedule of quantity approved for Rs. 60,815/- (Rupees Sixty thousand eight hundred fifteen) only.

Executive Engineer,
 HP/BWD/Division,
 Nerchowk.

DNIT NO. (14) FOR THE YEAR 2024-25

Page No. 31

Draft Schedule of Quantity

Estimated Cost:-Rs. 49563.00
 Earnest Money:- Rs. 1000.00
 Time:- One Month

Name of work:- Addition & alteration work in the campus of SLBS Govt. Medical College & Hospital at Nerchowk.
 Sub Head:- C/o aluminium partition in Admin Block outside of M.S. Office in first floor

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount	
			In Figure	In words			
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mited and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) *For fixed portion Anodised aluminium (anodised transparent or dyed to required shade) according to IS: 1868, Minimum anodic coating of grade AC 15)	49.48	544.23	Rupees Five Hundred Forty Four and paise twenty three only	Per Kg	26929.00	
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mited and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) *For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)	15.14	686.40	Rupees Six hundred Eighty Six and paise forty only	Each	10391.00	
3	Providing and fixing 12 mm thick prelaminated particle board with decorative lamination on one side and balancing lamination on other side, flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge	3.10	Sqm	1096.75	Rupees One Thousand Ninety Six and paise Seventy Five only	Per Sqm	3400.00

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount
			In Figure	In words		
4	Providing and fixing glazing with float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm) in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item)	4.29 Sqm	1611.95	Rupees One Thousand Six Hundred Eleven and paise Ninety Five only	Per Sqm	6915.00
5	Providing and fixing aluminium handles 200 mm, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete.	2.00 No.	76.70	Rupees Seventy Six and paise Seventy only	Each	153.00
6	Providing and fixing aluminium sliding door bolts 300x16 mm, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete.	2.00 No.	266.65	Rupees Two Hundred Sixty Six and paise Sixty Five only	Each	533.00
7	Providing and fixing aluminium lower bolts 300x10 mm, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete.	1.00 No.	122.50	Rupees One Hundred Twenty Two and paise Fifty only	Each	123.00
8	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer DC-40 SM (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete.	1.00 No.	1044.70	Rupees One Thousand Forty Four and paise Seventy only	Each	1045.00
9	Providing and fixing aluminium hanging type floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete.	1.00 No.	73.20	Rupees Seventy Three and paise Twenty only	Each	73.00
						49563.00

Right schedule of quantity approved for Rs. 49,563/- (Rupees Forty nine thousand five Hundred Sixty Three) only.

*Executive Engineer,
HP PWD Division,
Merchowk.*