



"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 24.02.2025 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 21.02.2025 up to 10.00 A.M. to 12:00 P.M. and tender form can be had from this office on 22.02.2025 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Repair & maintenance of Raja Bharola Nagan Harizan Basti Tramat upto village Chakka road Km. 0/0 to 4/500 under SCSP (SH:- Construction of Breast wall at km. 3/578 to 3/582).	Rs. 84,373/-	Rs. 1,700/-	Rs. 350/-	Class "D"	Three months
2	C/O Guini Kotla link road km. 0/0 to 3/0 under SCSP (SH:- Providing and laying cement concrete pavement from km. 0/947 to 0/991).	Rs. 92,394/-	Rs. 1,800/-	Rs. 350/-	Class "D"	Three months
3	Restoration of rain damages on various roads under Joginder Nagar Sub Division HPPWD, Joginder Nagar (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and Construction of road side katcha drains etc.).	Rs. 99,060/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
4	Repair & Maintenance of Raja Nagan Harizan Basti Tramat upto Village Chakka road km. 0/0 to 4/500 under SCSP (SH:- Construction of Breast wall at km. 3/574 to 3/574).	Rs. 84,373/-	Rs. 1,700/-	Rs. 350/-	Class "D"	Three months
5	A/R & M/O to PWD rest house at Neri District Mandi (H.P.) (SH:- Providing and Supplying Colour Blow Up Natural Photo Painting Frame).	Rs. 99,200/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One month
6	A/R & M/O to Various road under Joginder Nagar Sub Division, HPPWD, Joginder Nagar (Ladruhin Section)(SH:- Painting & Writing work etc.).	Rs. 99,197/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
7	Restoration of rain damages on various roads under Lad Bharol Sub Division HPPWD, Lad Bharol (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and Construction of road side katcha drains etc.).	Rs. 99,060/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
8	C/O & M/T on Galu Bhatwari road to village Badan & Changdhar km. 0/00 to 1/850 GP Ropa Padhar (SH:- Formation Cutting in km. 0/930 to 0/990).	Rs. 98,207/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
9	Restoration of rain damages on Bharraru to Chhamb road (SH:- Construction of Breast Wal at Km. 2/100 to 2/108).	Rs. 99,293/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Three months
10	Repair & Maintenance of Raja Nagan Harizan Basti Tramat upto Village Chakka road km. 0/0 to 4/500 under SCSP (SH:- Construction of Breast wall at km. 3/574 to 3/578).	Rs. 84,373/-	Rs. 1,700/-	Rs. 350/-	Class "D"	Three months
11	C/O Guini Kotla link road km. 0/0 to 3/0 under SCSP (SH:- Providing and laying cement concrete pavement from km. 0/860 to 0/902).	Rs. 88,194/-	Rs. 1,800/-	Rs. 350/-	Class "D"	Three months
12	Restoration of rain damages on Nanidhar road km. 0/00 to 1/325 (SH:- Construction of retaining wall at km. 0/500 to 0/507.20).	Rs. 1,18,574/-	Rs. 2,400/-	Rs. 350/-	Class "D"	Three months
13	R/O Restoration of rain damages on Majhamoo Syuri road km. 0/0 to 3/0 (SH:-Construction of retaining wall at RD. 1/215 to 1/220 under Deposit SID:SDP/2023/291).	Rs. 61,591/-	Rs. 1,200/-	Rs. 350/-	Class "D"	Three months
14	Restoration of rain damages on various roads under Lad Bharol Sub Division HPPWD, Lad Bharol (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and Construction of road side katcha drains etc.).	Rs. 99,060/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
15	Restoration of rain damages on Joginder Nagar Aarthi Shanan road km. 0/0 to 1/500 (SH:- Construction of retaining/Edge wall at Railway Junction/Crossing)	Rs. 89,144/-	Rs. 1,800/-	Rs. 350/-	Class "D"	Three months
16	C/O Mohanghati to Rada Malu Ghatagia Bhatwara Bhanjrala Matroo road km. 1/360 to 5/360 (SH:- Hiring of excavator cum loader for construction of Bhanjrala to Bhatu road km. 0/0 to 0/800).	Rs. 99,060/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
17	C/O & M/T on Galu Bhatwari road to village Badan & Changdhar km. 0/00 to 1/850 GP Ropa Padhar (SH: Formation Cutting in km. 0/855 to 0/922)	Rs. 98,536/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
18	Construction of link road Ambulance road Sarwaldi to Harizan basti Batdhar 0/0 to 1/0 in GP Nauhli) (SH:- Formation cutting in km. 0/375 to 0/435 under Deposit SID: BSP/2024/59)	Rs. 87,409/-	Rs. 1,700/-	Rs. 350/-	Class "D"	Two months
19	C/O Guini Kotla link road km. 0/00 to 3/00 under SCSP (SH:- Providing and laying Cement Concrete Pavement from km. 0/903 to 0/946).	Rs. 90,327/-	Rs. 1,800/-	Rs. 350/-	Class "D"	Three months
20	Construction of Link road from Chandni to Thatri Dhar km. 0/00 to 0/675 in GP Tikru (SH:- Providing and Laying 600 mm dia RCC Hume Pipe at km. 0/015 & 900mm at km. 0/645 under Deposit(SID:SDP/2024/420).	Rs. 41,969/-	Rs. 800/-	Rs. 350/-	Class "D"	One month
21	Restoration of rain damages on various roads under Joginder Nagar Sub Division HPPWD, Joginder Nagar (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and Construction of road side katcha drains etc.).	Rs. 99,060/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months

22	R/O restoration of rain damages on Majhmoor Syuri road km. 0/0 to 3/0 (SH:- Construction of retaining wall at RD. 1/240 to 1/246 under deposit SID:NDF/2023/634).	Rs. 99,743/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Three months
23	Construction of link road Ambulance road Sarvaldi to Harizan basti Batdhar 0/0 to 1/0 in GP Nauhli (SH:- Formation cutting in km. 0/300 to 0/375 under Deposit SID: BSP/2024/59)	Rs. 86,274/-	Rs. 1,700/-	Rs. 350/-	Class "D"	Two months
24	Restoration of rain damages on link from Khuddi Karlon to Bhabhori Mata temple km. 0/0 to 4/0 (SH:- P/L kharanja stone soling & cement concrete pavement from km. 0/155 to 0/172 under deposit SID:NDF/2023/924)	Rs. 57,358/-	Rs. 1,200/-	Rs. 350/-	Class "D"	Three months
25	Restoration of rain damages on various road under Joginder Nagar Division Joginder Nagar (Harabag Section) (SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc.).	Rs. 99,060/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One month
26	Construction & M/T on Galu Bhatwari road to village Badan & Changdhar dhar km. 0/00 to 1/850 under OTNMP head (SH:- Formation Cutting in km. 1/0 to 1/070).	Rs. 98,818/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
27	Restoration of rain damages on link from Khuddi Karlon to Bhabhori Mata temple km. 0/0 to 4/0 (SH:- P/L kharanja stone soling & cement concrete pavement from km. 0/135 to 0/155 under deposit SID:NDF/2023/924)	Rs. 67,481/-	Rs. 1,300/-	Rs. 350/-	Class "D"	Three months
28	Construction & M/T on Galu Bhatwari road to village Badan & Changdhar dhar km. 0/00 to 1/850 under OTNMP head (SH:- Formation Cutting in km. 1/090 to 1/162).	Rs. 99,039/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
29	A/R & M/O to various Non residential building under Joginder Nagar Sub Division HPPWD., Joginder Nagar District Mandi (H.P.) (SH:- Supplying & fixing Solar light and benches at Ladruhin section)	Rs. 88,978/-	Rs. 1,800/-	Rs. 350/-	Class "D"	Two months
30	Restoration of rain damages on various roads under Lad-Bharol Sub Division HPPWD., Lad-Bharol (Neri Section) (SH:- Hiring of Tipper for shifting and carriage of various type of materials etc).	Rs. 99,000/-	Rs. 2,000/-	Rs. 350/-	Class "D"	One months
31	Restoration of rain damages on Baijnath Lad-Bharol Kandapatan road Km. 36/0 to 46/0 (Neri Section)(SH:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side Katcha drains etc.	Rs. 99,060/-	Rs. 2000/-	Rs. 350/-	Class "D"	One months
32	Construction & M/T of link road to Harizan Basti Gyola under SCSP Km. 0/0 to 1/700 G.P. Kass (SH:- Providing and laying soling G-I size 90mm to 45mm at Km. 1/195 to 1/295)	Rs. 91,337/-	Rs. 1,800/-	Rs. 350/-	Class "D"	Two months
33	R/R damages on various roads under Joginder Nagar Sub Division No.II HPPWD., Joginder Nagar (Makreri Section) (SH:- Supplying and stacking of hard fuel wood for patch work).	Rs. 99,000/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
34	A/R & M/O various road under Joginder Nagar Sub Division No.II HPPWD., Joginder Nagar (Makreri Section)(SH:- Supplying and stacking of hard fuel wood for patch work).	Rs. 99,000/-	Rs. 2,000/-	Rs. 350/-	Class "D"	Two months
35	Construction & M/T of link road to Harizan Basti Gyola under SCSP Km. 0/0 to 1/700 G.P. Kass (SH:- Providing and laying soling G-I size 90mm to 45mm at Km. 1/295 to 1/395)	Rs. 91,337/-	Rs. 1,800/-	Rs. 350/-	Class "D"	Two months

Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2024-25- 24761-810

Dated: 13/02/2025

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder

Job - 1

E.No - 405

552

SCHEDULE OF QUANTITY

Name of Work : Repair & maintenance of Raja Bharola Nagan Harizan Basti Tram at upto village Chakka road km. 0/0 to 4/500 under SCSP (Sh:-Construction of breast wall at km. 3/578 to 3/582)			Estimate Cost: Earnest Money: Time Limit :			84,373.00 1,700.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.44	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	4.68	Per cubic metre				

3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	16.60	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	7.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joghinder Nagar

Job - 2

SCHEDULE OF QUANTITY

Name of Work : C/O Guini Kotla link road Km. 0/0 to 3/0. under SCSP (Sub head:- Providing & laying cement concrete pavement from km 0/947 to 0/991)					Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit		Rate		AMOUNT Rs. P
					Figures	Words	
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge.The rate is inclusive all taxes levy by the government time to time excluding GST.	13.86	Per Cubic metre				
Total							

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-3

Schedule of Quantity

Estimated Cost:- 99060.00
 Earnest Money:- 2000.00
 Time:- Two months

Name of work:- Restoration of rain damages on various roads under Joginder Nagar Sub-Division HPPWD, Joginder Nagar (SH: Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk,shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge.The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
Total:-						


 Executive Engineer
 B&R Division HP PWD,
 HP PWD, Joginder Nagar

E.No-403

557

SCHEDULE OF QUANTITY

Name of Work : Repair & maintenance of Raja Bharola Nagan Harizan Basti Tram at upto village Chakka road km. 0/0 to 4/500 under SCSP (Sh:-Construction of breast wall at km. 3/570 to 3/574)

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.44	Per cubic metre			84,373.00 1,700.00 Three Months
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	4.68	Per cubic metre			

3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	16.60	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	7.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Jalandhar Nagar

Job - 5

SCHEDULE OF QUANTITY

Line of Work : A/R & M/O to PWD Rest House at Neri District Mandi (H.P)
 i.e. Providing and Supplying colour blow up natural photo painting frame)

				Estimate Cost: Earnest Money: Time Limit :		
				Rate	AMOUNT	
				Figures	Words	Rs. P
Description of work	No. or Qty.	Unit				
Providing and supplying colour blow up sites of Himachal Pradesh land scaps, temples, lakes etcetre world class extra ordinary creative and artistic photos complete with finishing and matt chemical lamination on high class board of 8 mm (eight millimeter) size 23"x 33" (twenty three inch by thirty three inch) coverage area including moulding complete as per PWD specification and as desired by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive all taxes levy by the government time to time including GST.	16.00	Each				
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar



SCHEDULE OF QUANTITY

Name of Work : A/R & M/O to various road under Joginder Nagar Sub Division, HPPWD J.Nagar (Ladruhin Section) (Sub Head:- painting & writing work etc.)				Estimate Cost: Earnest Money: Time Limit :		
				99,197.00 2,000.00 Two Months		
Sr. No.	Description of Item	Qty	Unit	Rate		Amount
				Figures	In words	
1	Painting one coat (excluding priming coat) on previously painted steel and other metal surface with ready mixed paint brushing to give an even shade, including cleaning the surface of all dirt, dust and other foreign matter and sand papering as required. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	92.59	Per square metre			
2	Painting one extra coat on previously painted steel and other metal surface with ready mixed paint brushing to give an even shade, including cleaning the surface of all dirt, dust and other foreign matter and sand papering as required. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	92.59	Per square metre			
3	Painting one coat (excluding priming coat) on previously painted concrete/masonry/plastered surface with ready mixed paint brushing to give in all shade, including cleaning the surface of all dirt, dust and other foreign matter and sand papering as required. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	84.63	Per square metre			
4	Painting one extra coat on previously painted concrete/masonry/plastered surface with ready mixed paint brushing to give an even shade, including cleaning the surface of all dirt, dust and other foreign matter and sand papering as required. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	84.63	Per square metre			
5	Painting new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade, including cleaning the surface of all dirt, dust and other foreign matter and sand papering as required. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.					

a)	Hindi (Matras commas and like not to be measured and paid for. Half letters shall be counted as half only)	12500.00	Per centimeter height per letter.			
b)	English and Roman (Hyphens, commas nad the link not to be paid for).	9000.00	Per centimeter height per letter.			

~~Executive Engineer~~
B & R Division HP.PWD,
Joginder Nagar

Schedule of Quantity

Estimated Cost:- 99060.00
 Earnest Money:- 2000.00
 Time:- Two Months

Name of work:- Restoration of rain damages on various roads under Lad-Bharol Sub Division HP.PWD, Lad-Bharol (Sub Head:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator/breaker machineries to be deployed dressing of road side katcha drain and removal of slips, debris etc. including cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
						Total:-


 Executive Engineer
 B&R Division HP.PWD,
 Jagginder Nagar

Job - 8

SCHEDULE OF QUANTITY

Name of Work: C/O & M/T on Galu Bhatwari road to village Badan & Changdhar km 0/00 to 1/850 GP Ropa Padhar (Sh: Formation Cutting in km 0/930 to 0/990)							Estimate Cost: 98,207.00 Earnest Money: 2,000.00 Time Limit : Two Months			
SCHEDULE OF QUANTITY							Rate		AMOUNT	
							Figures	Words		Rs.
Sr. No.	Description of work						No. or Qty.	Unit		
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 37.84 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.						398.26	Per cubic metre		
Total										


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

590

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Bhararu to Chhamb road (Sub Head:-Construction of breast wall at km. 2/100 to 2/108)			Estimate Cost: Earnest Money: Time Limit :			99,293.00 2,000.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.00	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	6.64	Per cubic metre				

3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	18.80	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	8.00	Each			
	Total					


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job-10

E.No-404

555

SCHEDULE OF QUANTITY

Name of Work : Repair & maintenance of Raja Bharola Nagan Harizan Basti Tramati upto village Chakka road km. 0/0 to 4/500 under SCSP (Sh:-Construction of breast wall at km. 3/574 to 3/578)			Estimate Cost: Earnest Money: Time Limit :			AMOUNT Rs. P	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Words	
				Figures			P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.44	Per cubic metre				
2	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	4.68	Per cubic metre				

3	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	16.60	Per cubic metre		
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	7.00	Each		
Total					


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job-11

E.No-406

558

SCHEDULE OF QUANTITY

Name of Work : C/O Guini Kotla link road Km. 0/0 to 3/0. under SCSF (Sub head:- Providing & laying cement concrete pavement from km 0/860 to 0/902)				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expansion and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.23	Per Cubic metre			
Total						

~~Executive Engineer~~
B & R Division HP.PWD,
Joginder Nagar

EN0.267

Job-12

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Nanidhar road km 0/00 to 1/325 (SH: Construction of Retaining wall at km. 0/500 to 0/507.20)				Estimate Cost: Earnest Money: Time Limit :			1,18,574.00 2,400.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P		
				Figures	Words			
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	6.30	Per cubic metre					
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	22.82	Per cubic metre					

3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.36	Per cubic metre			
4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D. technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	12.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job-13

E No. 338

SCHEDULE OF QUANTITY

Name of Work: R/O Restoration of rain damages on Majharnu Siyuri road km.0/0 to 3/0 (Sub Head:-Construction of retaining wall at RD 1/215 to 1/220 under Deposit SID:SDF/2023/291)				Estimate Cost: 61,591.00 Earnest Money: 1,200.00 Time Limit : Three Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	3.45	Per cubic metre			
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	11.75	Per cubic metre			
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	3.00	Per cubic metre			

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Jodinder Nagar

Job-14

Schedule of Quantity

Estimated Cost:- 99060 00
 Earnest Money:- 2000 00
 Time:- Two Months

Name of work:- Restoration of rain damages on various roads under Lad-Bharol Sub Division HP.PWD, Lad-Bharol (Sub Head:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator/breaker machineries to be deployed dressing of road side katcha drain and removal of slips, debris etc. including cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out by the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
Total:-						

 Executive Engineer
 B&R Division HP.PWD,
 Jodhpur Nagar


SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on Joginder Nagar Aarthi Shanan road Km. 0/0 to 1/500 (Shi:- Construction of retaining /edge wall at Railway Junction/crossing)			Estimate Cost: Earnest Money: Time Limit :			89,144.00 1,800.00 Three Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	4.68	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	17.02	Per cubic metre				
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	4.08	Per cubic metre				

ENR 366

506-15

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	6.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job-16

Schedule of Quantity

Estimated Cost:- 99060.00
 Earnest Money:- 2000.00
 Time:- Two months

Name of work:- Construction of Mohanghatti to Rada Malu Ghatagla Bhartwara Bhanjrala Matroo road Km 1/360 to 5/360 (SH: Hiring of excavator cum loader for C/O Bhanjrala to Bhatu road Km 0/0 to 0/800)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for formation cutting i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk,shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge.The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
				Total:-		

Executive Engineer
 B&R Division HP.PWD,
 HP. PWD, Joginder Nagar

Job-16

Schedule of Quantity

Estimated Cost:- 99060.00
 Earnest Money:- 2000.00
 Time:- Two months

Name of work:- Construction of Mohanghatti to Rada Malu Ghatagla Bhartwara Bhanjirala Matroo road Km 1/360 to 5/360 (SH: Hiring of excavator cum loader for C/O Bhanjirala to Bhatu road Km 0/0 to 0/800)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for formation cutting i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk,shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
						Total:-


 Executive Engineer
 B&R Division HP.PWD,
 HP.PWD, Joginder Nagar

Job-17

SCHEDULE OF QUANTITY

Name of Work: C/O & M/T on Galu Bhatwari road to village Badan & Changdhar km 0/00 to 1/850 GP Ropa Padhar (Sh: Formation Cutting in km 0/855 to 0/922)				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil. setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 37.96 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	399.58	Per cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-18

SCHEDULE OF QUANTITY

Name of Work: Construction of link road Ambulance road Sarwaldi to Harizan basti Batdhar km 0/0 to 1/0 in GP Nauhli) (SH:- Formation cutting in Km.0/375to 0/435 under Deposit SID:BSP/2024/59)				Estimate Cost: Earnest Money: Time Limit :			87,409.00 1,700.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Words	AMOUNT	
				Figures			Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 17.09 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	427.20	Per cubic metre					
Total								


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-19

E-10-408

556

SCHEDULE OF QUANTITY

Name of Work : C/O Guini Kotla link road Km. 0/0 to 3/0. under SCSP (Sub head:- Providing & laying cement concrete pavement from km 0/903 to 0/946)				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	13.55	Per Cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD,
Jodhpur Nagar

Job-20

SCHEDULE OF QUANTITY

Name of Work : Construction of Link road from Chandni to Thatri Dhar km 0/00 to 0/675 in GP Tikru (Sub Head:- Providing and laying 600mm dia RCC hume pipe at Km 0/015 & 900mm dia at km 0/645 under Deposit SID: SDP/2024/420))				Estimate Cost: Earnest Money: Time Limit :		41,969.00 800.00 One Month
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	7.80	Per cubic metre			
2	Providing and laying 600mm (Six hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.00	Per running metre			
3	Providing and laying 900mm (nine hundred millimetre) diameter reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 complete within all leads, lifts carriage of material and other incidentals. The rate is inclusive all taxes levy by the government time to time excluding GST.	5.00	Per running metre			
Total						

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-21

Schedule of Quantity

Estimated Cost:- 99060.00
 Earnest Money:- 2000.00
 Time:- Two months

Name of work:- Restoration of rain damages on various roads under Joginder Nagar Sub-Division HPPWD, Joginder Nagar (SH: Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
Total:-						


 Executive Engineer
 B&R Division HP.PWD,
 HP.PWD, Joginder Nagar

Job-22

Eno 339

(463)

SCHEDULE OF QUANTITY

Name of Work : R/O Restoration of rain damages on Majharnu Siyuri road km.0/0 to 3/0 (Sub Head:- Construction of retaining wall at RD 1/240 to 1/246 under Deposit SID:NDF/2023/634)			Estimate Cost: Earnest Money: Time Limit :			AMOUNT Rs. P	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Words	
				Figures			
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D.technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost .The rate is inclusive all taxes levy by the government time to time excluding GST.	5.82	Per cubic metre				
2	Providing and laying cement concrete 1:5:10(one cement: five sand:ten graded crushed / broken stone aggregate 40 mm (forty millimeters) nominal size) plums and curing complete including the cost of form work in Retaining walls Breast walls , in or under water complete including, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including cost of form work as per drawings and MORD technical specifications section 800, 900,1200 & 1600 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is inclusive all taxes levy by the government time to time excluding GST.	19.02	Per cubic metre				
3	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals.The rate is inclusive all taxes levy by the government time to time excluding GST.	4.32	Per cubic metre				

4	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe extending through the full width of the structures with slope of 1 (v): 20(H) towards drainage face complete as per drawing and M.O.R.D.technical specification clauses 614, 709 & 1206.6 and as per the directions of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is inclusive all taxes levy by the government time to time excluding GST.	8.00	Each			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job-23

E No. 438

SCHEDULE OF QUANTITY

Name of Work: Construction of link road Ambulance road Sarwaldi to Harizan basti Batdhar km 0/0 to 1/0 in GP Nauhli (SH:- Formation cutting in Km.0/300 to 0/375 under Deposit SID:BSP/2024/59)				Estimate Cost: Earnest Money: Time Limit :			86,274.00 1,700.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Words	AMOUNT	
				Figures			Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 16.87 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	421.65	Per cubic metre					
Total								


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on link road from Khuddi Karlton to Bhabhori Mata temple Km. 0/0 to 4/0. (Sub Head:-P/L kharanja stone soling & cement concrete pavement from Km. 0/155 to 0/172 under deposit SID:NDF/2023/924)				Estimate Cost: Earnest Money: Time Limit :			57,528.00 1,200.00 Three Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P	
				Figures	Words		
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	8.03	Per Cubic metre				
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five milimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	6.69	Per Cubic metre				
Total							

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Schedule of Quantity

Name of work:- Restoration of rain damages on various roads under Joginder Nagar Division Sub Division , Joginder Nagar(Harabag Section).
Sub Head:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/o road side katcha drains etc.
Estimated Cost:- 99060.00
Earnest Money:- 2000.00
Time:- One month

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for removal of slips,dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk,shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-in-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge.The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
Total:-						

Executive Engineer,
B&R Division HP.PWD,
Joginder Nagar

Job-26

SCHEDULE OF QUANTITY

Name of Work: Construction & M/T of link road from Galu Bhatwari road to village Badan & Chhanang dhar km.0/0 to 1/850 under OTMNP head (Sub Head:-Formation cutting from km. 1/0 to 1/070)			Estimate Cost: Earnest Money: Time Limit:			98,818.00 2,000.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT	
				Figures	Words	Rs.	P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 38 67cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	400.72	Per cubic metre				
		Total					


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-27

ENo. 352

(192)

SCHEDULE OF QUANTITY

Name of Work : Restoration of rain damages on link road from Khuddi Karlon to Bhabhori Mata temple Km. 0/0 to 4/0. (Sub Head:-P/L kharanja stone soling & cement concrete pavement from Km. 0/135 to 0/155 under deposit SID:NDF/2023/924)				Estimate Cost: Earnest Money: Time Limit :		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST.	9.45	Per Cubic metre			
2	Construction of un-reinforced cement concrete pavement as per design and drawing with expension and construction joints, over a prepared sub base, with 43 (forty three) grade cement as per technical clause and specifications M-20 (twenty) grade course and fine aggregate conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity including form work with steel channels and plates and entire carriage of material with in all leads and lifts complete as per the direction of Engineer-in-charge.The rate is inclusive all taxes levy by the government time to time excluding GST.	7.87	Per Cubic metre			
Total						


 Executive Engineer
 B & R Division HP.PWD,
 Joginder Nagar

Job-28

SCHEDULE OF QUANTITY

Name of Work:Construction & M/T of link road from Galu Bhatwari road to village Badan & Chhanang dhar km.0/0 to 1/850 under OTMNP head (Sub Head:-Formation cutting from km. 1/090 to 1/162)				Estimate Cost: 99,039.00 Earnest Money: 2,000.00 Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 38.16 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	401.62	Per cubic metre			
Total						


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job - 29

ENo. 445

608

SCHEDULE OF QUANTITY

Name of Work : A/R & M/O to various Non residential building under Joginder Nagar Sub Division HPPWD J.Nagar District Mandi (H.P). (Sub Head:- Supplying & fixing of Solar light and benches at Ladruhin section)				Estimate Cost: Earnest Money: Time Limit :			88,978.00 1,800.00 Two Months	
Sr. No.	Description of work	No. or Qty.	Unit	Rate		Words	AMOUNT	
				Figures			Rs.	P
1	Providing and fixing single side Solar Street light including 15 (fifteen) watt 2 (two) Nos light and 60 (sixty) watt solar pannel and with necessary structure having 6 (six) meter 75mm (seventy five millimeter) diameter G.I. Pole complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	4.00	Each					
2	Supply and installation of cast iron 3seater (Three seater) garden benches for three person for garden of size 1750x450x450mm (one thousand seven hundred by four hundred fifty by four hundred fifty millimeters) bench & 1750x300x890mm (One thousand seven hundred fifty by three hundred by eight hundred ninty millimeters) along with back rest fixed with ground with base plate 400x120x8mm (four hundred by one hundred twenty by eight millimetres) painted with power coated paint for smooth finish, wash able and wash proof, The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	3.00	Each					
Total								


Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job - 30

599

Schedule of Quantity

Estimated Cost:- 99000.00
 Earnest Money:- 2000.00
 Time:- One month

Name of work:- Restoration of rain damages on various roads under Lad-Bharol Sub Division, HPPWD, Lad-Bharol (Neri Section) (SH: Hiring of Tipper for shifting and carriage of various type of materials etc.)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hire charges of tipper for carriage/shifting of soling stone earth, moorum, premix material, seal coat etc. having capacity of 5.50 (five point five zero) cubic metre per trip and covering 70 (seventy) kilometers per day (9AM to 5PM), the contractor/owner of tipper shall bear the expense of POL charges, repair of machineries including driver and helper wages. Any accident and other damages to private and Govt property occur during the working hours in the work shall be the responsibility of the contractor and disposal of excavated material/ slips debris with in all leads and lifts as per the direction of Engineer-in-Charge. The rates are inclusive of all taxes including GST levy by the Govt. time to time.	22.00			Per day	
						Total:-

Executive Engineer,
 B&R Division HP.PWD,
 Joginder Nagar

Job-31

598

Schedule of Quantity

Estimated Cost:- 99060.00
Earnest Money:- 2000.00
Time:- One month

Name of work:- Restoration of rain damages on Bajinath Lad-Bharol Kandapattan road Km. 36/0 to 46/0 (Neri Section)
Sub Head:- Hiring of excavator cum loader for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Hydraulic Excavator having capacity of 1.00 (one point zero) cubic meter loader capacity for removal of slips, dressing of berms, clearing of road side drains, debris and C/O road side katcha drains etc. i/c cost of fuel oil lubricants and wages of operating staff, any repair/breakage during operation will be carried out bt the contractor/owner at his own risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hour will be accounted for the payment. Earth cutting in all kind of soils i/c loading in to tipper/truck within all leads and lifts to the entire satisfaction of Engineer-In-Charge. The payment will be made on the submission of the copy of log book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt. time to time.	78.00			Per working hours	
Total:-						

Executive Engineer,
B&R Division, HPPWD,
Joginder Nagar

Job-32

SCHEDULE OF QUANTITY

Particulars of Work : Construction & M/T of Link road to Harizan Basti Gyola Under SCSP Km 0/00 to 1/700 G.P. Kass Head:- Providing and laying Soling G-I size 90mm to 45mm at km 1/195 to 1/295)				Estimate Cost: Earnest Money: Time Limit :		
Description of work	No. or Qty.	Unit		Rate		AMOUNT Rs. P
				Figures	Words	
Preparation of sub grade by dressing to camber (Earth work for cutting involved for sub grade to be provided for separately depending upon the classification of soil completed as per HPPWD specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	351.75	Per square metre				
Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and reworking the sub grade complete as per HPPWD Specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	351.75	Per square metre				
Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and number applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading -1 (one) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.	35.18	Per cubic metre				
Total						

Executive Engineer
B & R/Division HP.PWD.
Joginder Nagari

206-33

Schedule of Quantity

Estimated Cost:- 99000.00
 Earnest Money:- 2000.00
 Time:- Two months

Name of work : R/r damages on various roads under Joginder Nagar ,Sub Division No.II, HP.PWD.,Joginder Nagar (Makriri section)(Sub Head:- Supplying and stacking of hard fuel wood for patch work).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking at site of work dry hard fuel wood, the fuel wood shall be dry and have a minimum girth of nine inch but not exceeding one feet six inch including entire carriage of material within all leads, lifts and proper stack at site as the direction of Engineer-In-Charge .The rate is inclusive of all taxes including GST levy by the Govt. time to time.	132.00			Per quintal	
				Total:-		

 Executive Engineer
 B&R Division HP.PWD,
 Joginder Nagar

Job - 34

Schedule of Quantity

Estimated Cost:- 99000.00

Earnest Money:- 2000.00

Time:- Two months

Name of work : A/R&M/O various roads under Joginder Nagar ,Sub Division No.II, HP.PWD,,Joginder Nagar (Makriri section)(Sub Head:- Supplying and stacking of hard fuel wood for patch work).

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Supplying and stacking at site of work dry hard fuel wood, the fuel wood shall be dry and have a minimum girth of nine inch but not exceeding one feet six inch including entire carriage of material within all leads, lifts and proper stack at site as the direction of Engineer-In-Charge .The rate is inclusive of all taxes including GST levy by the Govt. time to time.	132.00			Per quintal	
				Total:-		

 Executive Engineer
B&R Division HP.PWD,
Joginder Nagar

Job-35

SCHEDULE OF QUANTITY

Description of work			Unit			Estimate Cost: Earnest Money: Time Limit :		
			No. or Qty.			Rate	Figures	Words
Preparation of sub grade by dressing to camber (Earth work for cutting involved for sub grade to be laid for separately depending upon the classification of soil completed as per HPPWD specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.			351.75	Per square metre				
Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub grade complete as per HPPWD Specifications complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.			351.75	Per square metre				
Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading -1 (one) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges and to the entire satisfaction and direction of Engineer - in- Charge. The rate is inclusive all taxes levy by the government time to time excluding GST.			35.18	Per cubic metre				
Total								

Executive Engineer
B & R Division HP.PWD.
Jalinder Nagar