

OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811

E-MAIL:- cc-sol-hp@nic.com

No.PW-SD/CB-Tender/-2024-25- 13541-51

Dated:- 17⁰²/₂₀₂₅


To

✓ The Executive Engineer (IT Cell),
Nigam Vihar, Nirman Bhawan,
HPPWD, Shimla-2,
Email ID:-cc-pwd-hp@nic.in

Subject: - Publication of e-Tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19th June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.


Executive Engineer,
B&R Division,
HP.PWD, Solan

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3rd HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.


Executive Engineer,
B&R Division,
HP.PWD, Solan.

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Exigency

Sealed item rate tenders are hereby invited on Form No.6 & 8 by the Executive Engineer, Solan B&R Division, H.P. PWD. Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act, 1968. The important dates of tender are as under:

Sr.No.	Tender Schedule	Dates	Time
1	The last date for receipt of application for tender form.	21.02.2025	Upto 3.00 P.M.
2	The last date sale of tender forms.	22.02.2025	Upto 4.00 P.M.
3	The date for receipt of tender forms.	24.02.2025	Upto 10.30 P.M.
4	The date of opening of tender	24.02.2025	At 11.00 A.M.

The tender shall be received upto 10.30 A.M. on 24.02.2025 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan. The tender must accompany with each tender, conditional tenders and the tenders received without earnest money will be simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost. (Rs.)	Earnest Money (Rs.)	Time	Cost Form
1	Restoration of rain damages on various roads under Oachghat Sub Division (SH:- Hiring of JCB/ loader cum-excavator for removal of slips)	98800/-	2000/-	One month	Rs.350/-
2	Repair and Maintenance of Type-III quarter set No. 6 near ITI colony Solan (SH:- Providing and laying fixing wood work and flooring works)	99527/-	2000/-	Two Months	Rs.350/-
3	Repair and Maintenance of Type-II quarter set No.33 at tank road Solan (SH:- Providing and laying flooring, painting, distempering and sanitary fitting)	99399/-	2000/-	Two Months	Rs.350/-
4	Repair and Maintenance of Type-III quarter set No. 6 near ITI colony Solan (SH:- Providing and fixing steel work, painting, distempering and sanitary fitting)	97570/-	2000/-	Two Months	Rs.350/-
5	Construction of ambulance road from Brewery Solan (NH 05) to village Tikkar Km. 0/00 to 1/800 under MNP (SH: - F/C,CD and Soling in Km.0/00 to 1/800) (SW: - Construction of PCC retaining wall at Rd.0/445 to 0/458)	99522/-	2000/-	One Month	Rs.350/-
6	Construction of link road from Kothi Delgi road Km.0/00 to 2/945 under MNP (SH: - ROFD in Km.0/00 TO 0/031)	99014/-	2000/-	One Month	Rs.350/-

7	Construction of link road from Kothi Delgi road Km.0/00 to 2/9.45 under MNP (SH: - ROFD in Km.0/065 TO 0/085)	97659/-	2000/-	One Month	Rs.350/-
8	Restoration of rain Damages on Paughat Haripur road (Saheed Roshan Lal Marg) Km.0/00 to 9/00 (SH: - Construction of R/wall at Rd.8/135 to 8/137.20)	94337/-	2000/-	One Month	Rs.350/-
9	Construction of link road Upper Plah to Laxman Dham Km. 0/00 to 1/200 under MNP (SH: - C/O 5/7-meter-wide road including essential CD and Soling in Km. 0/00 to 1/200) (SW: -ROFD at Rd.1/180 to 1/210)	99791/-	2000/-	One Month	Rs. 350/-
10	Construction of link road Upper Plah to Laxman Dham Km. 0/00 to 1/200 under MNP (SH: - C/O 5/7-meter-wide road including essential CD and Soling in Km. 0/00 to 1/200) (SW: -ROFD at Rd.1/240 to 1/270)	99625/-	2000/-	One Month	Rs.350/-
11	Annual repair and maintenance of Tikkari Tananji road Km.9/180 to 11/580 (SH: - ROFD & improvement of curves at Rd.10/705 to 10/765)	94685/-	2000/-	One Month	Rs.350/-
12	Annual repair and maintenance of Kufri Chail Kandaghat road Km.25/00 to 57/00 (SH:- Clearance of side Drains in Km.48/00 to 50/500)	91875/-	2000/-	One Month	Rs. 350/-
13	Annual repair and maintenance of Kufri Chail Kandaghat road Km.25/00 to 57/00 (SH:- Clearance of side Drains in Km.54/00 to 56/500)	91875/-	2000/-	One Month	Rs. 350/-
14	Construction of HPPWD Rest house building at Sayri Tehsil Kandaghat, District Solan (HP) (SH: - Providing and laying Water supply & sanitary installation and C/o edge wall at back side of building)	98554/-	2000/-	Two Months	Rs. 350/-
15	Construction of 60 mtr Span Bridge Over Ashwani Khad at Rd.2/870 on DDL Factory to Chaura road Km.0/00 to 3/420 (SH:- Conducting bearing capacity of soil test of Middle Pier) Job No.3	99360/-	2000/-	One Month	Rs. 350/-
16	Restoration of rain damages on Parwanoo Kasauli Dharampur Subathu Solan road Km.57/320 to 65/320 (SH:- Hiring of JCB/ loader cum-excavator for removal of slips)	99750/-	2000/-	One Month	Rs. 350/-
17	Restoration of rain damages on Parwanoo Kasauli Dharampur Subathu Solan road Km.57/320 to 65/320 (SH:- Hiring of Tipper for carriage of slips)	96000/-	2000/-	One Month	Rs. 350/-
18	Repair and Maintenance of Type-III quarter set No.4 Near ITI colony Solan (SH:- Providing and laying tile work, plastering, painting and distemping)	45851/-	1000/-	One Month	Rs. 350/-

	R/R damages on various road under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slip) Kandaghat Section -I	99750/-	2000/-	One Month	Rs. 350/-
20	R/R damages on various road under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slip) Kandaghat Section -II	99750/-	2000/-	One Month	Rs. 350/-
21	R/R damages on various road under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slip) Sadhupul Section	99750/-	2000/-	One Month	Rs. 350/-
22	R/R damages on various road under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slip) Chail Section	99750/-	2000/-	One Month	Rs. 350/-
23	R/R damages on various road under Kandaghat sub-division (SH: Hiring of tipper for carriage of slip) Chail Section	96000/-	2000/-	One Month	Rs. 350/-
24	R/R damages on various road under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slip) Chhausha Section	99750/-	2000/-	One Month	Rs. 350/-
25	R/R damages on various road under Kandaghat sub-division (SH: Hiring of JCB/loader cum excavator for removal of slip) Mamligh Section	99750/-	2000/-	One Month	Rs. 350/-
26	R/R damages on various road under Kandaghat sub-division (SH: Hiring of tipper for carriage of slip) Kandaghat Section -I	96000/-	2000/-	One Month	Rs. 350/-
27	A/R & M/O Kandaghat sub-division (SH: Supplying and stacking of crushed sand etc.) Chail Section	98350/-	2000/-	Fifteen Days	Rs. 350/-

TERMS & CONDITIONS:-

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.



Executive Engineer,
B&R Division,
HPPWD, Solan

Exigency Certificate

It is certified that the tenders which were invited vide this office NIT No. PW-SD/CB-Tender/2024-25-13541 - 51 Dated: 17⁰²/₂₅ are of emergent nature of work and in public interest.

Dated:-

Place:- Solan


Executive Engineer
B&R Division
HPPWD, Solan

Schedule of Quantity

No.		Description of work		Schedule of Quantity			
Job No. :- 1	Qty.	Unit	Rate in		Amount		
			Figures	words			
Name of work: - Restoration of rain damages on various roads under Oachghat Sub Division (SH:- Hiring of JCB/ loader cum-excavator for removal of slips)							
1	Hiring of JCB / loader cum-excavator						
Terms and Conditions :-		104.00	Per hour	950.00	Rupees Nine Hundred Fifty Only		
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.						
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.						
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.						
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.						
(e)	Minimum work as per PWD norms must be executed by the machinery hired.						
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .						
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour						
Total in figures :-							
Total in Words :-		Rupees Two Thousand Two Hundred Fifty Only					
Quoted Percentage rate upto Three Digits :-			(+) / (-)				

Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD.Solan.

Schedule of Quantity

Description of work

Job No. :- 2.

Name of Work :- Repair and Maintenance of Type-III quarter set No. 6 near ITI colony Solan (SH:- Providing and laying fixing wood work and flooring works)

Qty.	Unit	Rate in		Amount
		Figures	words	
			Estimated Cost:-	99527.00
			Earnest Money:-	2000.00
			Time limit :-	Two months
1	Providing and fixing 18 mm thick (Eighteen Millimeter) Pre-laminated flat pressed 3 layer (medium density) particle board or graded wood particle board IS : 3087 marked, with one side decorative and other side balancing lamination Grade I, Type II exterior grade IS : 12823 marked, in shelves with screws and fittings wherever required, edges to be painted with polyurethane primer (fittings to be paid separately) as per H.P.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	23.76	Per Square meter	1086.75
			Rupees One Thousand Eighty Six and Paise Seventy Five Only	25821.00
2	Providing and fixing 25 mm thick ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters M.S. Piano hinges . (for cupboard) including ISI marked nickel plated bright finished IS : 3818 marked with necessary screws	10.80	Per square meter.	2273.45
			Rupees Two Thousand Two Hundred Seventy Three and Paise Forty Five Only	24553.00
3	Providing and fixing mild steel Tower bolts (barrel type) anodized transparent or dyed to required shade and color with screws etc. Complete as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.			
3.1	200*10 (two Hundred Fifty into Ten) millimeters size	6.000	Each	296.35
			Rupees Two Hundred Ninety Six and Paise Thirty Five Only	1778.00
4	Providing and fixing bright finished brass handles with screws etc. as per HP.PWD specification including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts , including all incidental charges.			
			Rupees NIL Only	
4.1	125 mm (one hundred twenty five millimeter)	10.000	Each	202.55
			Rupees Two Hundred Two and Paise Fifty Five Only	2026.00

ing and fixing 2mm (two)millimeter thick PVC antistatic vinyl Flooring plain or
 cured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp
 proofing treatment to be paid for separately) as per direction of Engineer-in-Charge and
 HP.PWD. specification including carriage of all labour equipment and material to various
 location through all modes of transportation in all leads and lifts, including all incidental
 charges.

	40.35	Per square meter.	1123.90	Rupees One Thousand One Hundred Twenty Three and Paise Ninety Only	45349.00
Total:-					99527.00
Rupees Ninety Nine Thousand Five Hundred Twenty Seven Only					
Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No.193 for the 2024-25

Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Description of work

Job No. :- 3

Name of Work :- Repair and Maintenance of Type-II quarter set No.33 at tank road Solan (SH:- Providing and laying flooring, painting, distempering and sanitary fitting)

1	Providing and fixing Raj Nagar Plain white marble/ Udaipur green marble/ Zebra black marble 18 mm thick having area of slab over 0.50 sqm, gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc.complete at all levels as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	2.31	Per square meter.	3620.70	Rupees Three Thousand Six Hundred Twenty and Paise Seventy Only	8364.00
2	Providing and fixing In flooring on a bed of 10 mm thick mortar 1:4 (1 acid proof cement : 4 coarse sand) acid and/or alkali resistant tiles of approved make and colour using acid and/or alkali resisting mortar bedding, and joints filled with acid and/or alkali resisting cement as per IS : 4457, complete as per H.P.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	7.03	Per square meter	1358.30	Rupees One Thousand Three Hundred Fifty Eight and Paise Thirty Only	9549.00
3	Marble tiles (polished) Raj Nagar 8 mm thick Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade complete as per H.P.PWD. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	18.72	Per square meter	1068.95	Rupees One Thousand Sixty Eight and Paise Ninety Five Only	20011.00
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	159.85	Per Square Meter	85.10	Rupees Eighty Five and Paise Ten Only	13603.00
5	Distempering One coat with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacturer, including applying additional coats wherever required, to achieve even shade and colour as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	159.85	Per Square Meter	31.75	Rupees Thirty One and Paise Seventy Five Only	5075.00

	Preparing and preparing the surface smooth including necessary repairs to scratches etc. complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	159.85	Per square meter.	11.15	Rupees Eleven and Paise Fifteen Only	1782.00
	Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications painting wood work with deluxe multi surface paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	64.23	Per Square Meter	94.30	Rupees Ninety Four and Paise Thirty Only	6057.00
8	Repairs to plaster of thickness 12 mm to 20 mm (twelve to twenty millimeter) thick with cement mortar 1:4 (one cement is to four sand) in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in- Charge.	38.30	Per Square Meter	264.35	Rupees Two Hundred Sixty Four and Paise Thirty Five Only	10125.00
9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) 15 mm nominal outer dia pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge.	15.00	Per running meter	293.80	Rupees Two Hundred Ninety Three and Paise Eighty Only	4407.00
10	Providing and placing on terrace (at all floor levels) 1000 litre Capacity polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank as per HP.PWD specification, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	1000.00	Per Liter	8.80	Rupees Eight and Paise Eighty Only	8800.00
11	Providing and fixing 15mm (fifteen millimeters) nominal bore C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	4.00	Each	532.00	Rupees Five Hundred Thirty Two Only	2128.00
12	Providing and fixing 15 mm (fifteen millimeters) nominal bore C.P. brass bib cock of approved quality conforming to IS:8931 as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	4.00	Each	418.95	Rupees Four Hundred Eighteen and Paise Ninety Five Only	1676.00
13	Providing and fixing 15 mm (fifteen millimeters) nominal bore uplasticed PVC connection pipe 45 cm length with brass unions as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	4.00	Each	83.00	Rupees Eighty Three Only	332.00
14	Providing and fixing P.V.C. 32 mm dia Flexible waste pipe for sink or wash basin including P.V.C. waste fittings complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	2.00	Each	101.10	Rupees One Hundred One and Paise Ten Only	202.00

	and fixing 100 mm (Hundred millimetre) sand cast Iron grating for Gully trap as per specification including carriage of all labour, equipment and material to various on through all modes of transportation in all lead and lift, including all incidental charges.	4.00	Each	44.60	Rupees Forty Four and Paise Sixty Only	178.00
17	Providing and fixing 110 mm X 90 mm (one hundred ten into ninety millimeters) dia PVC floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete as per HP.PWD specification, including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	4.00	Each	347.00	Rupees Three Hundred Forty Seven Only	1388.00
17.1	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	12.00	Per Running Meter	333.70	Rupees Three Hundred Thirty Three and Paise Seventy Only	4004.00
17.2	90 mm (ninety millimeters) dia.	6.00	Per Running Meter	286.30	Rupees Two Hundred Eighty Six and Paise Thirty Only	1718.00
Total:-						99399.00
Rupees Ninety Nine Thousand Three Hundred Ninety Nine Only						

T/S No.192 for the 2024-25

Sr. No. for the year 2024-25

Draft Schedule of Quantity approved for Rs. 99399.00 only.

Amit
Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Description of work

Job No. :-

14

Name of Work :- Repair and Maintenance of Type-III quarter set No. 6 near ITI colony Solan (SH:- Providing and fixing steel work, painting, distempering and sanitary fitting)

Schedule of Quantity					
Description of work	Qty.	Unit	Rate in		Amount
			Figures	words	
Name of Work :- Repair and Maintenance of Type-III quarter set No. 6 near ITI colony Solan (SH:- Providing and fixing steel work, painting, distempering and sanitary fitting)				Estimated Cost: -	97570.00
				Earnest Money:-	2000.00
				Time limit: -	Two months
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works in position and applying a priming coat of approved steel primer using structural steel etc. as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	256.12	Per Kilogramme	Rupees One Hundred Seven and Paise Forty Five Only	27520.00
2	Providing corrugated G.S. sheet 1.00 mm thick with zinc coating not less than 275 gm/m² roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of putlins, rafters and trusses and including cutting to size and shape wherever required as per HP.PWD. specification including carriage of all labour qupment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	14.63	Per square meter.	Rupees One Thousand One Hundred Fifty Six and Paise Fifty Five Only	16920.00
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	96.00	Per Square Meter	Rupees Eighty Nine and Paise Ninety Only	8630.00
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	213.72	Per Square Meter	Rupees Eighty Five and Paise Ten Only	18188.00
5	Distempering One coat with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	213.72	Per Square Meter	Rupees Thirty One and Paise Seventy Five Only	6786.00

	Painting and preparing the surface smooth including necessary repairs to scratches including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	213.72	Per square meter.	11.15	Rupees Eleven and Paise Fifteen Only	2383.00
	Painting One or more coats on old work with synthetic enamel paint on new wood and wood based surface with ready mixed paint, brushing to give an even shade including cleaning all dirt, dust and other foreign matter, sand papering and stopping as per HP.PWD. specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges and as per direction of engineer in charge.	112.430	Per Square Meter	53.85	Rupees Fifty Three and Paise Eighty Five Only	6054.00
	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required as per HP.PWD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all lead and lift, including all incidental charges.	1.00	Each	5666.60	Rupees Five Thousand Six Hundred Sixty Six and Paise Sixty Only	5667.00
9	Providing and fixing 15 mm (fifteen millimeters) nominal bore C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	5.00	Each	552.35	Rupees Five Hundred Fifty Two and Paise Thirty Five Only	2762.00
10	Providing and fixing 15mm (fifteen millimeters) nominal bore C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 as per HP.PWD specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	5.00	Each	532.00	Rupees Five Hundred Thirty Two Only	2660.00
Total:-						97570.00
Rupees Ninety Seven Thousand Five Hundred Seventy Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.191 for the 2024-25

Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Description of work

Job No. :- 5.

Name of Work :- Construction of ambulance road from Brewery Solan (NH 05) to village Tikkar Km. 0/00 to 1/800 under MNP (SH: - F/C, CD and Soling in Km.0/00 to 1/800) (SW: - Construction of PCC retaining wall at Rd.0/445 to 0/458)

Job No. :- 5.		Description of work				
Qty.	Unit	Rate in			Amount	
		Figures	words			
			Estimated Cost: -	99522.00		
			Earnest Money:-	2000.00		
			Time limit :-	One months		

Name of Work :- Construction of ambulance road from Brewery Solan (NH 05) to village Tikkar Km. 0/00 to 1/800 under MNP (SH: - F/C, CD and Soling in Km.0/00 to 1/800) (SW: - Construction of PCC retaining wall at Rd.0/445 to 0/458)						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	8.80	Per Cubic Meter	392.00	Rupees Three Hundred Ninety Two Only	3450.00
2	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	18.69	Per Cubic Meter	4737.00	Rupees Four Thousand Seven Hundred Thirty Seven Only	88535.00
3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	7.00	Each	242.00	Rupees Two Hundred Forty Two Only	1694.00

ing behind abutment, wing wall and return wall, breast walls, retaining walls and
 up to all heights, depths and levels complete as per HP.PWD. Specification clause
 104.3.8 (one thousand two hundred four point three point eight) Granular material,
 including carriage of all labour equipment and material to various locations through all
 modes of transportation in all lead and lift and all incidental charges.

	5.40	Per Cubic Meter	1082.00	Rupees One Thousand Eighty Two Only	5843.00
Total:-					99522.00
Rupees Ninety Nine Thousand Five Hundred Twenty Two Only					
Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No. 200 for the 2024-25
 Sr. No. for the year 2024-25

Executive Engineer
 B&R Division, HP.PWD. Solan.

Schedule of Quantity

Job No. :- 6.

Schedule of Quantity					
Description of work	Qty.	Unit	Rate in		Amount
			Figures	words	
Job No :- 6				Estimated Cost:-	99014.00
				Earnest Money:-	2000.00
				Time limit :-	One month

Name of Work :- Construction of link road from Kothi Delgi road Km.0/00 to 2/945 under MNP (SH: - ROFD in Km.0/00
CO 0/031)

1	Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer-in-Charge at site. according to the HP.PWD. specification and sorting out useful and un-useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site (to be arranged by the contractor) as per satisfaction of Engineer- in -Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures to complete the work (if required). Any loss to the public and private property during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	496.99	Per Cubic Meter	199.63	Rupees One Hundred Ninety Nine and Paise Sixty Three Only	99014.00
	Total:-					99014.00
					Rupees Ninety Nine Thousand Fourteen Only	
	Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No.189 for the 2024-25
 Sr. No. for the year 2024-25

Executive Engineer
 B&R Division, HP.PWD. Solan.

Schedule of Quantity

Schedule of Quantity					
Description of work	Qty.	Unit	Rate in		Amount.
			Figures	words	
Job No. :- 7.				Estimated Cost: -	97659.00
				Earnest Money:- -	2000.00
				Time limit : -	One month

1	Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer-in-Charge at site, according to the HP.PWD. specification and sorting out useful and un-useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site (to be arranged by the contractor) as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures to complete the work (if required). Any loss to the public and private property during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	489.20	Per Cubic Meter	199.63	Rupees One Hundred Ninety Nine and Paise Sixty Three Only	97659.00
Total:-						97659.00
Rupees Ninety Seven Thousand Six Hundred Fifty Nine Onl						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.190 for the 2024-25
Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Job No. :- 8 .

Description of work	Qty.	Unit	Rate in		Amount
			Figures	words	
				Estimated Cost: -	94337.00
				Earnest Money:-	2000.00
				Time limit :-	One months

ne of Work :- Restoration of rain Damages on Paughat Haripur road (Sahed Roshan Lal Marg) Km.0/00 to 9/00 (SH:-
struction of R/wall at Rd.8/135 to 8/137.20)

2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with incidental charges.	10.98	Per Cubic Meter	392.00	Ruppes Three Hundred Ninety Two Only	4304.00
		1.06	Per Cubic Meter	4179.00	#NAME?	4430.00
3	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with incidental charges.	17.49	Per Cubic Meter	4737.00	Ruppes Four Thousand Seven Hundred Thirty Seven Only	82850.00

	weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	4.00	Each	242.00	Rupees Two Hundred Forty Two Only	968.00
5	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	1.65	Per Cubic Meter	1082.00	Rupees One Thousand Eighty Two Only	1785.00
	Total:-					94337.00
	Rupees Ninety Four Thousand Three Hundred Thirty Seven Only					
	Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No. 196 for the 2024-25
Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Description of work

Qty.

Unit

Figures

Rate in .

Amount

Job No. :- 9

Estimated Cost :- 99791.00
Earnest Money :- 2000.00
Time limit :- One month

Name of Work :- Construction of link road Upper Plah to Laxman Dham Km. 0/00 to 1/200 under MNP (SH: - C/O 5/7- meter-wide road including essential CD and Soling in Km. 0/00 to 1/200) (SW: -ROFD at Rd.1/180 to 1/210)

1	Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer -in-Charge at site, according to the HP.PWD. specification and sorting out useful and un- useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site (to be arranged by the contractor) as per satisfaction of Engineer- in -Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures to complete the work (if required). Any loss to the public and private property during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	499.88	Per Cubic Meter	199.63	Rupees One Hundred Ninety Nine and Paise Sixty Three Only	99791.00
	Total:-					99791.00
	Rupees Ninety Nine Thousand Seven Hundred Ninety One Only					
	Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No.204 for the 2024-25
Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Description of work

Job No. :- 10

Name of Work :- Construction of link road Upper Plah to Laxman Dham Km. 0/00 to 1/200 under MNP (SH:- C/O 5/7-
neter-wide road including essential CD and Soling in Km. 0/00 to 1/200) (SW:- ROFD at Rd.1/240 to 1/270)

Job No. :- 10		Qty.	Unit	Rate in		Amount
				Figures	words	
Name of Work :- Construction of link road Upper Plah to Laxman Dham Km. 0/00 to 1/200 under MNP (SH: - C/O 5/7- meter-wide road including essential CD and Soling in Km. 0/00 to 1/200) (SW: -ROFD at Rd.1/240 to 1/270)		Estimated Cost: -				99625.00
		Earnest Money: -				2000.00
		Time limit : -				One month
1	Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer -in-Charge at site. according to the HP.PWD. specification and sorting out useful and un- useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site (to be arranged by the contractor) as per satisfaction of Engineer- in -Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures to complete the work (if required). Any loss to the public and private property during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	499.05	Per Cubic Meter	199.63	Rupees One Hundred Ninety Nine and Paise Sixty Three Only	99625.00
Total:-						99625.00
Rupees Ninety Nine Thousand Six Hundred Twenty Five Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.205 for the 2024-25
Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 11						
				Estimated Cost:-		94685.00
				Earnest Money:-		2000.00
				Time limit :-	One month	

Name of Work :- Annual repair and maintenance of Tikkari Tananji road Km.9/180 to 11/580 (SH:- ROFD & improvement of curves at Rd.10/705 to 10/765)

1	Cutting in earth work in hilly area in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting out to required lines, levels as shown on the drawing and directed by the Engineer -in-Charge at site. according to the HP.PWD. specification and sorting out useful and un- useful material and transportation of the un-useful material for disposing at approved dumping site or otherwise and including payment of prescribed charges of dumping to the owner of dumping site (to be arranged by the contractor) as per satisfaction of Engineer- in -Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures to complete the work (if required). Any loss to the public and private property during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	474.30	Per Cubic Meter	199.63	Rupees One Hundred Ninety Nine and Paise Sixty Three Only	94685.00
Total:-						94685.00
Rupees Ninety Four Thousand Six Hundred Eighty Five Only						
Quoted Percentage rate upto Three Digits :-				(+) / (-)		

T/S No.195 for the 2024-25
Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Description of work

Quantity

Job No. :-

12.

Qty.

Unit

Rate in

Figures words

Amount

Estimated Cost:-

91875.00

Earnest Money:-

2000.00

Time limit :-

One Month

Name of Work :- Annual repair and maintenance of Kufri Chail Kandaghat road Km.25/00 to 57/00 (SH:- Clearance of side Drains in Km.48/00 to 50/500)

1	Removal of earth from the choked hill side drain manually and clearance of unlined drain to specified line, grade and level / dressing it on the berms/ shoulder portion or dispose surplus earth on the valley side / dumping site to be arranged by the contractor, including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	2500.000	Per running meter	34.50	Rupees Thirty Four and Paise Fifty Only	86250.00
2	Trimming of grass and weeds from the shoulder / berms and disposing of the same to suitable location including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	2500.000	Per Square Meter	2.25	Rupees Two and Paise Twenty Five Only	5625.00
Total :-						91875.00
Rupees Ninety One Thousand Eight Hundred Seventy Five Only						
Quoted Percentage rate upto Three Digits :-				(+) / (-)		

T/S No.208 for the 2024-25
Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Description of work

Job No. :- 13.

Name of Work :- Annual repair and maintenance of Kufri Chail Kandaghat road Km.25/00 to 57/00 (SH:- Clearance of side Drains in Km.54/00 to 56/500)

Description of work				Qty.	Unit	Rate in		Amount
						Figures	words	
						Estimated Cost: -		91875.00
						Earnest Money: -		2000.00
						Time limit :-		One Month
Name of Work :-Annual repair and maintenance of Kufri Chail Kandaghat road Km.25/00 to 57/00 (SH:- Clearance of side Drains in Km.54/00 to 56/500)								
1	Removal of earth from the choked hill side drain manually and clearance of unlined drain to specified line, grade and level / dressing it on the berms/ shoulder portion or dispose surplus earth on the valley side / dumping site to be arranged by the contractor, including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	2500.000	Per running meter	34.50	Rupees Thirty Four and Paise Fifty Only			86250.00
2	Trimming of grass and weeds from the shoulder / berms and disposing of the same to suitable location including all leads, lifts and carriage of materials as per direction of Engineer-in-Charge.	2500.000	Per Square Meter	2.25	Rupees Two and Paise Twenty Five Only			5625.00
	Total :-							91875.00
Rupees Ninety One Thousand Eight Hundred Seventy Five Only								
Quoted Percentage rate upto Three Digits :-				(+) / (-)				

T/S No.208 for the 2024-25
Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Description of work

Quantity

Job No. :- 14,

Name of Work :- Construction of HPPWD Rest house building at Sayri Tehsil Kandaghat, District Solan (HP) (SH:- Providing and laying Water supply & sanitary installation and C/o edge wall at back side of building)

1	Qty.	Unit	Rate in		Amount
			Figures	words	
			Estimated Cost:-		98554.00
			Earnest Money:-		2000.00
			Time limit :-		Two Month
2	9.60	Per Cubic Meter	392.00	Rupees Three Hundred Ninety Two Only	3763.00
2	7.43	Per Cubic Meter	171.40	Rupees One Hundred Seventy One and Paise Forty Only	1274.00

Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesing / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.

Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in All kinds of soil, foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.

	and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	9.50	Per Cubic Meter	4737.00	Rupees Four Thousand Seven Hundred Thirty Seven Only	45002.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	11.00	Each	242.00	Rupees Two Hundred Forty Two Only	2662.00
5	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	2.88	Per Cubic Meter	1082.00	Rupees One Thousand Eighty Two Only	3116.00
6	Providing and fixing on wall face 110-mm diameter unplasticised Rigid Single socketed PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, as per HP.PWD. specification including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges.	70.00	Per Running Meter	260.55	Rupees Two Hundred Sixty and Paise Fifty Five Only	18239.00
7	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.					
7.1	110 mm (one hundred ten) millimeters Plain Bend	12.00	Each	129.85	Rupees One Hundred Twenty Nine and Paise Eighty Five Only	1558.00
7.2	110 mm (one hundred ten) millimeters Shoe	6.00	Each	113.80	Rupees One Hundred Thirteen and Paise Eighty Only	683.00

8	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour as per HP.PWD specification including carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts , including all incidental charges.	6.00	Each	117.80	Rupees One Hundred Seventeen and Paise Eighty Only	707.00
9	Constructing masonry Chamber 60x60x75 cm inside, in brick work with common burnt clay F.P.S.(non modular) bricks of class designation 7.5 in cement mortar 1:4 (1 cement : 4 coarse and) for water meter complete with C.I. double flap surface box 400x200x200 mm (inside) with locking arrangement and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand:10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design e as per standard design as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges	2.00	Each	415.15	Rupees Four Hundred Fifteen and Paise Fifteen Only	830.00
		3.00	Each	6906.70	Rupees Six Thousand Nine Hundred Six and Paise Seventy Only	20720.00
Total :-						98554.00
Rupees Ninety Eight Thousand Five Hundred Fifty Four Only						
Quoted Percentage rate upto Three Digits :-				(+) / (-)		

T/S No.210 for the 2024-25
Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Description of work	Qty.	Unit	Rate in		Amount
			Figures	words	
Job No. :- 15.			Estimated Cost:-		99360.00
			Earnest Money:-		2000.00
			Time limit :-		One month

Name of work:-Construction of 60 mtr Span Bridge Over Ashwani Khad at Rd.2/870 on DDL Factory to Chaura road
Km.0/00 to 3/420 (SH:- Conducting bearing capacity of soil test of Middle Pier) Job No.3

1	Carryout planning and monitoring Geo Technical Investigation and sub surface exploration at the propose location of the Bridge by drilling 3 (three) Nubmers bore hole 13.80 (Thirteen point Eighty) metre deep at site as per IS 2800-1979 using percussion/ Caty/ RC.ODEX methed required for drilling in collepsible strata, conglomerate boulder , pebbles , sand , gravels, site and clay etc. including cost of attachment, extractable casing,consumable stores, bits water, POL, gravel pack in annular space etc. complete in all respect as per direction of entire stisfaction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	13.800	Per running meter	7200.00	Rupees Seven Thousand Two Hundred Only	99360.00
Total:-						99360.00
Rupees Ninety Nine Thousand Three Hundred Sixty Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD. Solan.

Job No.- 16.

Estimated Cost: - 99750.00

Earnest Money: - 2000.00

SCHEDULE OF QUANTITY.

Time Limit: - One Month.

Name of work: - Restoration of Rain Damages on Parvahoo Kasauli Dharampur Subathu Solan Road Km. 57/320 to 65/320 (SH:- Hiring of JCB/Loader cum-excavator for removal of slips).

Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	2	3	4	5	6	7
1	Hiring of JCB / loader cum-excavator .					
	Terms and Conditions :-					
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.	105.000	Per hour.	950.00	Rupees nine hundred fifty & paisa nil only.	99750.00
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.					
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
	Total in words.				Rupees Ninety nine thousand seven hundred fifty only.	
	Quoted Percentage rate			(+)/(-)		
					Total:-	99750.00

Sno. for the year 2024-25.

Executive Engineer,
Solan B&R Division,
H.P.P.W.D; Solan.

SCHEDULE OF QUANTITY.

Restoration of Rain Damages on Parvannu Kasauli Pharampur Subathu Solar Panel	27/09/2023	2000.00
Time Limit: -		One Months

Description of items

carriage of slips).

		Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	2	3	4	5	6	7
1	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. And as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	24.00	Per day	4000.00	Rupees four thousand and paise nil only.	96000.00
					Total:-	96000.00
					Total in words. Rupees Ninety Six thousand only.	
					Quoted Percentage rate (+)/(-)	

Sno.	for the year 2024-25.
1	1
2	2
3	3
4	4
5	5
6	6
7	7
8	8
9	9
10	10
11	11
12	12
13	13
14	14
15	15
16	16
17	17
18	18
19	19
20	20
21	21
22	22
23	23
24	24
25	25
26	26
27	27
28	28
29	29
30	30
31	31
32	32
33	33
34	34
35	35
36	36
37	37
38	38
39	39
40	40
41	41
42	42
43	43
44	44
45	45
46	46
47	47
48	48
49	49
50	50
51	51
52	52
53	53
54	54
55	55
56	56
57	57
58	58
59	59
60	60
61	61
62	62
63	63
64	64
65	65
66	66
67	67
68	68
69	69
70	70
71	71
72	72
73	73
74	74
75	75
76	76
77	77
78	78
79	79
80	80
81	81
82	82
83	83
84	84
85	85
86	86
87	87
88	88
89	89
90	90
91	91
92	92
93	93
94	94
95	95
96	96
97	97
98	98
99	99
100	100

**Executive Engineer,
Solán B&R Division,
H.P.P.W.D.; Solán.**

H.P.P.W.D.;Solun.

Qty.

Unit

Rate in

Figures

words

Amount

Estimated Cost:-

45851.00

Earnest Money:-

1000.00

Time limit :-

One month

Work :- Repair and Maintenance of Type-III quarter set No.4 Near ITI colony Solan (SH:- Providing and laying tile k, plastering, painting and distemping)

Repairs to plaster of thickness 12 mm to 20 mm (twelve to twenty millimeter) thick with cement mortar 1:4 (one cement is to four sand) in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.

Marble tiles (polished) Raj Nagar 8 mm thick Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade complete as per H.P.P.W.D. Specification, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.

Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer in Charge and as per HP.P.W.D. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.

Distemping One coat with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacturer, including applying additional coats wherever required, to achieve even shade and colour as per direction of Engineer in Charge and as per HP.P.W.D. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.

Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per direction of Engineer in Charge and as per HP.P.W.D. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.

15.51	Per Square Meter	264.35	Rupees Two Hundred Sixty Four and Paise Thirty Five Only	4100.00
2.80	Per square meter	1068.95	Rupees One Thousand Sixty Eight and Paise Ninety Five Only	2993.00
240.38	Per Square Meter	85.10	Rupees Eighty Five and Paise Ten Only	20456.00
240.38	Per Square Meter	31.75	Rupees Thirty One and Paise Seventy Five Only	7632.00
240.38	Per square meter.	11.15	Rupees Eleven and Paise Fifteen Only	2680.00

Job No.:- 20

SCHEDULE OF QUANTITY.Name of work: - Restoration of Rain Damages on various roads under Kandaghat Sub-Division (SH:- Hiring of JCB/Loader cum-excavator for removal of slips).
(Kandaghat Section-II)Estimated Cost: - 99750.00
Earnest Money: - 2000.00
Time Limit: - One Month.

Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	2	3	4	5	6	7
1	Hiring of JCB / loader cum-excavator .					
	Terms and Conditions :-					
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.	105.000	Per hour.	950.00	Rupees nine hundred fifty & paisa nil only.	99750.00
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.					
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
					Total:-	99750.00
	Total in words.				Rupees Ninety nine thousand seven hundred fifty only.	
	Quoted Percentage rate			(+)/(-)		

Sno. for the year 2024-25.

Executive Engineer,
Solani B&R Division,
H.P.P.W.D; Solan.

Job No.:- 21

SCHEDULE OF QUANTITY.Name of work:- Restoration of Rain Damages on various roads under Kandaghat Sub-Division (SH:- Hiring of JCB/Loader cum-excavator for removal of slips).
(Sadhupul Section)

Estimated Cost: -

99750.00

Earnest Money: -


2000.00

Time Limit: -

One Month.

Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	2					
1	Hiring of JCB / loader cum-excavator .	3	4	5	6	7
	Terms and Conditions :-					
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.	105.000	Per hour.	950.00	Rupees nine hundred fifty & paisa nil only.	99750.00
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.					
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
	Total in words.				Rupees Ninety nine thousand seven hundred fifty only.	99750.00
	Quoted Percentage rate			(+)/(-)		

Sno. for the year 2024-25.


 Executive Engineer,
 Solan B&R Division,
 H.P.P.W.D; Solan.

Estimated Cost: -	99750.00
-------------------	----------

Earnest Money: -	2000.00
------------------	---------

Time Limit: -	One Month.
---------------	------------

CB/Loader cum-excavator for removal of slips).

Sl. No.	Particulars	Time Limit	One Month
	Reconstruction of Rail Damages on various roads under Kandaghat Sub-Division (SH:- Hiring of JCB/Loader cum-excavator for removal of slips).		

Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	2	3	4	5	6	7
1	Hiring of JCB / loader cum-excavator .					
	Terms and Conditions :-					
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.	105.000	Per hour.	950.00	Rupees nine hundred fifty & paisa nil only.	99750.00
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.					
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
					Total:-	99750.00
					Total in words-	
					Rupees Ninety nine thousand seven hundred fifty only.	
					Quoted Percentage rate	
					(+)/(-)	

Sno.	for the year 2024-25.
------	-----------------------

M.L.
Executive Engineer,
Solani B & R Division,
H.P.P.W.D.; Solani.

Job No.:- 24

Name of work: - Restoration of Rain Damages on various roads under Kandaghat Sub-Division (SH:- Hiring of JCB/Loader cum-excavator for removal of slips).
(Chaussha Section)

SCHEDULE OF QUANTITY.

Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	2	3	4	5	6	7
1	Hiring of JCB / loader cum-excavator .					
	Terms and Conditions :-					
(a)	Hire charges should include expenses on account of establishment, POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd.					
(b)	Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents.					
(c)	Hire charges should also include all local or out side taxes including of road tax entry tax and other taxes if any.	105.000	Per hour.	950.00	Rupees nine hundred fifty & paisa nil only.	99750.00
(d)	Hire charges shall be payable only on signing of contract agreement and bringing the machinery/vehicles to the site as per the direction of Engineer-in-Charge.					
(e)	Minimum work as per PWD norms must be executed by the machinery hired.					
(f)	The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one cum. Respectively and BHP is 72. The machinery should be of latest Model .					
(g)	Quantity of excavated/removed material should not be less than 28 cum/per hour					
					Total:-	99750.00
		Total in words.				
		Rupees Ninety nine thousand seven hundred fifty only.				
		Quoted Percentage rate				
		(+)/(-)				

Sno. for the year 2024-25.

Executive Engineer,
Solani B&R Division,
H.P.P.W.D; Solan.

SCHEDULE OF QUANTITY.

Restoration of Rain Damages on various roads and streets

(Kandaghat Section-I)

Estimated Cost: -	96000.00
Earnest Money: -	2000.00
Time Limit: -	One Month

(Kandaghat Section-I)						
Sno.	Description of items	Quantity.	Unit.	Rate in figure.	Rate in Words.	Amount.
1	2	3	4	5	6	7
1	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. And as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	24.00	Per day	4000.00	Ruppes four thousand and paisa nil only.	96000.00
Total in words.		Total:-				96000.00
Quoted Percentage Rate		Ruppes Ninety Six thousand only.				
		(+)/(-)				

Sno.	for the year 2024-25.

At-
Executive Engineer,
Solani B&R Division,
H.P.P.W.D.; Solani.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
					Estimated Cost:-	98350.00
					Earnest Money:-	2000.00
					Time limit :-	Fifteen days

Name of work: -Annual repair and maintenance of Kandaghat Sub Division (SH : - Supply and stacking of crushed Sand etc.) (Chail Section)

1	Supplying and stacking at site sand of approved quarry which should be sharp clelan and chemically free from adhesive coating, partical of shanke and organic matter and free from impurities like iron particles, alkalis, salt and laminated material which may effect adversely its strength and appearances of mortar. Amount of defective substances, fine clay, fine silt etc. shall not exceed by more than 4% (four percent) as per direction of Engineer-in-Charge at site.	70.00	Per Cubic Meter	1405.00	Rupees Thousand Hundred Five Only	One Four	98350.00
Total in figures :-							98350.00
Total in Words :-							
Quoted Percentage rate :-			(+) / (-)				
Rupees Ninety Eight Thousand Three Hundred Fifty Only							

Sr. No. for the year 2024-25

Executive Engineer
B&R Division, HP.PWD.Solan.