




Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO.PWD/BD/TA/NIT/2024-25/-
18899- 18908 DATED 21/2/2025 ARE URGENT NATURE
AND PUBLIC INTEREST.


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

“NOTICE INVITING TENDER”

Sealed percentage rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **20.02.2025** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **19.02.2025** between **2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **18.02.2025 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O Dharamshala Dadh Palampur Holta Chadhiar Sandhole Road (SH: C/O R/Wall at RD 59/120 to 59/124.50)	Rs.99,496/-	Rs.2,000/-	Rs.350/-	One Month
2	C/O Dharamshala Dadh Palampur Holta Chadhiar Sandhole Road (SH: R/Wall at RD 59/130 to 59/134.50)	Rs.98,626/-	Rs.2,000/-	Rs.350/-	One Month
3	C/O Paprola to Andretta Road Km 0/00 to 6/300 (SH: Construction of 2.00 Mtr. Span RCC slab culvert at RD 3/700) (SW: Construction of sub Structure and bed block)	Rs.97,537/-	Rs.2,000/-	Rs.350/-	Two Months
4	C/O link road from Harer to Kandral Road (SH: Supplying and stacking, G-II (63 to 45 mm).	Rs.99,000/-	Rs.2,000/-	Rs.350/-	One Month
5	Restoration of Rain Damages on Lohardi to Andharli Malhan road Km 0/00 to 2/500 (SH: C/O unlined Surface drain at various RDs and maintenance of earthen shoulder and dressing of berms at Various reaches)	Rs.99,780/-	Rs.2,000/-	Rs.350/-	One Month
6	Restoration of damages due to OFC on Baijnath Bhattu road and various roads under Bir Sub-Division (SH: Providing and fixing of road studs)	Rs.99,000/-	Rs.2,000/-	Rs.350/-	Two Months
7	C/O Samshan Ghat Nehar Ward No.6, 7 Dhanag (SH: C/O E/Wall & P/L Stone Soling and C.C. Pavement) SDP/2023/1134 Deposit work.	Rs.98,393/-	Rs.2,000/-	Rs.350/-	Two Months
8	Special Repair in Office of Civil-Judge-Cum-JMFC. (SH: Repair of Main Door & Window Panel and Fixing of Collapsible door, glass panes etc.)	Rs.58,831/-	Rs.1,200/-	Rs.350/-	Two Months
9	C/O on Holta Chadhiar Road (Providing and Fixing Sitting Bench on Chadhiar Bus Stand) Deposit work (VKV/2024/1483)	Rs.48,432/-	Rs.1,000/-	Rs.350/-	One Month
10	C/O Main Road to Captan Jagdish House VPO Kudail Km 0/00 to 0/700 (SH: P/L 60mm thick Paver Block at Km 0/600 to 0/624) Under MMGSY	Rs.99,43 2/-	Rs.2,000/-	Rs.350/-	Two Months

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
2. The Pan Number, latest Income Tax clearance certificate and EPF No (Where applicable) duly attached with the application.
3. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
4. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.

E.E.

5. Only two tenders form will be issued to the contractor/firm which may be noted.
6. The contractor will also have to attach the labour employer license from the labour office with the application.
7. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
8. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
9. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
10. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
11. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
12. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer,
Bajjnath Division.,
H.P.PWD..Bajjnath.

For & On behalf of the governor of H.P.

NO:-PWD/BD/TA/NIT/2025/- 18899-18908

Dated:-07.02.2025

- 1 Copy to the F.C.Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Bajjnath Division.,
H.P.PWD..Bajjnath.

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O Dharamshala Dada Palampur Holta Chadhiar Sandhole Road
(Sh:- C/O R/W all at RD 59/120 to 59/124.50)

Estimate Cost: 99,496.00/-
Earnest Money: 2,000.00/-
Time Limit : One month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	6.48	Per Cum	290.00	Rupees Two Hundred & Ninety Only	1,879.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	17.91	Per Cum	4950.00	Rupees Four Thousand Nine Hundred & Fifty Only	88,655.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	3.78	Per Cum	990.00	Rupees Nine Hundred & Ninety Only	3,742.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.00	Each	290.00	Rupees Two Hundred & Ninety Only	5,220.00
Total						99,496.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

D.N.T.T. Checked and approved for Rs.

99,496.00 only

Rupees Ninety Nine Thousand Four Hundred Ninety Six Only

Executive Engineer
Bajnath Division
HPWD Bajjnath

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O Dharamshala Dada Palampur Holta Chadhar Sandhole Road
(Sh:- C/O R/Wall at RD 59/130 to 59/134.50)

Estimate Cost: 98,626.00/-
Earnest Money: 2,000.00/-
Time Limit: One month

Sr. No.	Description of work	No. or Qty.	Unit	Time Limit : one month		AMOUNT Rs. p
				Figures	Rate Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In – Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	6.48	Per Cum	290.00	Rupees Two Hundred & Ninety Only	1,879.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone age- 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	17.91	Per Cum	4950.00	Rupees Four Thousand Nine Hundred & Fifty Only	88,655.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	3.78	Per Cum	990.00	Rupees Nine Hundred & Ninety Only	3,742.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614.709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	15.00	Each	290.00	Rupees Two Hundred & Ninety Only	4,350.00

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

D.N.I.T. Checked and approved for Rs.

Rupees Ninety Eight Thousand Six Hundred Twenty Six Only

Executive Engineer
Bajinath Division
HPPWD Bajinath

98,626.00 only

DNT/DRAFT SCHEDULE OF QUANTITY

(3)

Name of Work:- C/O Paprola to Andretta Road km 0/00 to 6/300
(SH:- Construction of 2.00 mtr span RCC slab culvert at RD 3/700 .
(SW:- Construction of sub Structure and bed block .

Estimate Cost: 97,537.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sl. No.	Description of work	No. or Qty.	Unit	Rate to be entered by the		AMOUNT Rs. P
				Figures	Words	
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805 ,806,807,1202 and 1204 M-15 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	11.78	Cum	6150.00	Rupees Six Thousand One Hundred Fifty Only	72447.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805 ,806,807,1202 and 1205 RCC M-20 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.61	Cum	6950.00	Rupees Six Thousand Nine Hundred Fifty Only	25090.00
						97537.00
	Quated rates Percentage in figures					
	Quated rates Percentage in words					

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

D.N.I.T. Checked and approved for Rs. 97,537.00 only
Rupees Ninety Seven Thousand Five Hundred Thirty Seven Only

Executive Engineer
Bajnath Division
HPPWD Bajnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work: - C/O link road from Harer to Kandral Road
(SH: Supplying and stacking, G-II (63 to 45 mm)).

Estimate Cost: 99,000.00/-
Earnest Money: 2,000.00/-
Time Limit : One Month

SCHEDULE OF WORKS

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMC Rs.
				Figures	Words	
1	Supplying and stacking at site broken/crushed stone aggregate from hard stone of approved quarry 63mm to 45mm (sixty three to forty five millimeter) of disintegrated pieced deleterious and organic matter from the approved quarry in specified stacks as per instruction of Engineer-in-Charge. The aggregates shall be free of elongated and flaky pieces, soft and disintegrated stones and vegetable and other deleterious matter. The aggregates shall be stacked in proper stacks of road side clear of carriage way and shoulders or on even ground as per the instruction of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	45.00	Per Cubic metre	2,200.00	Ruppes Two Thousand Two Hundred Only	9
	Quated rates Percentage in figures					9
	Quated rates Percentage in words					

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

D.N.I.T. Checked and approved for Rs.

99,000.00 only

Ruppes Ninety Nine Thousa

Executive Engineer
Bajinath Division
HPPWD Bajinath

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work : Restoration of Rain Damages on Lohardi to Andharli Malhan road km 0/00 to 2/500

(SH: C/O unlined Surface drain at various RDs and maintenance of earthen shoulder and dressing of berms at Various reaches)

Estimate Cost: 99,780.00/-
Earnest Money: 2,000.00/-
Time Limit : One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Construction of Unlined Surface drains of average cross sectional area 0.20 Sqm (Point two zero square meter) in soil to specified lines, grade, levels and dimensions Excavated material to be used in embankment with a lift upto 3 mtr (three meter) and lead of 50 mtr (fifty meter) (average lead 25 mtr) (twenty five meter) as per technical Clause 1903 within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	1040.00	Per Running metre	56.00	Rupees Fifty Six Only	58,240.00
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC (optimum moisture content) upto a lead of 1000 m (one thousand meter) within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals. the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	1538.50	Per Square metre	27.00	Rupees Twenty Seven Only	41,540.00
	Total					99,780.00
	Quated rates Percentage in figures					
	Quated rates Percentage in words					

D.N.I.T. Checked and approved for Rs. 99,780.00 only

Rupees Ninety Nine Thousand Seven Hundred Eighty On

Executive Engineer
 Bajinath Division
 HPPWD Bajinath

- Condition :-**
1. Rate should be quoted for all heights including all leads and lifts
 2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

SCHEDULE OF QUANTITY
Name of work:-Restoration of damages due to OFC on Baijnath Bhattu road and various roads under Bir Sub division
(SH:-Providing and fixing of road studs)

Estimate Cost 99000.00 ✓
 Earnest Money 2000.00 ✓
 Time limit Two months ✓

Sr. No.	Description of item	Quantity.	Rate in figures.	Rate in words.	Unit	Amount.
1	Providing and fixing of Solar road stud having 3 LED's of colour red to a side (total 6 nos.) housed in a tough pressure casted aluminium alloy of any size (125 mm* 25mm) with built in stem of suitable length for fixing with epoxy, LED's, solar cells, battery and light sensor well protected inside under tough unbreakable polycarbonate transparent sheet roof system workable for 2-3 days (nights) after full charge in 8-10 hours complete as per directions of Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	33.00 ✓	3000.00 ✓	(Rs. Three Thousand only) ✓	each ✓	99000.00 ✓
	Total					99000
	Quated rates Percentage in figures					
	Quated rates Percentage in words					

D.N.I.T. Checked and approved for Rs.

99,000.00 only ✓
 Rupees Ninety Nine Thous

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per Indian standard in market should confirm to bureau of Indian standards

Executive/Engineer
 Baijnath Division
 HPPWD Baijnath

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work : C/O Samsan Ghat Nehar Ward no.6, 7 Dhanag
(SH: C/O E/wall & P/L Stone soling and C C Pavement) SDP/203/1134 DEPOSIT WORK.

Estimate Cost: 98,393.00/-
Earnest Money: 2,000.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.71	Per Cum	290.00	Rupess Two Hundred & Ninety Only	496.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	3.66	Per Cum	4950.00	Rupess Four Thousand Nine Hundred & Fifty Only	18,117.00
3	Providing sweep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.00	Each	290.00	Rupess Two Hundred & Ninety Only	580.00
4	Providing and laying hard stone Soling properly hand packed intersects with Kharanja stone and consolidating with power / hand roller to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	9.00	Per Cubic metre	1,850.00	Rupess One Thousand Eight Hundred Fifty Only	16,650.00
5	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 Kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	9.00	Per Cubic metre	6,950.00	Rupess Six Thousand Nine Hundred Fifty Only	62,550.00
Total						98,393.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						

D.N.T. Checked and approved for Rs.

98,393.00 only

Rupess Ninety Eight Thousand Three Hundred Ninety Three Only

Executive Engineer

Bajinath Division

HPPWD Bajinath

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

260

DNT/DRAFT SCHEDULE OF QUANTITY

Name of Work :- Special Repair in Office of Civil-Judge-Cum-JMFC.
(SH:-Repair of Main Door & Window Panel and Fixing of Collapsible door , glass panes etc)

Estimate Cost: 58,831.00
Earnest Money: 1,200.00
Time Limit : Two Months

Sr.No	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing glazing with glass panes of 4mm thickness (weight not less than 10.00 kg/sqm. in aluminium door, window, ventilator shutters and partition etc with PVC/neoprens gasket etc. complete as per the architectural drawings and the directions of Engineer-In-charge (cost of aluminium snap beading shall be paid in basic item.) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge.	1.69	Per Square metre	603.90	Ruppes Six Hundred & Three - Paise Ninety Only	1,021.00
2	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately.) Sal wood The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.004	Cum	95,763.05	Ruppes Ninety Five Thousand Seven Hundred & Sixty Three - Paise Five Only	383.00
3	Providing and fixing in position collapsible steel shutters with vertical channels 20 mm X10 mm X2mm and braced with flat iron diagonals 20 mm X5 mm size with top and bottom rails of T.Iron 40 mm X40 mm X6 mm with 38 mm dia steel pulley complete with bolts and nuts looking arrangements, stoppers, handles, including applying a priming coat of red lead paint. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.60	Sqm	8,500.00	Ruppes Eight Thousand Five Hundred Only	30,600.00
4	Providing and fixing anodised aluminium work for door, window, ventilators and partitions with extruded built up standard tubular and other sections of approved make conforming to IS 733 and IS 1285 anodised transparent or dyed to required shade according to IS 1868. (Minimum anodic coating of grade AC 15) fixed with raw/plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC/neoprene felt etc. Aluminium sections shall be smooth, rustfree, straight, mitred and jointed mechanically where ever required including cleat angle, aluminium, snap beading for glazing/paneling C.P. brass/stainless steel screws. All complete as per architectural drawings and the directions of Engineer-In-Charge. For doors windows and ventilators and glazed partitions frames. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	58.48	Per Kg	405.55	Ruppes Four Hundred & Five - Paise Fifty Five Only	23,717.00
5	Providing and fixing glazing in aluminium door, window, ventilator shutters and partition etc with PVC/neoprens gasket etc. complete as per the architectural drawings and the directions of Engineer-In-charge (cost of aluminium snap beading shall be paid in basic item.) Glazing with glass panes of 5.50mm thickness (weight not less than 13.75 kg/ sqm.	5.15	Per Sqm	603.90	Ruppes Six Hundred & Three - Paise Ninety Only	3,110.00
Quoted rates Percentage in figures						58,831.00
Quoted rates Percentage in words						

D.N.T. Checked and approved for Rs.

58,831.00 only

Ruppes Fifty Eight Thousand Eight Hundred Thirty One Only

Executive Engineer
Bajnaath Division
HPPWD Bajnaath

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - In - Charge in advance before actual use on work and any or all material which are available as per Indian standard in market should confirm to bureau of Indian standards

DNIT/DRAFT SCHEDULE OF QUANTITY

9

Name of work : C/O on Holta Chadhiar Road
(SH:- Providing and Fixing Sitting Bench on Chadhiar Bus Stand) Deposit work (VKV/2024/1483)

Estimate Cost: 48,432.00
Earnest Money: 1,000.00
Time Limit : One Month

Sl. No.		Description of work	No. or Qty.	Unit	Rates		AMOUNT Rs.
					Figures	Words	
1		Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars, ladders, railing, brackets and similar works including Carriage of Material with in all lifts complete in all respect as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	440.29	Per Kilogram	110.00	Rupees One Hundred Ten Only	
		Quated rates Percentage in figures					48
		Quated rates Percentage in words					

D.N.I.T. Checked and approved for Rs.

48,432.00 only

Rupees Forty Eight Thousand Four Hundred Thirty

Executive Engineer
Bajinath Division
HPPWD Bajinath

D.N.I.T./ SCHEDULE OF QUANTITY

Name of work :- C/O Main Road to Captain Jagdish House VPO kudail km 0/00 to 0/700
(Sh:- P/L 60mm thick Paver Block at Km 0/600 TO 0/624). *under mmsy*

Estimated Cost: Rs. 99432.00
Earnest Money: Rs. 2,000.00
Time Limit : Two Months

SCHEDULE OF WORKS

Sr No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Providing concrete for plain / reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 PCC Grade M-20 Nominal Mix 1:2:4 (one cement : two sand; four aggregate) per the direction of Engineer-in-charge including entire carriage of materials within all leads and lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, GST or other taxes imposed by the Government.	0.77	Cum	6950.00	Rupees Six Thousand Nine Hundred & Fifty Only	5352.00
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge 60mm (sixty millimeter) thick cement concrete paver block of M-35 grade with approved colour, design & pattern. The rate including of octroi, royalty, Malkhana, tolltax, Sale Tax or other taxes imposed by the government	58.80	Sqm	1,600.00	Rupees One Thousand Six Hundred Only	94080.00
TOTAL						99432.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						

D.N.I.T. Checked and approved for Rs. 99,432.00 only

Rupees Ninety Nine Thousand Four Hundred Thirty Two Only

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

Executive Engineer
Bajnath Division
HPPWD Bajnath