

**Himachal Pradesh
Public works Department**

Notice Inviting Tender

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD: Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **22-02-2025 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non-refundable) up to 5.00 P.M. on **21-02-2024**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 20-02-2025**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	RRD on Chail Gohar Pandoh road km. 0/00 to 24/00 (SH:- C/o PCC edge wall at RD 2/325 to 2/331 and U-Shape drain in km. 2/325 to 2/356)	98464	2000	Two Months
2	C/o link road from Burahta to Kathla road km. 0/00 to 6/080 Tehsil- Chachiot, Distt. Mandi (SH:- Preparation of Forest Diversion case) Job No. I	88500	1800	Two Months
3	C/o link road from Burahta to Kathla road km. 0/00 to 6/080 Tehsil- Chachiot, Distt. Mandi (SH:- Preparation of Digital Plan i/c Online submission and compensatory afforestation maps of forest cases) Job No.II	88500	1800	Two Months
4	Construction of tunna Bhurla road via Dari , Ger, Kunsot Km. 0/00 to 6/500 (SH:- P/L stone solling at RD 1/560 to 1/660) Under SCSP	98966	2000	Two Months
5	RRD on Tandi Nandi road km. 0/00 to 9/500 (SH:- cutting of branches of trees shrubs and trimming of grass and weeds in km. 4/700 to 9/500)	98662	2000	Two Months
6	Construction of gohar Neori road km. 0/00 to 5/000 (SH:- improvement of Sharp Curve at km. 0/220 to 0/285)	98990	2000	Two Months

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the percentage rates in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I

dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.

7. The contractor can apply only for one work at a time.
8. Conditional and incomplete tenders shall be rejected.
9. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,
Gohar Division (B&R),
HPPWD Gohar.

Dated

11/02/2025

No. PW-GHR-Tender/NIT/2024 11299-11312
Copy along with Tender inviting Notice forwarded for information:-

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
3. The Superintending Engineer 1stCircle, HP.PWD Mandi.
4. ✓ The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.
5. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
6. The Block Development Officer Gohar.
7. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
8. Various contractors.
9. Notice Board/DB/AB.

04
Executive Engineer,
Gohar Division (B&R),
HPPWD., Gohar.

BILL OF QUANTITY

Name of Work:- RRD on Chail Gohar Pandoh road km. 0/00 to 24/0 (SH:- C/o PCC edge wall at RD. 2/325 to 2/331 and U- shape drain in km. 2/325 to 2/356) .

Estimated cost Rs. - 98464.00

Earnest Money cost Rs. - 2000.00

Time - Two Month

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	28.04	Per Cubic metre	322.00		
2	Providing and Laying concrete for plain/reinforced concrete in open foundations P.C.C nominal mix 1:5:10 (one cement :five sand : ten graded stone aggregate 40 mm fourty millimetre aggregates) complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.	4.68	Per cubic metre	4793.45		
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:3:6 (one cement: three sand : six graded stone aggregated) P.C.C grade M 10 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	11.31	Per Cubic metre	5924.15		
Total						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Executive Engineer
Gohar Division
H.P.P.W.D. Gohar

BILL OF QUANTITY

of work :- C/o link road from Burahta to Kathala road km. 0/00 to 6/080 Tehsil-Chachiot,
Dist- Mandi. (SH:-Preparation of Forest Diversion case) Job No. I

Estimated cost Rs. 88500.00

Earnest Money cost Rs. - 1800.00

Time - Two Months

Sl. No	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Preparation of Forest Diversion case under Forest Conservation Act-1980 including preparation of all essential papers of (excluding revenue papers) the road alignment and collection of other field data. and all relevant documents/ Formats mandatory required would be attached with the case as per latest requirement of Ministry of Environment and forest conservation Govt. of India after getting the joint inspection/ site including computer typing in 6 copies, binding complete including online submission and getting it approved from Nodal Officer Forest /Department Shimla and after that hard copies getting it through HP,PWD Sub division Gohar, HP,PWD Division Gohar, Office of concerned range Officer, Office of DFO Nachan and Conservator of Forest Department Mandi Nodal Officer Shimla including attending all the observations, if raised at any time by any office and to prepare the same by neatly and accurately filling in all the formats/Documents with Geo reference/Digital map Global Positioning System Coordinators collection from site including preparation of KMLs files, CA site KML, CA site digital map etc. online submission of forest with scanning of all papers in PDF files as per requirement and as per direction of Engineer-in-charge.	1.000	Per Job	88500		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Executive Engineer
Gohar Division
H.P.P.W.D. Gohar

291

BILL OF QUANTITY

Name of work :- C/o link road from Burahtha to Kathala road km. 0/00 to 6/080 Tehsil-Chachiot,
Distt- Mandi. (SH:-Preparation of Digital Plan i/c Online Submission and compensatory afforestation maps of Forest cases) Job No. II

Estimated cost Rs. - 88500.00

Earnest Money cost Rs. - 1800.00

Time - Two Months

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Preparation of Forest Deversion case under Forest Conservation Act-1980 including preparation of all essential papers of (excluding revenue papers) the road alignment and collection of other field data. and all relevant documents/ Formats mandatory required would be attached with the case as per latest requirement of Ministry of Environment and forest conservation Govt. of India after getting the joint inspection/ site including computer typing in 6 copies, binding complete including online submission and getting it approved from Nodal Officer Forest /Department Shimla and after that hard copies getting it through HP,PWD Sub division Gohar, HP,PWD Division Gohar, Office of concerned range Officer, Office of DFO Nachan and Conservator of Forest Department Mandi Nodal Officer Shimla including attending all the observations, if raised at any time by any office and to prepare the same by neatly and accurately filling in all the formats/Documents with Geo reference/Digital map Global Positioning System Coordinaters collection from site including preparation of KMLs files, CA site KML, CA site digital map etc. online submission of forest with scanning of all papers in PDF files as per requirement and as per direction of Engineer-in-charge.	1.000	Per job	88500		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY**Name of Work:- Construction of Tunna Bhurla road via Dari, Ger, Kunsot KM 0/000 to 6/500 (SH:- P/L stone
solling at RD. 1/560 to 1/660) Under SCSP****Estimated cost Rs. - 98960.00****Earnest Money cost Rs. - 2000.00****Time - Two Month**

Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Stone solling 150mm (one hundred fifty millimetre) spread thickness (finished work including materials and labour) properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD. specification complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	48.00	Per Cubic metre	2061.80		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Executive Engineer
Gohar Division
H.P.P.W.D. Gohar

BILL OF QUANTITY						
Name of Work:- RRD on Tandi Nandi road km. 0/00 to 9/500 (SH:- Cutting of branches of trees shrubs and trimming of grass and weeds in km. 4/700 to 9/500) .					Estimated cost Rs. - 98662.00	
					Earnest Money cost Rs. - 2000.00	
					Time - One Month	
Sl. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Cutting of branches of trees shrubs and trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials with in all leads and lifts as per the direction of EGINEER - in - Charge.	11676.00	Per Square Meter	8.45		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- Construction of Gohar Neori road km 0/00 to 5/000 (SH:- Improvement of Sharp Curve at km 0/220 to 0/285)							Estimated cost Rs. - 98,990/-
							Earnest Money cost Rs. 2000/-
							Time - Two Month
SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words	
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required setting out to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer-in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries , materials , tools equipment's and sefety measures and incidentals necessary to complete the work by all means (if any required) recovery for 39.30 cubic metre @ Rs. 300.00 per cubic metre amount Rs.11,790/- shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect including all leada and lifts and materials and as per direction of Engineer in charge .	471.56	Per Cubic meter	209.92			
	Total:-						
	Percentage rate Quoted in figure						
	Percentage rate Quoted in words						

04
Executive Engineer
Gohar Division (B&R)
H.P.W.D Gohar.