

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Registered

NO. PWP/CB/Tender Notice/2024-25- 1950-52
To

Dated:- 15/07/2024

✓ The Executive Engineer (IT Cell),
HPPWD, Nigam Vihar, Shimla-2.

Subject :- Regarding publication of Tender Notice on departmental
website to be opened on 25.07.2024.

Enclosed please find herewith the tender notice alongwith schedule of quantity for
uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP, No. PBW (B) A
(3) 1/2020 dated Shimla-2 the 16th July 2021.


1. Certified that the tender mentioned in the notice is exigencies/emergency of urgent nature and in
public interest.

Enclosures:- Notice Inviting tender and schedule of quantity.


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

Copy forwarded along with tender notice via e mail for information to:-

1. The Superintending Engineer Nahan 12th Circle HP.PWD Nahan for information please.
2. Notice Board.


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage rate tender are hereby invited by the Executive Engineer Paonta (B&R) Division HP.PWD Paonta Sahib on behalf of Governor of HP from the approved/ eligible contractor registered in HPPWD for the work, so as to reach in this office on 25.07.2024 up to 2:00 PM and shall be opened on 25.07.2024 the same day at 2:30 PM in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 4.00 PM on 24.07.2024 for which the applications should reach in this office up to 4.00 PM on 23.07.2024. The tender form will be issued to the contractor giving proof of registration as GST.

The earnest money in the shape of NSC / Time deposit account / Saving account in any of the Post Office in HP or FDR/CDR from nationalized bank duly pledged in the name of Executive Engineer Paonta B&R Division HP.PWD Paonta Sahib must be accompanied with the application. Conditional tender and tender received without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all tenders without assigning the reason. If there happens to be any holiday the same will be open on the next working day.

Sr. No.	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form	Class
1	Construction of link road to village Thakkar Kujewala road Km. 0/0 to 4/750. (SH:- Providing and laying G II at RD. 2/540 to 3/100). Under SCSP.	Rs. 3,18,667/-	Rs. 6500/-	Three months	350/-	C & D Class
2	Construction of link road to village Thakkar Kujewala road Km. 0/0 to 4/750. (SH:- Providing and laying G II at RD. 3/100 to 3/655). Under SCSP.	Rs. 3,24,517/-	Rs. 6500/-	Three months	350/-	C & D Class
3	Construction of link road to village Thakkar Kujewala road Km. 0/0 to 4/750. (SH:- Providing and laying G II at RD. 2/0 to 2/540). Under SCSP.	Rs. 3,15,742/-	Rs. 6500/-	Three months	350/-	C & D Class
4	Restoration of rain damages of link road from Jamnighat Jheelbankabara to Dhaunwala road Km. 0/0 to 5/020. (SH:- C/O retaining wall in cement concrete at RD. 4/628 to 4/635 & 4/684 to 4/700).	Rs. 3,70,002/-	Rs. 7500/-	Three months	350/-	C & D Class
5	Restoration of rain damages on link road village Katwari Bagrath to Jallal River Km. 0/0 to 5/00. (SH:- Construction of Retaining wall in wire crate at RD 3/880 to 3/395).	Rs. 4,99,744/-	Rs. 10000/-	Three months	350/-	C & D Class
6	Construction of link road to village Jhivar Basti Bharapur Km. 0/0 to 1/460. (SH:- Providing and laying interlocking tiles at	Rs. 4,75,976/-	Rs. 10,000/-	Three months	350/-	C & D Class

	RD.0/325 to 0/425). Under MNP.					
7	Construction of road from Lohgarh to Banda Bahadur Guruwara Sahib Km. 0/0 to 4/200. (SH:- C/O Hume pipe culvert 900 mm dia at RD. 0/510 & Improvement of curves from RD. 1/140 to 1/174).	Rs. 4,90,522/-	Rs. 10,000/-	Three months	350/-	C & D Class
8.	Construction of road from Lohgarh to Banda Bahadur Guruwara Sahib Km.0/0 to 4/200.(SH:- C/O Hume pipe culvert 900 mm dia at RD. 0/910 & Improvement of curves from RD. 1/174 to 1/213).	Rs. 4,88,646/-	Rs. 10,000/-	Three months	350/-	C & D Class
9.	Construction of link road from Main road Kundio to Jhabha Basti 0/0 to 1/600. (SH:- C/O Hume pipe culvert 900 mm dia at RD. 0/750). Under MNP.	Rs. 3,66,361/-	Rs. 8,000/-	Three months	350/-	C & D Class
10.	Construction of link road from NH-72 to Gadriya Basti Surajpur km. 0/0 to 0/630. (SH:- Construction of cutting in earth work, road & filling at RD. 0/570 to 0/600). Under MNP.	Rs. 4,51,980/-	Rs. 10,000/-	Two months	350/-	C & D Class
11.	Restoration of rain damages on Badripur Jamniwala Parduni road km. 0/0 to 15/0. (SH:- Construction of Retaining wall in cement concrete from RD. 12/540 to 12/548, 12/549 to 12/557 and 12/605 to 12/614).	Rs. 4,73,168/-	Rs. 9,500/-	Three months	350/-	C & D Class
12	Restoration of rain damages to various roads under Paonta Sub- Division No. II HP.PWD Paonta Sahib. (SH:- Hiring of JCB and Tractor with trolley for removal of slips, Dressing of berms and cleaning of side drain and filling of pot holes on various roads).	Rs. 4,97,250/-	Rs. 10,000/-	Two months	350/-	C & D Class
13.	Restoration of rain damages to various roads under Paonta Sub- Division No. II HP.PWD Paonta Sahib. (SH:- Hiring of Tractor with trolley for disposal of debris, removal of slips with JCB, and carriage of materials for filling depressions/pot holes and carriage of waste materials on various roads).	Rs. 96,000/-	Rs. 2,000/-	Two months	350/-	C & D Class

14.	Construction of link road to Harijan Basti Dadhyat Km. 0/00 to 1/565. (SH:- Construction of 5/7 mtr. wide road formation cutting and filling in km. 1/370 to 1/550) & Construction of R/walls in essential RDs). Under SCSP.	Rs. 4,04,101/-	Rs. 8,500/-	Two months	350/-	C & D Class
15.	Construction of link road from Main road Kundion to Jhabha Basti 0/0 to 1/600. (SH:- C/O Hume pipe culvert 900 mm dia at RD. 0/865). Under MNP.	Rs. 3,66,361/-	Rs. 8,000/-	Three months	350/-	C & D Class
16.	Construction of link road from NH-72 to Gadriya Basti Surajpur km. 0/0 to 0/630. (SH:- Construction of cutting in earth work, embankment and wire crate at RD. 0/600 to 0/630). Under MNP.	Rs. 4,78,211/-	Rs. 10,000/-	Two months	350/-	C & D Class
17	Restoration of rain damages on Kolar Bilaspur road Km. 0/0 to 12/0. (SH:- C/O wire crate R/wall at RD. 3/680 to 3/695)	Rs. 4,84,510/-	Rs. 10000/-	Two months	350/-	C & D Class
18	Restoration of rain damages on Kolar Bilaspur road Km. 0/0 to 12/0. (SH:- C/O Retaining wall in wire crate at RD. 4/310 to 4/312.50 and 4/420 to 4/426)	Rs. 4,90,478/-	Rs. 10000/-	Three months	350/-	C & D Class
19	Restoration of rain damages on link road to village Kodewala Km. 0/0 to 1/020. (SH:- C/O Breast wall in km. 0/820 to 0/882).	Rs. 4,74,429/-	Rs. 9500/-	Three months	350/-	C & D Class
20	Restoration of rain damages to Lohgarh to Banda Bahadur road Km. 0/0 to 4/200. (SH:- C/O Retaining wall in wire crate at RD. 0/170 to 1/190).	Rs. 3,63,784/-	Rs. 7,500/-	Three months	350/-	C & D Class
21	Restoration of rain damages on various roads under Baila Section & Dhaulakuan Section in HP. PWD (B&R) Sub Division Dhaulakuan. (SH:- Hiring of JCB and tractor with trolley for removal of slips and debries, Dressing of berms, filling of pot holes & opening of block drain).	Rs. 4,95,000/-	Rs. 10,000/-	Three months	350/-	C & D Class
22	Restoration of rain damages on various roads under Baila Section at various roads. (SH:- Construction of unlined surfaces drains on link road to village Bakhan Kelewala and removal of slips in Girinagar Jatton road km. 0/0 to 24/400, Link road to village Thakkar Kujjewala.).	Rs. 4,91,203/-	Rs. 10,000/-	Three months	350/-	C & D Class

23	Restoration of rain damages on Rampur Bharapur Gunglow road km. 0/0 to 5/0. (SH:- Construction of Retaining wall in cement concrete from RD. 0/920 to 0/945).	Rs. 3,78,715/-	Rs. 7,600/-	Three months	350/-	C & D Class
24	Restoration of rain damages in Majra Section & Dhaulakuan Section on various roads. (SH:- Construction of unlined surface drains on Badripur Jamniwala Parduni road km. 15/100 to 19/800, Link road to village Churak Majri km. 0/0 to 5/0 & Jagatpur Parduni road km. 0/0 to 5/0).	Rs. 4,71,889/-	Rs. 10,000/-	Three months	350/-	C & D Class
25	Restoration of rain damages on Kolar Section, Dhaulakuan Sub Division. (SH:- Making up loss of materials on shoulder, Construction of unlined surface drain and dressing of berms at various RDs).	Rs. 4,98,343/-	Rs. 10000/-	Three months	350/-	C & D Class
26	Restoration of rain damages on link road from NH-707 to Bhaddar Kali Mata Mandir km. 0/0 to 2/400. (SH:- Construction of Retaining wall in wire crate above existing wire crate at RD. 0/338 to 0/354). Deposit work).	Rs. 4,98,948/-	Rs. 10000/-	Three months	350/-	C & D Class
27	Restoration of rain damages on Badripur Jamniwala Parduni road km. 0/0 to 15/0. (SH:- Construction of Breast wall in km. 9/182 to 9/207).	Rs. 3,00,051/-	Rs. 6,100/-	Three months	350/-	C & D Class
28	Restoration of rain damages on various roads under Baila Section in HP. PWD (B&R) Sub Division Dhaulakuan. (SH:- Hiring of JCB and tractor with trolley for removal of slips and debries, Dressing of berms, filling of pot holes & opening of block drain of Jamta Rajban road, Girinagar Jatton road, Katwari Bagrath to Jallal river, Swar Landasi Kharkari road & Mehat Gawana Khalli Naddi road of various RDs).	Rs. 4,97,040/-	Rs. 10,000/-	Three months	350/-	C & D Class
29	Restoration of rain damages to Paonta Puruwalla Singhpura Bhagani Gojjar Dakpathar road (MDR-94) km. 0/0 to 26/500. (SH:- Construction of Retaining wall in wire Crate from RD. 26/0 to 26/018).	Rs. 4,91,310/-	Rs. 10,000/-	Two months	350/-	C & D Class
30	Repair and maintenance of Paonta Sahib (Main Bazar) to Rampurghat road km. 0/0 to 5/0. (SH:- Providing and laying Interlocking tiles 80 mm thick at RD. 4/600	Rs. 4,99,747/-	Rs. 10,000/-	Two months	350/-	C & D Class


	to 4/640).Under NCAP Deposit.					
31	Repair and maintenance of Paonta Sahib (Main Bazar) to Rampurghat road km. 0/0 to 5/0. (SH:- Providing and laying Interlocking tiles 80mm thick at RD. 4/641 to 4/665).Under NCAP Deposit.	Rs. 2,99,768/-	Rs. 6,000/-	Two months	350/-	C & D Class
32	Repair and maintenance of Paonta Sahib (Main Bazar) to Rampurghat road km. 0/0 to 5/0. (SH:- Providing and laying Interlocking tiles 80mm thick at RD. 4/666 to 4/706).Under NCAP Deposit.	Rs. 4,99,747/-	Rs. 10,000/-	Two months	350/-	C & D Class
33	A/R & M/O HPPWD (B&R) Division Building at Paonta Sahib. (SH:- Deployment of 2 Nos Sweeper for HP.PWD Division & Sub Division No. I & II offices).	Rs. 2,15,232/-	Rs. 4500/-	12 months	350/-	C & D Class
34.	Preparation of detailed Project report for- (i) C/o link road from NH 707 via Mata Bhadarkali Mandir to forest check post at Kolar Bilaspur road km. 0/000 to 2/400. and (ii) Improvement and up-gradation on NH 07 to Misserwala towards Majra, Churak-Majri Parduni road Km. 0/000 to 15/000). Under NABARD.	Rs. 4,52,000/-	Rs. 9,100/-	Two months	350/-	C & D Class
35	Preparation of detailed Project report for- (i) Construction/Improvement of road from Singhapura to Dhoul Rao, Arli Bhagani Rangad Basti Km. 0/0 to 5/920. and (ii) Construction of road alongwith CD & 3 Nos. bridges soil investigation at Gram Panchayat Haripur Khol in Banda Bhadur Guruduvara to village Lohgarh road in km. 0/000 to 4/800.. Under NABARD.	Rs. 3,03,920/-	Rs. 7,000/-	Two months	350/-	C & D Class

CERTIFICATE:- Certified that the tenders mentioned above in this notice are exigencies/emergency of urgent nature and in public interest.

Conditions:-

- The tender document shall be issued to only those contractors / firms:-
1. Who possess valid Contractor Registration Number.
 2. Who possess valid GST Registration Number.
 3. Who possess valid Permanent Account Number.
 4. Who Possess valid EPF Number.
 5. Ambiguous / telegraphic / conditional tenders or tenders by FAX / E-mail shall not be entertained / considered in any case.
 6. If any date mentioned above happens to be local/gazetted holiday, the same shall be processed on next days.

7. The earnest money for above cited work should be submitted with the applications for purchase of tender form, no exemption for earnest money will be allowed.
8. The contractor / Firms are requested to insert the rate of each item in words as well as in figures/failing which XEN reserves the right to accept/ reject any or all tenders.
9. List of machinery tool plants as per schedule F Sr. No. 6.19 Ref. Clause No. 18 i.e. R.C. and purchase bills alongwith proof of ownership/Affidavit hire basis for bitumen work.



Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib

No.PWP/CB-Tender Notice/2023-24- 1953-2002

Dated:- 15/07/2024

Copy forwarded to the following for information and necessary action please:-

1. The Engineer-in- Chief, HP. PWD Shimla-I
2. All the Superintending Engineer, in HP.PWD
3. The Sub Divisional Magistrate Paonta Sahib.
4. All the Executive Engineer in HP.PWD.
5. The Executive Engineer I&PH Division Paonta Sahib.
6. The Block Development Officer Block Paonta Sahib.
7. All the Assistant Engineer working under this Division.
8. The Executive Officer Municipal Committee Paonta Sahib.
9. All head of the Branches in this division.
10. Notice Board.


Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib

Job No-1

Draft Schedule of Quantity					
Name of work:- Construction of link road to village Thakkar Kujewala road Km 0/0 to 4/750.(SH:- Providing and laying G II at RD 2/540 to 3/100); under SCSP.					
Sub heads and items of work			Estimated cost:-318667/- only		
S.N	Qty	Unit	Figures	Rate in	
				Words	Amount
1	141.63	Per cubic metre	2250.00	Rs Two thousand two hundred fifty and paise zero only	318667
Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 (eighty to hundred) kN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2(Two) as per Technical Specification Clause 405, by manual means including haulage of materials with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.					
Total					318667



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No- 2

Draft Schedule of Quantity

Name of work:- Construction of link road to village Thakkar Kujewala road Km 0/0 to 4/750. (SH:- Providing and laying G II at RD 3/100 to 3/655) under SCSP.					Estimated cost:- 324517/- only	
					Earnest Money:- 6500/- only	
					Time:- Three Months	
S.N	o	Sub heads and items of work	Qty	Unit	Rate in	
					Figures	Words
1		Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 (eighty to hundred) kN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2(Two) as per Technical Specification Clause 405, by manual means including haulage of materials with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.	144.23	Per cubic metre	2250.00	Rs Two thousand two hundred fifty and paise zero only
					Total	324517



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No-3

Draft Schedule of Quantity						
Name of work:- Construction of link road to village Thakkar Kujewala road Km 0/0 to 4/750. (SH:- Providing and laying G II at RD 2/0 to 2/540) under SCSP.				Estimated cost:- 315742/- only		
				Earnest Money: -6500/- only		
				Time: - Three Months		
S.N o	Sub heads and items of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 (eighty to hundred) kN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2(Two) as per Technical Specification Clause 405, by manual means including haulage of materials with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.	140.33	Per cubic metre	2250.00	Rs Two thousand two hundred fifty and paise zero only	315742
Total						315742



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No- 4

Draft Schedule of Quantity

Name of work:- Restoration of rain damages of link road from Jamnighat Jheelbankabara to Dhaunwala road Km 0/0 to 5/020.(SH)-Construction of Retaining wall in cement concrete at RD 4/628 to 4/635 & 4/684 to 4/700).					Estimated cost:- 370002/- only	
Sub heads and items of work					Earnest Money: -7500/- only	
S.N	Qty	Unit	Figures	Rate in		Amount
				Words	Words	
1	21.60	Per cubic metre	190.00	Rs One hundred and paise nil only	ninety	4104
2	72.36	Per cubic metre	4955.20	Rs Four thousand nine hundred fifty five and paise twenty only		358558
3	20.00	each	367.00	Rs Three hundred sixty seven and paise nil only		7340
				Total		370002

Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No - 5

Draft Schedule of Quantity						Estimated cost:-499744/- only
Name of work:-Restoration of rain damage on link road Village Katwari Bagrath to Jallal river Km 0/0 to 5/00.(SH):- Construction of Retaining wall in wire crate at RD 3/880 to 3/395).						Earnest Money:-10000/- only
Sub heads and items of work						Time:- Three Months
S.N	Qty	Unit	Figures	Rate in		Amount
				Words	Words	
1	19.05	Per cubic metre	190.00	Rs One hundred ninty and paise nil only		3620
2	157.500	Per Cubic metre	3150.00	Rs Three thousand one hundred fifty and paise nil only		496125
Total						499745

Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No. 06

Draft Schedule of Quantity						
Name of Work:- Construction of link road to village Jhivar Basti Bharapur Km 0/0 to 1/460. (SH:- Providing and laying interlocking tile at RD 0/325 to 0/425) under MNP.						
Estimated cost:- 475976/- only						
Earnest Money:- 10000/- only						
Time:- Three Months						
S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in	
					Words	Amount
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	32.50	Per cubic metre	4955.20	Rs Four thousand nine hundred fifty five and paise twenty only	161044
2	Providing and laying of interlocking concrete block pavement (ISI Marka) having thickness 80 mm (eighty millimetre) as per drawing and technical specification clause 1504. including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge	304.80	Per Square metre	960.00	Rs Nine hundred sixty and paise nil only	292608
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	3.78	Per cubic metre	5905.85	Rs Five thousand nine hundred five and paise eighty five only	22324
					Total	475976



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No-07 P-1

Draft Schedule of Quantity

Name of work:- Construction of road from Lohgarh to Banda Bahadur Gurudwara Sahib Km 0/0 to 4/200. (SH:-C/o Hume pipe culvert 900 mm dia at RD 0/510 & Improvement of curves from RD 1/140 to 1/174).

Estimated cost:-490522/- only
Earnest Money:-10000/- only
Time:- Three Months

S.N	Sub heads and items of work	Qty	Unit	Rate in			Amount
				Figures	Words		
0				190.00	Rs One hundred ninety and paise nil only		5898
1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	31.04	Per cubic metre				
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.02	Per cubic metre	4955.20	Rs Four thousand nine hundred fifty five and paise twenty only		10010
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.79	Per cubic metre	5905.85	Rs Five thousand nine hundred five and paise eighty five only		16477
4	Providing and laying concrete 1:3:6 (One cement: three sand: six graded stone aggregate 40mm nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802,803,1202 & 1203. P.C.C. grade M-10 (Mechanical mix) including carriage of materials with in all leads, lifts and other incidentals	11.38	Per cubic metre	5424.85	Rs Five thousand four hundred twenty four and paise eighty five only		61735
5	Providing and laying 900 mm dia (nine hundred millimetre diameter) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108, including all leads lifts and carriage of materials, as per the direction of Engineer-In charge.	7.50	Per running metre	3882.55	Rs Three thousand eight hundred eighty two and paise fifty five only		29119

P-2

6	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	30.93	Per Cubic metre	302.00	Rs Three hundred two and paise nil only	9341
7	Excavation in hilly area in all kinds soils such as pick work, jumper work, soft and hard rock including chiseling, wedging out of rock (where blasting is prohibited) if required and saturated soil and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawings and as directed by the Engineer-in-Charge. The recovery of the stones whether use full or not for 157.71 (One hundred fifty seven decimal seventy one) cubic metres in all cases at the rate of Rupees 300/- only (Three hundred only) per cubic metre shall be effected on pro-rata basis. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be fully compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	1577.19	Per cubic metre	226.95	Rs Two hundred twenty six and paise ninety five only	357943
					Total	490522



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

P-1

Job No-8

Draft Schedule of Quantity

Name of work:- Construction of road from Lohgarh to Banda Bahadur Gurudwara Sahib Km 0/0 to 4/200. (SH:-C/o Hume pipe culvert 900 mm dia at RD 0/910 & Improvement of curves from RD 1/174 to 1/213).					Estimated cost:-488646/- only	
					Earnest Money:-10000/- only	
					Time:- Three Months	
S.N	Sub heads and items of work	Qty	Unit	Figures	Rate in	Amount
					Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	31.04	Per cubic metre	190.00	Rs One hundred ninety and paise nil only	5898
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.02	Per cubic metre	4955.20	Rs Four thousand nine hundred fifty five and paise twenty only	10010
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.79	Per cubic metre	5905.85	Rs Five thousand nine hundred five and paise eighty five only	16477
4	Providing and laying concrete 1:3:6 (One cement: three sand: six graded stone aggregate 40mm nominal size) for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802,803,1202 & 1203. P.C.C. grade M-10 (Mechanical mix) including carriage of materials with in all leads, lifts and other incidentals	11.38	Per cubic metre	5424.85	Rs Five thousand four hundred twenty four and paise eighty five only	61735
5	Providing and laying 900 mm dia (nine hundred millimetre diameter) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108, including all leads lifts and carriage of materials, as per the direction of Engineer-In charge.	7.50	Per running metre	3882.55	Rs Three thousand eight hundred eighty two and paise fifty five only	29119
6	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	30.93	Per Cubic metre	302.00	Rs Three hundred two and paise nil only	9341

7	Excavation in hilly area in all kinds soils such as pick work, jumper work, soft and hard rock including chiseling, wedging out of rock (where blasting is prohibited) if required and saturated soil and their intermediate classification of soil setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawings and as directed by the Engineer-in-Charge. The recovery of the stones whether use full or not for 157.71 (One hundred fifty seven decimal seventy one) cubic metres in all cases at the rate of Rupees 300/- only (Three hundred only) per cubic metre shall be effected on pro-rata basis. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be fully compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	1568.92	Per cubic metre	226.95	Rs Two hundred twenty six and paise ninety five only	356066
					Total	488646

Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No-9

Estimated cost :- Rs :- 3.66.361/-
Earnest Money:- Rs:- 8,000/-
Time:- Three Months.

SCHEDULE OF QUANTITY

Name of work :- Construction of link road from Main road Kundion to Jhabha Basti 0/0 to 1/600(SH)-C/O Hume pipe culvert
900 mm dia at RD.0750) under MNP.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	54.75	Per cubic metre	190.00	Rs. One hundred ninety & paise Nil only	10403.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer-in-Charge.	1.96	Per cubic metre	4955.20	Rs. four thousand nine hundred fifty five & paise twenty only	9712.00
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix (1:2:4) within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	2.79	Per cubic metre	5905.00	Rs. Five thousand nine hundred five & paise Nil only	16475.00
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:3:6 within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	51.26	Per cubic metre	5424.00	Rs. Five thousand four hundred twenty four & paise Nil only	278034.00
5	Providing weap holes in plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structure with slope of 1 V:20 H towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	12.00	Each	280.00	Rs. Two hundred eighty & paise Nil only	3360.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material RCC within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	8.64	Per cubic metre	1150.00	Rs. One thousand one hundred fifty & paise Nil only	9936.00
7	Providing and laying 900mm dia reinforced cement concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing excluding excavation protection work, back filling concrete and masonry work in head walls and parapets clause 1108 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	7.50	Per Running metre	3880.00	Rs. Three thousand eight hundred eighty & paise Nil only	29100.00
8	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	30.93	Per cubic metre	302.00	Rs. Three hundred two & paise Nil only	9341.00
	Total :-					366361.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- The Rates should be quoted for all heights including all leads and lifts.
- The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-


Executive Engineer,
Paonta HP, PWD, Division
Paonta Sahib

Job - 10

SCHEDULE OF QUANTITY

Name of work :- Construction of link road from NH- 72 to Gadriya Basti Surajpur km 0/0 to 0/630 (SH:- Construction of Cutting in earth work, road and filling at RD 0/570 to 0/600) (Under MNP)

Estimated cost :- Rs :- 4,51,980/-
Earnist Money:- Rs:- 10,000/-
Time:- Two Months.

Sr No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	234.00	Per cubic metre	302.00	Rs. Three hundred two & paise Nil only	70668.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	43.20	Per cubic metre	190.00	Rs. One hundred ninety & paise Nil only	8208.00
4	Providing and laying non - pressure NP2 class (light duty) RCC pipe with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (one cement: two sand) including testing of joints etc. complete 600 mm dia RCC pipe including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	7.50	Per Running Metre	2280.00	Rs. Two thousand two hundred eighty and paise Nil only	17100.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (waved diagonally) including 10 % (Ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five Kilogramme) each as per drawing and technical Specifications Clause 1301, including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	114.84	Per Cubic metre	3100.00	Rs. Three thousand one hundred & paise Nil only	356004.00
	Total :-					451980.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP.PWD. Division
Paonta Sahib

Job No-11

Draft Schedule of Quantity						
Name of work:- Restoration of rain damages on Badripur Jamiwala Parduni road Km 0/0 to 15/0 (SH):- Construction of Retaining wall in cement concrete from RD 12/540 to 12/548, 12/549 to 12/557 and 12/605 to 12/614).						
Sub heads and items of work						
S.N	Qty	Unit	Figures	Rate in	Amount	
o				Words		
1	40.20	Per cubic metre	190.00	Rs One hundred ninty and paise nil only	7638	
2	82.22	Per cubic metre	5424.85	Rs Five thousand four hundred twenty four and paise eighty five only	446031	
3	30.00	each	367.00	Rs Three hundred sixty seven and paise nil only	11010	
4	28.11	Per Cubic metre	302.00	Rs Three hundred two and paise nil only	8489	
				Total	473168	



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No-12

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages to various roads under Sub Division No.II HPPWD Paonta Sahib. (SH:- Hiring of JCB and Tractor with trolley for removal of slips, dressing of berms and cleaning of side drains and filling of pot holes on various roads.)							Estimated Cost:- 497250/- Only. Earnest Money:- 10000/- Only Time Limit: - Two Months.	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount		
				Figures	Words			
1	Hiring of hydraulic excavator cum loader of 1 cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the directions of Engineer-in Charge.	350.00 hours	Per hour	1055.00	Rs. One thousand fifty five and zero paise only	369250.00		
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor and will be borne by the contractor at his own cost. The break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	40.00 Days	Per day	3200.00	Rs. Three thousand two hundred and zero paise only.	128000.00		
						G.Total	497250.00	


Executive Engineer,
Paonta B&R Division
HP. PWD. Paonta Sahib

Job 14.

SCHEDULE OF QUANTITY

Name of work :- Construction of link road to Harijan Basti Dadhyat km 0/0 to 1/565 (SH:- Construction of 5/7 mtr.wide road formation cutting and filling in km 1/370 to 1/550) & Construction of R/walls in essential RDs (under SCSP)

Estimated cost :- Rs :- 4,04,101/-
Earnist Money:- Rs:- 8,500/-
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto all lead, lift upto as per technical specification clause 1603.1 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	281.43	Per Cubic metre	194.80	Rs. One hundred Seventeen & paise Nil only	54823
2	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	221.37	Per cubic metre	302.00	Rs. Three hundred two & paise Nil only	66854
3	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	26.55	Per cubic metre	190.00	Rs. One hundred ninety & paise Nil only	5045
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M 10 Nominal mix 1:3:6 including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	48.30	Per Cubic metre	5424.00	Rs. Five thousand one hundred eighty and paise Nil only	261979
5	Providing weep holes in bricks/stone masonry plain/reinforced concrete abutment wing wall return wall with 100mm dia PVC pipe extended through the full width of the structure with slope of 1 vertical and 20 in horizontal towards drawing face complete as per specification clause 614,709,1204,3.7. including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	55.00	Each	280.00	Rs. Two hundred Sixty five & paise Nil only	15400
	Total :-					404101.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- The Rates should be quoted for all heights including all leads and lifts.
- The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Job 15

Name of work :- Construction of link road from Main road Kundion to Jhabha Basti 0/0 to 1/600(SH)-C/O Hume pipe culvert
900 mm dia at RD.0865 under MNP.

SCHEDULE OF QUANTITY

Estimated cost :- Rs :- 3,66,361/-
Earnest Money:- Rs:- 8,000/-
Time:- Three Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material, including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	54.75	Per cubic metre	190.00	Rs. One hundred ninety & paise Nil only	10403.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand, eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	1.96	Per cubic metre	4955.20	Rs. four thousand nine hundred fifty five & paise twenty only	9712.00
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix (1:2:4) within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	2.79	Per cubic metre	5905.00	Rs. Five thousand nine hundred five & paise Nil only	16475.00
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:3:6 within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	51.26	Per cubic metre	5424.00	Rs. Five thousand four hundred twenty four & paise Nil only	278034.00
5	Providing weep holes in plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of structure with slope of 1 V:20 H towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	12.00	Each	280.00	Rs. Two hundred eighty & paise Nil only	3360.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material RCC within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	8.64	Per cubic metre	1150.00	Rs. One thousand one hundred fifty & paise Nil only	9936.00
7	Providing and laying 900mm dia reinforced cement concrete pipe NP2 for culverts on first class bedding of granular materials in single row including fixing excluding excavation protection work, back filling concrete and masonry work in head walls and parapets clause 1108 including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-Charge.	7.50	Per Running metre	3880.00	Rs. Three thousand eight hundred eighty & paise Nil only	29100.00
8	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	30.93	Per cubic metre	302.00	Rs. Three hundred two & paise Nil only	9341.00
Total :-						366361.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- The Rates should be quoted for all heights including all leads and lifts.
- The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Job-16.

SCHEDULE OF QUANTITY

Name of work :- Construction of link road from NH- 72 to Gadiya Basti Surajpur km 0/0 to 0/630 (SH:- Construction of Cutting in earth work, embankment and wire crate at RD 0/600 to 0/630) (Under MNP)

Estimated cost :- Rs :- 4,78,211/-
Earnist Money:- Rs:- 10,000/-
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	261.00	Per cubic metre	302.00	Rs. Three hundred two & paise Nil only	78822.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	50.40	Per cubic metre	190.00	Rs. One hundred ninety & paise Nil only	9576.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (weaved diagonally) including 10 % (Ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five Kilogramme) each as per drawing and technical Specifications Clause 1301. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	123.75	Per Cubic metre	3150.00	Rs. Three thousand one hundred fifty & paise Nil only	389813.00
	Total :-					478211.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Job No-17

Draft Schedule of Quantity						
Name of work:- Restoration of rain damage on Kolar Bilaspur road km 0/0 to 12/0 (SH:- C/o wire crate R/wall at RD 3/680 to 3/695)						
Estimated cost:-484510/- only						
Earnest Money:-10000/- only						
Time:- Two Month						
S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in	
					Words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	29.92	Per cubic metre	190.00	Rs One hundred ninety only	5685
2	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg(Twenty five kilogramme) each complete including carriage of materials within all leads, lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	148.13	Per Cubic metre	3150.00	Rs Three thousand fone hundred fifty only	466594
3	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	40.50	Per Cubic metre	302.00	Rs Three hundred two only	12231
					Total	484510

Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Tab No-18

Draft Schedule of Quantity						
Name of work:- Restoration of rain damages link road to Kolar Bilaspur road Km 0/0 to 12/0. (SH)- Construction of Retaining wall in wire crate at RD 4/310 to 4/312.50 and RD 4/420 to 4/426).						
Sub heads and items of work			Estimated cost:-490478/- only		Earnest Money:-10000/- only	
			Time:- Three Months			
S.N	Qty	Unit	Figures	Rate in		Amount
				Rs	Words	
1	51.02	Per cubic metre	190.00	One hundred and paise nil only	ninty	9694
2	152.63	Per Cubic metre	3150.00	Three thousand one hundred fifty and paise nil only		480784
Total						490478



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No-19

Draft Schedule of Quantity						
Name of work:- Restoration of rain damage on link road to village Kodewala Km 0/0 to 1/020. (SH:- Construction of Breast wall in Km 0/820 to 0/882).						
Sub heads and items of work			Estimated cost:- 474429/- only		Earnest Money:- 9500/- only	
S.No	Qty	Unit	Figures	Rate in		Amount
				Words	Rs	
1	62.00	Per cubic metre	190.00	Rs One hundred ninety and paise nil only	11780	11780
4	83.70	Per cubic metre	5424.85	Rs Five thousand four hundred twenty four and paise eighty five only	454060	454060
3	60.00	each	367.00	Rs Three hundred sixty seven and paise nil only	22020	22020
Total						487860

Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No-200

Draft Schedule of Quantity						Estimated cost:-363784/- only
Name of work:- Restoration of rain damages to Lohgarh to Banda Bahadur road Km 0/0 to 4/200. (SH:-C/o Retaining wall in wire crate at RD 0/170 to 1/190).						Earnest Money:-7500/- only
						Time:- Three Months
S.N	Sub heads and items of work	Qty	Unit	Figures	Rate in Words	Amount
o						
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	28.80	Per cubic metre	190.00	Rs One hundred ninety and paise nil only	5472
2	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg(Twenty five kilogramme) each complete including carriage of materials within all leads,lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	113.750	Per Cubic metre	3150.00	Rs Three thousand one hundred fifty and paise nil only	358312
					Total	363784



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No-21

Draft Schedule of Quantity						Estimated cost:-495000/- only
Name of work:- Restoration of rain damages on various roads under Baila section & Dhaulakuan section in HP PWD (B&R) Sub Division Dhaulakuan. (SH:- Hiring of JCB and tractor with trolley for removal of slips and debries, dressing of berms, filling of pot holes & opening of block drain.)						Earnest Money:-10000/- only
						Time:- Three Months
S.N	Sub heads and items of work	Qty	Unit	Figures	Rate in Words	Amount
0						
1	Hiring of hydraulic excavator cum loader of 1 cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of operators, Pol charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the directions of Engineer - in- Charge.	360.00	Per hrs	1055.00	Rupees One thousand fifty five and paise nil only	379800
2	Hiring of tractor with trolley i/c operating and service staff as required and including Pol and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor and will be borne by the contractor at his own cost. The break down or any kind of hindrance charges of Machinery or operating staff shall be met out of his own cost. Other condition shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of Engineer - in-	36.00	Per day	3200.00	Rupees three thousand two hundred and paise nil only	115200
					Total	495000

Note:- The cost of P.O.L.charge wear and tear of machinery salary and livery charges of operator and cleaner and repair of machinery etc. shall be born by the contractor himself and nothing will be paid for the same.



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No- 22.

Draft Schedule of Quantity						Estimated cost:- 491203/- only	
Name of work:- Restoration of rain damages in Balla Section at various roads. (SH:-Construction of unlined surfaces drains on link road to village Bakhani Kelewala and removal of slips on Girinagar Jatton road Km 0/0 to 24/400, Link road to village Thakkar Kujjewala).						Earnest Money:- 10000/- only	
						Time:- Three Months	
S.No	Sub heads and items of work	Qty	Unit	Figures	Rate in Words	Amount	
1	Construction of unlined surface drains by mechanical of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307 including all eads lifts and carriage of materials, as per the	3145.00	Per running metre	62.80	Rs Sixty two and paise eighty only	197506	
2	Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material within a left upto 1.5 mtr and lead upto 1000 mtrs as per technical specification clause 302.3.5. and 1611 including carriage of materials within all leads, lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	2025.50	Per cubic metre	145.00	Rs One hundred forty five and paise zero only	293697	
						Total	
						491203	

Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No-23

Draft Schedule of Quantity						Estimated cost:-378715/- only
Name of work:- Restoration of rain damages on Rampur Bharapur Gunglow road Km 0/0 to 5/0.(SH:- Construction of Retaining wall in cement concrete from RD 0/920 to 0/945).						Earnest Money:-7600/- only
Sub heads and items of work						Time:- Three Months
S.No	Qty	Unit	Figures	Rate in		Amount
				Words		
1	30.00	Per cubic metre	190.00	Rs One hundred ninty and paise nil only		5700
2	73.50	Per cubic metre	4955.20	Rs Four thousand nine hundred fifty five and paise twenty only		364207
3	24.00	each	367.00	Rs Three hundred sixty seven and paise nil only		8808
				Total		378715

✓

Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No-24

Draft Schedule of Quantity							Estimated cost:-471889/- only
Name of work:- Restoration of rain damages in Majra & Dhaulakuan Section on various roads. (SH:-Construction of unlined surfaces drains on Badripur Jamniwala Parduni road Km 15/100 to 19/800, Link road to village Churak Majri Km 0/0 to 5/0 & Jagatpur Parduni road Km 0/0 to 5/0).							Earnest Money:-10000/- only
							Time:- Three Months
S.N	o	Sub heads and items of work	Qty	Unit	Figures	Rate in	Amount
						Words	
1		Construction of unlined surface drains by mechanical of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307 including all eads lifts and carriage of materials, as per the	7514.15	Per running metre	62.80	Rs Sixty two and paise eighty only	471889
Total							471889



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No-25

Draft Schedule of Quantity						
Name of work:- Restoration of rain damages to Kolar section, Dhaulakuan Sub Division. (SH:- Making up loss of materials on shoulder, Construction of unlined surface drain and dressing of berms at various RDs).						
S.N	Sub heads and items of work	Qty	Unit	Figures	Rate in Words	Amount
0						
1	Maintenance of Earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materials, as per the direction of Engineer-In charge.	6000.00	Per square metre	18.00	Rs Eighteen and paise nil only	108000
2	Construction of unlined surface drains by mechanical of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307 including all eads lifts and carriage of materials, as per the	1950.00	Per running metre	62.80	Rs Sixty two and paise eighty only	122460
3	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000m as per Technical Specification Clause 1903 including carriage of materials, as per the direction of Engineer-In charge.	4212.00	Per square metre	63.60	Rs Sixty three and paise sixty only	267883
					Total	498343



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No-26

Draft Schedule of Quantity						
Name of work:- Restoration of rain damages on link road from NH-707 to Bhaddar Kali Mata Mandir Km 0/0 to 2/400. (SH:- Construction of Retaining wall in wire crate above existing wire crate at RD 0/338 to 0/354). Deposit Work.				Estimated cost:- 498948/- only		
				Earnest Money:- 10000/- only		
				Time:- Three Months		
S.N	Sub heads and items of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg (Twenty five kilogramme) each complete including carriage of materials within all leads, lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge.	155.520	Per Cubic metre	3150.00	Rs Three thousand one hundred fifty and paise nil only	489888
2	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	30.00	Per Cubic metre	302.00	Rs Three hundred two and paise nil only	9060
					Total	498948

Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No-27

Draft Schedule of Quantity

Draft Schedule of Quantity					Estimated cost:-300051/- only	
Name of work:-Restoration of rain damages to Badripur Jamniwala Parduni road Km 0/0 to 15/00, (SH:- Construction of Breast wall in km 9/182 to 9/207).					Earnest Money:- 6100/- only	
S.N o	Sub heads and items of work	Qty	Unit	Figures	Rate in	Amount
				190.00	Words Rs One hundred ninty and paise nil only	
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	29.25	Per cubic metre	4955.20	Rs Four thousand nine hundred fifty five and paise twenty only	287154
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 40 mm nominal size)including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge. .	57.95	Per cubic metre	367.00	Rs Three hundred sixty seven and paise nil only	7340
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-	20.00	each			
					Total	300051



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job 28

Draft Schedule of Quantity						Estimated cost:-497040/- only
Name of work:- Restoration of rain damages on various roads under Ballia section in HP.PWD (B&R) Sub Division Dhaukuan.(SH:- Hiring of JCB and tractor with trolley for removal of slips and debris, dressing of berms, filling of pot holes & opening of block drain of Jamta Rajban road, Girinagar Jatton road, Katwari Baghrath to Jallal river, Swar landasi Kharkari road & Mehat Gawana Khalli Naddi road of various RDs.).						Earnest Money:- 10000/- only Time:- Three Months
S.N	Sub heads and items of work	Qty	Unit	Figures	Rate in Words	Amount
o						
1	Hiring of hydraulic excavator cum loader of 1 cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of operators, Pol charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the directions of Engineer - in- Charge.	368.00	Per hrs	1055.00	Rupees One thousand fifty five and paise nil only	388240
2	Hiring of tractor with trolley i/c operating and service staff as required and including Pol and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor and will be borne by the contractor at his own cost. The break down or any kind of hindrance charges of Machinery or operating staff shall be met out of his own cost. Other condition shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of Engineer - in-	34.00	Per day	3200.00	Rupees three thousand two hundred and paise nil only	108800
					Total	497040

Note:- The cost of P.O.L.charge wear and tear of machinery salary and livery charges of operator and cleaner and repair of machinery etc. shall be born by the contractor himself and nothing will be paid for the same.



Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job 29

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages to Paonta Puruwalla Singhpura Bhagani Gojjar Dakpathar road (MDR-
S4) km. 0/0 to 26/500 (SH:-Construction of retaining wall in wire crate from RD 26/0 to 26/018)

Estimated cost :- Rs :- 4,91,310/-
Earnist Money:- Rs:- 10,000/-
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material. including all leads, lifts and carriage of materials and other incidental charges complete as per entire satisfaction of the Engineer-in-charge.	58.50	Per cubic metre	190.00	Rs. One hundred ninety & paise Nil only	11115
2	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia GI wire conforming to IS:280 and IS: 4826 in 100 mm x 100 mm mesh (weaved diagonally) including 10 % (Ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 kg (Twenty five Kilogramme) each as per drawing and technical Specifications Clause 1301. including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	148.50	Per Cubic metre	3150.00	Rs. Three thousand one hundred fifty & paise Nil only	467775.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material RCC within in all leads, lift and other incidentals complete as per entire satisfaction of Engineer-in-Charge.	10.80	Per cubic metre	1150.00	Rs. One thousand one hundred fifty & paise Nil only	12420.00
	Total :-					491310.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP PWD, Division
Paonta Sahib

Job 30

SCHEDULE OF QUANTITY

Name of work :- Repair and Maintenance of Paonta Sahib (Main Bazaar) to Rampurghat road km 0/0 to 5/0 (SH:- Providing and laying Interlocking tiles 80 mm thick at RD 4/600 to 4/640) under NCAP Deposit

Estimated cost :- Rs :- 4,99,747/-
Earnist Money:- Rs:- 10,000/-
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Construction of granular sub-base by providing well graded material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401, including all leads, lifts and carriage of materials complete as per entire satisfaction of Engineer-in-charge.	22.50	Per Cubic metre	1930.00	Rs. One thousand nine hundred thirty & paise Nil only	43425
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	30.00	Per cubic metre	4955.20	Rs. four thousand nine hundred fifty five & paise twenty only	148656.00
3	Providing and laying of interlocking concrete block pavements having thickness 80 mm as per drawing and Technical Specification close 1504 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	300.00	Per Square metre	960.00	Rs. Nine hundred sixty & paise Nil only	288000.00
4	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 III. P.C.C. grade M 20 Nominal mix (1:2:4) (one cement: two sand: four graded crushed alone aggregates) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	3.33	Per Cubic metre	5,905.85	Rs. Five thousand nine hundred five & paise eighty five only	19666.00
	Total :-					499747.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP PWD., Division
Paonta Sahib

Job 31

SCHEDULE OF QUANTITY

Name of work :- Repair and Maintenance of Paonta Sahib (Main Bazaar) to Rampurghat road km 0/0 to 5/0 (SH:-
Providing and laying Interlocking tiles 80 mm thick at RD 4/641 to 4/665) under NCAP Deposit

Estimated cost :- Rs :- 2,99,768/-
Earnest Money:- Rs:- 6,000/-
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Construction of granular sub-base by providing well graded material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401, including all leads, lifts and carriage of materials complete as per entire satisfaction of Engineer-in-charge.	13.39	Per Cubic metre	1930.00	Rs. One thousand nine hundred thirty & paise Nil only	25843
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	17.85	Per cubic metre	4955.20	Rs. four thousand nine hundred fifty five & paise twenty only	88450.00
3	Providing and laying of interlocking concrete block pavements having thickness 80 mm as per drawing and Technical Specification close 1504 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	178.50	Per Square metre	960.00	Rs. Nine hundred sixty & paise Nil only	171360.00
4	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 III. P.C.C. grade M 20 Nominal mix (1:2:4) (one cement: two sand: four graded crushed stone aggregates) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	2.39	Per Cubic metre	5,905.85	Rs. Five thousand nine hundred five & paise eighty five only	14115.00
	Total :-					299768.00

Quoted rate in Figure (+/-) (.....%)

Quoted rate in words (+/-) (.....%)

Condition :-

- 1). The Rates should be quoted for all heights including all leads and lifts.
- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Job 32

SCHEDULE OF QUANTITY

Name of work :- Repair and Maintenance of Paonta Sahib (Main Bazaar) to Rampurghat road km 0/0 to 5/0 (SH:- Providing and laying Interlocking tiles 80 mm thick at RD 4/666 to 4/706) under NCAP Deposit

Estimated cost :- Rs :- 4,99,747/-
Earnest Money:- Rs:- 10,000/-
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Construction of granular sub-base by providing well graded material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401, including all leads, lifts and carriage of materials complete as per entire satisfaction of Engineer-in-charge.	22.50	Per Cubic metre	1930.00	Rs. One thousand nine hundred thirty & paise Nil only	43425
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 nominal mix C.C. 1:4:8 (one cement four sand: eight crushed aggregates) including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	30.00	Per cubic metre	4955.20	Rs. four thousand nine hundred fifty five & paise twenty only	148656.00
3	Providing and laying of interlocking concrete block pavements having thickness 80 mm as per drawing and Technical Specification clause 1504 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in charge.	300.00	Per Square metre	960.00	Rs. Nine hundred sixty & paise Nil only	288000.00
4	Plain/reinforced cement concrete in substructure complete as per drawings and technical specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 III. P.C.C. grade M 20 Nominal mix (1:2:4) (one cement: two sand: four graded crushed stone aggregates) including carriage of materials with in all leads, lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	3.33	Per Cubic metre	5,905.85	Rs. Five thousand nine hundred five & paise eighty five only	19686.00
Total :-						499747.00

Quoted rate in Figure (+/-) (.....%)

Quoted rate in words (+/-) (.....%)

Condition :-

1). The Rates should be quoted for all heights including all leads and lifts.

2). The contractor shall procure all the materials conforming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Job No-33

Draft Schedule of Quantity					
Name of work:- A/R & M/O HPPWD (B & R) Division Building at Paonta Sahib (SH:- Deployment of 2 Nos Sweeper for HP.PWD Division Office & Sub-Division I & II Office.)					
Sub heads and items of work					
S.N	Qty	Unit	Figures	Rate in Words	Amount
1	2X12	Per month	8968.00	Rs Eight thousand nine hundred sixty eight paise zero only	215232
Deployment of Sweeper for daily 4 (four) Hours for full one year to clean PWD Division building clearance of waste water rains sewer lines etc complete in all respect and as per the direction of Engineer-In charge.					215232
Total					215232

Executive Engineer,
B&R Division,
HP PWD, Paonta Sahib.

Job No - 34

SCHEDULE OF QUANTITY

Name of work:- Preparation of detailed Project report for i) C/O link road from NH 707 via Mata Bhaderkali Mandir to forest check post at Kolar, Bilaspur road km 0/000 to 2/400. and ii) Improvement and upgradation on NH 07 to Misserwala towards Majra ,churak,Majri purduni road km 0/000 to 15/000. Under NABARD

Estimated cost :- Rs :- 4,52,000/-
Earnest Money:- Rs:- 9,100/-
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Preparation of detailed project report (DPR) complete in all respect in km 0/0 to 5/920 in all provisions as per crust design based on CBR value of conducting desired tests and survey work with cross sections L- section and plans etc. strictly as per ministry of road development (MORD) guide lines and specification in manuscript scrutiny/ from and submission of the same to higher office for approval. If any correction/ammdments will be desired by the head office the same may be corrected as desired and directed by the Engineer -In charge and complete in all respect. After approval the same from the head office should be submitted in five fair copies and soft copy.	17.400	Per km	26000.00	Rs. Twenty Six Thousand & paise Nil only	452400
Total :-						452400

Quoted rate in Figure (+/-) (.....%)

Quoted rate in words (+/-) (.....%)

Conditions:-

- 1). Submission of manuscript, fair copies and working estimate of detailed project report along with analysis of rates to get these approved from competent aouthorities and letter on after approval from NABARD preparing the working estimate of same along with bill of quantity and schedule of quantity of the job.

Payment Schedule:-

- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.
- 3 Work will be carried out strictly as per guide lines and specification of HP PWD.
- 4 40% Payment will be released after submission of DPR
- 5 Balance 60% Payment will be paid after getting approval from competent authority.
- 6 In case of delay in completion of services, a penalty equal to 0.05% of the contract price per day subject to maximum 5% of the contract value will be imposed and shall be recovered from payment due. However, in case of delay due to reasons beyond the control of consultant, suitable extension of time will be granted.

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Job No-38

SCHEDULE OF QUANTITY

Name of work:- Preparation of detailed Project report for i) Construction/Improvement of road from Singapura To Dhoul
Row, Arli Bhagani Ragad Basti km 0/0 to 5/920) & ii) Construction of road alongwith CD & 3 Nos.bridges soil investigation
at gram Panchayat Haripur Khol in Bandha Bahadur Guruduwara to village Lohgarh road in km 0/000 to 4/800. Under
NABARD

Estimated cost :- Rs :- 3,03,920/-
Earnest Money:- Rs:- 7,000/-
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Preparation of detailed project report (DPR) complete in all respect in km 0/0 to 5/920 in all provisions as per crust design based on CBR value of conducting desired tests and survey work with cross sections L- section and plans etc. strictly as per ministry of road development (MORD) guide lines and specification in manuscript scrutiny/ from and submission of the same to higher office for approval. If any correction/amendments will be desired by the head office the same may be corrected as desired and directed by the Engineer -In charge and complete in all respect. After approval the same from the head office should be submitted in five fair copies and soft copy.	5.920	Per km	26000.00	Rs. Twenty five Thousand & paise Nil only	153920
3	Sub soil investigation in all type if soil/ strata by drilling bore holes of NX size (75 millimetre dia metre) ranging from 10.00 metre or above in depth for investigation of soil/ rock condition at site of wok including mobilization and de- mobilization for drilling, shifting of machinery to bore site, making plate from and water arrangement for drilling. The scope of wok include collection of disturbed and un- disturbed core samples plugging of bore holes preservation of core including relevant fluids and laboratory tests and submission of geological report of complex site of work including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	60.00	Per Running metre	2500.00	Rs. Two thousand five hundred & paise Nil only	150000
		Total :-				303920

Quoted rate in Figure (+/-) (.....%)

Quoted rate in words (+/-) (.....%)

Conditions:-

- 1). Submission of manuscript, fair copies and working estimate of detailed project report along with analysis of rates to get these approved from competent authorities and letter on after approval from NABARD preparing the working estimate of same along with bill of quantity and schedule of quantity of the job.

Payment Schedule:-

- 2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.
- 3 Work will be carried out strictly as per guide lines and specification of HP PWD.
- 4 40% Payment will be released after submission of DPR & Hydraulic data.
- 5 Balance 60% Payment will be paid after getting approval from competent authority.
- 6 In case of delay in completion of services, a penalty equal to 0.05% of the contract price per day subject to maximum 5% of the contract value will be imposed and shall be recovered from payment due. However, in case of delay due to reasons beyond the control of consultant, suitable extension of time will be granted.

Signature of the contractor with full address:-



Executive Engineer,
Paonta HP PWD, Division
Paonta Sahib