



Office of
Executive Engineer HP.PWD. Division Baijnath
Himachal Pradesh Public Works Department
Phone No. 01894-263035 E-Mail:- ee-baij-hp@nic.in

"Corrigendum"

The tenders called vide this office letter No.PWD/BD/TA/NIT/2025/-20242-51 dated 06.03.2025 published in web site of "Public works Department Government of Himachal Pradesh for the work appearing at Sr. No.8 "C/O Kolkar to Kalyar Basti Road (SH: C/O R/wall at RD 0/695 to 0/710) Estimated Cost. Rs.99,496/- Earnest Money Rs.2,000/- and Time limit One Month may be read as "Estimated cost Rs.87,722/- Earnest Money Rs.1,800/- Time Limit. One Month"

Other terms and conditions of the N.I.T. will remain un-changed.

Executive Engineer
Baijnath Division,
HP.PWD., Baijnath.

NO:-PWD/BD/TA/NIT/2025/- 20555-63 Dated:-17.03.2025

- 1 Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
- 2 The Engineer-in-chief, HPPWD, Shimla.
- 3 The Chief Engineer (MZ), HPPWD, Mandi.
- 4 The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 5 All the Assistant Engineer working under this Division.
- 6 Drawing Branch in this office.
- 7 Notice Board.
- 8 The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
Baijnath Division.,
H.P.PWD. Baijnath.

Name of work: C/O Kolkar to Kalvar Basti Road
(Sh:- C/O R/Wall at RD 0/695 to 0/710).

DNI/DRAFT SCHEDULE OF QUANTITY

Estimate Cost: 87,722.00/-
Earnest Money: 1,800.00/-
Time Limit: One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	5.85	Per Cum	290.00	Rupees Two Hundred & Ninety Only	1,697.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone age, 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	16.50	Per Cum	4950.00	Rupees Four Thousand Nine Hundred & Fifty Only	81,675.00
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	15.00	Each	290.00	Rupees Two Hundred & Ninety Only	4,350.00
Quoted rates Percentage in figures		Total				
Quoted rates Percentage in words		87,722.00				

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

D.N.L.T. Checked and approved for Rs. 87,722.00 only
Rupees Eighty Seven Thousand Seven Hundred Twenty Two Only

Executive Engineer
Bajnath Division
HPPWD Bajnath

(8)