

**Himachal Pradesh  
Public works Department**

**Notice inviting Tender**

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **20-03-2025 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non-refundable) up to 5.00 P.M. **on 19-03-2025**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 18-03-2025**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	Construction of Dan Mandheri via Padhru road km. 0/00 to 5/500 (SH:- Providing and laying Kharanja Stone soling at Rd 4/850 to 4/980) Under MMSY	99610	2000	Two Months
2	Restoration of road damage on Chambi kangar road km. 0/00 to 5/00 (SH:- c/o catch pit for RCC Hume Pipe culvert at RD 2/365 & PCC Retaining wall at RD. 2/780 to 2/784)	83624	1700	Two Months
3	Restoration of road damage on Chambi kangar road km. 0/00 to 5/00 (SH:- c/o PCC Retaining wall for protection of road at RD 2/315 to 2/319.50)	85441	1700	Two Months
4	Construction and M/T Dugrain to Samih road km. 0/00 to 2/00 (SH:- Providing and laying G-II at 0/822 to 0/909.50) Under OTMNP	99258	2000	Two Months
5	Construction and M/T Dugrain to Samih road km. 0/00 to 2/00 (SH:- Providing and laying G-II at RD 0/300 to 0/388) Under OTMNP	99833	2000	Two Months
6	Construction of Dan Mandheri via Padhru road km. 0/00 to 5/500 (SH:- Providing and laying Kharanja Stone soling at Rd 4/100 to 4/230.50) Under MMSY	99968	2000	Two Months
7	Construction of Dan Mandheri via Padhru road km. 0/00 to 5/500 (SH:- Providing and laying Kharanja Stone soling at Rd 1/300 to 1/430) Under MMSY	99610	2000	Two Months
8	RRD on Harizan Basti Sanghral in G.P Chhamyar road Km. 0/00 to 5/390 (SH:- Unlined surface drain, Surface dressing, earth filling and removal of slip at Rd 2/500 to 5/390)	99616	2000	Two Months
9	Construction and M/T Dugrain to Samih road km. 0/00 to 2/00 (SH:- Providing and laying G-I at RD 0/806 to 0/909.50) under OTMNP	92075	2000	Two Months
10	Restoration of Damages due to laying of OFC in Shimla Mandi via Tattapani road km. 146/00 to 172/400 (SH:- Repair of surfaced dressing and earth filling at Km. 149/00 to 152/00)	99501	2000	Two Months



**Himachal Pradesh  
Public works Department**

11	Repari of Gohar neori road km. 0/00 to 5/00 (SH:- Unlined surface drain, cutting of branches, surface dressing, Maintenance of earthen shoulder etc.	98229	2000	Two Months
12	RRD on Dol to Sekhra road km. 0/00 to 4/00 (SH:- Surface dressing, earth filling and removal of slip at RD 2/00 to 4/00)	83439	1700	Two Months
13	RRD on BBMB colony to Sushan Jawala road Km. 0/00 to 3/500 9SH:- Maintenance of earthen shoulders, Removal of slips and clearing at various RD's)	98263	2000	Two Months
14	RRD on chunahan to Malhanu road km. 0/00 to 4/300 and Dan Madheri Padhru raod 0/00 to 5/500 under Sub Division dhanotu (SH:- Removal of slips in various RD's at road chunahan to malhanu road km /00 to 4/300 and Dan Madheri Padhru road km. 0/00 to 5/500)	93017	2000	Two Months
15	RRD on various roads under Baggi Section Sub-Division dhanotu (SH:- Removal of slips in various RD's at road Kattal Nattal to Dharmdawara road km. 0/00 to 13/00 (S Portion 0/00 to 4/00 and 7/00 to 13/00)	99834	2000	Two Months

**Certified that tender of above works are being called for emergent nature in exigency of public interest.**

**GENERAL CONDITIONS:-**

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the percentage rates in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the additional performance security will have to borne by the bidders as per the said notifications.
7. The contractor can apply only for one work at a time.
8. Conditional and incomplete tenders shall be rejected.
9. The Executive Engineer reserves the right to accept or reject the tender without any reason.

Executive Engineer,  
Gohar Division (B&R),  
HPPWD Gohar.

Dated 12-03-2025

No. PW-GHR-Tender/NIT/2024

12320-39

**Copy along with Tender inviting Notice forwarded for information:-**

1. The Deputy Commissioner, Mandi H.P.
2. The Engineer-in-Chief HP.PWD.Shimla.
1. The Superintending Engineer 1<sup>st</sup>Circle, HP.PWD Mandi.
2. The Executive Engineer (IT Cell) O/O Engineer-in-Chief, HPPWD Nirman Bhawan, Nigam Vihar, Shimla-2 for uploading the NIT on departmental website please.
3. The Sub- Divisional Officer (Civil) Chachiot at Gohar.
4. The Block Development Officer Gohar.
5. The Assistant Engineer HPPWD Sub- Division Gohar/Dhanotu.
6. Various contractors.
7. Notice Board/DB/AB.

Executive Engineer,  
Gohar Division (B&R),  
HPPWD, Gohar.

BILL OF QUANTITY						
Name of work :- Construction of Dan Mandheri via Padhru road km 0/00 to 5/500 (SH:- Providing and laying Kharanja Stone solling at Rd 4/850 to 4/980) Under MMSY					Estimated cost Rs. - 99,610/-	
					Earnest Money cost Rs. 2,000/-	
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (In. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm spread thickness (finished work including materials and labour) including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	50.05	Per Cubic meter	1990.20		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

  
 Executive Engineer  
 Gohar Division (B&R)  
 HP.PWD



# BILL OF QUANTITY

Work:- Restoration of road damage on Chambli Kangar road Km 0/00 to 5/500 (SI:- C/o Catch pit for  
dume pipe culvert at RD 2/365 & PCC Retaining wall at RD. 2/780 to 2/784 )

Estimated cost Rs. - 83624.00

Earnest Money cost Rs. - 1700.00

Time - Two Month

Sr No	Description of work	No.or Qty.	Unit	Estimated Rate (In. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.76	Per Cubic metre	230.00		
2	Providing and Laying concrete for plain/reinforced concrete in open foundations P.C.C nominal mix 1:5:10 (one cement :five sand : ten graded stone aggregate 40 mm fourty millimetre aggregates) complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 Including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.	12.00	Per cubic metre	4350.20		
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 Nominal mix 1:3:6 (one cement: three sand : six graded stone aggregated ) including carriage of materials within all leads and lifts as per directoin of Engineer-In-Charge.	1.52	Per Cubic metre	5050.20		
4	Random Rubble Stone masonry in cement mortar 1:6 (one cement : six sand) for substructure complete as per drawing & technical specification Clauses 702,704,1202 and 1203 Including curing complete within all leads, lifts carriage of material and other incidentals.	3.34	Per Cubic metre	5250.20		
5	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	2.40	Per cubic metre	1050.60		
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diametre) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	5.00	Each	380.70		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

94  
Executive Engineer  
Gohar Division (B&R)  
HP.PWD Gohar.

# **BILL OF QUANTITY**


**Work:-** Restoration of road damage on Chambhi Kangar road Km 0/00 to 5/500 (SH:- C/o PCC wing wall for protection of road at RD. 2/315 to 2/319.50 )

Estimated cost Rs. - 85441.00

Earnest Money cost Rs. - 1700.00

Time - Two Month

Sr No	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	5.94	Per Cubic metre	230.00		
2	Providing and Laying concrete for plain/reinforced concrete in open foundations P.C.C nominal mix 1:5:10 (one cement :five sand : ten graded stone aggregate 40 mm fourty millimetre aggregates) complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts as per direction of Engineer-in-Charge.	17.80	Per cubic metre	4350.20		
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	3.06	Per cubic metre	1050.60		
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 with in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	9.00	Each	380.70		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

  
 Executive Engineer  
 Gohar Division (B&R)  
 H&PWD Gohar.

(329)

### BILL OF QUANTITY

Name of work :- Construction and M/T Dugrain to Samih road km 0/00 to 2/00 (SH:- Providing and laying G-II at Rd 0/822 to 0/909.50) Under OTMNP

Estimated cost Rs. - 99,258/-

Earnest Money cost Rs. 2,000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density <b>Grading 2</b> as per Technical Specification Clause 405. as per direction of Engineer - in - charge .	39.70	Per Cubic meter	2500.20		
	<b>Total:-</b>					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

94  
 Executive Engineer  
 Ghar Division  
 P.P.W.D. Gohar

## BILL OF QUANTITY

Name of work :- Construction and M/T Dugrain to Samih road km 0/00 to 2/00 (SH:- Providing and laying G-II at Rd 0/300 to 0/388) Under OTMNP

Estimated cost Rs. - 99,833/-

Earnest Money cost Rs. 2,000/-


Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density <b>Grading 2</b> as per Technical Specification Clause 405. as per direction of Engineer - in - charge .	39.93	Per Cubic meter	2500.20		
	<b>Total:-</b>					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Executive Engineer  
Gohar Division  
M.P.N.W.D. Gohar

## BILL OF QUANTITY

Name of work :- Construction of Dan Mandheri via Padhru road km 0/00 to 5/500 (SH:- Providing and laying Kharanja Stone soling at Rd 4/100 to 4/230.50) Under MMSY						Estimated cost Rs. - 99,968/-
						Earnest Money cost Rs. 2,000/-
						Time - Two Month
SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm spread thickness (finished work including materials and labour) including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	50.23	Per Cubic meter	1990.20		
	<b>Total:-</b>					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

  
 Executive Engineer  
 Gohar Division (B&R)  
 HP.PWD Gohar.




**BILL OF QUANTITY**

Name of work :- Construction of Dan Mandheri via Padhru road km 0/00 to 5/500 (SH:- Providing and laying Kharanja Stone soling at Rd 1/300 to 1/430) Under MMSY					Estimated cost Rs. - 99,610/-	
					Earnest Money cost Rs. 2,000/-	
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Stone soling properly handpacked filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm spread thickness (finished work including materials and labour) including carriage of materials , with in all leads .lifts as per direction of Engineer - in - charge .	50.05	Per Cubic meter	1990.20		
	<b>Total:-</b>					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

04  
Executive Engineer  
Gohar Division (B&R)  
HP.PWD Gohar.


## BILL OF QUANTITY

Name of work :- RRD on Harizan Basti Sanghral in G.P Chhamyar road KM 0/00 to 5/390 (SH:- Unlined surface drain, Surface dressing, earth filling and Removal of slip at RD 2/500 to 5/390 )					Estimated cost Rs. - 99,616/-	
					Earnest Money cost Rs.2,000/-	
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals.	2808.00	per square metre	15.10		
2	Construction of unlined surface drains of average cross-sectional area 0.20sqm ( zero point two zero square metre ) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metre as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1820.00	per square metre	22.20		
3	Removal of landslide/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1.5 m and land upto 1000 meter as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	159.95	per Cubic metre	105.10		
<b>Total:-</b>						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

  
 Executive Engineer  
 Gohar Division (B&R)  
 HP.PWD Gohar

# **BILL OF QUANTITY**

Name of work :- Construction and M/T Dugrain to Samih road km 0/00 to 2/00 (SH:- Providing and laying G-I at Rd 0/806 to 0/909.50) Under OTMNP					Estimated cost Rs. - 92,075/-	
					Earnest Money cost Rs. 2,000/-	
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening/binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density <b>WBM Grading 1</b> as per Technical Specification Clause 405. (By manual . means ) including all leads , lifts of material and other incidentals as per direction of Engineer –in –Charge complete in all respect.	37.58	Per Cubic meter	2450.10		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

  
 Executive Engineer  
 Gehar Division  
 H.P.P.W.D. Goh



## BILL OF QUANTITY


Name of work :- Restoration of Damages due to laying of OFC in Shimla Mandi via Tattapani road km 146/00 to 172/400 (SH:- Repair of surface dressing and earth filling at km 149/00 to 152/00)

Estimated cost Rs. - 99,501/-

Earnest Money cost Rs.2,000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals.	2578.50	per square metre	15.10		
2	Maintenance of earthen shoulder (Filling with fesh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	2005.50	per square metre	30.20		
	<b>Total:-</b>					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

  
 Executive Engineer  
 Gohar Division (B&R)  
 H.D.P.W.D. Gohar.

## BILL OF QUANTITY

Name of work :- Repair of Gohar Neori road km 0/00 to 5/00 (SH:- Unlined surface drain, cutting of branches, Surface dressing, Maintenance of earthen shoulder etc.)

Estimated cost Rs. - 98,229/-

Earnest Money cost Rs.2,000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of earthen shoulder (Filling with fesh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1740.00	per square metre	30.20		
2	Construction of unlined surface drains of average cross-sectional area 0.20sqm ( zero point two zero square metre ) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metere as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1455.00	per Running metre	26.20		
3	Cutting of branches of trees shrubs and trimming of grass and weeds cutting of branches of trees and shrubs from the road way or with in R.O.W including disposal of wood and leaves to suitable location as per technical specification Clause 1914.as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	2800.00	per square metre	2.70		
	<b>Total:-</b>					
	<b>Percentage rate Quoted in figure</b>					
	<b>Percentage rate Quoted in words</b>					

04  
Executive Engineer  
Gohar Division (B&R)  
HP&WD Gohar.

308

## BILL OF QUANTITY


Name of work :- RRD on Dol to Sekhra road km 0/00 to 4/00 (SH:- Surface dressing, earth filling and Removal of slip at RD 2/00 to 4/00 )

Estimated cost Rs. - 83,439/-

Earnest Money cost Rs.1700/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of earthen shoulder (Filling with fesh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	451.50	per square metre	30.20		
2	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals.	825.00	per square metre	15.10		
3	Removal of landslide/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1.5 m and land upto 1000 meter as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	545.63	per Cubic metre	105.10		
<b>Total:-</b>						
<b>Percentage rate Quoted in figure</b>						
<b>Percentage rate Quoted in words</b>						

  
 Executive Engineer  
 Gohar Division (B&R)  
 HP.PWD Gohar.



## BILL OF QUANTITY

Name of work :- RRD on BBMB colony to Sushan Jawala road KM 0/00 to 3/500 (SH:- Maintenance of earthen shoulders, Removal of slips and clearing at various Rd's)

Estimated cost Rs. - 98,263/-

Earnest Money cost Rs.2,000/-



Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Construction of unlined surface drains of average cross-sectional area 0.20sqm ( zero point two zero square metre ) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metre as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1050.00	per Running metre	22.20		
2	Maintenance of earthen shoulder (Filling with fesh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	843.75	per square metre	30.20		
3	Removal of landslide/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1.5 m and land upto 1000 meter as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	470.71	per Cubic metre	105.10		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Executive Engineer  
Gohar Division  
H.P.P.W.D. Gohar


# BILL OF QUANTITY

Name of work:- RRD on Chunahan to Malhanu road km 0/00 to 4/300 and Dan Madheri Padhru road km 0/00 to 5/500 under Sub Division Bhanotu (SM:- Removal of slips in various RD's at road Chunahan to Malhanu road km 0/00 to 4/300 and Dan Madheri Padhru road km 0/00 to 5/500)						Estimated cost Rs. 93,017/-
						Earnest Money cost Rs. 2000/-
						Time - Two Month
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	885.03	Per Cubic meter	105.10		
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					

  
 Executive Engineer  
 Gohar Division  
 H.P.P.W.D. Gohar  


## BILL OF QUANTITY

Name of work :- RRD on various roads under Baggi section Sub Division Dhanotu (SH:- Removal of slips in various RD's at road Kattal Nattal to Dharmdawara road km 0/00 to 13/00 (Portion 0/00 to 4/00 and 7/00 to 13/00))					Estimated cost Rs. 99,834/-	
					Earnest Money cost Rs. 2000/-	
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1000 m as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals in all leads and lifts and as per direction of Engineer in charge.	949.90	Per Cubic meter	105.10		
Total:-						
Quoted rate in figure						
Quoted rate in words						

  
 Executive Engineer  
 Gohar Division  
 H.P.P.W.D. Gohar