

OFFICE OF THE EXECUTIVE ENGINEER,  
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG

PH: 01907-222229 Fax: 222229 , e-mail : [ee-kar-hp@nic.in](mailto:ee-kar-hp@nic.in)

No.PW-KSG-E-Tenders/2024-  
To

9144

Dated:- 28-3-2025

The Executive Engineer (IT) Cell,  
HPPWD, Nirman Bhawan, Nigam Vihar,  
Shimla-2.

**Subject :-**

Regarding publication of Tender notice on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. PBW(B)A(3)1/2024 dated 03.01.2024 enclosed please find herewith the copy of tender notice for the publishing on departmental web-site.

*Certified that the works mentioned in the Tender Notice are urgent in nature.*

**Encl:- As above.**

Executive Engineer,  
B&R Division,  
HP PWD Karsoog



OFFICE OF THE EXECUTIVE ENGINEER,  
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG  
PH: 01907-222229 Fax: 222229 , E-mail : [cc-kar-hp@nic.in](mailto:cc-kar-hp@nic.in)  
Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **09.04.2025 upto 11.00 AM** and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 08.04.2025** for which the application should reach in this office **upto 1.00 PM 08.04.2025**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening of tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	R/R damages on various roads under Alsindi Section under Churag Sub-Division (SH:- Removal of land slide slips on Kumru to Khadaihn road Km. 0/00 to 5/00 and Bagshar to Seri Km. 0/00 to 8/00)	99,522/-	2,000/-	One month	350/-
2	C/o link road from Rashog Deom road to Khaneoli road (SH:- C/o earthen shoulder & maintenance of berm at various RDs)	99,294/-	2,000/-	One month	350/-
3	C/o link road from Shakelar to Tuman KM. 0/00 to 2/700 (SH:- C/o earthen shoulder & maintenance of berm at various RDs)	99,523/-	2,000/-	One month	350/-
4	C/o Chamanpur Sihni road KM. 0/0 to 2/500 (SH:- C/o R/wall at RD 0/012 to 0/015)	99,890/-	2,000/-	One month	350/-
5	R/R damages on due to laying OFC cable on Chindi Pangna road KM. 0/0 to 12/480 (SH:- Hiring of road roller for rolling of road shoulder & berms in KM. 0/00 to 12/480)OFC Deposit	98,340/-	2,000/-	One month	350/-
6	C/o Chholdhar to Panoutdehra road Km. 0/0 to 2/700 (SH:- C/o R/wall at RD 2/611 to 2/614) Balance work (SCDP)	88,723/-	1800/-	Two months	350/-
7	C/o Kotlu Katanda road Km. 0/0 to 34/500 (SH:- Removal of slips at various RDs)	96,361/-	2,000/-	One month	350/-
8	C/o link road from Bakhedi Mandap to Dohnap Bhanu in GP Bagaila Km. 0/0 to 4/0 (C/o earthen shoulder & maintenance of berm at various RDs)	99,314/-	2,000/-	One month	350/-
9	C/o Khaneol to Sidh Chausi road KM. 0/00 to 7/00 (SH:- C/o earthen shoulder & maintenance of berm at various RDs)	98,309/-	2,000/-	One month	350/-

10	C/o link road from Dateha to Harizan Basti Chova via Kehu in gP Nanj Km. 0/00 to 3/470 (SH:- C/o earthen shoulder & maintenance of berm at various RDs)	99,854/-	2,000/-	One month	350/-
11	C/o Katanda to Pokhi road Km. 0/00 to 10/00 (SH:- C/o earthen shoulder & maintenance of berm at various RDs)	98,733/-	2,000/-	One month	350/-
12	R/R damages on Bhanthal to Punni road Km. 0/00 to 3/00 and Rikki to Bahan Gadhiman KM. 0/0 to 5/00 (SH:-Hiring of JCB for removal of slips on various road)	97,750/-	2,000/-	One month	350/-
13	R/R damages on Puni to Naswar road Km. 0/00 to 3/00 (SH:- Hiring of JCB for removal of slips on various rds)	98,900/-	2,000/-	One month	350/-
14	A/R & M/O on Bakhrot Sanarli Keoldhar Luhri (Sainj) road Km. 0/00 to 41/800 under Karsog Division (SH:- Cutting of Tree at various RDs)	48,860/-	1,000/-	Three months	350/-
15	C/o road from village Sarahan to haripur College (SH:- C/o unlined shoulder & maintenance of berm at various Rds)	99,754/-	2,000/-	One month	350/-
16	C/o link road Kot to Chindi vai Jaban (SH:- C/o earthen shoulder & maintenance of berm at various RDs)	98,124/- 2,000		One month	350/-
17	C/o Sanarli to Karsog Km. 0/0 to 3/300 (C/o earthen shoulder & maintenance of berm at various RDs)	99,765/-	2,000/-	One month	350/-

#### TERMS & CONDITIONS:-

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.

No. PW-E-Tender-NIT/23

9140-43

Executive Engineer  
B&R Division  
HPPWD Karsog

Dated:- 28.3.2025

1. All the Assistant Engineers, working under this Division.
2. Notice board of this office.

Executive Engineer,  
B&R Division,  
HP PWD Karsog

# Percentage Schedule Of Quantity

Estimated Cost      99522  
Earnest Money      2000  
Time      One Year

Name of Work:- RRD on various roads under Alsindi Section under Churag Sub Division ( SH:- Removal of land slide slips on Kumru to Khadain road KM 0/00 to 5/00 and Bagshar to Seri KM 0/00 to 8/00)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs.	Total Amount with all taxes including GST In Words
1	Removal of landslides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of stops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals	829.35	Cum	120.00	99522.00	Rupees Ninety Nine Thousand Five Hundred & Twenty Two Only
Total in Figures					99522	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,  
Karsog Division,  
CHPPWD, Karsog.



# Percentage Schedule Of Quantity

Estimated Cost 99294  
Earnest Money 2000  
Time One Month

Name of Work:- C/O link road from Rashog Deom road to Khaneoli road ( Sub Head:- C/O earthen shoulder & maintenance of berm at various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.				Unit.				Estimated Rate (In Rs.)				Total Amount with all taxes including GST In Rs. P				Total Amount with all taxes including GST In Words			
		176.85				Per Cubic Meter				268.50				47484.00				Rupees Forty Seven Thousand Four Hundred Eighty Four and Paise Zero Only			
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement to Table 300.1 with any meter lead as per technical specification clause 303.1 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	2355.00				Per Square Meter				22.00				51810.00				Rupees Fifty One Thousand Eight Hundred Ten and Paise Zero Only			
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903. as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.													99294.00							
Total in Figures														99294.00							
Quoted Rate in Figures						Select								0.00							
Quoted Rate in Words						Zero and Paise Zero Only															

Executive Engineer,  
Karsog Division,  
QHPWD, Karsog.

# Percentage Schedule Of Quantity

Estimated Cost 99523  
Earnest Money 2000  
Time One Month

Name of Work:- C/O link road from Shakelar to Tuman Km. 0/00 to 2/700 ( Sub Head:- C/O earthen shoulder & maintenance of berm at various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement to Table 300.1 with any meter lead as per technical specification clause 303.1 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	182.25	Per Cubic Meter	268.50	48934.00	Rupees Forty Eight Thousand Nine Hundred Thirty Four and Paise Zero Only
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903, as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	2239.50	Per Square Meter	22.00	50589.00	Rupees Fifty Thousand Five Hundred Eighty Nine and Paise Zero Only
Total in Figures					99523.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		

Executive Engineer,  
Karsog Division,  
DPPWD, Karsog.

# Percentage Schedule Of Quantity

Estimated Cost      99890  
Earnest Money      2000  
Time      Two Month

Name of Work:-Construction of Chamanpur Sihni Road Km 0/0 to 2/500 (SH:- C/O RWall at RD 0/012 to 0/015)

## Sub-Head and items of works.

Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	2.40	Per Cubic Metre	390.20	936.00	Rupees Nine Hundred & Thirty Six Only
2	Providing and laying concrete for pair/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	17.29	Per Cubic Metre	5500.00	95095.00	Rupees Ninety Five Thousand & Ninety Five Only
3	Providing weapholes in brick masonry/stone masonry plain /reinforced concrete abutment wing wall, return wall with 100mm(One hundred milli meter) dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	6.00	Each	373.15	2239.00	Rupees Two Thousand Two Hundred & Thirty Nine Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.35	Per Cubic Metre	1200.00	1620.00	Rupees One Thousand Six Hundred & Twenty Only
Total in Figures					99890	
Quoted Rate in Figures						
Quoted Rate in Words						


Executive Engineer,  
Karsog Division,  
QHPWD, Karsog.

### Percentage Schedule Of Quantity

Estimated Cost	98340
Earnest Money	2000
Time	One Month

**Name of Work:- R/R Damages on Due to Laying OFC Cable on Chindi Pangna road Km 0/0 to 12/480(SH:- Hiring of Road Roller for rolling of road shoulder & berms in Km 0/00 to 12/480) (OFC Deposit)**

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In	Toatal Amount with all taxes including GST In	Toatal Amount with all taxes including GST In
1	Hiring of road roller for consolidation/rolling of road shoulder/berms with power road roller 8 to 10 tonne capacity after laying granular matenal in road shoulder, berms up to any leads and lifts as per direction of Engineer-In-Charge. The Roller should work minimum 8.00 hours from 9.00 AM to 5.00 PM daily. Any loss to the public/private property or any accident etc happened during the course of hiring period execution shall be absolute responsibility of the Road Roller owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for roller will be provided by the owner, the repair and spare watch and ward of road roller also be done by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	23 days	Per Day	4275.65	98340.00	Rupees Ninety Eight Thousand Three Hundred & Fourty Only
<b>Total in Figures</b>					<b>98340.00</b>	
<b>Quoted Rate in Figures</b>						
<b>Quoted Rate in Words</b>						

  
**Executive Engineer,**  
**Karsog Division,**  
**PPWD, Karsog.**



## Percentage Schedule Of Quantity

Estimated Cost      88723  
Earnest Money      1800  
Time      Two Months

**Name of Work:- C/O Chholdhar to Panoutdehra Road Km 0/0 to 2/700 (SH:- C/O R/Wall at RD 2/611 to 2/614)(Balance work) SCDP**

Sub-Head and Items of works.						
Sr.No.		No. Or Qty.	Unit.	Estimated Rate (In	Total Amount with all taxes	Total Amount with all taxes including GST In
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	12.30	Per Cubic Metre	379.90	4673.00	Rupees Four Thousand Six Hundred & Seventy Three Only
2	Providing and laying concrete for pain/reinforced concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	9.52	Per Cubic Metre	5500.00	52360.00	Rupees Fifty Two Thousand Three Hundred & Sixty Only
3	Providing weap holes in brick masonry/stone masonry plain /reinforced concrete abutment wing wall,return wall with 100mm(One hundred milli meter) dia PVC pipe extending through the full with the structure with slope of 1(V): 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204,3.7 As per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.	9.00	Each	373.15	3358.00	Rupees Three Thousand Three Hundred & Fifty Eight Only
4	Providing and laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600 mm with smaller size towards the soil and bigger size to wards the wall and providing over the entire surface behind abutment, wing wall, return wall to the full height, compacted to firm condition complete as per drawing and technical specification clause 1204,3.8. as per direction of Engineer - in - Charge including carriage of material within all leads and lifts and other incidentals.	23.61	Per Cubic Metre	1200.00	28332.00	Rupees Twenty Eight Thousand Three Hundred & Thirty Two Only
Total in Figures					88723	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.

# Percentage Schedule Of Quantity

Estimated Cost 99314  
Earnest Money 2000  
Time One Month

Name of Work:- C/O link road from Bakhedi Mandap to Dohnap Bhanu in G.P. Bagaila Km. 0/00 to 4/00 ( Sub Head:- C/O earthen shoulder & maintenance of berm at various RD's)						
Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement to Table 300.1 with any meter lead as per technical specification clause 303.1 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	142.88	Per Cubic Meter	268.50	38363.00	Rupees Thirty Eight Thousand Three Hundred Sixty Three and Paise Zero Only
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903. as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	2770.50	Per Square Meter	22.00	60951.00	Rupees Sixty Thousand Nine Hundred Fifty One and Paise Zero Only
Total in Figures					99314.00	
Quoted Rate in Figures			Select			
Quoted Rate in Words			Zero and Paise Zero Only			
					0.00	

Executive Engineer,  
Karsog Division,  
QHPPWD, Karsog.

# Percentage Schedule Of Quantity

Estimated Cost      98309  
Earnest Money      2000  
Time      One Month

Name of Work:- C/O Khaneel to Sidh Chauasi road Km. 0/00 to 7/00 ( Sub Head:- C/O earthen shoulder & maintenance of berm at various RD's)

## Sub-Head and items of works.

Sr.No.		No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. p	Total Amount with all taxes including GST in Words
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement to Table 300.1 with any meter lead as per technical specification clause 303.1 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	211.28	Per Cubic Meter	268.50	56729.00	Rupees Fifty Six Thousand Seven Hundred Twenty Nine and Paise Zero Only
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903. as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	1890.00	Per Square Meter	22.00	41580.00	Rupees Forty One Thousand Five Hundred Eighty and Paise Zero Only
Total in Figures					98309.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			

Executive Engineer,  
Karsog Division,  
CHPPWD, Karsog.

# Percentage Schedule Of Quantity

Estimated Cost  
Earnest Money  
Time

96361  
2000  
Two Months

Name of Work:- C/O Kotlu Katanda Road Km 0/0 to 34/500 (SH:- Removal of slips at various Rd's)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Toatal Amount with all taxes including GST in Rs. p	Toatal Amount with all taxes including GST in Words
1	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other Incidentals.	803.01	Cum	120.00	96361.00	Rupees Ninety Six Thousand Three Hundred & Sixty One Only
Total in Figures					96361.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,  
Karsog Division,  
JHPPWD, Karsog



## Percentage Schedule Of Quantity

Estimated Cost      99854  
Earnest Money      2000  
Time      One Month

Name of Work:- C/O link road from Dateha to Harizan Basti Chova via Kethu In G.P. Nainj Km. 0/00 to 3/470 ( Sub Head:- C/O earthen shoulder & maintenance of berm at various RD's)						Time	One Month
Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words	
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement to Table 300.1 with any meter lead as per technical specification clause 303.1 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	179.55	Per Cubic Meter	268.50	48209.00	Rupees Forty Eight Thousand Two Hundred Nine and Paise Zero Only	
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903. as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	2347.50	Per Square Meter	22.00	51645.00	Rupees Fifty One Thousand Six Hundred Forty Five and Paise Zero Only	
Total In Figures					99854.00		
Quoted Rate in Figures			Select		0.00		
Quoted Rate in Words		Zero and Paise Zero Only					

Executive Engineer,  
Karsog Division,  
CHPPWD, Karsog.

# Percentage Schedule Of Quantity

Estimated Cost      98733  
Earnest Money      2000  
Time      One Month

Name of Work:- C/O Katanda to Pokhi road Km. 0/00 to 10/00 ( Sub Head:- C/O earthen shoulder & maintenance of berm at various RD's)						
Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement to Table 300.1 with any meter lead as per technical specification clause 303.1 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	279.23	Per Cubic Meter	268.50	74973.00	Rupees Seventy Four Thousand Nine Hundred Seventy Three and Paise Zero Only
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903. as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	1080.00	Per Square Meter	22.00	23760.00	Rupees Twenty Three Thousand Seven Hundred Sixty and Paise Zero Only
Total in Figures					98733.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words			Zero and Paise Zero Only			


Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.

# Percentage Schedule Of Quantity

Estimated Cost      97750  
 Earnest Money      2000  
 Time      One Month

Name of Work:- R/R Damages on Bhanthal to Punni road km 0/00 to 3/00 and Rikki to Bhahan Gadhiman km 0/0 to 5/00 (SH:- Hiring of JCB for removal of slips on various road )

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Hining of JCB/excavator for removal of slips and boulder in all kinds of soil including roy portion and saturated and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. The machine/JCB should work minimum 8.00 hours from 9:00 AM to 5:00 PM daily and remove at least 25.0 cum. Quantity of slips per hour. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	85.00	Per Hours	1150.00	97750.00	Rupees Ninety Seven Thousand Seven Hundred & Fifty Only
Total in Figures					97750.00	
Quoted Rate in Figures						
Quoted Rate in Words						

  
 Executive Engineer,  
 Karsog Division,  
 QPMPWD, Karsog.

# Percentage Schedule Of Quantity

**Name of Work:- R/R Damages on Punni to Naswar road km 0/00 to 3/00 (Sh:- Hiring of JCB for removal of slips on various road )**

**Estimated Cost**      98900  
**Earnest Money**      2000  
**Time**      One Month

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Hiring of JCB/excavator for removal of slips and boulder in all kinds of soil including roy portion and saturated and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. The machine/JCB should work minimum 8.00 hours from 9:00 AM to 5:00 PM daily and remove at least 25.0 cum. Quantity of slips per hour. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner, the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred Only
<b>Total in Figures</b>					98900.00	
<b>Quoted Rate in Figures</b>						
<b>Quoted Rate in Words</b>						

  
**Executive Engineer,**  
**Karsog Division,**  
**94PWPD, Karsog.**



# Percentage Schedule Of Quantity

Estimated Cost  
Earnest Money

48860  
1000

Time

Three Months

Name of Work:- A/R & M/O on Bakhtrot Sanari Kelodhar Luhri (Saini) road Km 0/00 to 41/800 Under Karsog Division ( Sub Head:- Cutting of Tree at various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Felling trees of the girth (measured at a height of 1 metre(one metre) above ground level) including cutting of trunks and branches removing the roots and stacking of serviceable material and disposal of unserviceable materials. or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	3.00	Each	16286.70	48860.00	Rupees Fourty Eight Thousand Eight Hundred & Sixty Only
Total in Figures					48860.00	
Quoted Rate in Figures					0.00	
Quoted Rate in Words						

Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.

# Percentage Schedule Of Quantity

Estimated Cost  
Earnest Money  
Time

9975.4  
2000  
One Month

Name of Work:- C/O road from Village Sarahan to Haripur College ( Sub Head:- C/O earthen shoulder & maintenance of berm at various RD's)						
Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit	Estimated Rate (In Rs.)	Total Amount with all taxes including GST In Rs. P	Total Amount with all taxes including GST In Words
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement to Table 300.1 with any meter lead as per technical specification clause 303.1 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	182.25	Per Cubic Meter	268.50	48934.00	Rupees Forty Eight Thousand Nine Hundred Thirty Four and Paise Zero Only
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903. as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	2310.00	Per Square Meter	22.00	50820.00	Rupees Fifty Thousand Eight Hundred Twenty and Paise Zero Only
Total In Figures					99754.00	
Quoted Rate in Figures			Select		0.00	
Quoted Rate in Words				Zero and Paise Zero Only		

Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.

# Percentage Schedule of Quantity

Estimated Cost 98124  
Earnest Money 2000  
Time Two Months

Name of Work:- C/O link road Kot to Chindi via Jaban (SH:- C/O earthen shoulder & maintenance of berm at various RD's)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST in Rs. P	Total Amount with all taxes including GST in Words
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead any as per technical specification clause 303.1 or as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	245.25	Per Cubic Meter	268.50	65850.00	Rupees Sixty Five Thousand Eight Hundred Fifty and Paise Zero Only
2	Making up loss of material/ Irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment of OMC upto any as per technical specification clause 1903 or as per direction of Engineer-in-Charge including cartage of material within all leads and lifts and other incidentals.	1467.00	Per Square metre	22.00	32274.00	Rupees Thirty Two Thousand Two Hundred Seventy Four and Paise Zero Only
Total in Figures					98124.00	
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.

# Percentage Schedule Of Quantity

Estimated Cost      99765  
Earnest Money      2000  
Time      One Month

Name of Work:- C/O Sanarli to Karsog road Km. 0/00 to 3/300 ( Sub Head:- C/O earthen shoulder & maintenance of berm at various RD's)						
Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (in Rs.)	Total Amount with all taxes including GST In Rs. p	Total Amount with all taxes including GST In Words
1	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement to Table 300.1 with any meter lead as per technical specification clause 303.1 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	155.25	Per Cubic Meter	268.50	41685.00	Rupees Forty One Thousand Six Hundred Eighty Five and Paise Zero Only
2	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification clause 1903. as per drawing and technical specification clauses 802, 803, 1202 and 1203 or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	2640.00	Per Square Meter	22.00	58080.00	Rupees Fifty Eight Thousand Eighty and Paise Zero Only
<b>Total in Figures</b>					99765.00	
<b>Quoted Rate in Figures</b>			Select		0.00	
<b>Quoted Rate in Words</b>				Zero and Paise Zero Only		

Executive Engineer,  
Karsog Division,  
HPPWD, Karsog.