

Office of Executive Engineer Baijnath Division HP.PWD, Baijnath Himachal Pradesh Public works Department Baijnath-176125 Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

NO: PWD/BN/TA/NIT/2025-26/-To

1757-62 Dated: 2015125

The Executive Engineer, (IT Cell), Nirman Bhawan Nigam Vihar, Shimla-2.

Subject:-

Publication of Tender Notice on the Departmental website.

Dear Sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No.PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the Notice Inviting Tender are urgent/emergent nature of works in public interest. Kindly ensure the prompt publication of the same on the website.

Encl: Notice Inviting Tender & Schedule of Quantity.

Yours faithfully,

Executive Engineer, Baijnath Division, HP.PWD, Baijnath.

Copy forwarded for information to:-

- 1. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
- 2. All the Assistant Engineers working under this Division.
- 3. The Drawing Branch of this office.
- 4. Notice Board.

Executive Engineer, Baijnath Division., H.P.PWD..Baijnath.

Office of



Executive Engineer Baijnath Division HP.PWD, Baijnath⁻ Himachal Pradesh Public works Department Baijnath-176125 Phone No. 01894-263035 Fax 262704 e-mail:-<u>ee-baij-hp@nic.in</u>

<u>"NOTICE INVITING TENDER"</u>

Sealed percentage rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **31.05.2025** up to **11.30** A.M and will be opened on the same day at **12.00** Noon in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **30.05.2025** up to **12.00** Noon.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O R/Wall nearby Sh. Harnam Singh House ward no.5 at Chobin (SH: C/O R/Wall (SDF/2024/1653)	97,923/-	2,000/-	Rs.350/-	Two Months
2	C/O R/Wall nearby the house of Sh. Subhash Chand village Ghankhetar (SH: C/O R/Wall for protection of Subhash Chand house at RD 0/00 to 0/008) (Deposit work SDF/2024/1440)	98,629/-	2,000/-	Rs.350/-	Two Months
3	C/O Pucca Path along with puli at Kotli (SH: C/O 2.00 mtr. Span Pulli 0.90 mtr. wide, Kharnja stone soling & PCC for footpath Deposit work (SDP/2024/818) (Head load)	93,652/-	1,900/-	Rs.350/-	Two Months
4	C/O Paprola to Andretta road Km 0/00 to 6/300 (SH: Construction of 2.00 mtr. Span RCC Slab culvert at RD 3/700 (SW: Construction of sub Structure)(Under OFC)	99,999/-	2,000/-	Rs.350/-	Two Months
5	C/O Samudayak Bhawan Nanwar (SH: Providing and Fixing structural steel work etc.) (Deposit work SDF/2024/1655)	98,230/-	2,000/-	Rs.350/-	One Month

1. The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.

2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.

3. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.

4. Only two tenders form will be issued to the contractor/firm which may be noted.

- 5. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- 6. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- 7. The contractor shall have all required machinery such as Truck/Tipper,Mixture,water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- 8. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
- 9. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- 10. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

Executive Engineer, Baijnath Division., H.P.PWD. Baijnath. For & On behalf of the governor of H.P.

			T	4	ω.		2	(Sh: No. 1	
Quated rates Percentage in words	Quated rates Percentage in figures		Malkana, folitax, of other taxes innoised by the povertification.	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V).20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals.the rate including of octroi, royality,	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and tifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	drawing and Morth technical specification section 800, 900 &1200 for nominal mix 1.5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per	Sr. Description of work: C/O R/Wall (SDF/2024/1653). Sr. No. Description of work No. Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per direction of EngineerCharge. Including cleaning of slush which may arrise out during and there including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	DNIT/DRAFT SCHEDULE OF QUANTITY
			100	10.00	3.55		18.19	5.06 5.06	QUANT
		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		Each	Per Cum		Per Cum	Unit Per Cum	YTY
			A CONTRACTOR	290.00	990.00		4950.00	Earnest Money: 2,000.00/- Time Limit :Two Months Rate 290.00 Rupees Tw Ninety On	Estimate Cost: 97,923.00/-
				Rupees Two Hundred & Ninety Only	Rupees Nine Hundred & Ninety Only	Nume Hundred & Fitty Only	Rupees Four Thousand	st Money: 2,000.00/- Limit :Two Months Figures Words 0.00 Rupees Two Hundred & Ninety Only	97,923.00/-
			97,923.00	2,900.00	3,5 15,00		90,041.00	AMOUNT <u>Rs. P</u> 1,467.00	

Condition :-

Rate should be quoted for all heights including all leads and lifts
Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

D.N.I.T. Checked and approved for Rs. and approved for Rs. 97,923.00 only Rupees Ninety Seven Thousand Nine Hundred Twenty Three Only

Executive Engineer Baijnath Division HPPWD Baijnath

4

Executive Engineer Baijnath Division HPPWP Baijnath D.N.I.T. Checked and approved for Rs. 98,629.00 only Rupees Ninety Eight Thousand Six Hundred Twenty Nine Only ~

Condition :-

1. Rate should be quoted for all heights including all leads and lifts

2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

			4	ω	2	Name (Sh: 0 1
Quated rates Percentage in words	Quated rates Percentage in figures	Total	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V);20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204,3.7. including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royality, Malkana. tolltax, or other taxes imposed by the government.	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals. including entire carriage of materials within all leads and lifts and other incidentals. Including entire carriage of materials within all leads and lifts and other incidentals. Including entire carriage of materials within all leads and lifts and other incidentals. Including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.	Name of work: C/O R/Wall for protection of Subhash chand house at RD 0/00 to 0/008) (Deposit work SDF/2024/1440) Sr. Description of work No. or U 1 Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arrise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental, the rate including of octroi, royality, Malkana, tolltax, or other taxes imposed by the government.
			7.00	4.24	18.32	No. or 5:92
			Each	Per Cum	Per Cum	Unit Per Cum
			290.00	00.00	4950.00	Estimate Cost: 98,629,00/- Earnest Money: 2,000.00/- Time Limit :Two Months Rate 290.00 Rupees Two Ninety Onl Ninety Onl
			Rupees Two Hundred & Ninety Only	Rupees Nine Hundred & Ninety Only	Rupees Four Thousand Nine Hundred & Fifty Only	98,629,00/- wo Months Rate Rupees Two Hundred & Ninety Only
		98,629.00	2,030.00	4,198.00	90,684.00	AMOUNT Rs. P 1,717.00

D

Г					7 10	\$ m Z	
	4	ω ·	N		Sr.	Name (SH:- work	
	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805 ,806,807,1202 and 1205 RCC M-20 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 804, 805 ,806,807,1202 and 1204 M-15 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (P.C.C M-10- 1:3:6 as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 m, dressing of sides and bottom and backfilling in trenches with excavated suitable material.(Ordinary rock and hard rock) as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	Description of work	of Work :C/O Pucca Path along with puli : C/O 2.00 mtr span pulli 0.90 mtr wide , Kh (SDP/2024/818 .) (Head load)	DNIT/DRAFT SCHEDULE OF QUANTITY
	0.48	2 <u>1</u>	4.95 \	1.19	No. or Qty.	or footpat	ULE OF
	Cum	Cuy	Cum	Per Cubic metre	Unit	th Deposit	QUANTITY
	9,903.00			517.65	Rate Figures	Estimate Cost: 93,652.00/- Earnest Money: 1,900.00/- Time Limit : Two Months	
	Rupees Nine Thousand Nine Hundred & Three Only	Rupees Eight Thousand Eight Hundred & Eight - Paise Ninety Only	Rupees Nine Thousand Three Hundred & Six - Paise Sixty Only	Rupees Five Hundred & Seventeen - Paise Sixty Five Only	te Words	93,652.00/- : 1,900.00/- 'wo Months	
	4/53.00		46068.00	616.00	AMOUNT Rs. P		

3 (a)

			0	ک ب	
Quated rates Percentage in Words	government.	Providing and laying hard stone Soilng properly hand packed intersects with kharanja stone to requested graidient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate including of octroi, royality, Malkana, tolltax, Sale Tax or other taxes imposed by the	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 Granular material and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	Supplying, fitting, and placing HYSD bar reinforcement in super structure complete as per drawing and technical specifications Clauses 1002, 1005,1010 and 1202 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	
		7.43	1.70	40.00	
		Per Cubic metre	Cum	6	
		2,450.00	861.10	99.00	
		2,450.00 Rupees Two Thousand Four Hundred Fifty Only	Rupees Light Hundred & Sixty One - Paise Ten Only	Rupees Ninety Nine Only	· · · · · · · · · · · · · · · · · · ·
	93,652.00	18,204.00	1404.00	3960.00	(d) ()

D.N.I.T. Checked and approved for Rs. 93,652.00 only Rupees Ninety Three Thousand Six Hundred Fifty Two Only

•

Executive Engineer Baijnath Division HPPWD Baijnath

0
H
L
~
V
N
T
-
~
-
TO
1
0
14
H
-
-
-
[-]
0
0
H
-1
-
\sim
DNIT/DRAFT SCHEDULE OF QUANTITY
M
1
-
4
. 1
F
1
-
-
1

1

		T					-		INO.	2	S)	(S)	Na
Quated rates Percentage in words	Quated rates Percentage in figures		taxes imposed by the government.	incidental. The rate is including octroi, royality, GST, toll tax, Sale Tax or other	Including carriage of materials within all leads and lifts and other	,806,807,1202 and 1204 M-15 as per direction of Engineer-in-Charge.	as per drawings and technical specifications Clause 802, 804, 805	Providing concrete for plain/reinforced concrete in open foundations complete		L Description of work	(SW:- Construction of sub Structure) (Umdu ofc)	(SH:- Construction of 2.00 mtr span RCC slab culvert at RD 3/700.	Name of Work: -C/O Paprola to Andretta Road km 0/00 to 6/300
								16.26	Qty.	No.or			
								Cum		Unit			
								6150.00	Figures	Rate to be ente	Time Limit : Two Months	Earnest Money:2,000.00	Estimate Cost: 99,999.00
						Hundred Fifty Only	Thousand One	Rupees Six	es Words	Rate to be entered by the Bidder in	vo Months	:2,000.00	99,999.00
		999999.00						999999.00	Rs. P	AMOUNT		*	

D.N.I.T. Checked and approved for Rs. 99,999.00 only Rupees Ninety Nine Thousand Nine Hundred Ninety Nine Only

Condition :-

 Rate should be quoted for all heights including all leads and lifts
Sample of all material to be used on work shall be got approved from Engineer in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

> Executive Engineer Baijnath Division HPPWD Baijnath

			÷.	
		-	N SI	Name (SH:-
		Steel posit bracl the d		DN Name of work : C/O Samudayak Bhawan Nanwar (SH:- Providing and Fixing structural steel work etc) (Deposit SDF/2024/1655)
		l work tion ar kets ar lirection r taxes		k : C/0 ling an
		weldend app ad sim on of I s impo) Samu d Fixir
		ed in b lying a illar w Engine sed by		ıdayak ıg stru
		uilt up a prim vorks i ver-in- the g		Bhaw
		Steel work welded in built up sections, trusses and framed work, including cutting , hoisting , fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars , ladders , railling brackets and simillar works including Carriage of Material with in all lifts complete in all respect as I the direction of Engineer-in-Charge. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.		an Nan steel wo
		ons,tru at of r ng Ca e. The nent.		war ork etc
		isses a ed leav rriage rate is	Des)(D
		ind fra d pain of Ma s inclu	Description of work	eposit S
		med v t.In gr tterial ding c	ofwor	SDF/20
	5	vork, ir atings with i octroi,	¥	24/165
		ncludii frame n all li royali		DNIT.
		ng cuti d guai fts coi ty, GS		DRA
		ting ,h rd bars nplete T, tol	SCHE	DNIT/DRAFT SCHEDULE OF
		oisting , lado in all l tax, S	SCHEDULE OF WORKS	HED
		g ,fixii lers ,ra respe Sale T	OF WC	ULE
		Steel work welded in built up sections, trusses and framed work, including cutting , hoisting , fixing in position and applying a priming coat of red lead paint. In gratings framed guard bars , ladders , railling, brackets and simillar works including Carriage of Material with in all lifts complete in all respect as per the direction of Engineer-in-Charge. The rate is including octroi, royality, GST, toll tax, Sale Tax or other taxes imposed by the government.	ORKS	
	D.7	A CONTRACTOR		QUANTITY
	D.N.I.T. Checked and approved for Rs. Rupees Ninety E	972.57	No.or Qty.	TITY
	Check			
	ed and	Per Kilogram	Unit	
Executive Baijnath HPPWD	appro			Estin Earı Tim
H H H	oved for es Nir		Figures	Estimate Cost: 98,230.00 Earnest Money: 2000.00 Time Limit : One Month.
Engineer Division Baijnat	or Rs. nety E	.01.00	S	ost: 98 oney: 2
	ight T	One Only One Only	Rates	;,230.0 2000.00 Mont
	98 housai	nly	Words	
	8,230.(nd Tw			
	approved for Rs. 98,230.00 only Rupees Ninety Eight Thousand Two Hundred Thirty Only			
	ly dred 7		AMC Rs.	
*	Chirty	98230.00	ă	
	Only	230.00	20 00	