

Himachal Pradesh
Public Works Department
HP.PWD Division Shahpur, Distt. Kangra (H.P)-176206
e-mail id: ee-shahpur-pwd@hp.gov.in
"NOTICE INVITING TENDERS"

Sealed percentage rate tenders on form 6 & 7/8 are hereby invited by the Executive Engineer, Shahpur Division HP.PWD Shahpur on behalf of Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under in H.P General Sales Tax Act 1968 so as to reach in his office on or before **06-06-2025 up to 11:00 AM.** and the same shall be opened on the same day at 11:30 AM. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on **05-06-2025 up to 5:00 P.M** and the application for issue of tender form shall be received on **04-06-2025** up to 12:00 Noon.

The earnest money in the shape of NSC/FDR/Saving account of the Post office/ Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/incomplete tenders & tenders without earnest money will be summarily rejected. The offer of tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit	Cost of tender form
1	Construction of Shamshanghat shed at Satyal Basti Ward No-01 in G.P Ambari (Deposit work.) (S.H Construction of Shed.)	70,226.00	1410.00	Two Months	350/-
2	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 18/00 to 18/400).	98,904.00	2000.00	One Month	350/-
3	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 18/400 to 19/00).	99,232.00	2000.00	One Month	350/-
4	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 19/00 to 20/00).	99,068.00	2000.00	One Month	350/-
5	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 21/00 to 21/500).	98,649.00	2000.00	One Month	350/-
6	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 21/500 to 22/00).	98,888.00	2000.00	One Month	350/-
7	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 23/00 to 24/00).	98,190.00	2000.00	One Month	350/-
8	A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 24/00 to 25/00).	98,461.00	2000.00	One Month	350/-
9	A/R and M/O Pargod to Kalru road km 0/00 to 4/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 0/00 to 1/00).	98,859.00	2000.00	One Month	350/-
10	A/R and M/O Pargod to Kalru road km 0/00 to 4/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 2/00 to 3/00).	98,440.00	2000.00	One Month	350/-
11	A/R and M/O Pargod to Kalru road km 0/00 to 4/00. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 3/00 to 4/00).	97,673.00	2000.00	One Month	350/-

12	Construction of Jeepable road from Vakil Singh House to Kartar Singh House Village Gubber. (Deposit work). (S.H:- Construction of C.C. Pavement at RD 0/036 to 0/070 and Edge wall at RD 0/007 to 0/014).	97,198.00	1950.00	Two Months	350/-
13	Replacement of old CGI Roofing at Home Guard camp at Dhanotu Tehsil Shahpur Distt Kangra ((H.P).SDF/2024/1043 (Deposit work). (S.H):-Dismantling of roofing and Providing and fixing prepainted sheet (front side).	98,345.00	2000.00	Two Months	350/-
14	C/o Puhara Churtha Road Km. 0/00 to 4/500.(S.H:-Providing and laying 450 MM Hume pipe culvert at RD Km 1/120.)	90,026.00	18000.00	Two Months	350/-
15	A/R and M/O Chambi to Dharamshala (MDR-45) road km 0/00 to 12/800. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 2/00 to 2/500).	98,041.00	2000.00	One Month	350/-
16	A/R and M/O Chambi to Dharamshala (MDR-45) road km 0/00 to 12/800. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 2/600 to 3/00).	98,425.00	2000.00	One Month	350/-
17	A/R and M/O Chambi to Dharamshala (MDR-45) road km 0/00 to 12/800. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 3/150 to 3/550).	98,450.00	2000.00	One Month	350/-
18	A/R and M/O Chambi to Dharamshala (MDR-45) road km 0/00 to 12/800. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 3/570 to 4/000).	97,644.00	2000.00	One Month	350/-
19	A/R and M/O Chambi to Dharamshala (MDR-45) road km 0/00 to 12/800. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 7/00 to 7/550).	98,192.00	2000.00	One Month	350/-
20	Construction of Jeepable road from Vakil Singh House to Kartar Singh House Village Gubber. (Deposit work). (S.H:- Construction of C.C. Pavement at RD 0/071 to 0/103.20 and Edge wall at RD 0/014 to 0/020).	93,411.00	1900.00	Two Months	350/-
21	A/R and M/O Dadhamb Durgella Bhatech via Tandu road km 0/00 to 6/450. (Under MMSRRY 2025-26). (S.H:-Repair of Pot Hole / patch work between km 3/00 to 3/700)	95,502.00	1950.00	One Month	350/-
22	A/R and M/O Dadhamb Durgella Bhatech via Tandu road km 0/00 to 6/450. (Under MMSRRY 2025-26). (S.H:-Repair of Pot Hole / patch work between km 4/500 to 5/00)	98,189.00	2000.00	One Month	350/-
23	A/R and M/O Dadhamb Durgella Bhatech via Tandu road km 0/00 to 6/450. (Under MMSRRY 2025-26). (S.H:-Repair of Pot Hole / patch work between km 3/800 to 4/300)	97,725.00	2000.00	One Month	350/-
24	Replacement of old CGI Roofing at Home Guard camp at Dhanotu Tehsil Shahpur Distt Kangra ((H.P).SDF/2024/1043 (Deposit work). (S.H):- Dismantling of roofing and Providing and fixing prepainted sheet (Right side).	99,177.00	2000.00	Two Months	350/-
25	A/R and M/Odder to Lanjhani road km 0/00 to 2/900. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 1/00 to 1/700)	98,708.00	2000.00	One Month	350/-
26	A/R and M/Odder to Lanjhani road km 0/00 to 2/900. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 1/800 to 2/400)	96,718.00	1950.00	One Month	350/-
27	Construction of Shamshanghat shed at Satyal Basti Ward No-01 in G.P Ambari (Deposit work.) (S.H Construction of Shed.)	92,068.00	1850.00	Two Months	350/-
28	Preparation of forest diversion case under FCA,1980 for construction of link road Thamba Manoh in Tehsil Shahpur Distt KangraRD 0/0 Km to 6/026 Km. (S.H :-Preparation of forest diversion case under FCA,1980).	95,000.00	2000.00	Six Months	350/-

29	Landslide Disaster Related Mitigation work on Salli to Khari-Behi road Km. 0/00 to 9/570. (S.H :-Protection work in wire crate at Rd 3/070 to 3/077.50.	98,115.00	2000.00	Two Months	350/-
30	Replacement of old CGI Roofing at Home Guard camp at Dhanotu Tehsil Shahpur Distt Kangra ((H.P).SDF/2024/1043 (Deposit work). (S.H:- Dismantling of roofing and Providing and fixing prepainted sheet (Left side).	99,642.00	2000.00	Two Months	350/-
31	A/R and M/O Keyorian Dalho Baag road km 0/00 to 2/570. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 1/00 to 1/800)	97,204.00	1950.00	One Month	350/-
32	Preparation of forest diversion case under FCA,1980 for construction of link road from Shahpur Jawali road to Thehr Chelian Nera in Sub- Tehsil Harchakian Distt Kangra RD 0/0 Km to 2/285 Km. (S.H :-Preparation of forest diversion case under FCA,1980).	95,000.00	2000.00	Six Months	350/-
33	A/R and M/O Keyorian Dalho Baag road km 0/00 to 2/570. (Under MMSRRY 2025-26).(S.H:-Repair of Pot Hole / patch work between km 1/900 to 2/570)	96,216.00	1900.00	One Month	350/-
34	Preparation of forest diversion case under FCA,1980 for construction of link road from Sialeta to Banu Mahadev Dhanotu in Tehsil Shahpur Distt Kangra RD 0/0 Km to 6/673 Km. (S.H :-Preparation of forest diversion case under FCA,1980).	95,000.00	2000.00	Six Months	

Certified that tender of above works are being called of urgent nature in public interest.

Terms & Conditions: -

1. The contractor/firm should be produce the attested copy of latest enlistment and renewal enlistment in HP.PWD. GST No. and EPF No. with the application falling which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The Contractor/Firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.

Executive Engineer,
Shahpur Division,
HP.PWD Shahpur.

(on behalf of Governor of Himachal Pradesh)

No.PWD/SD/Tender/NIT/2025-26/-

759-67

Dated: 28/05/25

Copy to following for information and necessary action:-

1. The Superintending Engineer, 5th Circle HPPWD Palampur.
2. The Executive Engineer (IT), Nigam Vihar Shimla. He is requested to upload the same on the department website.
3. All the Assistant Engineer under this Division.
4. The Drawing/Accounts Branch in this office.
5. N.I.T Register.
6. Notice Board

Executive Engineer,
Shahpur Division,
HP.PWD Shahpur.

SCHEDULE OF QUANTITY

ESTIMATED ₹ 70226.00
EARNEST ₹ 1410.00
TIME LIMIT Two Months

NAME OF WORK :- Construction of Shamshanghat Shed at Satyal Basti Ward No-01 in G.P Ambari. (Deposit work).

SUB-HEAD :- Construction of Shed.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing 0.60mm (Zero point six zero millimetre) thick pre-painted steel sheet roofing of TATA Durashine/ SAIL/ Reliance/ Jindal steel over steel trussed in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (six millimetre) dia metre with prepainted limpet and rubber washers complete with all accesoriees as required, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	42.35 Squire metres	1450.10	Rupees One Thousand Four Hundred Fifty And Paise Ten Only	Per Squire metres	61412.00
2	Providing and fixing pre-painted sheet ridge (Factory made) having proper Gola Shape or hips of TATA Durashine/ SAIL/ Reliance/ Jindal steel 60cm (sixty centimetre) over all with 0.60mm (zero pint six zero millimetre) thick prepainted steel sheet in roofing with hot dipped metalic zinc coated sheets with top coat of regular modified polyster organic coating of 20 (twenty) microns over 5 (five) microns primer coating & back coat of polyster of 5 (five) microns over 5 (five) microns primer coating including fixing with prepainted iron J or L hooks, bolts & nuts 6mm (six millimetre) dia with prepainted G.I. limpet and bitumen washers complete with all accessories as required, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	16.00 Running metre	550.90	Rupees Five Hundred Fifty And Paise Ninety Only	Per Running metre	8814.00
TOTAL :-						70226.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

2

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98904.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 18/00 to 18/400).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and ravelling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	196.00	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	27773.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	223.40	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	5027.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	223.40	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	66104.00
TOTAL :-						98904.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure),				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD-SR-1

3

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99232.00
EARNEST MONEY:- ₹ 2000.00
TIME LIMIT :- One Month

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 24/00. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 18/400 to 19/00).

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and ravelling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	99.00	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	14028.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	267.60	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6021.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	267.60	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	79183.00
TOTAL :-						99232.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

135
Executive Engineer,
Shahpur Division,
HBPWD Shahpur

4

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 99068.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 26/00. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 19/00 to 20/00).

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface,damaged edges and ravelling as per technical sepcification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	36.50	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	5172.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.90	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6635.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.90	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	87261.00
TOTAL :-						99068.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Wards (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HRPWD Shahpur

5

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98649.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 26/600. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 21/00 to 21/500).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface,damaged edges and ravelling as per technical sepcification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	25.00	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	3543.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	298.70	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6721.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bltumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	298.70	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	88385.00
TOTAL :-						98649.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPRWD Shahpur

16

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98888.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 26/600. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 21/500 to 22/00).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface,damaged edges and ravelling as per technical sepcification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	57.00	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	8077.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	285.21	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6417.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	285.21	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	84394.00
TOTAL :-						98888.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur



SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98190.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 26/600. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 23/00 to 24/00).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface, damaged edges and ravelling as per technical specification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	27.25	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	3861.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	296.26	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6666.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @10 binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	296.26	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	87663.00
TOTAL :-						98190.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(8)

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 98461.00
EARNEST MONEY:- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Ranital 32 mile Kotla road km 18/00 to 26/600. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 24/00 to 25/00).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface,damaged edges and ravelling as per technical sepcification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	23.00	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	3259.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	299.00	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6728.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates uslng penetration grade bltumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	299.00	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	88474.00
TOTAL :-						98461.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

79

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98859.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Pargod to Kalru road km 0/00 to 4/00. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 0/00 to 1/00).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface,damaged edges and ravelling as per technical sepcification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	71.20	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	10089.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	278.80	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6273.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bltumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	278.80	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	82497.00
TOTAL :-						98859.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPBWD Shahpur

10

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98440.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Pargod to Kalru road km 0/00 to 4/00. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 2/00 to 3/00).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface,damaged edges and ravelling as per technical sepcification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	90.60	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	12838.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause S03. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	268.85	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6049.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfication of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	268.85	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	79553.00
TOTAL :-						98440.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HBPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 97673.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Pargod to Kalru road km 0/00 to 4/00. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 3/00 to 4/00).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Maintenance of WBM road including filling up of pot holes, ruts and rectifying corrugated surface,damaged edges and ravelling as per technical sepcification Clause 1906 as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	83.50	141.70	Rupees One Hundred Forty One And Paise Seventy Only	Per square metre	11832.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	269.60	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6066.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10'sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	269.60	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	79775.00
TOTAL :-						97673.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD-Shahpur

SCHEDULE OF QUANTITY

12


ESTIMATED COST:- ₹ 97198.00
 EARNEST MONEY:- ₹ 1950.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Jeepable road from Vakil Singh House to Kartar Singh House Village Gubber. (Deposit work).

SUB-HEAD :- Construction of C.C. Pavement at RD 0/036 to 0/070 and Edge wall at RD 0/007 to 0/014).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structures such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.20 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2870.00
2	Stone filling with hard stone of approved quality dryhand packed tightly under floor. as per specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	6.90 Cubic metre	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	5865.00
3	Construction of plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement and any other equivalent type as per Clause 1501 using M25 (Grade), (design mix) concrete having coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic meter) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification section 1500 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	10.50 Cubic metre	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	75075.00

4	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.45 Cubic metre	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	11638.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope 1(V):20(H)(One vertical : Twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	5.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	1750.00
TOTAL :-						97198.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

13


ESTIMATED COST :- ₹ 98345.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Replacement of old CGI Roofing at Home Guard camp at Dhanotu Tehsil Shahpur Distt Kangra ((H.P).SDF/2024/1043 (Deposit work).

SUB-HEAD :- Dismantling of roofing and Providing and fixing prepainted sheet (front side).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Dismantling of roofing including ridges, hips, valleys gutter etc.and stacking the serviceable materials and disposal of un-serviceable materials with in 20 (twenty) metre, as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	45.50 Square metre	69.80	Rupees Sixty Nine And Paise Eighty Only	Per square metre	3176.00
2	Providing and fixing 0.60mm (Zero decimal Six Zero milimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	38.60 Square metre	1350.70	Rupees One Thousand Three Hundred Fifty And Paise Seventy Only	Per square metre	52137.00
3	Providing and fixing ridges or hips 60 cm (Sixty centimetres) over all with 0.60mm (Zero decimal Sixty milimetres) thick prepainted steel sheet ISI marked - Z 120 of approved make in ridges of Sail / Reliance / Jindal /Tata Durashine with hot dipped metallic Zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six milimetres) diametres with prepainted G.I. limpet and bitumen washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	15.50 Running metre	575.75	Rupees Five Hundred Seventy Five And Paise Seventy Five Only	Per running metre	8924.00
4	Providing and fixing plain M.S. B.P. sheet of TATA/SAIL/JINDAL steel 2.00 mm (Two decimal zero millimeter) thick fixed in eaves board / facia / soffits /ceiling including cutting, fixing and welding to steel rafter, member and applying a coat of red lead primer with gas/ electric welding in position complete (frame work is to be measured and paid for separately) within all leads, lifts of materials and other. incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	14.10 Square metre	1650.50	Rupees One Thousand Six Hundred Fifty And Paise Fifty Only	Per square metre	23272.00

5	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in beams, joists, channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government.	103.20 Kilograms	105.00	Rupees One Hundred Five Only	Per Kilogram	10836.00
TOTAL :-						98345.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

14

SCHEDULE OF QUANTITY


ESTIMATED COST :- ₹ 90026.00
 EARNEST MONEY :- ₹ 1800.00
 TIME LIMIT : Two Months

NAME OF WORK :- C/o Puhara Churtha Road Km. 0/00 to 4/500.

SUB-HEAD :- Providing and laying 450 MM Hume pipe culvert at RD Km 1/120.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	21.87 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	7655.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M-ten) nominal mix 1:3:6 (one cement isto three sand isto six crushed stone aggregate 40 mm (forty millimetre) nominal size on ground in or under water including curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arrise at the time of laying concrete complete for all heights/ depths including the cost of form work in toe wall etcetera as per drawings and M.O.R.D. technical specification section/ clause 800,900 & 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	10.78 Cubic metres	5380.00	Rupees Five Thousand Three Hundred Eighty Only	Per cubic metre	57996.00

3	Providing and laying (to level or slope) 450mm dia. (Four hundred-fifty millimetres) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP 3 for culverts on first class bedding of granular material in single row including providing and fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete bedding and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1102 and as per direction of Engineer – In- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	7.50 Running metre	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per Running metre	24375.00
TOTAL :-						90026.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HRPWD Shahpur

13

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98041.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Chambi to Dharamshala (MDR-45) road km 0/00 to 12/800. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 2/00 to 2/500}

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	2.22	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	4995.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	292.23	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6575.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	292.23	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	86471.00
TOTAL :-						98041.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD, Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98425.00
 EARNEST MONEY: - ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Chambi to Dharamshala (MDR-45) road km 0/00 to 12/800. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 2/600 to 3/00)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	2.90	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	6525.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	288.63	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6494.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	288.63	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	85406.00
TOTAL :-						98425.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 H.P.W.D. Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98450.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Chambhi to Dharamshala (MDR-45) road km 0/00 to 12/800. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 3/150 to 3/550]

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	2.90	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	6525.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	288.71	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6496.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	288.71	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	85429.00
TOTAL :-						98450.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HBPWD Shahpur

18

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 97644.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Chambi to Dharamshala (MDR-45) road km 0/00 to 12/800. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 3/570 to 4/00)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.93	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	4343.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	293.03	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6593.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	293.03	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	86708.00
TOTAL :-						97644.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 98192.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Chambi to Dharamshala (MDR-45) road km 0/00 to 12/800. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 7/00 to 7/550

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.99	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	4478.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.33	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6622.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.33	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	87092.00
TOTAL :-						98192.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shampur Division,
HPRWD Shampur

20

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 93411.00
EARNEST MONEY :- ₹ 1900.00
TIME LIMIT : Two Months

NAME OF WORK :- Construction of Jeepable road from Vakil Singh House to Kartar Singh House Village Gubber. (Deposit work).

SUB-HEAD :- Construction of C.C. Pavement at RD 0/071 to 0/103.20 and Edge wall at RD 0/014 to 0/020).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	8.10 Cubic metre	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	2835.00
2	Stone filling with hard stone of approved quality dry hand packed tightly under floor. as per specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana, GST and all type of other taxes imposed by the Government.	6.70 Cubic metre	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	5695.00
3	Construction of plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement and any other equivalent type as per Clause 1501 using M25 (Grade), (design mix) concrete having coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm (twenty five millimetre), mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic meter) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification section 1500 and as directed by the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	9.95 Cubic metre	7150.00	Rupees Seven Thousand One Hundred Fifty Only	Per cubic metre	71143.00

4	Providing and Laying mechanically mixed and vibrated plain cement concrete as per drawings and MORD technical specifications section 800, 900, 1200 and 1600 nominal mix 1:4:8 (One cement isto Four sand isto Eight graded/crushed stone aggregate) 40mm (Forty milimetres) nominal size) for all type of structure like retaining wall / Breast wall etcetra including cost of form work and curing complete as per the direction of Engineer-in-charge including carriage of material, within all leads, lifts of materials and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.45 Cubic metre	4750.00	Rupees Four Thousand Seven Hundred Fifty Only	Per cubic metre	11638.00
5	Providing and laying 100mm (one Hundred millimeter) dia P.V.C pipe weep holes in brick masonry/stone masonry, plain / reinforced concrete, Abutments, Wing walls, Return walls and retaining/breast walls extended through the full width of the structure with slope I(V):20(H){One vertical : Twenty Horizontal} towards draining face complete as per drawing and MORD technical specification section 700 and 1200 and as per direction of Engineer-in- charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	6.00 Number	350.00	Rupees Three Hundred Fifty Only	Each	2100.00
TOTAL :-						93411.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

(21)

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 95502.00
 EARNEST MONEY :- ₹ 1950.00
 TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Dadhamb Durgella Bhatech via Tandur road km 0/00 to 6/450. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 3/00 to 3/700

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	2.45	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	5513.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	282.63	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6359.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	282.63	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	83630.00
TOTAL :-						95502.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

(23)

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98189.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Dadhamb Durgella Bhatech via Tandur road km 0/00 to 6/450. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 4/500 to 5/00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.99	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	4478.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.32	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6622.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	294.32	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	87089.00
TOTAL :-						98189.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD-Shahpur

22

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 97725.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Dadhamb Durgella Bhatech via Tandur road km 0/00 to 6/450. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 3/800 to 4/300

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	2.32	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	5220.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	290.53	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6537.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	290.53	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	85968.00
TOTAL :-						97725.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

(24)


ESTIMATED COST: - ₹ 99177.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Two Months

NAME OF WORK :- Replacement of old CGI Roofing at Home Guard camp at Dhanotu Tehsil Shahpur Distt Kangra ((H.P).SDF/2024/1043 (Deposit work).

SUB-HEAD :- Dismantling of roofing and Providing and fixing prepainted sheet (Right side).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Dismantling of roofing including ridges, hips, valleys gutter etc.and stacking the serviceable materials and disposal of un-serviceable materials with in 20 (twenty) metre, as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	47.10 Square metre	69.80	Rupees Sixty Nine And Paise Eighty Only	Per square metre	3288.00
2	Providing and fixing 0.60mm (Zero decimal Six Zero milimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	40.50 Square metre	1350.70	Rupees One Thousand Three Hundred Fifty And Paise Seventy Only	Per square metre	54703.00
3	Providing and fixing ridges or hips 60 cm (Sixty centimetres) over all with 0.60mm (Zero decimal Sixty milimetres) thick prepainted steel sheet ISI marked - Z 120 of approved make in ridges of Sail / Reliance / Jindal /Tata Durashine with hot dipped metallic Zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six milimetres) diametres with prepainted G.I. limpet and bitumen washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	18.50 Running metre	575.75	Rupees Five Hundred Seventy Five And Paise Seventy Five Only	Per running metre	10651.00
4	Providing and fixing plain M.S. B.P. sheet of TATA/SAIL/JINDAL steel 2.00 mm (Two decimal zero millimeter) thick fixed in eaves board / fascia / soffits /ceiling including cutting, fixing and welding to steel rafter, member and applying a coat of red lead primer with gas/ electric welding in position complete (frame work is to be measured and paid for separately) within all leads, lifts of materials and other. incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	12.45 Square metre	1650.50	Rupees One Thousand Six Hundred Fifty And Paise Fifty Only	Per square metre	20549.00

5	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint in beams, joists, channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government.	95.10 Kilograms	105.00	Rupees One Hundred Five Only	Per Kilogram	9986.00
TOTAL :-						99177.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

23

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 98708.00
 EARNEST MONEY:- ₹ 2000.00
 TIME LIMIT : One Month

NAME OF WORK :- A/R and M/Odder to Lanjhani road km 0/00 to 2/900. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 1/00 to 1/700]

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.71	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	3848.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	297.93	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6703.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	297.93	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	88157.00
TOTAL :-						98708.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPWD Shahpur

26

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 96718.00
EARNEST MONEY: - ₹ 1950.00
TIME LIMIT: - One Month

NAME OF WORK :- A/R and M/Odder to Lanjhani road km 0/00 to 2/900. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 1/800 to 2/400)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate. size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.51	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	3398.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	293.09	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6595.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @1e binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	293.09	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	86725.00
					TOTAL :-	96718.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure) .				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY

27


ESTIMATED COST: - ₹ 92068.00
 EARNEST MONEY: - ₹ 1850.00
 TIME LIMIT : Two Months

NAME OF WORK :- Construction of Shamshanghat Shed at Satyal Basti Ward No-01 in G.P Ambari. (Deposit work).

SUB-HEAD :- Construction of Shed.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation in foundation, trenches etc. in earth work in all classification of soil such as pick work, jumper work, pick jumper work, blasting work, jumper blasting work, soft and hard blasting and saturated soil, de-watering, including wedging out rocks where blasting work is prohibited, chiseling or any other mixed variety of soil, including shoring, shuttering and pumping out water upto any depth or any quantam of water including slush which may be arise during de-watering removal of slush and stacking the serviceable and un-serviceable material clear from the edge of excavation as direction of Engineer-In-Charge and retuning the stacked soil in 15cm (Fifteen centimeter) layers, when required into plinths, sides of foundation etc; consolidating each deposited layer by ramming, watering and then disposing of all excavated earth as directed by the Engineer-in-Charge, within all leads, lifts of materials and other incidentals as per approved drawing, design and as directed by the Engineer-in-Charge. The rates inclusive of octroi, royalty, Malkhana, toll taxes, GST and any other taxes imposed by the Government.	2.90 Cubic metres	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	1015.00
2	Providing and laying in position machine batched and machine mixed cement concrete work of grade M-20 (M- twenty) design mix to obtain the compressive strength of 20N/mm 2 (twenty newton per Square milimetre) for reinforced cement concrete work, using cement with cement content not less than @ 360 kg/cum. (three hundred sixty kilogram per cubic metre) or as per approved design mix for all work upto plinth level to give a smooth surfaces mechanically mixed and vibrated including curing complete and pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per approved drawing, design, specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	0.46 Cubic metres	6250.00	Rupees Six Thousand Two Hundred Fifty Only	Per cubic metre	2875.00

3	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 20mm (twenty) millimeter nominal size mechanical mixed in cement mortar 1:6 (one cement six sand) as per the entire satisfaction and direction of the Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government.	2.46 Cubic metres	4850.50	Rupees Four Thousand Eight Hundred Fifty And Paise Fifty Only	Per cubic metre	11932.00
4	Boulder filling dry hand packed under floor including watering, ramming, consolidating and dressing complete as per PWD specification. The rate is inclusive of cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	3.10 Cubic metres	950.00	Rupees Nine Hundred Fifty Only	Per cubic metre	2945.00
5	Providing and laying cement concrete 1:6:12 (one cement isto 6 coarse sand isto twelve graded / crushed stone aggregate 40 mm (twenty millimetre) nominal size excluding cost of centering and shuttering in foundation and plinths and curing complete including carriage of material in all leads, lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	2.97 Cubic metres	3150.00	Rupees Three Thousand One Hundred Fifty Only	Per cubic metre	9356.00
6	Structural steel work of TATA/ SAIL riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete, including carriage of material within all leads, lifts and other incidentals, as per approved drawing, design, specifications and as directed by Engineer-In-Charge. The rate is inclusive of octroi, royalty, malkana, toll tax, GST and all type of other taxes imposed by the Government.	6.09 Quintal	10500.00	Rupees Ten Thousand Five Hundred Only	Per Quintal	63945.00
TOTAL :-						92068.00
Quoted Rate in Figure (%)			(Amount to be quoted by the contractor in Figure)			
Quoted Rate in Words (%)			(Amount to be quoted by the contractor in words)			


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

28

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 95000/-
 EARNST MONEY :- ₹ 2000.00
 TIME LIMIT : Six Months

NAME OF WORK :- Preparation of forest diversion case under FCA, 1980 for the construction of Link road Thamba Thehar Manoh in Tehsil Shahpur, District Kangra RD 0/0 km to 6/026 km.

SUB-HEAD :- Preparation of Forest Diversion Case under FCA, 1980)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Preparation of KML File and Geo Reference Digital map of proposed land and CA Area. Preparation of CA Scheme, Reclamation Plan, Cost Benefit Analysis, Muck Management, uploading Main Application Part I on Parivesh portal complete in all respect. Assistance to User Agency to attend the queries and clarification sought by MoEF. Submission of Stage I compliance report for obtaining Stage II Approval. Assistance to User Agency to make presentation for REC Meeting as required by MoEF. The Rates are inclusive of all equipments within all leads and lifts and other incidentals. The rate including octroi royalty, Malkana toll tax sale tax or other taxes imposed by the Government.	1.000 nos	95000.00	Rs Ninty Five thousand only	each	95000.00
TOTAL :-						95000.00
	Quated Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quated Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 98115.00
EARNEST MONEY: - ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Landslide Disaster Related Mitigation work on Salli to Khari- Behi road Km. 0/00 to 9/570.

SUB-HEAD :- Protection work in wire crate at Rd 3/070 to 3/077.50.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	11.81	350.00	Rupees Three Hundred Fifty Only	Per cubic metre	4134.00
2	Providing and laying of boulder apron or gabion walls laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boundaries weighing not less than 40 Kg (Forty kilogram) each as per drawing and technical specification clause 1300, as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	27.35	3184.50	Rupees Three Thousand One Hundred Eighty Four And Paise Fifty Only	Per cubic metre	87096.00
3	Back filling with granular material behind abutments, wing walls, return walls and retaining walls complete as per drawing and M.O.R.D. technical specification section 1200, 1600 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials within all leads, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, GST or any other taxes imposed by the Government.	8.10	850.00	Rupees Eight Hundred Fifty Only	Per cubic metre	6885.00
TOTAL :-						98115.00
<u>Quoted Rate in Figure (%)</u>		11	(Amount to be quoted by the contractor in Figure)			
<u>Quoted Rate in Words (%)</u>		11	(Amount to be quoted by the contractor in words)			

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

SCHEDULE OF QUANTITY


ESTIMATED COST:- ₹ 99642.00
EARNEST MONEY:- ₹ 2000.00
TIME LIMIT : Two Months

NAME OF WORK :- Replacement of old CGI Roofing at Home Guard camp at Dhanotu Tehsil Shahpur Distt Kangra ((H.P).SDF/2024/1043 (Deposit work).

SUB-HEAD :- Dismantling of roofing and Providing and fixing prepainted sheet (Lift side).

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Dismantling of roofing including ridges, hips, valleys gutter etc.and stacking the serviceable materials and disposal of un-serviceable materials with in 20 (twenty) metre, as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	47.10 Square metre	69.80	Rupees Sixty Nine And Paise Eighty Only	Per square metre	3288.00
2	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick prepainted steel sheet ISI marked - Z 120 of Tata Durashine/ Sail / Reliance / Jindal steel in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyster of 5 (five) microns over 5 (Five) microns primer fixing with prepainted iron J or L hooks,bolts and nuts with prepainted limpet and rubber washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	39.50 Square metre	1350.70	Rupees One Thousand Three Hundred Fifty And Paise Seventy Only	Per square metre	53353.00
3	Providing and fixing ridges or hips 60 cm (Sixty centimetres) over all with 0.60mm (Zero decimal Sixty millimetres) thick prepainted steel sheet ISI marked - Z 120 of approved make in ridges of Sail / Reliance / Jindal /Tata Durashine with hot dipped metallic Zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm (Six millimetres) diametres with prepainted G.I. limpet and bitumen washers complete with all accessories as required within all leads, lifts of materials and other. incidentals. as per approved architectural drawing, design and specification as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	19.50 Running metre	575.75	Rupees Five Hundred Seventy Five And Paise Seventy Five Only	Per running metre	11227.00
4	Providing and fixing plain M.S. B.P. sheet of TATA/SAIL/JINDAL steel 2.00 mm (Two decimal zero millimeter) thick fixed in eaves board / fascia / soffits /ceiling including cutting, fixing and welding to steel rafter, member and applying a coat of red lead primer with gas/ electric welding in position complete (frame work is to be measured and paid for separately) within all leads, lifts of materials and other. incidentals. as per approved drawing, design and as directed by the Engineer-in-Charge. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	13.50 Square metre	1650.50	Rupees One Thousand Six Hundred Fifty And Paise Fifty Only	Per square metre	22282.00

5	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In beams, joists, channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government.	90.40 Kilograms	105.00	Rupees One Hundred Five Only	Per Kilogram	9492.00
TOTAL :-						99642.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				


 Executive Engineer,
 Shahpur Division,
 HPPWD Shahpur

31

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 97204.00
EARNEST MONEY:- ₹ 1950.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Keyorian Dalho Baag road km 0/00 to 2/570. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 1/00 to 1/800)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.34	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	3015.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	295.82	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6656.00
2	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0-9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8 10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the	295.82	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	87533.00
TOTAL :-						97204.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HRPWD Shahpur

32

SCHEDULE OF QUANTITY

ESTIMATED COST: ₹ 95000/-

EARNEST MONEY ₹ 2000.00

TIME LIMIT Six Months

NAME OF WORK Preparation of forest diversion case under FCA, 1980 for the construction of Link road from Shahpur Jawali Road to Thehr Chelian Nera in Sub-Tehsil :- Harchakian, District Kangra RD 0/0 km to 2/285 km.

SUB-HEAD :- Preparation of Forest Diversion Case under FCA, 1980)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Preparation of KML File and Geo Reference Digital map of proposed land and CA Area. Preparation of CA Scheme, Reclamation Plan, Cost Benefit Analysis, Muck Management, uploading Main Application Part I on Parivesh portal complete in all respect. Assistance to User Agency to attend the queries and clarification sought by MoEF. Submission of Stage I compliance report for obtaining Stage II Approval. Assistance to User Agency to make presentation for REC Meeting as required by MoEF. The Rates are inclusive of all equipments within all leads and lifts and other incidentals. The rate including octroi royalty, Malkana toll tax sale tax or other taxes imposed by the Government.	1.000 nos	95000.00	Rs Ninty Five thousand only	each	95000.00
TOTAL :-						95000.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HPPWD Shahpur

33

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 96216.00
EARNEST MONEY:- ₹ 1900.00
TIME LIMIT : One Month

NAME OF WORK :- A/R and M/O Keyorian Dalho Baag road km 0/00 to 2/570. (Under MMSRRY 2025-26).

SUB-HEAD :- Repair of Pot Hole / patch work between km 1/900 to 2/570)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting by mechanically means stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm(seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two milimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD technical specifications section 400 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST and any other taxes imposed by the Government	1.71	2250.00	Rupees Two Thousand Two Hundred Fifty Only	Per cubic metre	3848.00
2	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.225 kgs (Zero decimal two hundred twenty five kilogramme) per square metre on the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. as per direction of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	290.10	22.50	Rupees Twenty Two And Paise Fifty Only	Per square metre	6527.00
3	Providing, laying and rolling of close-graded Mix Seal Surfacing surfacing material of 20 mm thickness composed of 11.2 mm to 0~9 mm (Type-A) @0. 2704 kg/per ten square meter aggregates using penetration grade bitumen @ie binders content @22.00kg/10 sqm or 5.11% by weight and minimum density of MSS should be 2.10 gm/cc to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in a suitable plant, laying and rolling with a three wheel 8-10 kN static roller and finishing to required level and grades as per Technical Specification Clause 509 including all leads, lifts and carriage of materials complete as per entire satisfaction of the Engineer in Charge. including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, GST or any other taxes imposed by the Government.	290.10	295.90	Rupees Two Hundred Ninety Five And Paise Ninety Only	Per square metre	85841.00
TOTAL :-						96216.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Executive Engineer,
Shahpur Division,
HRPWD Shahpur

34

SCHEDULE OF QUANTITY

ESTIMATED COST: ₹ 95000/-

EARNEST MONEY ₹ 2000.00

TIME LIMIT Six Months

NAME OF WORK Preparation of forest diversion case under FCA, 1980 for the construction of Link road from Laleta to Banu Mahadev Dhanotu in Tehsil Shahpur, District

SUB-HEAD :- Kangra RD 0/00 to 6/673 Km.

SUB-HEAD :- Preparation of Forest Diversion Case under FCA, 1980)

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Preparation of KML File and Geo Reference Digital map of proposed land and CA Area. Preparation of CA Scheme, Reclamation Plan, Cost Benefit Analysis, Muck Management, uploading Main Application Part I on Parivesh portal complete in all respect. Assistance to User Agency to attend the queries and clarification sought by MoEF. Submission of Stage I compliance report for obtaining Stage II Approval. Assistance to User Agency to make presentation for REC Meeting as required by MoEF. The Rates are inclusive of all equipments within all leads and lifts and other incidentals. The rate including octroi royalty, Malkana toll tax sale tax or other taxes imposed by the Government.	1.000 nos	95000.00	Rs Ninty Five thousand only	each	95000.00
TOTAL :-						95000.00
Quated Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quated Rate in Words (%)		(Amount to be quoted by the contractor in words)				

139
Executive Engineer,
Shahpur Division,
HPPWD Shahpur