



OFFICE OF THE EXECUTIVE ENGINEER

B & R DIVISION, HPPWD, SOLAN-173212

TEL.NO:- 01792-223811 E-MAIL:- cc-sol-lhp@nic.com

No.PW-SD/CB-Tender/-2025-26- 2305-15

Dated:- 28/05/25.

To

✓ The Executive Engineer (IT Cell),
Nigam Vihar, Nirman Bhawan,
HPPWD, Shimla-2,
Email ID:-cc-pwd-lhp@nic.in

Subject: - Publication of e-Tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on departmental website as per Notification Pr. Secy(PW) to the Govt. of HP letter NO.PBW(B)A(3)1/2020 dated: 19th June, 2021 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl: - Schedule of quantities.

Executive Engineer,
B&R Division,
HP.PWD, Solan

Copy along with tender notice forwarded for information and necessary action please to:-

1. The Chief Engineer (S.Z), HP.PWD, Nirman Bhawan, Nigam Vihar, Shimla.
2. The Superintending Engineer, 3rd HP.PWD, Solan.
3. The Drawing Branch & Accounts Branch of this office.
4. Notice Board.

Executive Engineer,
B&R Division,
HP.PWD, Solan.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Exigency

Scaled item rate tenders are hereby invited on Form No.6 & 8 by the Executive Engineer, Solan B&R Division, H.P. PWD, Solan (H.P.) on behalf of the Governor of Himachal Pradesh for the following works from the registered contractors of appropriate class enlisted in H.P.PWD, whose registrations stood renewed as per revised instructions and also registered dealers under the Himachal Pradesh, General Sales Tax Act, 1968. The important dates of tender are as under:

Sr.No.	Tender Schedule	Dates	Time
1	The last date for receipt of application for tender form.	02.06.2025	Upto 3.00 P.M.
2	The last date sale of tender forms.	03.06.2025	Upto 4.00 P.M.
3	The date for receipt of tender forms.	04.06.2025	Upto 10.30 P.M.
4	The date of opening of tender	04.06.2025	At 11.00 A.M.

The tender shall be received upto 10.30 A.M. on 04.06.2025 and will be opened on the same day at 11.00 AM in the presence of office against cash payment as shown below (Non-refundable) during the working hours. The earnest money in the shape of National Saving Certificate, FDRs/Account/Saving account in any of the Post Office/Nationalized Bank in H.P. duly intending contractors or their authorized representatives who may like to be present. The tender form can be had from this pledged in favour of the Executive Engineer, (B&R) Division, H.P.PWD, Solan must accompany with each tender, conditional tenders and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 120 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Time	Cost of Form
1	Repair and maintenance of type-I quarter set Nmo. 3,4,7&8 HPPWD colon Jawahar park at Solan (SH: Painting and distempering work)	91387/-	2000/-	One Month	Rs.350/-
2	Preparation of estimate, drawing & surveying for the pedestrian path from Kotla nallah to Distt. Hospital Solan Distt. Solan	85000/-	1700/-	Fifteen Days	Rs.350/-
3	Preparation of detailed estimate for the C/o type-IV (officers) and type-V qtrs. near Chester Hills Solan Distt. Solan HP	85000/-	1700/-	Fifteen Days	Rs.350/-
4	Preparation of detailed estimate for the C/o type-III and type- IV (staff) quarters near Chester Hills Solan Distt. Solan HP	85000/-	1700/-	Fifteen Days	Rs.350/-
5	Preparation of detailed estimate for the C/o parking project for Municipal corporation at Mauja Thodo, Tehsil & Distt. Solan HP	85000/-	1700/-	Fifteen Days	Rs.350/-
6	Construction of Kandaghat Mahi road km 0/0 to 4/450 (SH: Providing and laying Gr-II from 1/0 to 1/400 in digged width against deposit) Deposit work	98532/-	2000/-	One Month	Rs.350/-
7	Repair of path to Sh. Vishambar Thakur house at Domchar (SH: Construction of PCC Retaining wall) Deposit work - Job-1	94277/-	2000/-	One Months	Rs.350/-

8	Providing and laying 30mm thick BC on link road to Govt. Polytechnic Kandaghat km 0/050 to 0/100 (Deposit work)	98874/-	2000/-	One Month	
9	Providing and laying 30mm thick BC on link road to Govt. Polytechnic Kandaghat km 0/0 to 0/050 (Deposit work)	99899/-	2000/-	One Month	Rs. 350/-
10	Repair of path to Sh. Vishambar Thakur house at Domchar (SH: Construction of PCC Retaining wall) Deposit work Job-II	94761/-	2000/-	One Month	Rs.350/-
11	Providing and laying WBM Gr-II for profile correction on various roads in Kandaghat sub-division under MMSRRY 2025-26 Job-I	99610/-	2000/-	One Month	Rs.350/-
12	Providing and laying WBM Gr-II for profile correction on various roads in Kandaghat sub-division under MMSRRY 2025-26 Job-II	97475/-	2000/-	One Month	Rs. 350/-
13	Providing and laying WBM Gr-II for profile correction on various roads in Kandaghat sub-division under MMSRRY 2025-26 Job-III	99093/-	2000/-	One Month	Rs. 350/-
14	Providing and laying WBM Gr-II for profile correction on various roads in Kandaghat sub-division under MMSRRY 2025-26 Job-IV	99093/-	2000/-	One Month	Rs. 350/-
15	Restoration of rain damages on link road to Ayurvedic Dispensary via Mini secretariat Kandaghat (SH: construction of PCC R/wall at RD 0/120 to 0/126.50)	94443/-	2000/-	One Month	Rs. 350/-
16	Restoration of rain damages on link road to Ayurvedic Dispensary via Mini secretariat Kandaghat Deposit work (SH: construction of PCC R/wall at RD 0/126.50 to 0/133)	95653/-	2000/-	One Month	Rs. 350/-
17	Restoration of rain damages on link road to Ayurvedic Dispensary via Mini secretariat Kandaghat Deposit work (SH: construction of PCC R/wall at RD 0/133 to 0/139.50)	94927/-	2000/-	One Month	Rs. 350/-
18	Renovation of Gents Toilet (RHS) in Judicial court complex Kandaghat as per the provision of physically disabled & Transgender friendly norms Job-IV	99931/-	2000/-	One Month	Rs. 350/-
19	Renovation of Ladies Toilet (RHS) in Judicial court complex Kandaghat as per the provision of physically disabled & Transgender friendly norms Job-III	99497/-	2000/-	One Month	Rs. 350/-
20	Renovation of Gents Toilet (LHS) in Judicial court complex Kandaghat as per the provision of physically disabled & Transgender friendly norms Job-II	99934/-	2000/-	One Month	Rs. 350/-
21	Renovation of Ladies Toilet (LHS) in Judicial court complex Kandaghat as per the provision of	99542/-	2000/-	One	Rs. 350/-

	physically disabled & Transgender friendly norms Job-I			Month	
22	Construction of Rajasav Sadan building at Solan (SH: Protection work at top of ceiling (Deposit work)	83143/-	1700/-	One Month	Rs. 350/-
23	Construction of Kandaghat Mahi road km 0/0 to 4/450 (SH: Providing and laying Gr-II from 1/400 to 1/800 in digged width against deposit (Deposit work)	99940/-	2000/-	One Month	Rs. 350/-
24	Renovation of Ladies/Gents Toilet in Judicial court complex Solan as per the provision of physically disabled & Transgender friendly norms	99542/-	2000/-	One Month	Rs. 350/-

TERMS & CONDITIONS:-

1. The tender form will not be issued to those contractors whose performance has been found unsatisfactory.
2. The contractor should have submitted the proof of registration, EPF No. & GST No. at the time of tender application. Failure should not be issued tender forms.
3. Application without earnest money will not be entertained.
4. Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reason.

Executive Engineer,
B&R Division,
HPPWD, Solan

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 1					Estimated Cost: -	91387.00
					Earnest Money: -	2000.00
				Time limit : -		One months
Name of Work :-Repair and maintenance of Type-I quarter set No.3, 4, 7 & 8 HPPWD colony Jawahar Park at Solan (SH:- Painting and distempering work)						

1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using primer as per manufacturers specifications painting wood work with deluxe multi surface paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	79.82	Per Square Meter	124.50	Rupees One Hundred Twenty Four and Paise Fifty Only	9938.00
2	Distempering One coat with 1st quality acrylic distemper, having V.O.C (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	545.72	Per Square Meter	138.10	Rupees One Hundred Thirty Eight and Paise Ten Only	75364.00
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete as per direction of Engineer in Charge and as per HP.PWD. Specification including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	545.72	Per square meter.	11.15	Rupees Eleven and Paise Fifteen Only	6085.00
Total:-						91387.00
Rupees Ninety One Thousand Three Hundred Eighty Seven Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.26 for the 2025-26
Sr.No. for the year 2025-26

Executive Engineer
B&R-Division, HP.PWD. Solan.

SCHEDULE OF QUANTITY

Description of work

Job No. :- 2

Name of work: - Preparation of Estimate, Drawing & Surveying for the Pedestrian path from Kotla nallah to Distt. Hospital Solan, Distt. Solan (HP)

Job No. :- 2		Qty.	Unit	RATE In		AMOUNT
				Figures	Words	Rs.
				Estimated Cost: -		85000.00
				Earnest Money: -		1700.00
				Time Limit: -		Fifteen days
Name of work: - Preparation of Estimate, Drawing & Surveying for the Pedestrain path from Kotla nallah to Distt. Hospital Solan, Distt. Solan (HP)						
1	Preparation of Detailed Project Report for the pedestrain path Kotla Nallah to Distt Hospital Solan) in all respect in fairout form and submission of the same to higher office for approval, if any amendment/ correction as desired by the head office, the same may be corrected as desired. After approval of estimate the DNIT and justification of tender in fair manner be prepared and approved of same competent authority , as per direction of Engineer in charge. The rates are inclusive octrol,royalty, Malkana, toll tal, sale tax, or other taxes imposed by government.	1.00	Per Job	85000.00	Rupees Eighty Five Thousand Only	85000.00
Total in figures :-						85000.00
Total in Words:-		Rupees Eighty Five Thousand Only				
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

SCHEDULE OF QUANTITY

Description of work

Job No. :- 3

Qty. Unit

RATE In
Figures Words
Estimated Cost: -
Earnest Money: -
Time Limit: -

AMOUNT
Rs.
85000.00
1700.00
Fifteen days

Name of work: - Preparation of detailed estimate for the C/o Type - IV (Officers) & Type - V qtrs near Chester Hills Solan, Distt. - Solan (H.P).

1	Preparation of Detailed Project Report for the Type - IV (Officers) & Type - V qtrs near Chester Hills Solan, Distt. - Solan (H.P) in all respect in fairout form and submission of the same to higher office for approval. If any amendment/correction as desired by the head office, the same may be corrected as desired and directed by the Engineer in charge complete in all respect. After approval the same should be submitted in five copies as per condition . After approval of estimate the DNIT and justification of tender in fair manner be prepared and approved of same competent authority, as per direction of Engineer in charge. The rates are inclusive octrol,royalty, Malkana, toll tal, sale tax, or other taxes imposed by government.	1.00	Per Job	85000.00	Rupees Eighty Five Thousand Only	85000.00
Total in figures :-						85000.00
Total in Words:-		Rupees Eighty Five Thousand Only				
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

SCHEDULE OF QUANTITY

Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
			Figures	Words	
Job No. :- 4.			Estimated Cost: -		85000.00
			Earnest Money: -		1700.00
			Time Limit: -		Fifteen days

Name of work: - Preparation of detailed estimate for the C/o Type-III & Type-IV (Staff) quarters near Chester Hills Solan, Distt. Solan (HP)

1	Preparation of Detailed Project Report for the C/o Type - III & Type - IV (Staff) qtrs near Chester Hills Solan, Distt. - Solan (H.P) in all respect in fairout form and submission of the same to higher office for approval. If any amendment/correction as desired by the head office, the same may be corrected as desired and directed by the Engineer in charge complete in all respect. After approval the same should be submitted in five copies as per condition . After approval of estimate the DNT and justification of tender in fair manner be prepared and approved of same competent authority , as per direction of Engineer in charge. The rates are inclusive octrol,royalty, Malkana, toll tal, sale tax, or other taxes imposed by government.	1.00	Per Job	85000.00	Rupees Eighty Five Thousand Only	85000.00
Total in figures :-						
Total in Words:-						
Quoted Percentage rate upto Three Digits :-						
Rupees Eighty Five Thousand Only						
			(+) / (-)			

Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY						
Description of work	Qty.	Unit	RATE In		AMOUNT Rs.	
			Figures	Words		
Job No. :- 56			Estimated Cost: -		85000.00	
			Earnest Money: -		1700.00	
			Time Limit: -		Fifteen days	
Name of work: - Preparation of detailed estimate for the C/o Parking Project for Municipal Corporation at Mauja Thodo, Teh. & Distt. - Solan (H.P).						
1	Preparation of Detailed Project Report for the C/o Parking Project for Municipal Corporation at Mauja Thodo Teh. & Distt. Solan (H.P) in all respect in fairout form and submission of the same to higher office for approval. If any amendment/correction as desired by the head office, the same may be corrected as desired and directed by the Engineer in charge complete in all respect. After approval the same should be submitted in five copies as per condition. After approval of estimate the Dnit and justification of tender in fair manner be prepared and approved of same competent authority, as per direction of Engineer in charge. The rates are inclusive octrol,royalty, Malkana, toll tal, sale tax, or other taxes imposed by government.	1.00	Per Job	85000.00	Rupees Eighty Five Thousand Only	85000.00
Total in figures :-						
Total in Words:-						
Rupees Eighty Five Thousand Only						
Quoted Percentage rate upto Three Digits :-						
			(+) / (-)			

Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Description of work

SCHEDULE OF QUANTITY

Job No. :- 56

Qty.

Unit

RATE In

Figures Words

AMOUNT
Rs.

Estimated Cost: -

85000.00

Earnest Money: -

1700.00

Time Limit: -

Fifteen days

Name of work: - Preparation of detailed estimate for the C/o Parking Project for Municipal Corporation at Mauja Thodo, Teh. & Distt. - Solan (H.P).

1	Preparation of Detailed Project Report for the C/o Parking Project for Municipal Corporation at Mauja Thodo Teh. & Distt. Solan (H.P) in all respect in fairout form and submission of the same to higher office for approval. If any amendment/correction as desired by the head office, the same may be corrected as desired and directed by the Engineer in charge complete in all respect. After approval the same should be submitted in five copies as per condition. After approval of estimate the Duit and justification of tender in fair manner be prepared and approved of same competent authority, as per direction of Engineer in charge. The rates are inclusive octrol,royalty, Malkana, toll tal, sale tax, or other taxes imposed by government.	1.00	Per Job	85000.00	Ruppes Eighty Five Thousand Only	85000.00
Total in figures :-						85000.00
Total in Words:-		Ruppes Eighty Five Thousand Only				
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Sr.
No.

Schedule of Quantity

Description of work

Job No. :- 6.

Qty.

Unit

Rate in

Figures

words

Amount

Estimated Cost: -

Earnest Money: -

Time limit: -

One month

Name of Work :- Construction of Kandaghat Mahi road Km.0/00 to 4/450 (SH; - Providing and laying Gr-II from 1/00 to 1/400 in digged width against Deposit) (Deposit work)

1 Providing and laying, spreading by Mechanical means and compacting stone aggregates of WBM Grading- II i.e. 63mm to 45mm (sixty three millimeters to fourty five millimeters) size @ 0.91cum (point nine one cubic meters) per 10 (ten) square meters upto compacted thickness of 75mm (seventy five millimeters) including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 (eighty to hundred) kN static roller in stages to proper grade and camber, applying and brooming, stone screening of type B of size 11.2mm (eleven point two millimeters) @ 0.20 (point two) cubic meters per ten square meters and binding materials @ 0.060cum (point zero six cubic meter) per 10 (ten) square meters to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading II as per MORD Technical Specification Clause 405 (Four hundred five) upto entire satisfaction of Engineer-in-Charge, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.

42.00

Per Cubic
Meter

2346.00

Rupees Two Thousand
Three Hundred Forty
Six Only

98532.00

Total:-

98532.00

Quoted Percentage rate upto Three Digits :-

Rupees Ninety Eight Thousand Five Hundred Thirty Two On

(+) / (-)

T/S No. 29 for the 2025-26

Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Sr. No.

Schedule of Quantity

Description of work

Job No. :- 7.

Qty.

Unit

Figures

Rate in

words

Amount

Name of Work :- Repair of Path to Sh. Vishambar Thakur house at Domehar (SH:- Construction of PCC Retaining wall)
(Deposit work)

Estimated Cost:-	94277.00
Earnest Money:-	2000.00
Time limit :-	One months

1

Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.

10.00

Per Cubic
Meter

392.00

Rupees Three Hundred
Ninety Two Only

3920.00

2

Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.

1.60

Per Cubic
Meter

4179.00

Rupees Four Thousand
One Hundred Seventy
Nine Only

6686.00

3

Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.

16.50

Per Cubic
Meter

4737.00

Rupees Four Thousand
Seven Hundred Thirty
Seven Only

78161.00

4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	6.00	Each	242.00	Rupees Two Hundred Forty Two Only	1452.00
5	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	3.75	Per Cubic Meter	1082.00	Rupees One Thousand Eighty Two Only	4058.00
Total:-						
Rupees Ninety Four Thousand Two Hundred Seventy Seven Only						
Quoted Percentage rate upto Three Digits :-						
(+) / (-)						
94277.00						

T/S No. 04 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
	Job No. :- 8			Figures	words	
						Estimated Cost:-
						Earnest Money:-
						Time limit :-
Name of Work :- Providing and laying 30 mm thick BC on link road to Govt. Polytechnic Kandaghat Km.0/050 to 0/100 (Deposit work)						
1	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg (zero point two five to zero point three kilogramme) per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 (five zero three) and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lift and other incidental charges.	242.50	Per Square Meter	19.90	Rupees Nineteen and Paise Ninety Only	4826.00
2	Providing and laying bituminous macadam (BM) 50 (fifty) millimeter with hot mix plant using crushed aggregates of grading 19 (nineteen) millimeter nominal size (25-10mm @ 38.7%, 10-5mm @ 43.5% & 5mm & below (stone dust) @ 14.5% of volume of aggregate) as per Table 500.4 (five zero zero point four) premixed with bituminous binder / bitumen VG-10 @ 3.3% of total weight of mix, transported to site upto all lead laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per Technical Specification Clause 504. (five hundred four) including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges	0.61	Per Cubic Meter	9422.20	Rupees Nine Thousand Four Hundred Twenty Two and Paise Twenty Only	5748.00

3	Providing and laying bituminous concrete 30mm (Thirty millimetres) thick with 100-120 (one hundred to one hundred twenty) TPH batch type hot mix plant producing an average output of 75 (seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.5 (Five point five) per cent of total weight of mix, aggregate Grading II (thirteen millimetres nominal size) i.e. 13.2 - 10 mm thirty per cent, 10 - 5 mm twenty five per cent, 5 mm and below forty three per cent of volume of aggregate and filler @ 2 per cent of weight of aggregates, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 (five zero nine) complete in all respects and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	7.28	Per Cubic Meter	12129.15	Rupees Twelve Thousand One Hundred Twenty Nine and Paise Fifteen Only	88300.00
	Total:-					98874.00
	Rupees Ninety Eight Thousand Eight Hundred Seventy Four Only					
	Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No. 07 for the 2025-26
 Sr. No. for the year 2025-26
 Executive Engineer
 B&R Division, HP.PWD. Solan.

Schedule of Quantity

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 9.						
					Estimated Cost:-	99899.00
					Earnest Money:-	2000.00
				Time limit :-		One months
Name of Work :- Providing and laying 30 mm thick BC on link road to Govt. Polytechnic Kandaghat KM.0/00 to 0/050 (Deposit work)						

1	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg (zero point two five to zero point three kilogramme) per sqm on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 (five zero three) and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lift and other incidental charges.	245.25	Per Square Meter	19.90	Rupees Nineteen and Paise Ninety Only	4880.00
2	Providing and laying bituminous macadam (BM) 50 (fifty) millimeter with hot mix plant using crushed aggregates of grading 19 (nineteen) millimeter nominal size (25-10mm @ 38.7%, 10-5mm @ 43.5% & 5mm & below (stone dust) @ 14.5% of volume of aggregate) as per Table 500.4 (five zero zero point four) premixed with bituminous binder / bitumen VG-10 @ 3.3% of total weight of mix, transported to site upto all lead laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per Technical Specification Clause 504. (five hundred four) including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges	0.61	Per Cubic Meter	9422.20	Rupees Nine Thousand Four Hundred Twenty Two and Paise Twenty Only	5748.00

3	Providing and laying bituminous concrete 30mm (Thirty millimetres) thick with 100-120 (one hundred to one hundred twenty) TPH batch type hot mix plant producing an average output of 75 (seventy five) tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 5.5 (five point five) per cent of total weight of mix, aggregate Grading II (thirteen millimetres nominal size) i.e. 13.2 - 10 mm thirty per cent, 10 - 5 mm twenty five per cent, 5 mm and below forty three per cent of volume of aggregate and filler @ 2 per cent of weight of aggregates, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 509 (five zero nine) complete in all respects and as per direction of Engineer in charge including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	7.36	Per Cubic Meter	12129.15	Rupees Twelve Thousand One Hundred Twenty Nine and Paise Fifteen Only	89271.00
	Total:-					99899.00
	Rupees Ninety Nine Thousand Eight Hundred Ninety Nine Only					
	Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No. 06 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 10.						
Name of Work :- Repair of Path to Sh. Vishambar Thakur house at Domehar (SH: - Construction of PCC Retaining wall)						
(Deposit work) (Job No. 2)						
					Time limit :-	One months
					Estimated Cost:-	94761.00
					Earnest Money:-	2000.00
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	10.00	Per Cubic Meter	392.00	Rupees Three Hundred Ninety Two Only	3920.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	1.60	Per Cubic Meter	4179.00	Rupees Four Thousand One Hundred Seventy Nine Only	6686.00

3	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	16.50	Per Cubic Meter	4737.00	Rupees Four Thousand Seven Hundred Thirty Seven Only	78161.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	8.00	Each	242.00	Rupees Two Hundred Forty Two Only	1936.00
5	Backfilling behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per HP.PWD. Specification clause 1204.3.8 (one thousand two hundred four point three point eight) Granular material, including carriage of all labour equipment and material to various locations through all modes of transportation in all lead and lift and all incidental charges.	3.75	Per Cubic Meter	1082.00	Rupees One Thousand Eighty Two Only	4058.00
Total:-						94761.00
Rupees Ninety Four Thousand Seven Hundred Sixty One Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No. 05 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 11					Estimated Cost:-	99610.00
					Earnest Money:-	2000.00
					Time limit :-	One months

Name of Work :- Providing and laying WBM Grade-II for profile correction on various roads in Kandaghat Sub Division (Under MMSRRY 2025-26) (Job No. 1)

1	Providing and laying, spreading by Mechanical means and compacting to 75mm (seventy five millimeters) compacted thickness stone aggregates of Grading- III, 53mm to 22.5 mm (fifty three millimeters to twenty two point five millimeters) size @ 0.91cum (point nine one cubic meters) per 10 (ten) square meters to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 (eighty to hundred) kN static roller in stages to proper grade and camber, applying and brooming, stone screening of type B of size 11.2mm (eleven point two millimeters) @ 0.20 (point two zero) cubic meters per ten square meters to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per MORD Technical Specification Clause 405 (Four hundred five) and entire satisfaction & direction of Engineer-in-Charge, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	44.33	Per Cubic Meter	2247.00	Rupees Two Thousand Two Hundred Forty Seven Only	99610.00
Total:-						99610.00
Rupees Ninety Nine Thousand Six Hundred Ten Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No. 08 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
	Job No. :- 12 .			Figures	words	
					Estimated Cost :-	97475.00
					Earnest Money :-	2000.00
					Time limit :-	One months
Name of Work :- Providing and laying WBM Grade-II for profile correction on various roads in Kandaghat Sub Division (Under MMSRRY 2025-26) (Job No. 2)						
1	Providing and laying, spreading by Mechanical means and compacting to 75mm (seventy five millimeters) compacted thickness stone aggregates of Grading- III, 53mm to 22.5 mm (fifty three millimeters to twenty two point five millimeters) size @ 0.91cum (point nine one cubic meters) per 10 (ten) square meters to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 (eighty to hundred) kN static roller in stages to proper grade and camber, applying and brooming, stone screening of type B of size 11.2mm (eleven point two millimeters) @ 0.20 (point two zero) cubic meters per ten square meters to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per MORD Technical Specification Clause 405 (Four hundred five) and entire satisfaction & direction of Engineer-in-Charge, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	43.38	Per Cubic Meter	2247.00	Rupees Two Thousand Two Hundred Forty Seven Only	97475.00
	Total:-					97475.00
Rupees Ninety Seven Thousand Four Hundred Seventy Five Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No. 09 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 13					Estimated Cost: -	99093.00
					Earnest Money: -	2000.00
					Time limit :-	One months

Name of Work :- Providing and laying WBM Grade-II for profile correction on various roads in Kandaghat Sub Division (Under MMSRRY 2025-26) (Job No.3)

1	Providing and laying, spreading by Mechanical means and compacting to 75mm (seventy five millimeters) compacted thickness stone aggregates of Grading- III, 53mm to 22.5 mm (fifty three millimeters to twenty two point five millimeters) size @ 0.91cum (point nine one cubic meters) per 10 (ten) square meters to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 (eighty to hundred) kN static roller in stages to proper grade and camber, applying and brooming, stone screening of type B of size 11.2mm (eleven point two millimeters) @ 0.20 (point two zero) cubic meters per ten square meters to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per MORD Technical Specification Clause 405 (Four hundred five) and entire satisfaction & direction of Engineer-in-Charge, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	44.10	Per Cubic Meter	2247.00	Rupees Two Thousand Two Hundred Forty Seven Only	99093.00
Total:-						99093.00
		Rupees Ninety Nine Thousand Ninety Three Only				
Quoted Percentage rate upto Three Digits :-		(+) / (-)				

T/S No.14 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 14					Estimated Cost :-	99093.00
					Earnest Money:-	2000.00
					Time limit :-	One months

Name of Work :- Providing and laying WBM Grade-II for profile correction on various roads in Kandaghat Sub Division (Under MMSRRY 2025-26) (Job No.4)

1	Providing and laying, spreading by Mechanical means and compacting to 75mm (seventy five millimeters) compacted thickness stone aggregates of Grading- III, 53mm to 22.5 mm (fifty three millimeters to twenty two point five millimeters) size @ 0.91cum (point nine one cubic meters) per 10 (ten) square meters to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 (eighty to hundred) kN static roller in stages to proper grade and camber, applying and brooming, stone screening of type B of size 11.2mm (eleven point two millimeters) @ 0.20 (point two zero) cubic meters per ten square meters to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per MORD Technical Specification Clause 405 (Four hundred five) and entire satisfaction & direction of Engineer-in-Charge, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	44.10	Per Cubic Meter	2247.00	Rupees Two Thousand Two Hundred Forty Seven Only	99093.00
Total:-						99093.00
Rupees Ninety Nine Thousand Ninety Three Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.15 for the ~~2025-26~~
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 15.						
Name of Work :- Restoration of rain damages on link road to Ayurvedic Dispensary via Mini Secretariate Kandaghat Deposit work (SH:- Construction of PCC R/wall at Rd.0/0/0120 to 0/126.50)						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	10.01	Per Cubic Meter	392.00	Rupees Three Hundred Ninety Two Only	3924.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	1.63	Per Cubic Meter	4179.00	Rupees Four Thousand One Hundred Seventy Nine Only	6812.00

3	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	17.16	Per Cubic Meter	4737.00	Rupees Four Thousand Seven Hundred Thirty Seven Only	81287.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	10.00	Each	242.00	Rupees Two Hundred Forty Two Only	2420.00
	Total:-					94443.00
	Rupees Ninety Four Thousand Four Hundred Forty Three Only					
	Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No. 27 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 16				Estimated Cost :-		95653.00
				Earnest Money :-		2000.00
				Time limit :-		One Months
Name of Work :- Restoration of rain damages on link road to Ayurvedic Dispensary via Mini Secretariate Kandaghat (Deposit work)(SH: - Construction of PCC R/wall at Rd.0/0126.50 to 0/133)						
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	10.01	Per Cubic Meter	392.00	Rupees Three Hundred Ninety Two Only	3924.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	1.63	Per Cubic Meter	4179.00	Rupees Four Thousand One Hundred Seventy Nine Only	6812.00

3	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	17.16	Per Cubic Meter	4737.00	Rupees Four Thousand Seven Hundred Thirty Seven Only	81287.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	15.00	Each	242.00	Rupees Two Hundred Forty Two Only	3630.00
	Total:-					95653.00
		Rupees Ninety Five Thousand Six Hundred Fifty Three Only				
	Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No. 28 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 17.						
					Estimated Cost :-	94927.00
					Earnest Money:-	2000.00
					Time limit :-	One Months
Name of Work :- Restoration of rain damages on link road to Ayurvedic Dispensary via Mini Secretariate Kandaghat (Deposit work)(SH: - Construction of PCC R/wall at Rd.0/133 to 0/139.50)						

1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall, culvert, drain and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited). Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and its disposal including dressing of sides and bottom and backfilling in trenches with excavated suitable material, trimming, filling of unevenness blindages and finishing of the road to specified dimensions. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) or as directed by the Engineer-in-Charge. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	10.01	Per Cubic Meter	392.00	Rupees Three Hundred Ninety Two Only	3924.00
---	--	-------	-----------------	--------	--------------------------------------	---------

2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	1.63	Per Cubic Meter	4179.00	Rupees Four Thousand One Hundred Seventy Nine Only	6812.00
---	--	------	-----------------	---------	--	---------

3	Providing and laying Plain Cement Concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded stone aggregate 25mm (twenty five millimeters) nominal size) Mechanically mixed and vibrated for plain/reinforced concrete and curing complete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	17.16	Per Cubic Meter	4737.00	Rupees Four Thousand Seven Hundred Thirty Seven Only	81287.00
---	--	-------	-----------------	---------	--	----------

4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all lead and lift and other incidentals.	12.00	Each	242.00	Rupees Two Hundred Forty Two Only	2904.00
	Total:-					94927.00
	Rupees Ninety Four Thousand Nine Hundred Twenty Seven Only					
	Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No. 31 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Schedule of Quantity									
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount			
				Figures	words				
Job No. :- 13				Estimated Cost :-		99931.00			
				Earnest Money :-		2000.00			
				Time limit :-		One month			
Name of Work :- Renovation of Gents Toilet (RHS) in Judicial Court Complex Kandaghat as per the provisions of Physically Disabled & Transgender Friendly norms (Job No.4)									
1	Providing and fixing White Vitreous China basin for disable (DIS WHT 93801) with including all materials T&P etc. basin approved as per E/I (make Jaguar or equivalent)	1.00	Each	14625.00	Rupees Fourteen Thousand Six Hundred Twenty Five Only	14625.00			
2	Providing and fixing foldable Grab bars for Disable (WAC - SAP - BG 0800 CSN) with Hinges, Fixing accessories and Accessories set, including all materials T&P etc. Complete approved as per E/I (make Jaguar or equivalent)	1.00	Each	10725.00	Rupees Ten Thousand Seven Hundred Twenty Five Only	10725.00			
3	Providing and fixing Grab bars for Disable (WAC-SAP-BR0600CSN) with Hinges, Fixing Accessories and Accessories set , including all materials T&P etc. complete approved as per E/I (make Jaguar or equivalent)	3.00	Each	3837.00	Rupees Three Thousand Eight Hundred Thirty Seven Only	11511.00			
4	Providing and fixing uplasticised PVC connection pipe with brass unions 45 cm length 15 mm nominal bore	4.00	Each	88.25	Rupees Eighty Eight and Paise Twenty Five Only	353.00			
5	Providing and fixing Soap dish including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	2.00	Each	1086.20	Rupees One Thousand Eighty Six and Paise Twenty Only	2172.00			
6	Providing & Fixing White Vitreous China Urinal including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	3.00	Each	11135.05	Rupees Eleven Thousand One Hundred Thirty Five and Paise Five Only	33405.00			
7	Providing & Fixing Bib Cock with wall flange including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	4.00	Each	1445.55	Rupees One Thousand Four Hundred Forty Five and Paise Fifty Five Only	5782.00			

8	Providing & Fixing long nose bib cock with wall flange including all materials T & P etc. Complete. approved as per E/I (Make Jaguar or equivalent)	4.00	Each	1809.10	Rupees One Thousand Eight Hundred Nine and Paise Ten Only	7236.00
9	Providing and fixing PVC waste pipe for snk or wash basin including PVC Flexible pipe 32 mm dia	3.00	Each	1004.60	Rupees One Thousand Four and Paise Sixty Only	3014.00
10	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 Ltr	2.00	Each	916.50	Rupees Nine Hundred Sixteen and Paise Fifty Only	1833.00
11	Providing & Fixing Piller cock including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	2.00	Each	2872.25	Rupees Two Thousand Eight Hundred Seventy Two and Paise Twenty Five Only	5745.00
12	Providing & Fixing Anguler Cock with wall flange including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	3.00	Each	1176.60	Rupees One Thousand One Hundred Seventy Six and Paise Sixty Only	3530.00
	Total:-					99931.00
Rupees Ninety Nine Thousand Nine Hundred Thirty One Only						
	Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No.13 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	

Job No. :- 19

Estimated Cost :- 99497.00
Earnest Money :- 2000.00

Time limit :- One months

Name of Work :- Renovation of Ladies Toilet (RHS) in Judicial Court Complex Kandaghat as per the provisions of Physically Disabled & Transgender Friendly norms (Job No.3)

1	Providing and fixing white European wall hung water closet for <i>Disable (DIS WHT 93951 UF)</i> PP soft close seat cover, Hinges, Fixing Accessories and Accessories set, including all materials T & P etc. Complete approved as per E/1 (Make Jaguar or equivalent)	1.00	Each	38350.00	Rupees Thirty Eight Thousand Three Hundred Fifty Only	38350.00
2	Providing and fixing White Vitreous China basin for disable (DIS WHT 93801) with including all materials T&P etc. basin approved as per E/1 (make jaguar or equivalent)	1.00	Each	14625.00	Rupees Fourteen Thousand Six Hundred Twenty Five Only	14625.00
3	Providing and fixing foldable Grab bars for Disable (WAC - SAP -BG 0800 CSN) with Hinges, Fixing accessories and Accessories set, including all materials T&P etc. Complete approved as per E/1 (make jaguar or equivalent)	1.00	Each	10725.00	Rupees Ten Thousand Seven Hundred Twenty Five Only	10725.00
4	Providing and fixing Grab bars for Disable (WAC-SAP-BR0600CSN) with Hinges, Fixing Accessoroes and Accessories set , including all materials T&P etc. complete approved as per E/1 (make jaguar or equivalent)	4.00	Each	3837.00	Rupees Three Thousand Eight Hundred Thirty Seven Only	15348.00
5	Providing and fixing uplasticised PVC connection pipe with brass unions 45 cm length 15 mm nominal bore	1.00	Each	88.25	Rupees Eighty Eight and Paise Twenty Five Only	88.00
6	Providing & Fixing White Vitreous China Urinal including all materials T & P etc. Complete. approved as per E/1 (Make jaguar or equivalent)	1.00	Each	11135.05	Rupees Eleven Thousand One Hundred Thirty Five and Paise Five Only	11135.00
7	Providing & Fixing Bib Cock with wall flange including all materials T & P etc. Complete approved as per E/1 (Make jaguar or equivalent)	1.00	Each	1445.55	Rupees One Thousand Four Hundred Forty Five and Paise Fifty Five Only	1446.00
8	Providing & Fixing long nose bib cock with wall flange including all materials T & P etc. Complete. approved as per E/1 (Make jaguar or equivalent)	1.00	Each	1809.10	Rupees One Thousand Eight Hundred Nine and Paise Ten Only	1809.00

9	Providing and fixing PVC waste pipe for sink or wash basin including PVC Flexible pipe 32 mm dia	1.00	Each	1004.60	Rupees One Thousand Four and Paise Sixty Only	1005.00
10	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 Ltr	1.00	Each	916.50	Rupees Nine Hundred Sixteen and Paise Fifty Only	917.00
11	Providing & Fixing Piller cock including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	1.00	Each	2872.25	Rupees Two Thousand Eight Hundred Seventy Two and Paise Twenty Five Only	2872.00
12	Providing & Fixing Angular Cock with wall flange including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	1.00	Each	1176.60	Rupees One Thousand One Hundred Seventy Six and Paise Sixty Only	1177.00
	Total:-					99497.00
Rupees Ninety Nine Thousand Four Hundred Ninety Seven Only						
	Quoted Percentage rate upto Three Digits :-		(+) / (-)			

T/S No. 12 for the year 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 20						
					Estimated Cost: -	99934.00
					Earnest Money: -	2000.00
				Time limit : -		One months
Name of Work :-Renovation of Gents Toilet (LHS) in Judicial Court Complex Kandaghat as per the provisions of Physically Disabled & Transgender Friendly norms (Job No.2)						

1	Providing and fixing white European wall hung water closet for <i>Disable(DIS WHT 93951 UF)</i> PP soft close seat cover, Hinges, Fixing Accessories and Accessories set, including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	1.00	Each	38350.00	Rupees Thirty Eight Thousand Three Hundred Fifty Only	38350.00
2	Providing and fixing White Vitreous China basin for disable (DIS WHT 93801) with including all materials T&P etc. basin approved as per E/I (make jaguar or equivalent)	1.00	Each	14625.00	Rupees Fourteen Thousand Six Hundred Twenty Five Only	14625.00
3	Providing and fixing foldable Grab bars for Disable (WAC - SAP -BG 0800 CSN) with Hinges, Fixing accessories and Accessories set, including all materials T&P etc. Complete approved as per E/I (make jaguar or equivalent)	1.00	Each	10725.00	Rupees Ten Thousand Seven Hundred Twenty Five Only	10725.00
4	Providing and fixing Grab bars for Disable (WAC-SAP-BR0600CSN) with Hinges, Fixing Accessores and Accessories set , including all materials T&P etc. complete approved as per E/I (make jaguar or equivalent)	4.00	Each	3837.00	Rupees Three Thousand Eight Hundred Thirty Seven Only	15348.00
5	Providing and fixing uplasticised PVC connection pipe with brass unions 45 cm length 15 mm nominal bore	3.00	Each	88.25	Rupees Eighty Eight and Paise Twenty Five Only	265.00
6	Providing and fixing Soap dish including all materials T & P etc. Complete approved as per E/I (Make jaguar or equivalent)	2.00	Each	1086.20	Rupees One Thousand Eighty Six and Paise Twenty Only	2172.00
7	Providing & Fixing Bib Cock with wall flange including all materials T & P etc. Complete approved as per E/I (Make jaguar or equivalent)	2.00	Each	1445.55	Rupees One Thousand Four Hundred Forty Five and Paise Fifty Five Only	2891.00
8	Providing & Fixing long nose bib cock with wall flange including all materials T & P etc. Complete. approved as per E/I (Make jaguar or equivalent)	2.00	Each	1809.10	Rupees One Thousand Eight Hundred Nine and Paise Ten Only	3618.00

9	Providing and fixing PVC waste pipe for sink or wash basin including PVC Flexible pipe 32 mm dia	2.00	Each	1004.60	Rupees One Thousand Four and Paise Sixty Only	2009.00
10	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 Ltr	2.00	Each	916.50	Rupees Nine Hundred Sixteen and Paise Fifty Only	1833.00
11	Providing & Fixing Piller cock including all materials T & P etc. Complete approved as per E/1 (Make Jaguar or equivalent)	2.00	Each	2872.25	Rupees Two Thousand Eight Hundred Seventy Two and Paise Twenty Five Only	5745.00
12	Providing & Fixing Anguler Cock with wall flange including all materials T & P etc. Complete approved as per E/1 (Make Jaguar or equivalent)	2.00	Each	1176.60	Rupees One Thousand One Hundred Seventy Six and Paise Sixty Only	2353.00
Total:-						99934.00
Rupees Ninety Nine Thousand Nine Hundred Thirty Four Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No. 11 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Schedule of Quantity									
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount			
				Figures	words				
Job No. :- 2)				Estimated Cost: -		99542.00			
				Earnest Money: -		2000.00			
				Time limit :-		One months			
Name of Work :-Renovation of Ladies Toilet (LHS) in Judicial Court Complex Kandaghat as per the provisions of Physically Disabled & Transgender Friendly norms) (Job No.1)									
1	Providing and fixing white European wall hung water closet for <i>Disable(DIS WHT 93951 UF)</i> PP soft close seat cover, Hinges, Fixing Accessories and Accessories set, including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	1.00	Each	38350.00	Rupees Thirty Eight Thousand Three Hundred Fifty Only	38350.00			
2	Providing and fixing White Vitreous China basin for disable (DIS WHT 93801) with including all materials T&P etc. basin approved as per E/I (make jaguar or equivalent)	1.00	Each	14625.00	Rupees Fourteen Thousand Six Hundred Twenty Five Only	14625.00			
3	Providing and fixing foldable Grab bars for Disable (WAC - SAP -BG 0800 CSN) with Hinges, Fixing accessories and Accessories set, including all materials T&P etc. Complete approved as per E/I (make jaguar or equivalent)	1.00	Each	10725.00	Rupees Ten Thousand Seven Hundred Twenty Five Only	10725.00			
4	Providing and fixing Grab bars for Disable (WAC-SAP-BR0600CSN) with Hinges, Fixing Accessores and Accessories set , including all materials T&P etc. complete approved as per E/I (make jaguar or equivalent)	3.00	Each	3837.00	Rupees Three Thousand Eight Hundred Thirty Seven Only	11511.00			
5	Providing and fixing uplasticised PVC connection pipe with brass unions 45 cm length 15 mm nominal bore	4.00	Each	88.25	Rupees Eighty Eight and Paise Twenty Five Only	353.00			
6	Providing & Fixing White Vitreous China Urinal including all materials T & P etc. Complete. approved as per E/I (Make Jaguar or equivalent)	1.00	Each	11135.05	Rupees Eleven Thousand One Hundred Thirty Five and Paise Five Only	11135.00			
7	Providing and fixing Soap dish including all materials T & P etc. Complete approved as per E/I (Make jaguar or equivalent)	2.00	Each	1086.20	Rupees One Thousand Eighty Six and Paise Twenty Only	2172.00			

8	Providing & Fixing Bib Cock with wall flange including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	2.00	Each	1445.55	Rupees One Thousand Four Hundred Forty Five and Paise Fifty Only	2891.00
9	Providing & Fixing long nose bib cock with wall flange including all materials T & P etc. Complete. approved as per E/I (Make Jaguar or equivalent)	1.00	Each	1809.10	Rupees One Thousand Eight Hundred Nine and Paise Ten Only	1809.00
10	Providing and fixing PVC waste pipe for sink or wash basin including PVC Flexible pipe 32 mm dia	1.00	Each	1004.60	Rupees One Thousand Four and Paise Sixty Only	1005.00
11	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 Ltr	1.00	Each	916.50	Rupees Nine Hundred Sixteen and Paise Fifty Only	917.00
12	Providing & Fixing Piller cock including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	1.00	Each	2872.25	Rupees Two Thousand Eight Hundred Seventy Two and Paise Twenty Five Only	2872.00
13	Providing & Fixing Anguler Cock with wall flange including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	1.00	Each	1176.60	Rupees One Thousand One Hundred Seventy Six and Paise Sixty Only	1177.00
	Total:-					99542.00
Rupees Ninety Nine Thousand Five Hundred Forty Two Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No.10 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Schedule of Quantity						
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	
Job No. :- 22				Estimated Cost :-		83143.00
				Earnest Money :-		1700.00
				Time limit :-		One Months

Name of Work :- Construction of Rajasav Sadan building at Solan (SH: - Protection work at Top of ceiling (Deposit work))

1	Brick work with common burnt clay machine moulded with F.P.S.(non modular) perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) as per H.P. PWD. specification including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts, including all incidental charges.	4.49	Per Cubic Meter	6280.00	Rupees Six Thousand Two Hundred Eighty Only	28197.00
2	Providing and fixing M.S. BP Sheet 1.66mm to 2mm thick in eaves board/ fascia/ soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts, including all incidental charges.	11.440	Per square meter.	1942.00	Rupees One Thousand Nine Hundred Forty Two Only	22216.00
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works in position and applying a priming coat of approved steel primer using structural steel etc. as per HP.PWD. Specification including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	300.00	Per Kg	109.10	Rupees One Hundred Nine and Paise Ten Only	32730.00
Total:-						83143.00
Rupees Eighty Three Thousand One Hundred Forty Three Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No. 32 for the 2025-26

Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Sr. No.	Description of work	Qty.	Unit	Rate in		Amount
				Figures	words	

Job No. :- 24.

Name of Work :- Construction of Kandaghat Mahi road Km.0/00 to 4/450 (SH; - Providing and laying Gr-II from 1/400 to 1/800 in digged width against Deposit) (Deposit work)

Estimated Cost: -	99940.00
Earnest Money:-	2000.00
Time limit :-	One month

1	Providing and laying, spreading by Mechanical means and compacting stone aggregates of WBM Grading- II i.e. 63mm to 45mm (sixty three millimeters to fourty five millimeters) size @ 0.91cum (point nine one cubic meters) per 10 (ten) square meters upto compacted thickness of 75mm (seventy five millimeters) including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 (eighty to hundred) kN static roller in stages to proper grade and camber, applying and brooming, stone screening of type B of size 11.2mm (eleven point two millimeters) @ 0.20 (point two) cubic meters per ten square meters and binding materials @ 0.060cum (point zero six cubic meter) per 10 (ten) square meters to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading II as per MORD Technical Specification Clause 405 (Four hundred five) upto entire satisfaction of Engineer-in-Charge, including carriage of all labour, equipments and materials to various locations through all modes of transportation in all lead & lifts and all incidental charges.	42.60	Per Cubic Meter	2346.00	Rupees Two Thousand Three Hundred Forty Six Only	99940.00
---	---	-------	-----------------	---------	--	----------

Total:-

99940.00

Quoted Percentage rate upto Three Digits :-

Rupees Ninety Nine Thousand Nine Hundred Forty Only	(+) / (-)	
---	-----------	--

T/S No. 30 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.

Schedule of Quantity

Schedule of Quantity									
Sr. No.	Description of work	Qty.	Unit	Rate in		Amount			
				Figures	words				
Job No. :- 24				Estimated Cost: -		99542.00			
				Earnest Money: -		2000.00			
				Time limit : -		One months			
Name of Work :-Renovation of Ladies Toilet (1st floor) in Judicial Court Complex (Solan) as per the provisions of Physically Disabled & Transgender Friendly norms (2019)									
SOLAN									
1	Providing and fixing white European wall hung water closet for Disabled(DIS WHT 93951 UF) PP soft close seat cover, Hinges, Fixing Accessories and Accessories set, including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	1.00	Each	38350.00	Rupees Thirty Eight Thousand Three Hundred Fifty Only	38350.00			
2	Providing and fixing White Vitreous China basin for disable (DIS WHT 93801) with including all materials T&P etc. basin approved as per E/I (make Jaguar or equivalent)	1.00	Each	14625.00	Rupees Fourteen Thousand Six Hundred Twenty Five Only	14625.00			
3	Providing and fixing foldable Grab bars for Disable (WAC - SAP -BG 0800 CSN) with Hinges, Fixing accessories and Accessories set, including all materials T&P etc. Complete approved as per E/I (make Jaguar or equivalent)	1.00	Each	10725.00	Rupees Ten Thousand Seven Hundred Twenty Five Only	10725.00			
4	Providing and fixing Grab bars for Disable (WAC-SAP-BR0600CSN) with Hinges, Fixing Accessores and Accessories set, including all materials T&P etc. complete approved as per E/I (make Jaguar or equivalent)	3.00	Each	3837.00	Rupees Three Thousand Eight Hundred Thirty Seven Only	11511.00			
5	Providing and fixing uplasticised PVC connection pipe with brass unions 45 cm length 15 mm nominal bore	4.00	Each	88.25	Rupees Eighty Eight and Paise Twenty Five Only	353.00			
6	Providing & Fixing White Vitreous China Urinal including all materials T & P etc. Complete. approved as per E/I (Make Jaguar or equivalent)	1.00	Each	11135.05	Rupees Eleven Thousand One Hundred Thirty Five and Paise Five Only	11135.00			
7	Providing and fixing Soap dish including all materials T & P etc. Complete approved as per E/I (Make Jaguar or equivalent)	2.00	Each	1086.20	Rupees One Thousand Eighty Six and Paise Twenty Only	2172.00			

8	Providing & fixing Bib Cock with wall flange including all materials T & P etc. Complete approved as per E/1 (Make Jaguar or equivalent)	2.00	Each	1445.55	Rupees One Thousand Four Hundred Forty Five and Paise Fifty Only	2891.00
9	Providing & fixing long nose bib cock with wall flange including all materials T & P etc. Complete. approved as per E/1 (Make Jaguar or equivalent)	1.00	Each	1809.10	Rupees One Thousand Eight Hundred Nine and Paise Ten Only	1809.00
10	Providing and fixing PVC waste pipe for sink or wash basin including PVC Flexible pipe 32 mm dia	1.00	Each	1004.60	Rupees One Thousand Four and Paise Sixty Only	1005.00
11	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete. 10 Ltr	1.00	Each	916.50	Rupees Nine Hundred Sixteen and Paise Fifty Only	917.00
12	Providing & fixing Piller cock including all materials T & P etc. Complete approved as per E/1 (Make Jaguar or equivalent)	1.00	Each	2872.25	Rupees Two Thousand Eight Hundred Seventy Two and Paise Twenty Five Only	2872.00
13	Providing & fixing Angular Cock with wall flange including all materials T & P etc. Complete approved as per E/1 (Make Jaguar or equivalent)	1.00	Each	1176.60	Rupees One Thousand One Hundred Seventy Six and Paise Sixty Only	1177.00
Total:-						99542.00
Rupees Ninety Nine Thousand Five Hundred Forty Two Only						
Quoted Percentage rate upto Three Digits :-			(+) / (-)			

T/S No. 10 for the 2025-26
Sr. No. for the year 2025-26

Executive Engineer
B&R Division, HP.PWD. Solan.