



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

NO: PWD/BN/TA/NIT/2025-26/- **3482-57**
To

Dated:-24.06.2025

✓ **The Executive Engineer, (IT Cell),
Nirman Bhawan Nigam Vihar,
Shimla-2.**

Subject:- Publication of Tender Notice on the Departmental website.


Dear Sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No.PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the Notice Inviting Tender are urgent/emergent nature of works in public interest. Kindly ensure the prompt publication of the same on the website.

Encl: Notice Inviting Tender
& Schedule of Quantity.

Yours faithfully,


Executive Engineer,
Baijnath Division,
HP.PWD, Baijnath.

Copy forwarded for information to:-

1. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
2. All the Assistant Engineers working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

✓
Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

"NOTICE INVITING TENDER"

Sealed percentage rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **04.07.2025** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **03.07.2025** between **2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **02.07.2025** up to **12.00 Noon**.


The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O road from Chobin (Jalar) to Balh km 0/00 to 1/00 (SH: C/O R/wall at RD 0/220 to 0/227.30) VKV/2023/1662 Deposit Work.	97,599/-	2,000/-	Rs.350/-	Two Months
2	Demolishing of Bridge at Village Hartada (Deposit work SDP/2023/379)	99,299/-	2,000/-	Rs.350/-	One Month
3	C/O Bhadar Ghar at Kathog/Baijnath (SH: C/O Civil Works) (Deposit work VKV/2023/1653)	98,876/-	2,000/-	Rs.350/-	One Month
4	C/O Rain Shelter at Rajot (SH: C/O Rain Shelter at RD 1/885) (Deposit work VKV/2023/966)	98,744/-	2,000/-	Rs.350/-	Two Months
5	C/O Jeepable road to Sh. Pyar Chand Dogra House at RD 0/00 to 0/030 (SH: C/O R/wall at RD 0/00 to 0/006) (MMG/2019/89)	99,830/-	2,000/-	Rs.350/-	Two Months
6	C/O Foot path from Rajgundha to Hanumangadi (SH: P/L Kharnja Stone Soling for foot path) (Deposit work BSP/2024/62)	99,938/-	2,000/-	Rs.350/-	Two Months
7	C/O Road from Chaniyara to House to Hoshiar Singh Mehta at Chobin (SH: P/L interlocking paver block 60mm concrete block in RD 0/207.19 to 0/230.82) (Deposit work VKV/2024/1175)	99,952/-	2,000/-	Rs.350/-	Two Months
8	C/O Bridge at Village Hartada (SH: Super structure) (Deposit work SDP/2021/1137)	91,255/-	1,900/-	Rs.350/-	One Month
9	C/O Building work 2 rooms in G.S.S.S. Jandpur (SH: Civil work) (Deposit work SDP/2023/1141)	99,996/-	2,000/-	Rs.350/-	Two Months
10	C/O Mahila Mandal Bhawan at Gawal (First Floor) (SH: C/O Civil work) (Deposit work VKV/2024/1188)	99,775/-	2,000/-	Rs.350/-	Two Months
11	C/O OBC Bhawan at Ghirtholi (2 nd Part) Balance work (SH: Civil work)	99,627/-	2,000/-	Rs.350/-	Two Months
12	C/O Mahila Mandal Bhawan at Sunehar (SH: Plastering & Wood work in frame of Door & window in first floor) Deposit work VKV/2024/42	46,658/-	1,000/-	Rs.350/-	Two Months
13	Completion of room P.M. Shri. G.U.S.S.S. Paprola (SH: P/L Panelled Glazed Shutter, Distemper Painting etc.) (Deposit work VKV/2024/1187)	97,300/-	2,000/-	Rs.350/-	Two Months

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.

E.E.

5. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
6. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
7. The contractor shall have all required machinery such as Truck/Tipper,Mixture,water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
8. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
9. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
10. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.


Executive Engineer,
Bajnath Division.,
H.P.PWD..Bajnath.
For & On behalf of the Governor of H.P.

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O Road from Chobin (Jahar) to Balh km 0/00 to 1/00.
(Sh:- C/O R/W wall at RD 0/220 to 0/227.30) VKY/2023/1662 *Draft work*

Estimate Cost: 97,599.00/-
Earnest Money: 2,000.00/-
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	6.98	Per Cum	290.00	Rupess Two Hundred & Ninety Only	2,024.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1.5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	17.70	Per Cum	4950.00	Rupess Four Thousand Nine Hundred & Fifty Only	87,615.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	5.99	Per Cum	990.00	Rupess Nine Hundred & Ninety Only	5,930.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	7.00	Each	290.00	Rupess Two Hundred & Ninety Only	2,030.00
Total						97,599.00

D.N.I.T. Checked and approved for Rs. **97,599.00 only**
Rupess Ninety Seven Thousand Five Hundred Ninety Nine Only

Executive Engineer
Bajnath Division
HPPWD Bajnath

DNIT/DRAFT SCHEDULE OF QUANTITY

2

Name of Work : Demolishing of Bridge at Village Hartada (Deposit work SDP/2023/379)

Estimate Cost: 99,299.00 ✓
 Earnest Money: 2,000.00
 Time Limit : One Month

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	3.22 ✓	Cum. ✓	1,024.45 ✓	Ruppes One Thousand & Twenty Four - Paise Fourty Five Only	3,299.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause, 800 and 1206.3 RCC M-25 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.00 ✓	Cum ✓	8000.00 ✓	Ruppes Eight Thousand Only	96000.00
						99,299.00 ✓

D.N.L.T. Checked and approved for Rs. 99,299.00 only ✓
 Ruppes Ninety Nine Thousand Two Hundred Ninety Nine Only

Executive Engineer
 Bajinath Division
 HPPWD Bajinath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Bhadar Char at Kathog / Baijnath
(SH:- C/O Civil works) (Deposit work VKV/2023/1653)

Estimate Cost: 98,876.00
Earnest Money: 2000.00
Time Limit : One month

Sr.n	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and fixing pre-painted sheet roofing of kotar metal single skin trapezoidal 10 (ten) refitted sheeting 0.60mm thickness having 1060mm (one thousand sixty millimetre) cover width cover all width 1126mm. 28mm crest depth at 353mm (three hundred fifty three millimetre) 2.50mm (two decimal fifty millimetre) the main crest with at top 25mm and at lower 81mm base metal of coil rolled steel coil with zinc waiting top coat with regular modified polysters coating of approved shade and balancing reverse coat 5.5mm (five decimal five millimetre) dia and 55mm (fifty five millimetre) length with EPDM seal complete in all respect. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	44.52	Sqm	1700.00	Ruppes One Thousand Seven Hundred Only	75,684.00
2	Providing and fixing pre-painted sheet ridge or hips 60cm (sixty centimetre) over all of kotar metal skin trapezoidal profiled sheeting 0.60mm cover with over all width 1126mm (one thousand one hundred twenty six) 28mm (twenty eight) crest depth at 353mm (three hundred fifty three) 2mm (two millimetre) C/C crest distance. There will be two ribs at the centre for stiffening heaving crest depth of 2.5mm (two decimal five millimetre) the main crest with at top zinc waiting top coat with regular modified polysters coating of approved shade and balancing reverse coat 5.5mm (five decimal five millimetre) dia and 550mm (five hundred fifty millimetre) length with DPDM seal complete in all respect as per approved drawing design. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	7.00	Rmt	790.00	Ruppes Seven Hundred Ninety Only	5,530.00
3	Providing and fixing plating M.S. B.P. sheet 1.66mm (one decimal sixty six millimetre) thick to 2.00mm in evels board/ Facia / Soffit / Ceiling including cutting fixing jointing with gass/electric welding to steel roofs members and applying a coat of red lead primer complete as per PWD specification (Frame work is to be measured paid for separately). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government	5.34	Per square metre	2,600.00	Ruppes Two Thousand Six Hundred Only	13,884.00
4	Applying terra cotta /cement paint specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	30.74	Per square metre	80.00	Ruppes Eighty Only	2,459.00
5	Painting two or more coats(excluding priming costs) on new steel and other metal surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	13.46	Per square metre	98.00	Ruppes Ninety Eight Only	1,319.00
						98,876.00
	Quoted rates Percentage in figures					
	Quoted rates Percentage in words					

D.N.I.T. Checked and approved for Rs.

98,876.00 only

Ruppes Ninety Eight Thousand Eight Hundred Seventy Six Only

Executive Engineer
Baijnath Division
HPPWD Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

49

Name of work :- C/O Rain Shelter at Rajot (SH:- C/O Rain Shelter at RD 1/885) (Deposit work VKV/2023/966)						DNIT/DRAFT SCHEDULE OF QUANTITY		Estimate Cost :- 98744.00 Earnest Money: 2,000.00 Time Limit : Two Months	
Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. p			
				Figures	Words				
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	3.60	Per Cum	290.00	Rupess Two Hundred & Ninety Only	1,044.00			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone age 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	1.20	Per cubic metre	5,600.00	Rupess Five Thousand Six Hundred Only	6,720.00			
3	Stone filling under floor complete as per PWD specification The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.80	Per Cubic metre	1 100.00	Rupess One Thousand One Hundred Only	1980.00			
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	2.40	Per cubic metre	6,950.00	Rupess Six Thousand Nine Hundred & Fifty Only	16,680.00			
5	Providing and fixing 100 mm Diameter mild steel hollow pipe (Heavy grade) embedded The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	15.00	Rmt	642.50	Rupess Six Hundred & Fourty Two - Paise Fifty Only	9,638.00			
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In grainings, frames, guard bar, ladder, railings, brackets, gates and similar works The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	324.87	kg	96.00	Rupess Ninety Six Only	31,188.00			

4(b)

7	Providing and fixing 0.60mm (zero point sixty millimeter) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating i/c fixing with pre-painted iron 1 or 1 hook's bolts and nuts 6mm (six millimeter) dia metre with pre-painted humpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	19.11	Sqm	1421.90	Rupees One Thousand Four Hundred & Twenty One - Paise Ninety Only	27,173.00
8	Providing and fixing plain M.S. B.P. sheet 1.66mm (one decimal sixty six millimeter) thick to 2.00mm in evels board/Facia / Soth / Ceiling including cutting, jointing with gas/electric welding to steel roof's members and applying a coat of red lead primer complete as per PWD specification (frame work is to be measured paid for separately). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.52	Per square metre	1,227.50	Rupees One Thousand Two Hundred & Twenty Seven - Paise Fifty Only	4,321.00
TOTAL						98,744.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						

D.N.I.T. Checked and approved for Rs. 98,744.00 only
Rupees Ninety Eight Thousand Seven Hundred Forty Four Only

Executive Engineer
Bajinath Division
HPPWD Bajinath

DNI/DRAFT SCHEDULE OF QUANTITIES

Name of work :- C/O Jeppable Road to Sh. Pyar Chand Dogra house at RD 0/00 to 0/030
(SH-C/O R/wall at RD 0/00 to 0/006) MYC/2019/89

Estimate Cost: 99,830.00
Earnest Money: 2,000.00
Time Limit: Two Months

Sr. No.	Description of work	No. or QTY.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks) (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M O R D technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.92	Per Cum	290.00	Rupees Two Hundred & Ninety Only	1,427.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Month technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.90	Per Cum	4900.00	Rupees Four Thousand Nine Hundred Only	92,610.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.68	Per Cum	990.00	Rupees Nine Hundred & Ninety Only	4,633.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.00	Each	290.00	Rupees Two Hundred & Ninety Only	1,160.00
Total						99,830.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						

D.N.T. Checked and approved for Rs.

Rupees Ninety Nine Thousand Eight Hundred Thirty Only

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

Executive Engineer
Bajnath Division
HPPWD Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :-C/O Foot path from Rajgundha to Hanumangadi
(SH:-P/L Kharanja Stone Soling for foot path) (Deposit work BSP/2024/62)

Estimate Cost: 99,938.00/-
Earnest Money: 2,000.00/-
Time Limit : Two months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. p
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling/ wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.(Head load)	37.50	Per Cum	460.00	Rupees Four Hundred & Sixty Only	17,250.00
2	Providing and laying hard stone Soling properly hand packed intersects with kharanja stone to requested gradient and camber including spreading watering and rolling of binding morrum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.(Head load)	33.75	Per Cubic metre	2,450.00	Rupees Two Thousand Four Hundred Fifty Only	82,688.00
Total						99,938.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						

D.N.I.T. Checked and approved for Rs. 99,938.00 only
Rupees Ninety Nine Thousand Nine Hundred Thirty Eight Only

Executive Engineer
Bajinath Division
HPPWD Bajinath

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O Road from Chanayara to House of Hoshnar Singh Mehta at chobin
(SH:- P/L interlocking paver block 60 mm concrete block in RD 0/207.19 to 0/230.82)
(Deposit Work VKV/2024/1175)

Estimate Cost: 99,952.00/-
Earnest Money: 2,000.00/-
Time Limit : Two months

Sr. No.	Description of work	No. or QTY.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Tweny) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORC technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.33	Per Cubic metre	6,950.00	Rupees Six Thousand Nine Hundred Fifty Only	2,294.00
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawing and Technical Specification Clause 1504 entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate shall include all lead, lift and proper stacking complete in all respect as per the direction of the Engineer-in-charge. 60 mm	67.35	Per Square metre	1450.00	Rupees One Thousand Four Hundred & Fifty Only	97658.00
						99,952.00
	Quoted rates Percentage in figures					
	Quoted rates Percentage in words					

D.N.I.T. Checked and approved for Rs. 99,952.00 only
Rupees Ninety Nine Thousand Nine Hundred Fifty Two Only

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

Executive Engineer
Bajinath Division
HPPWD Bajinath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work : C/O Bridge at Village Hartada .
(Sh:- Super structure) (Deposit work SDP/2021/1137)

Estimate Cost: 91,225.00
Earnest Money: 1,900.00
Time Limit : One Month

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause ,800 and 1206.3 RCC M-25 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	9.92 ✓	Cum. ✓	8000.00 ✓	Rupees Eight Thousand Only ✓	79360.00 ✓
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause ,800 and 1206.3 RCC M-30 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.13 ✓	Cum ✓	10500.00 ✓	Rupees Ten Thousand Five Hundred Only ✓	11865.00 ✓
						91,225.00 ✓

D.N.L.T. Checked and approved for Rs. 91,225.00 only
Rupees Ninety One Thousand Two Hundred Twenty Five Only

Executive Engineer
 Bajinath Division
 HPPWD Bajinath

DNT/DRAFT SCHEDULE OF QUANTITIES

⑨

Name of work :- C/O Building work 2 rooms in GSS Standpur
(SH:- Civil Work) (Deposit work SDP/2023/1141)

Estimate Cost: 99,996.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr.n	Description of work	No.or QTY.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying cement concrete 1:6:12 (One cement isto six sand isto twelve aggregate) graded crushed/broken stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and curing complete, excluding cost of form work in foundation and plinth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.76	CUM	4000.00	Rupees Four Thousand Only	11,040.00
2	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 20mm (twenty) millimeter nominal size mechanical mixed in cement mortar 1:6 (one cement six sand) including curing and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	15.15	CUM	4200.00	Rupees Four Thousand Two Hundred Only	63,630.00
3	Square rubble masonry coursed with hard stone of approved quality in foundation and plinth including racking out joints in cement mortar 1:6 (one cement : six sand) and curing complete including carriage of materials within all leads and lifts complete in all respect as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.69	CUM	5400.00	Rupees Five Thousand Four Hundred Only	25,326.00
						99,996.00
	Quoted rates Percentage in figures					
	Quoted rates Percentage in words					

D.N.L.T. Checked and approved for Rs. 99,996.00 only
Rupees Ninety Nine Thousand Nine Hundred Ninety Six Only

Executive Engineer
 Baijnath Division
 HPPWD Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Mahila Mandal Bhawan at Gawal (First floor)
(sh:- C/O civil work) (Deposit work VKV/2024/1188)

Estimate Cost: 99,775.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curing and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.13	Per cubic metre	7,500.00	Rupees Seven Thousand Five Hundred Only	38,475.00
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in foundations and plinth in cement mortar 1:4 (one cement : four coarse sand) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	10.20	sqm	700.00	Rupees Seven Hundred Only	7,140.00
3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). 2nd class Sal wood The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.40	Cum	62000.00	Rupees Sixty Two Thousand Only	24,800.00
4	Providing and fixing 0.60mm (zero point sixty millimeter) thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating the fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (six millimeter) dia metre with pre-painted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	18.35	Sqm	1600.00	Rupees One Thousand Six Hundred Only	29,360.00
Quoted rates Percentage in figures						99,775.00
Quoted rates Percentage in words						

D.N.L.T. Checked and approved for Rs. 99,775.00 only
 Rupees Ninety Nine Thousand Seven Hundred Seventy Five Only

Executive Engineer
 Baijnath Division
 HPPWD Baijnath

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O OBC Bhawan at Girtholi (2nd Part) Balance work
(SH:- Civil work)

Estimate Cost: 99,627.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete work grade M-20 design mix to obtain the minimum compressive strength of M-20 N/mm ² with cement contents not less than of 320kg/m ³ (three hundred twenty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in suspended floor, roofs, landing and their support balconies beams girders bressumers and cantilevers upto floor all level and curing complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	4.77	Per cubic metre	7100.00	Rupees Seven Thousand One Hundred Only	33,867.00
2	Providing for steel reinforcement for reinforced cement concrete work including bending, binding and placing in position complete in all respects as per drawing and design in all floor levels including the cost of binding wire as per PWD specification and approved design. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	685.00	Per kilo gram	96.00	Rupees Ninety Six Only	65,760.00
						99,627.00

D.N.T. Checked and approved for Rs.

99,627.00 only

Rupees Ninety Nine Thousand Six Hundred Twenty Seven Only

Executive Engineer
Bajinath Division
HPPWD Bajinath

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Mahila Mandal Bhawan at Sunchar
(SH:- Plastering & Wood work in frame of Door & window in first floor) Deposit work VKV/2024/42.

Estimate Cost:46,658 .00
Earnest Money: 1,000.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).2nd class Sal wood The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	0.36	Cum	62000.00	Rupess Sixty Two Thousand Only	22,320.00
2	15 mm (Fifteen) cement plaster in single coat on rough side of brick/ stone masonry for interior plastering upto floor two level with Cm 1:6 as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect.the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government	102.26	Sqm	238.00	Rupess Two Hundred Thirty Eight Only	24,338.00
						46,658.00
	Quated rates Percentage in figures					
	Quated rates Percentage in words					

D.N.I.T. Checked and approved for Rs. 46,658.00 only
Rupees Forty Six Thousand Six Hundred Fifty Eight Only

Executive Engineer
Bajinath Division
HPPWD Bajinath

DNIT/DRAFT SCHEDULE OF QUANTITY

15

Name of Work :- Completion of room P.M. Shri G.L.S.S. Paprola
(SH:- P/L Panelled Glazed Shutter, Distemper Painting etc) (Deposit work VKV/2024/1187)

Estimate Cost: 97,300.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate	Words	AMOUNT Rs. p
1	Providing and fixing 40 mm (Forty millimetre) thick panelled glazed or panelled and glazed shutter second class Deodar wood for doors, windows and clear story windows including bright finished black enamelled iron hinges with necessary screws as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.48	Per Square Metre	4850.00	Rupees Four Thousand Eight Hundred & Fifty Only	16878.00
2	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes, including ISI marked M.S. pressed but hinges bright finished of required size with necessary screws. Second class teak wood as per PWD specification including curving and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.24	Per square metre	4150.00	Rupees Four Thousand One Hundred & Fifty Only	13446.00
3	Providing and fixing 40 mm (Forty millimetre) thick second class Deodar wood wire gauge shutters using galvanised MS wire gauge of IS gauge designation 85G with wire of dia 0.56 mm (Zero decimal five six millimetre) for doors, windows and clearstory windows including bright finished black enamelled iron hinges with necessary screws as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.72	Per square metre	3650.00	Rupees Three Thousand Six Hundred & Fifty Only	24528.00
4	Applying Birita white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	160.25	Per square metre	85.00	Rupees Eighty Five Only	13621.00
5	Distemping (Two coats) with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar droppings and other foreign matter and also including preparing the surface even and sand papered smooth on walls. Priming coat with distemper primer. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	160.25	Per square metre	110.00	Rupees One Hundred & Ten Only	17628.00
6	Providing and fixing grills of required pattern in steel frames of windows etc. with M.S. flats with round beaded bolts and nuts or by screw plain grill as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	23.60	Per kilo gram	105.00	Rupees One Hundred & Five Only	2478.00
7	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied before painting wood surface @0.75 ltr/10 sqm of approved brand and manufacture rate are including priming coat. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	22.03	sqm	110.00	Rupees One Hundred & Ten Only	2423.00
8	Painting two or more coats(excluding priming costs) on new steel and other metal surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.95	Per square metre	65.00	Rupees Sixty Five Only	192.00

9	Providing and fixing anodized aluminum tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete 250x10mm (Two hundred fifty into ten millimeter) size. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	20.00	Each	150.00	Rupees One Hundred & Fifty Only	3,000.00
10	Providing and fixing anodized aluminum tower bolts (barrel type) anodized transparent or dyed to required shade and colour with screws etcetra complete 150x10mm (One hundred fifty into ten millimeter) size. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	20.00	Each	100.00	Rupees One Hundred Only	2,000.00
11	Providing and fixing 125 mm (one hundred twenty five millimeter) size oxidized M.S. handles with the necessary screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	2.00	Each	75.00	Rupees Seventy Five Only	150.00
12	Providing and fixing 100mm (one hundred millimeter) size oxidized M.S. handles with the necessary screws etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	5.00	Each	60.00	Rupees Sixty Only	300.00
13	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete 250x16 mm (two fifty into sixteen millimeter) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government	2.00	Each	214.20	Rupees Two Hundred & Fourteen - Paise Twenty Only	428.00
14	Himachi colour wash on undecorated wall surfaces (twocoats) to give an even shade including thoroughly brooming the surfaces to remove all dirt,dust,mortar drops and other foreign matter as per PWD specification including curing and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	22.78	sqm	10.00	Rupees Ten Only	228.00
	Quoted rates Percentage in figures					
	Quoted rates Percentage in words					97,300.00

Estimate Checked and approved for Rs.

97,300.00 only

Rupees Ninety Seven Thousand Three Hundred Only

Executive Engineer
Bainnath Division
HPPWD Bainnath