



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

NO: PWD/BN/TA/NIT/2025-26/-
To

2910-15

Dated:-05.06.5025

**The Executive Engineer, (IT Cell),
Nirman Bhawan Nigam Vihar,
Shimla-2.**

Subject:- Publication of Tender Notice on the Departmental website.

Dear Sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No.PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the Notice Inviting Tender are urgent/emergent nature of works in public interest. Kindly ensure the prompt publication of the same on the website.

Encl: Notice Inviting Tender
& Schedule of Quantity.

Yours faithfully,

Executive Engineer,
Baijnath Division,
HPPWD, Baijnath.

Copy forwarded for information to:-

1. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
2. All the Assistant Engineers working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer,
Baijnath Division.,
H.P.PWD..Baijnath.



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

"NOTICE INVITING TENDER"


Sealed percentage rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **19.06.2025** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **18.06.2025** between **2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **17.06.2025** up to **12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O Road from Chaniyara to House of Hoshiar Singh Mehta at Chobin (SH: P/L interlocking paver block 60mm concrete block in RD 0/183.56 to 0/207.19) (Deposit work VKV/2024/1175)	99,952/-	2,000/-	Rs.350/-	Two Months
2	C/O Baijnath Dhanag Road km 0/00 to 3/400 (SH: C/O B/wall at RD 0/983 to 0/989)	97,899/-	2,000/-	Rs.350/-	Two Months
3	C/O Ambulance road Rain Shelter Bhiot to Village Bhiot km 0/00 to 0/350 (SH: C/O R/wall at RD 0/200 to 0/204.60)	98,731/-	2,000/-	Rs.350/-	Two Months
4	A/R & M/O Baijnath Chobin Balander road of PWD under Baijnath Division HPPWD Baijnath (SH: Providing and fixing of dual directional retro reflective speed breaker/rumble strips for road safety) Under OFC	97,500/-	2,000/-	Rs.350/-	One Month
5	C/O Foot path from Rajgundha to Hanumangadi (SH: P/L Kharnja Stone Soling for foot path) (Deposit work BSP/2024/62)	99,938/-	2,000/-	Rs.350/-	Two Months
6	C/O Mahila Mandal Bhawan at Sunehar (SH: C/O Brick work, in first floor) (Deposit work VKV/2024/42)	99,665/-	2,000/-	Rs.350/-	Two Months
7	C/O Mahila Mandal Bhawan at Gowal (First floor) (SH: C/O Civil work) (Deposit work VKV/2024/1188)	99,875/-	2,000/-	Rs.350/-	Two Months
8	C/O OBC Bhawan at Ghirtholi (2 nd Part) Balance work (SH: Civil Work)	99,799/-	2,000/-	Rs.350/-	Two Months
9	Completion of room P.M Shri G.U.S.S.S Paprola (SH: P/L Brick work, Tiles work etc.) (Deposit work VKV/2024/1187)	97,889/-	2,000/-	Rs.350/-	Two Months
10	Repair of R/wall Lakhdatta Pir Committee Nanwar (SH: C/O R/wall at RD 0/00 to 0/009.70) (Deposit work SDF/2024/1960)	49,224/-	1,000/-	Rs.350/-	Two Months
11	Re-C/O R/wall of Sh. Prem Singh ward No. 3 Bharag (Sansal) (SH: C/O R/wall at RD 0/00 to 0/005.70) (Deposit work SDF/2024/1955)	49,342/-	1,000/-	Rs.350/-	Two Months
12	C/O Bhadar Ghar at Kathog/Baijnath (SH: C/O Civil Works) (Deposit work VKV/2023/1653)	99,926/-	2,000/-	Rs.350/-	One Month
13	C/O Building work 2 rooms in GSSS Jandpur (SH: Civil Work) (Deposit work SDP/2023/1141)	99,984/-	2,000/-	Rs.350/-	Two Months

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.

2. The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
3. In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
4. Only two tenders form will be issued to the contractor/firm which may be noted.
5. Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
6. The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
7. The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
8. The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
9. All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
10. The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.


Executive Engineer,
Bajnath Division.,
H.P.PWD..Bajnath.
For & On behalf of the governor of H.P.

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O Road from Chaniyara to House of Hoshnar Singh Mehta at chobin
(SH:- P/L interlocking paver block 60 mm concrete block in RD 0/183.56 to 0/207.19)
(Deposit Work VKV/2024/1175)

Estimate Cost: 99,952.00/-
Earnest Money: 2,000.00/-
Time Limit : Two months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.33	Per Cubic metre	6,950.00	Rupees Six Thousand Nine Hundred Fifty Only	2,294.00
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawing and Technical Specification Clause 1504 entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate shall include all lead, lift and proper stacking complete in all respect as per the direction of the Engineer-in-charge. 60 mm	67.35	Per Square metre	1450.00	Rupees One Thousand Four Hundred & Fifty Only	97658.00
	Quoted rates Percentage in figures					99,952.00
	Quoted rates Percentage in words					

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per Indian standard in market should confirm to bureau of Indian standards

D.N.I.T. Checked and approved for Rs. 99,952.00 only
Rupees Ninety Nine Thousand Nine Hundred Fifty Two Only

Executive Engineer
Bajnath Division
HPPWD Bajnath

1

DNIT/DRAFT SCHEDULE OF QUANTITY

DNIT/DRAFT SCHEDULE OF QUANTITY						Estimate Cost: 97,899.00/- Earnest Money: 2,000.00/- Time Limit : Two Months	
Sr. No.		Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
					Figures	Words	
1		Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.98	Per Cum	290.00	Rupees Two Hundred & Ninety Only	1,444.00
2		Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	18.90	Per Cum	4950.00	Rupees Four Thousand Nine Hundred & Fifty Only	93,555.00
3		Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	10.00	Each	290.00	Rupees Two Hundred & Ninety Only	2,900.00
Total							97,899.00
Quoted rates Percentage in figures							
Quoted rates Percentage in words							

D.N.I.T. Checked and approved for Rs.

97,899.00 only
Rupees Ninety Seven Thousand Eight Hundred Ninety Nine Only

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per Indian standard in market should confirm to bureau of indian standards

Executive Engineer
Baijnath Division
HPPWD Baijnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: C/O Ambulance Road Rain shelter Bhiot to Village Bhiot km 0/00 to 0/350.
(Sh:- C/O R/W all at RD 0/200 to 0/204.60)

Estimate Cost: 98,731.00/-
Earnest Money: 2,000.00/-
Time Limit : Two Months

AMOUNT

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling/wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and hauling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.83	Per Cum	290.00	Rupees Two Hundred & Ninety Only	1,401.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect: the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	17.62	Per Cum	4950.00	Rupees Four Thousand Nine Hundred & Fifty Only	87,219.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, including entire carriage of materials within all leads and lifts within all incidentals: the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	7.87	Per Cum	990.00	Rupees Nine Hundred & Ninety Only	7,791.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals: the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	8.00	Each	290.00	Rupees Two Hundred & Ninety Only	2,320.00
Total						98,731.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						

D.N.I.T. Checked and approved for Rs.

Rupees Ninety Eight Thousand Seven Hundred Thirty One Only

Executive Engineer
Bajnath Division
HPPWD Bajnath

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work : A/R & M/O Baijnath Chobin Balandar road of PWD under Baijnath Division HPPWD Baijnath
Sub Head: Providing and fixing of dual directionalak retro reflective speed breaker/rumble strips for road safety) under OFC

Estimate Cost: 97,500.00/-
Earnest Money: 2000.00/-
Time Limit : One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. p
				Figures	Words	
1	Providing and fixing dual directional speed breakers/rumble-strip yellow plastic high impact resistant plastic body of size 270 mm X145mmX25mm (two hundred seventy five into one hundred fifty into twenty five millimeter)having 6 (six) glass larger 12 mm (twelve millimeter) diameter reflector lenses to one side (12 Nos.both sides) for night vision provided with two steel zinc plated nails of 12 mm (twelve millimeter) diameter and 120 mm (one hundred millimeter) long for fixing to road including carriage of material with in all leads and lifts as per the direction of Engineer-in - Charge. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	150.00	Each	650.00	Rupees Six Hundred & Fifty Only	97,500.00
	Total					97,500.00
	Quoted rates Percentage in figures					
	Quoted rates Percentage in words					

D.N.I.T. Checked and approved for Rs. 97,500.00 only
Rupees Ninety Seven Thousand Five Hundred Only

Executive Engineer
Baijnath Division
HPPWD Baijnath

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Foot path from Rajgundha to Hanumangadi
(SH:-P/L. Kharanja Stone Soling for foot path) (Deposit work BSP/2024/62)

Estimate Cost: 99,938.00/-
Earnest Money: 2,000.00/-
Time Limit : Two months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government (Head load)	37.50	Per Cum	460.00	Rupees Four Hundred & Sixty Only	17,250.00
2	Providing and laying hard stone Soling properly hand packed intersects with kharanja stone to requested gradient and camber including spreading watering and rolling of binding mortum or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.(Head load)	33.75	Per Cubic metre	2,450.00	Rupees Two Thousand Four Hundred Fifty Only	82,688.00
Total						99,938.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						

D.N.I.T. Checked and approved for Rs. 99,938.00 only
Rupees Ninety Nine Thousand Nine Hundred Thirty Eight Only

Executive Engineer
Bajnath Division
HPPWD Bajnath

DNT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Mahila Mandal Bhawan at Sunehar
(SH:- C/O Brick Work, in first floor) Deposit work VKV/2024/42.

Estimate Cost: 99,665.00 ✓
Earnest Money: 2,000.00 ✓
Time Limit : Two Months ✓

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	12.86	Per cubic metre	7750.00	Rupees Seven Thousand Seven Hundred Fifty Only	99,665.00 ✓
	Quated rates Percentage in figures					
	Quated rates Percentage in words					
						99,665.00 ✓

D.N.I.T. Checked and approved for Rs. 99,665.00 only
Rupees Ninety Nine Thousand Six Hundred Sixty Five Only ✓

Executive Engineer
Bajnath Division
HPPWD Bajnath

D.N.I./DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Mahila Mandal Bhawan at Gawal (First floor)
(sh:- C/O civil work) (Deposit work VKV/2024/1188)

Estimate Cost: 99,875.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr. n	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. p
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete work, grade M-20 design mix to obtain the minimum compressive strength of M-20 N mm ² with cement contents not less than of 320kg/m ³ (three hundred twenty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in suspended floor, roofs, landing and shelves and their support balconies beams girders bressumers and cantilevers upto floor all level and curing complete The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.00	Per cubic metre	7000.00	Rupees Seven Thousand Only	14,000.00
2	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curing and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	11.45	Per cubic metre	7,500.00	Rupees Seven Thousand Five Hundred Only	85,875.00
Quoted rates Percentage in figures						99,875.00
Quoted rates Percentage in words						

D.N.I.T. Checked and approved for Rs. 99,875.00 only
Rupees Ninety Nine Thousand Eight Hundred Seventy Five Only

Executive Engineer
Bajjnath Division
HPPWD Bajjnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O OBC Bhawan at Girtholi
(SH:- Civil work)

(2nd Part) Balance work

Estimate Cost: 99,799.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Figures	Rate	AMOUNT Rs. P
				Words	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	5.08	Per Cum	290.00	Rupees Two Hundred Ninety Only	1,473.00
2	Centering and shuttering including strutting, propping etc. and removal of form work for :Foundations, footings, bases for columns The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	6.24	sqm	216.45	Rupees Two Hundred Sixteen And Paise Forty Five Only	1,351.00
3	Centering and shuttering including strutting, propping etc. and removal of form work for :Surface such as suspended floor etc The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	45.50	sqm	400.00	Rupees Four Hundred Only	18,200.00
4	Centering and shuttering including strutting, propping etc. and removal of form work for :Beams Cantilever girder etc The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	27.00	sqm	387.15	Rupees Three Hundred Eighty Seven And Paise Fifteen Only	10,453.00
5	Centering and shuttering including strutting, propping etc. and removal of form work for :Square, rectangular or polygonal in plan The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	9.15	sqm	514.75	Rupees Five Hundred Fourteen And Paise Seventy Five Only	4,710.00
6	Centering and shuttering including strutting, propping etc. and removal of form for Edges of slabs and breaks in floors and walls Under 20 cm (twenty centimetre) wide The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	20.00	running mtr	131.50	Rupees One Hundred Thirty One And Paise Fifty Only	2,630.00

7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (one Cement : four coarse sand) : Eight graded stone aggregate 40 (forty) mm nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	0.288	Cum.	5,300.00	Rupees Five Thousand Three Hundred Only	1,526.00
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one Cement : Two coarse sand) : four graded stone aggregate 40 (forty) mm nominal size in foundation Footings and Basis of columns The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	1.13	Per cubic metre	7,000.00	Rupees Seven Thousand Only	7,910.00
9	Providing and laying cement concrete work 1:2:4 (1 Cement:2 Sand:4 graded stone aggregate 20 mm nominal size) and curing complete excluding cost of form work and Coulmn Pillar Posts & sturts and the carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.06	Per cubic metre	7100.00	Rupees Seven Thousand One Hundred Only	14,626.00
10	Providing and laying mechanically mixed and vibrated reinforced cement concrete work grade M-20 design mix to obtain the minimum compressive strength of M-20 N.mm ² with cement contents not less than of 320kg/m ³ (three hundred twenty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in suspended floor, roofs, landing and shelves and their support balconies beams girders bressumers and cantilevers upto floor all level and curing complete The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.20	Per cubic metre	7100.00	Rupees Seven Thousand One Hundred Only	36,920.00
						99,799.00

D.N.I.T. Checked and approved for Rs. 99,799.00 only
Rupees Ninety Nine Thousand Seven Hundred Ninety Nine Only

Executive Engineer
Bajnath Division
HPPWD Bajinath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of Work :- Completion of room P.M. Shri G.U.S.S. Paprola
(SH:- P/L Brick Work, Tiles work etc) (Deposit work VKV/2024/1187)
Estimate Cost: 97,889.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr.n	Description of work	No.or	Unit	Rate	Words	AMOUNT
1	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curing and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.34	Per cubic metre	7850.00	Rupees Seven Thousand Eight Hundred & Fifty Only	26219.00
2	15mm Cement plaster in single coat on the rough side of brick/ concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth Cement Mortar 1:6 (1 Cement 6 Sand). The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	27.28	Per square metre	250.00	Rupees Two Hundred & Fifty Only	6820.00
3	Providing and fixing 10mm(ten millimeter) thick anti skid water proof stain and impet resistant heavy duty vetrified tiles Nitco or equivalent 600x600mmx10mm (Six hundred into six hundred into ten millimeter) manufactured of approved shade and colour in flooring, treads of steps and landings laid over 12mm thick cement mortar 1:3 (one cement isto three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	39.12	Per square metre	1550.00	Rupees One Thousand Five Hundred & Fifty Only	60636.00
4	Providing and laying white glazed tiles 6 mm (Six millimetre) thick in skirting, riser, steps and dedo 200x150 mm (Two hundred into one hundred fifty millimetre) size laid on bed of 12 mm (Twelve millimetre) thick cement mortar 1:3 (one cement : three sand) finished with flush pointing in white cement complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.01	Per square metre	1400.00	Rupees One Thousand Four Hundred Only	4214.00
	Quated rates Percentage in figures					97,889.00
	Quated rates Percentage in words					

D.N.I.T. Checked and approved for Rs. 97,889.00 only
Rupees Ninety Seven Thousand Eight Hundred Eighty Nine Only

Executive Engineer
Bajnath Division
HPPWD Bajnath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work: Repair of R/wall Lakshadatta Pir Committee Nanwar
(Sh:- C/O R/Wall at RD 0/00 to 0/009.70) (Deposit work, SDF/2024/1960)

Estimate Cost: 49,224.00/-
Earnest Money: 1,000.00/-
Time Limit: Two Months

St. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling, wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	3.01	Per Cum	290.00	Rupess Two Hundred & Ninety Only	873.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone egg, 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	8.63	Per Cum	5000.00	Rupess Five Thousand Only	43,150.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	2.91	Per Cum	990.00	Rupess Nine Hundred & Ninety Only	2,881.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	8.00	Each	290.00	Rupess Two Hundred & Ninety Only	2,320.00
Quoted rates Percentage in figures		Total				49,224.00
Quoted rates Percentage in words						

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer - in - Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

D.N.L.T. Checked and approved for Rs.

Rupess Forty Nine Thousand Two Hundred Twenty Four Only

Executive Engineer
Bajnath Division
HPPWD Bajnath

DNI/DRAFT SCHEDULE OF QUANTITIES

Name of work: **Re-C/O R/wall of sh. Prem singh ward no. 3 Bhaurag (Sansal)**
(Sh:- C/O R/Wall at RD 0/00 to 0/005.70) (Deposit work SDF/2024/955)

Estimate Cost: **49,342.00/-**
Earnest Money: **1,000,000/-**
Time Limit: **Two Months**

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks) (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-in-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.10	Per Cum	290.00	Rupess Two Hundred & Ninety Only	1,189.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	9.06	Per Cum	5000.00	Rupess Five Thousand Only	45,300.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	1.71	Per Cum	990.00	Rupess Nine Hundred & Ninety Only	1,693.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V)/20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	4.00	Each	290.00	Rupess Two Hundred & Ninety Only	1,160.00
Total						49,342.00
Quated rates Percentage in figures						
Quated rates Percentage in words						

Condition :-

1. Rate should be quoted for all heights including all leads and lifts
2. Sample of all material to be used on work shall be got approved from Engineer-in-Charge in advance before actual use on work and any or all material which are available as per indian standard in market should confirm to bureau of indian standards

Executive Engineer
Bajnath Division
HPPWD Bajjnath

D.N.I.T. Checked and approved for Rs. **49,342.00 only**
Rupess Forty Nine Thousand Three Hundred Forty Two Only

DNIT/DRAFT SCHEDULE OF QUANTITIES

Name of work :- C/O Bhadar Char at Kathing / Bajinath
(SH:- C/O Civil works) (Deposit work VKV/2023/1653)

Estimate Cost: 99,926.00
Earnest Money: 2000.00
Time Limit : One month

Sr.n	Description of work	No. or QTY.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	5.05	Per Cum	290.00	Rupees Two Hundred Ninety Only	1,465.00
2	Providing and laying cement concrete 1:6:12 (One cement isto six sand isto twelve aggregate) graded crushed/broken stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and curing complete, excluding cost of form work in foundation and plinth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.28	CUM	4400.00	Rupees Four Thousand Four Hundred Only	14,432.00
3	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 20mm (twenty) millimeter nominal size mechanical mixed in cement mortar 1:6 (one cement six sand) including curing and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	5.73	CUM	4800.00	Rupees Four Thousand Eight Hundred Only	27,504.00
4	Square rubble masonry coursed with hard stone of approved quality in foundation and plinth including racking out joints in cement mortar 1:6 (one cement : six sand) and curing complete including carriage of materials within all leads and lifts complete in all respect as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.18	CUM	6000.00	Rupees Six Thousand Only	7,080.00
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	1.09	CUM	7000.00	Rupees Seven Thousand Only	7,630.00
6	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curing and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	3.95	Per cubic metre	7,700.00	Rupees Seven Thousand Seven Hundred Only	30,415.00
7	cement concrete flooring of specified grade excluding the cost of centering and shuttering laid in one layer : 1:2:4 (one Cement : two coarse sand) : four graded stone aggregate 40 mm (Forty millimeter) nominal size) The rate including of octroi, royalty, Malkana, tolltax, Sale Tax or other taxes imposed by the government.	24.00	sqm	475.00	Rupees Four Hundred Seventy Five Only	11,400.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						99,926.00

D.N.I.T. Checked and approved for Rs. 99,926.00 only
Rupees Ninety Nine Thousand Nine Hundred Twenty Six Only

Executive Engineer
Bajinath Division
HPPWD Bajinath

DNIT/DRAFT SCHEDULE OF QUANTITY

Name of work :- C/O Building work 2 rooms in GSSJlandpur
(Sft:- Civil Work) (Deposit work SDP/2023/1141)

Estimate Cost: 99,984.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling (wedging out rocks) (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In-Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental, the rate including of octroi, royalty, Malkana, tolltax, or other taxes imposed by the government.	60.64	CUM	290.00	Rupees Two Hundred & Ninety Only	17,586.00
2	Providing and laying cement concrete 1:6:12 (One cement is to six sand is to twelve aggregate) graded crushed/broken stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and curing complete, excluding cost of form work in foundation and plinth. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	2.76	CUM	4000.00	Rupees Four Thousand Only	11,040.00
3	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (one cement : six sand : twelve graded stone aggregate 20mm (twenty millimeter nominal size mechanical mixed in cement mortar 1:6 (one cement six sand) including curting and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. The rate is including octroi, royalty, GST, toll tax, Sale Tax or other taxes imposed by the government.	16.99	CUM	4200.00	Rupees Four Thousand Two Hundred Only	71,358.00
						99,984.00
	Quoted rates Percentage in figures					
	Quoted rates Percentage in words					

D.N.I.T. Checked and approved for Rs. 99,984.00 only
Rupees Ninety Nine Thousand Nine Hundred Eighty Four Only

Executive Engineer
Bajinath Division
HPPWD Bajinath