



**"NOTICE INVITING TENDER"**

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 13.06.2025 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 10.06.2025 up to 10.00 A.M. to 12:00 P.M. and tender form can be had from this office on 12.06.2025 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

|    | Name of work                                                                                                                                                                                                                                                                                                                                                                                                                                    | Amount put to tender/<br>Estimated cost | Earnest Money | Cost of tender form | Eligible Class of Contractor | Time       |
|----|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------|---------------|---------------------|------------------------------|------------|
| 1  | Construction of road from NH-154 to Village Thulan km 0/0 to 1/500 (Sub Head:- Formation Cutting in km 0/840 to 0/915) under BASP Deposit Scheme ID BSP/2024/801                                                                                                                                                                                                                                                                                | Rs. 98,592/-                            | Rs. 2,000/-   | Rs. 350/-           | Class "D"                    | Two months |
| 2  | A/R & M/O Bhardoun Gangoti road km 0/00 to 6/800 (SH: Scarifying M/T GSB and providing & laying GSB, G-II, G-III and tarring on km 3/407 to 3/437)                                                                                                                                                                                                                                                                                              | Rs. 97,291/-                            | Rs. 1,900/-   | Rs. 350/-           | Class "D"                    | Two months |
| 3  | Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Gadiyara to Thara Raktal road Km. 3/0 to 7/0 (ii) Gadiyara to Thara road Km. 0/0 to 3/0 (Neri Section) (Sub Head:- Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work).                                                                                                                                                   | Rs. 80,090/-                            | Rs. 1,600/-   | Rs. 350/-           | Class "D"                    | Two months |
| 4  | Providing and laying patch work under MMSRRY for the year 2025-26 on Joginder Nagar Sarkaghat Ghumarwin road Km 8/0 to 13/0 (Makreri Section) (Sub Head:- Repair of pot hole (Patch work) in Km. 8/0 to 9/250).                                                                                                                                                                                                                                 | Rs. 69,209/-                            | Rs. 1,400/-   | Rs. 350/-           | Class "D"                    | Two months |
| 5  | Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Sandhapattan Basahi Banwar Kotli road Km. 0/0 to 3/0 & Km. 7/0 to 9/0 (ii) Pihar Bedhlu road Km. 1/0 to 1/500 and (iii) Suin Bhararpat up to vill. Bhardoun road Km. 0/0 to 2/0 (Lad Bharol section) (Sub Head:- Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work).                                                     | Rs. 71,108/-                            | Rs. 1,400/-   | Rs. 350/-           | Class "D"                    | Two months |
| 6  | Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Baijnath Lad Bharol Kandapattan road Km. 26/0 to 30/0 (ii) Bharan Kanharag Faglia road Km. 1/0 to 2/500 and (iii) Gagal to Bhager road Km. 0/0 to 1/0 & Km. 3/0 to 6/0 (Tullah section) (Sub Head:- Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work).                                                                  | Rs. 99,188/-                            | Rs. 2,000/-   | Rs. 350/-           | Class "D"                    | Two months |
| 7  | Providing and laying patch work under MMSRRY for the year 2025-26 on Joginder Nagar Sarkaghat Ghumarwin road Km 8/0 to 13/0 (Makreri Section) (Sub Head:- Repair of pot hole (Patch work) in Km. 9/400 to 10/500                                                                                                                                                                                                                                | Rs. 95,238/-                            | Rs. 1,900/-   | Rs. 350/-           | Class "D"                    | Two months |
| 8  | Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Baijnath Padhar road (portion Jatehar to Golwan) Km. 13/0 to 17/0 and (ii) Baijnath Lad Bharol Kandapattan road Km. 15/0 to 20/0 (Pandol section) (Sub Head:- Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work).                                                                                                        | Rs. 74,850/-                            | Rs. 1,500/-   | Rs. 350/-           | Class "D"                    | Two months |
| 9  | Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Sandhapattan Basahi Banwar Kotli road Km. 0/0 to 3/0 & Km. 42/0 to 50/0 (ii) Joginder Nagar Sarkaghat Ghumarwin road Km. 18/0 to 21/0 and (iii) Dhanotu Sajh road Km. 0/0 to 2/0 (Makreri section) (Sub Head:- Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work).                                                       | Rs. 93,563/-                            | Rs. 1,900/-   | Rs. 350/-           | Class "D"                    | Two months |
| 10 | Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Masoli to Banai road Km. 0/0 to 1/0 (ii) Balakrupi Darat Bagla road Km. 1/0 to 5/0 (iii) Link road to PWD rest house Km. 0/0 to 0/500 (iv) Zim-Zima Dul road Km. 0/0 to 1/0 (v) Dul - Galu road Km. 0/0 to 2/0 (Store & Harabag section) (Sub Head:- Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work).                 | Rs. 43,413/-                            | Rs. 900/-     | Rs. 350/-           | Class "D"                    | Two months |
| 11 | Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Chauntra to Chaugan Km. 0/0 to 1/200 (ii) Chauntra to Lower Chauntra Km. 0/0 to 0/800 and (iii) Ahju to Kaffaun road Km. 0/0 to 4/0 (Ladruhin & Chauntra section) (Sub Head:- Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work).                                                                                        | Rs. 67,365/-                            | Rs. 1,300/-   | Rs. 350/-           | Class "D"                    | Two months |
| 12 | Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Joginder Nagar Sarkaghat Ghumarwin road Km. 0/0 to 7/200 (ii) Baijnath Padhar road (portion Bihun to Nohali) Km. 62/0 to 66/0 (iii) Machhial to Har road Km. 0/0 to 1/860 and (iv) Majhamoo Kunduni Kufroo road Km. 2/0 to 6/0 (Local & Bhararu section) (Sub Head:- Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work). | Rs. 82,335/-                            | Rs. 1,600/-   | Rs. 350/-           | Class "D"                    | Two months |
| 13 | Providing and laying patch work under MMSRRY for the year 2025-26 on Joginder Nagar Sarkaghat Ghumarwin road Km 21/0 to 25/0 (Neri Section) (Sub Head:- Repair of pot hole (Patch work) in Km. 21/0 to 22/330).                                                                                                                                                                                                                                 | Rs. 76,940/-                            | Rs. 1,500/-   | Rs. 350/-           | Class "D"                    | Two months |

|    |                                                                                                                                                                                                                                                         |              |             |           |           |            |
|----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|-------------|-----------|-----------|------------|
| 14 | Construction of road from NH-154 to Village Thulan km 0/0 to 1/500 (Sub Head: -Formation Cutting in km 0/930 to 0/998) under BASP Deposit Scheme ID BSP/2024/801                                                                                        | Rs. 98,528/- | Rs. 2,000/- | Rs. 350/- | Class "D" | Two months |
| 15 | A/R & M/O Bhardoun Gangoti road km 0/00 to 6/800 (SH: Scarifying M/T GSB and providing & laying GSB, G-II, G-III and tarring on km 2/577 to 2/607)                                                                                                      | Rs. 97,291/- | Rs. 1,900/- | Rs. 350/- | Class "D" | Two months |
| 16 | Providing and laying patch work under MMSRRY for the year 2025-26 on Joginder Nagar Sarkaghat Ghumarwin road Km 21/0 to 25/0 (Neri Section) (Sub Head:- Repair of pot hole (Patch work) in Km. 23/800 to 25/0).                                         | Rs. 70,551/- | Rs. 1,400/- | Rs. 350/- | Class "D" | Two months |
| 17 | Providing and laying patch work on various road in Joginder Nagar Sub Division HPPWD., Joginder Nagar (under MMSRRY for the year 2025-26 (Sub Head:- Hiring of tractor with trolley for shifting of patch work & other materials to various locations). | Rs. 98,800/- | Rs. 2,000/- | Rs. 350/- | Class "D" | Two months |

Certified that tender of above works are being called of emergent nature in exigency of public interest

**Terms and conditions:-**

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,  
B&R Division HP PWD.,  
Joginder Nagar.  
District Mandi (HP) for on behalf of  
Governor of Himachal Pradesh  
Ph. 01908-222033

No. PW-JND-B&R-EA-VNIT/Press/2025-26-

4056-4105

Dated:-

02-06-2025

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Notice Board.
9. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,  
B&R Division HP PWD.,  
Joginder Nagar.

Job-1

55

## DNIT/DRAFT SCHEDULE OF QUANTITY

| Name of Work: Construction of road from NH-154 to village Thulan km.0/0to 1/500.(Sh:-Formation cutting in km.0/840 to 0/915) under BASP deposit scheme ID BSP/2024/24 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                |                    | Estimate Cost:<br>Earnest Money:<br>Time Limit : |  |                                                                    | Amount    |   |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|--------------------|--------------------------------------------------|--|--------------------------------------------------------------------|-----------|---|
| Sr.<br>No.                                                                                                                                                            | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | No. or<br>Qty. | Unit               | Rate                                             |  | Words                                                              | Rs.       | P |
|                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                |                    | Figures                                          |  |                                                                    |           |   |
| 1                                                                                                                                                                     | Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock ( where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 23.07cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST. | 461.42         | Per cubic<br>metre | 213.67                                           |  | Rupees Two<br>Hundred<br>Thirteen And<br>Paise Sixty<br>Seven Only | 98,592.00 |   |
| Total                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |                |                    |                                                  |  |                                                                    | 98,592.00 |   |

DNIT No - 55  
E-111-38  
Executive Engineer  
B & R Division HP.PWD,  
Joginder Nagar

Job 2

## SCHEDULE OF QUANTITY

| Name of Work : A/R & M/O Bhardon Gangoti road km. 0/0 to 6/800 (SH: Scarifying M/T GSB and providing & laying GSB, G-II, G-III and tarring on km. 3/407 to 3/437) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |             |                  | Estimate Cost: 97,291.00 -<br>Earnest Money: 1900.00 -<br>Time Limit : Two One Month |       |                 |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|------------------|--------------------------------------------------------------------------------------|-------|-----------------|
| Sr. No.                                                                                                                                                           | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | No. or Qty. | Unit             | Rate                                                                                 |       | AMOUNT<br>Rs. P |
|                                                                                                                                                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |             |                  | Figures                                                                              | Words |                 |
| 1                                                                                                                                                                 | Scarifying existing bituminous surfaces to a depth of 150 mm(One hundred fifty millimeters) by mechanical means.Scarifying the existing bituminous road surface to a depth of 150mm and disposal of scarified materials within all leads and lifts as HPPWD specification clause 301.4 and other incidental charges.The rate is inclusive all taxes levy by the government time to time excluding GST.                                                                                                                                                                                                                                                                                                     | 90.00       | Per square metre |                                                                                      |       |                 |
| 2                                                                                                                                                                 | Providing compacting original ground supporting subgrade by loosening of ground upto a level of 300mm (Thirty millimeters) below the subgrade level, watered graded and compacting in layers to meet requirement of table 300.1 and 300.2 (three hundred point one and three hundred point two) for subgrade construction as per technical specification clause 300.5.2. complete within all leads, lifts, carriage of material and other incidentals charges.The rate is inclusive all taxes levy by the government time to time excluding GST.                                                                                                                                                           | 99.00       | Per square metre |                                                                                      |       |                 |
| 3                                                                                                                                                                 | Providing & Laying, granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with retavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification clause as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges.The rate is inclusive all taxes levy by the government time to time excluding GST.                                                                                                                                                          | 12.38       | Per Cubic metre  |                                                                                      |       |                 |
| 4                                                                                                                                                                 | Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges.The rate is inclusive all taxes levy by the government time to time excluding GST.   | 7.09        | Per cubic metre  |                                                                                      |       |                 |
| 5                                                                                                                                                                 | Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-3 (three) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges.The rate is inclusive all taxes levy by the government time to time excluding GST. | 6.75        | Per cubic metre  |                                                                                      |       |                 |

70

|              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |                  |  |  |  |
|--------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------------------|--|--|--|
| 6            | Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.00 Kg/sqm using mechanical means as per technical specification complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | 90.00 | Per square metre |  |  |  |
| 7            | Providing and applying tack coat with bituminous emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30kg/sqm (0.275kg/sqm) on the prepared bituminous surface cleaned with Hydraulic broom as per technical specification complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 90.00 | Per square metre |  |  |  |
| 8            | Providing, laying and rolling by mechanical means bitumen (VG-10) of open graded premix carpet of 20mm (twenty millimetre) thickness composed of 13.2mm to 5.6mm (thirteen point two millimetre to five point six millimetre) aggregates either using penetration grade bitumen at the rate of 1.46 (one point four six ) kilograme per square metre to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in suitable plant, laying and rolling with a three wheel 80-100 kN (eighty-hundred kilo newton) static roller capacity, finished to required level and grades to be followed by seal coat of Type-B as per technical specification Clause 508 including all corrective measures such as patching pot holes, sealing of cracks including all profile correction for all depths and hauling of material with in all leads and lifts by all modes of transportation. The rate is inclusive all taxes levy by the government time to time excluding GST. | 90.00 | Per square metre |  |  |  |
| 9            | Providing and laying seal coat Type-B by mechanical means sealing the voids in a bituminous surface laid to the specified levels, grade and crossfall using Bitumen (VG-10) at the rate of 0.68 (zero point six eight) kilograme per square metre as per technical specification Clause 510 including hauling of material with in all leads and lifts by all modes of transportation. The rate is inclusive all taxes levy by the government time to time excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 90.00 | Per square metre |  |  |  |
| <b>Total</b> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |                  |  |  |  |

  
 Executive Engineer  
 B & R Division HP.PWD,  
 Joginder Nagar

Job - 3

### Schedule of Quantity

Estimated Cost:- 80090.00  
Earnest Money:- 1500 00  
Time:- Two Months

**Name of work:-** Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Gadiyara to Thara Raktal road Km. 3/0 to 7/0 and (ii) Gadiyara to Thara road Km. 0/0 to 3/0 (Neri section)

**Sub Head:-** Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work.


| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qty.  | Rate      |                | Unit            | Amount |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----------|----------------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       | In Figure | In Words       |                 |        |
| 1       | Supplying and stacking of Crushed/broken stone aggregate chipping 10mm to 12.5mm (ten millimeter to twelve point five millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time. | 28.89 |           |                | Per cubic metre |        |
| 2       | Supply and stacking of clean coarse sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stacks at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time.                                                                                                      | 6.42  |           |                | Per cubic metre |        |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |           | <b>Total:-</b> |                 |        |

  
Executive Engineer,  
B&R Division HP PWD,  
Joginder Nagar.

Job 4

## SCHEDULE OF QUANTITY

| Name of Work : Providing and laying patch work under MMSRRY for the year 2025-26 on Joginder Nagar Sarkaghat<br>Ghumarwin road Km 8/0 to 13/0 (Sub Head:- Repair of pot hole (Patch work) in Km. 8/0 to 9/250). |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                |                  |      | Estimate Cost:<br>Earnest Money:<br>Time Limit : |       | 69,209.00<br>1,400.00<br>Two Months |   |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|------------------|------|--------------------------------------------------|-------|-------------------------------------|---|
| Sr.<br>No.                                                                                                                                                                                                      | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | No. or<br>Qty. | Unit             | Rate | AMOUNT                                           |       | Rs.                                 | P |
|                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                |                  |      | Figures                                          | Words |                                     |   |
| 1                                                                                                                                                                                                               | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 0.30 kg (zero point three kilogramme) per Sqm, 20 mm thick pre-mix carpet with Bitumen VG-10 @ 1.40 kg (One point four six kilogramme) per Sqm and seal coat type B with bitumen VG-10 @ 0.68 kg (zero point six eight kilogramme) per Sqm as per technical specification clause 1904.2, 503 and 508.1. The rate including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST. | 220.34         | Per Square metre |      |                                                  |       |                                     |   |
| Total                                                                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                |                  |      |                                                  |       |                                     |   |

  
 Executive Engineer  
 B & R Division HP, PWD,  
 Joginder Nagar

### Schedule of Quantity

Estimated Cost:- 71108 00  
 Earnest Money:- 1400 00  
 Time:- Two Months

**Name of work:-** Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Sandha Pattan Bharol Basahi Banwar Kotli road Km 0/0 to 3/0 & Km. 7/0 to 9/0. (ii) Pihar Bedhlu road Km. 1/0 to 1/500. and (iii) Suin Bhararpat up to vill. Bhardoan road Km. 0/0 to 2/0. (Lad Bharol section)

**Sub Head:-** Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work.

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qty.  | Rate      |          | Unit            | Amount |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----------|----------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       | In Figure | In Words |                 |        |
| 1       | Supplying and stacking of Crushed/broken stone aggregate chipping 10mm to 12.5mm (ten millimeter to twelve point five millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time. | 25.65 |           |          | Per cubic metre |        |
| 2       | Supply and stacking of clean coarse sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stacks at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time                                                                                                       | 5.70  |           |          | Per cubic metre |        |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |           |          |                 |        |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |           | Total:-  |                 |        |

  
 Executive Engineer,  
 B&R Division HP PWD,  
 Jodhpur Nagar

# Job-6 Schedule of Quantity

Estimated Cost:- 99188.00  
 Earnest Money:- 2000.00  
 Time:- Two Months

**Name of work:-** Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Baijnath Lad Bharol Kandapatian road Km. 26/0 to 30/0 (ii) Bharan Kanharag Fagla road Km. 1/0 to 2/500. and (iii) Gagal Bhaheger road Km. 0/0 to 1/0 & Km 3/0 to 6/0. (Tullah section)

**Sub Head:-** Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work.

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qty.  | Rate      |          | Unit            | Amount |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----------|----------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       | In Figure | In Words |                 |        |
| 1       | Supplying and stacking of Crushed/broken stone aggregate chipping 10mm to 12.5mm (ten millimeter to twelve point five millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time. | 35.78 |           |          | Per cubic metre |        |
| 2       | Supply and stacking of clean coarse sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stacks at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time.                                                                                                      | 7.95  |           |          | Per cubic metre |        |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |           | Total:-  |                 |        |

  
 Executive Engineer,  
 B&P Division HP PWD.,  
 Joginder Nagar.

Job - 7

# SCHEDULE OF QUANTITY

| Name of Work : Providing and laying patch work under MMSRRY for the year 2025-26 on Joginder Nagar Sarkaghat Chumarwin road Km 8/0 to 13/0 (Sub Head:- Repair of pot hole (Patch work) in Km. 9/400 to 10/500) (Malesari Scheme) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                |                  | Estimate Cost:<br>Earnest Money:<br>Time Limit : |       | 95,238.00<br>1,900.00<br>Two Months |   |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|------------------|--------------------------------------------------|-------|-------------------------------------|---|
| Sr.<br>No.                                                                                                                                                                                                                       | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | No. or<br>Qty. | Unit             | Rate                                             |       | AMOUNT                              |   |
|                                                                                                                                                                                                                                  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                |                  | Figures                                          | Words | Rs.                                 | P |
| 1                                                                                                                                                                                                                                | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 0.30 kg (zero point three kilogramme) per Sqm, 20 mm thick pre-mix carpet with Bitumen VG-10 @ 1.46 kg (One point four six kilogramme) per Sqm and seal coat type B with bitumen VG-10 @ 0.68 kg (zero point six eight kilogramme) per Sqm as per technical specification clause 1904.2, 503 and 508.1. The rate including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST. | 303.21         | Per Square metre |                                                  |       |                                     |   |
| Total                                                                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                |                  |                                                  |       |                                     |   |

  
 Executive Engineer  
 B & R Division HP PWD.  
 Joginder Nagar

Job-8

### Schedule of Quantity

Estimated Cost:- 74850 00  
Earnest Money:- 1500 00  
Time:- Two Months

Name of work:- Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Baijnath Padhar road (portion Jatehar to Golwan) Km 13/0 to 17/0 and (ii) Baijnath Lad Bharol Kandapattan road Km. 15/0 to 20/0 (Pandol section)

Sub Head:- Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work.

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qty.  | Rate      |          | Unit            | Amount |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----------|----------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       | In Figure | In Words |                 |        |
| 1       | Supplying and stacking of Crushed/broken stone aggregate chipping 10mm to 12.5mm (ten millimeter to twelve point five millimeter) nominal size free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time. | 27.00 |           |          | Per cubic metre |        |
| 2       | Supply and stacking of clean coarse sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stacks at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time.                                                                                                      | 6.00  |           |          | Per cubic metre |        |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |           |          |                 |        |

  
Executive Engineer  
B&R Division HP PWD  
Jaginder Nagar

Job-9

## Schedule of Quantity

Estimated Cost:- 93563.00

Earnest Money:- 1900.00

Time:- Two Months

Name of work:- Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Sandha Pattan Lad Bharol Basahi Banwar Kotli road Km. 42/0 to 50/0. (ii) Joginder Nagar Sarkaghat Ghumarwin road Km. 18/0 to 21/0 and (iii) Dhanotu Sajh road Km. 0/0 to 2/0. (MAKREI SECTION)

Sub Head:- Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work.

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qty.  | Rate      |          | Unit            | Amount |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----------|----------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       | In Figure | In Words |                 |        |
| 1       | Supplying and stacking of Crushed/broken stone aggregate chipping 10mm to 12.5mm (ten millimeter to twelve point five millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time. | 33.75 |           |          | Per cubic metre |        |
| 2       | Supply and stacking of clean coarse sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stacks at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time.                                                                                                      | 7.50  |           |          | Per cubic metre |        |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |           | Total:-  |                 |        |

Executive Engineer,  
B&R Division HP PWD,  
Joginder Nagar.

Job - 10

Schedule of Quantity

Estimated Cost:- 43413 00  
Earnest Money:- 900 00  
Time:- Two Months

Name of work:- Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Masoli to Banal road Km. 0/0 to 1/0. (ii) Balakrupi Darat Bagla road Km. 1/0 to 5/0 (iii) Link road to PWD rest House Km. 0/0 to 0/500. (iv) Zim- Zima Dul road Km. 0/0 to 1/0 ( v) Dul-Galu road Km. 0/0 to 2/0. (Store & Hara Bag section)

Sub Head:- Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work.

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Qty.  | Rate      |          | Unit            | Amount |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----------|----------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       | In Figure | In Words |                 |        |
| 1       | Supplying and stacking of Crushed/broken stone aggregate chipping 10mm to 12.5mm (ten millimeter to twelve point five millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time. | 15.66 |           |          | Per cubic metre |        |
| 2       | Supply and stacking of clean coarse sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stacks at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt. time to time                                                                                                       | 3.48  |           |          | Per cubic metre |        |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |       |           | Total:-  |                 |        |

  
Executive Engineer,  
B&R Division HP PWD,  
Joginder Nagar.

Job - 11

### Schedule of Quantity

Estimated Cost:- 67365.00

Earnest Money:- 1300.00

Time:- Two Months

**Name of work:-** Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Chauntra to Chaugan Km. 0/0 to 1/200 (ii) Chauntra to Lower Chauntra Km. 0/0 to 0/800. (iii) Ahju to Kallaun road Km. 0/0 to 4/0. *(Ladakhim & Chauran Section)*

**Sub Head:-** Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work.

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Qty.  | Rate      |                | Unit            | Amount |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----------|----------------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       | In Figure | In Words       |                 |        |
| 1       | Supplying and stacking of Crushed/broken stone aggregate chipping 10mm to 12.5mm (ten millimeter to twelve point five millimeter) nominal size free form dirt, dust, disintegrated pieces, deleterious and organic matter in proper stack at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive of all taxes including GST levy by the Govt. time to time. | 24.30 |           |                | Per cubic metre |        |
| 2       | Supply and stacking of clean coarse sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stacks at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect The rate is inclusive of all taxes including GST levy by the Govt. time to time.                                                                                                      | 5.40  |           |                | Per cubic metre |        |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |           | <b>Total:-</b> |                 |        |

*[Signature]*  
Executive Engineer.  
B&R Division HP PWD.  
Joginder Nagar

Job-12

### Schedule of Quantity

Estimated Cost:- 82335 00  
Earnest Money:- 1600 00  
Time:- Two Months

**Name of work:-** Providing and laying patch work under MMSRRY for the year 2025-26 on (i) Joginder Nagar Sarkaghat Ghumarwin road Km 0/0 to 7/200 (ii) Baijnath Padhar road (portion Bihun to Nohali) Km. 62/0 to 66/0 (iii) Machhyal to Har road Km. 0/0 to 1/860 and (iv) Majharnoo Kunduni Kufroo road Km 2/0 to 6/0 (Local & Bhararu section)

**Sub Head:-** Supplying and stacking of crushed/broken stone aggregate 10mm to 12.5mm and sand for patch work.

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                             | Qty.  | Rate      |          | Unit            | Amount |
|---------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----------|----------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |       | In Figure | In Words |                 |        |
| 1       | Supplying and stacking of Crushed/broken stone aggregate chipping 10mm to 12.5mm (ten millimeter to twelve point five millimeter) nominal size free form dirt, dust, disintegrated pieces deleterious and organic matter in proper stack at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt time to time. | 29.70 |           |          | Per cubic metre |        |
| 2       | Supply and stacking of clean coarse sand free from dirt, dust, disintegrated pieces, deleterious and organic matter in proper stacks at site of work as per PWD specification and as directed by the Engineer-In-Charge including carriage of material with in all leads and lifts complete in all respect. The rate is inclusive of all taxes including GST levy by the Govt time to time.                                                                                                     | 6.60  |           |          | Per cubic metre |        |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |       |           |          |                 |        |

Executive Engineer  
B&R Division HP PWD  
Joginder Nagar

# SCHEDULE OF QUANTITY

| Name of Work : Providing and laying patch work under MMSRRY for the year 2025-26 on Joginder Nagar Sarkaghat Ghumarwin road Km 21/0 to 25/0 (Sub Head:- Repair of pot hole (Patch work) in Km. 21/0 to 22/330). (Non SCCM) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |             |                  | Estimate Cost:<br>Earnest Money:<br>Time Limit : |       | 76,940.00<br>1,500.00<br>Two Months |   |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|------------------|--------------------------------------------------|-------|-------------------------------------|---|
| Sr. No.                                                                                                                                                                                                                    | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | No. or Qty. | Unit             | Rate                                             |       | AMOUNT                              |   |
|                                                                                                                                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |             |                  | Figures                                          | Words | Rs.                                 | P |
| 1                                                                                                                                                                                                                          | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 0.30 kg (zero point three kilogramme) per Sqm, 20 mm thick pre-mix carpet with Bitumen VG-10 @ 1.46 kg (One point four six kilogramme) per Sqm and seal coat type B with bitumen VG-10 @ 0.68 kg (zero point six eight kilogramme) per Sqm as per technical specification clause 1904.2, 503 and 508.1. The rate including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST. | 246.76      | Per Square metre |                                                  |       |                                     |   |
| Total                                                                                                                                                                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |             |                  |                                                  |       |                                     |   |

Executive Engineer  
B & R Division HP.PWD.  
Joginder Nagar

Job-14

## SCHEDULE OF QUANTITY

| Name of Work: Construction of road from NH-154 to village Thulan km.0/0 to 1/500.(Sh:-Formation cutting in km.0/930 to 0/998) under BASP deposit scheme ID BSP/2024/8c/ |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |             |                 | Estimate Cost: 98528 -<br>Earnest Money: 2000 -<br>Time Limit : 000 Month |       |                 |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|-----------------|---------------------------------------------------------------------------|-------|-----------------|
| Sr. No.                                                                                                                                                                 | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | No. or Qty. | Unit            | Rate                                                                      |       | AMOUNT<br>Rs. P |
|                                                                                                                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |             |                 | Figures                                                                   | Words |                 |
| 1                                                                                                                                                                       | Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock ( where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transportation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 23.06cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST. | 461.12      | Per cubic metre |                                                                           |       |                 |
| Total                                                                                                                                                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |             |                 |                                                                           |       |                 |

  
Executive Engineer  
B & R Division HP.P.W.D.,  
Joginder Nagar

# SCHEDULE OF QUANTITY

| Name of Work : A/R & M/O Bhardon Gangoti road km. 0/0 to 6/800 (SH: Scarifying M/T GSB and providing & laying GSB, G-II, G-III and tarring on km. 2/577 to 2/607) |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |             |                  |         | Estimate Cost: 97,291.00<br>Earnest Money: 1900.00<br>Time Limit : One Month |                 |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|------------------|---------|------------------------------------------------------------------------------|-----------------|
| Sr. No.                                                                                                                                                           | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | No. or Qty. | Unit             | Rate    |                                                                              | AMOUNT<br>Rs. P |
|                                                                                                                                                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |             |                  | Figures | Words                                                                        |                 |
| 1                                                                                                                                                                 | Scarifying existing bituminous surfaces to a depth of 150 mm(One hundred fifty millimeters) by mechanical means.Scarifying the existing bituminous road surface to a depth of 150mm and disposal of scarified materials within all leads and lifts as HPPWD specification clause 301.4 and other incidental charges.The rate is inclusive all taxes levy by the government time to time excluding GST.                                                                                                                                                                                                                                                                                                     | 90.00       | Per square metre |         |                                                                              |                 |
| 2                                                                                                                                                                 | Providing compacting original ground supporting subgrade by loosening of ground upto a level of 300mm (Thirty millimeters) below the subgrade level, watered graded and compacting in layers to meet requirement of table 300.1 and 300.2 (three hundred point one and three hundred point two) for subgrade construction as per technical specification clause 300.5.2. complete within all leads, lifts, carriage of material and other incidentals charges.The rate is inclusive all taxes levy by the government time to time excluding GST.                                                                                                                                                           | 99.00       | Per square metre |         |                                                                              |                 |
| 3                                                                                                                                                                 | Providing & Laying, granular sub-base by providing well graded material, spreading in uniform layers with Tractor mount grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification clause as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges.The rate is inclusive all taxes levy by the government time to time excluding GST.                                                                                                                                                          | 12.38       | Per Cubic metre  |         |                                                                              |                 |
| 4                                                                                                                                                                 | Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-2 (two) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges.The rate is inclusive all taxes levy by the government time to time excluding GST.   | 7.09        | Per cubic metre  |         |                                                                              |                 |
| 5                                                                                                                                                                 | Providing, laying, spreading and compacting stone aggregates by manual means of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN (eighty-hundred kilo newton) static roller in stages to proper grade and camber applying and brooming, stone screening/ binding materials to fillup the interstices of course aggregate watering and compacting to the required density Grading-3 (three) as per technical specification clause 405 complete within all leads, lifts, carriage of material and other incidentals charges.The rate is inclusive all taxes levy by the government time to time excluding GST. | 6.75        | Per cubic metre  |         |                                                                              |                 |

88

|              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |       |                  |  |  |  |
|--------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|------------------|--|--|--|
| 6            | Providing and applying primer coat with bitumen emulsion (SS-I) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.00 Kg/sqm using mechanical means as per technical specification complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 90.00 | Per square metre |  |  |  |
| 7            | Providing and applying tack coat with bituminous emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30kg/sqm (0.275kg/sqm) on the prepared bituminous surface cleaned with Hydraulic broom as per technical specification complete within all leads, lifts, carriage of material and other incidentals charges. The rate is inclusive all taxes levy by the government time to time excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 90.00 | Per square metre |  |  |  |
| 8            | Providing, laying and rolling by mechanical means bitumen (VG-10) of open graded premix carpet of 20mm (twenty millimetre) thickness composed of 13.2mm to 5.6mm (thirteen point two millimetre to five point six millimetre) aggregates either using penetration grade bitumen at the rate of 1.46 (one point four six ) kilogramme per square metre to required line, grade and level to serve as wearing course on a previously prepared base, including mixing in suitable plant, laying and rolling with a three wheel 80-100 kN (eighty-hundred kilo newton) static roller capacity, finished to required level and grades to be followed by seal coat of Type-B as per technical specification Clause 508 including all corrective measures such as patching pot holes, sealing of cracks including all profile correction for all depths and hauling of material with in all leads and lifts by all modes of transportation. The rate is inclusive all taxes levy by the government time to time excluding GST. | 90.00 | Per square metre |  |  |  |
| 9            | Providing and laying seal coat Type-B by mechanical means sealing the voids in a bituminous surface laid to the specified levels, grade and crossfall using Bitumen (VG-10) at the rate of 0.68 (zero point six eight) kilogramme per square metre as per technical specification Clause 510 including hauling of material with in all leads and lifts by all modes of transportation. The rate is inclusive all taxes levy by the government time to time excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 90.00 | Per square metre |  |  |  |
| <b>Total</b> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |       |                  |  |  |  |

  
 Executive Engineer  
 B & R Division HP.PWD,  
 Joginder Nagar

Job -/6

# SCHEDULE OF QUANTITY

| Name of Work : Providing and laying patch work under MMSRRY for the year 2025-26 on Joginder Nagar Sarkaghat Ghumarwin road Km 21/0 to 25/0 (Sub Head:- Repair of pot hole (Patch work) in Km. 23/800 to 25/0). |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |             |                  | Estimate Cost:<br>Earnest Money:<br>Time Limit : |       | 70,551.00<br>1,400.00<br>Two Months |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|------------------|--------------------------------------------------|-------|-------------------------------------|
| Sr. No.                                                                                                                                                                                                         | Description of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | No. or Qty. | Unit             | Rate                                             |       | AMOUNT<br>Rs. P                     |
|                                                                                                                                                                                                                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |             |                  | Figures                                          | Words |                                     |
| 1                                                                                                                                                                                                               | Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat with bitumen VG-10 @ 0.50 kg (zero point three kilogramme) per Sqm. 20 mm thick pre-mix carpet with Bitumen VG-10 @ 1.46 kg (One point four six kilogramme) per Sqm. and seal coat type B with bitumen VG-10 @ 0.68 kg (zero point six eight kilogramme) per Sqm as per technical specification clause 1904.2, 503 and 508.1. The rate including hauling carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate is inclusive all taxes levy by the government time to time excluding GST. | 226.27      | Per Square metre |                                                  |       |                                     |
| Total                                                                                                                                                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              |             |                  |                                                  |       |                                     |

  
Executive Engineer  
B & R Division HP PWD  
Joginder Nagar

Job -17

## Schedule of Quantity

Estimated Cost:- 98800 00  
 Earnest Money:- 2000 00  
 Time:- Two months

**Name of work:-** Providing and laying Patch work on various road in Joginder Nagar Sub Division, HPPWD Joginder Nagar under MMSRRY for the year 2025-26  
**Sub Head:-** Hiring of Tractor with trolley for shifting of patch work & other materials to various locations.

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Qty.  | Rate      |          | Unit            | Amount |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----------|----------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       | In Figure | In Words |                 |        |
| 1       | Hiring of tractor with trolley in working condition per day basis (Eight working hour per day) with including sunday/holiday for carriage of patch work material etc. The operational, maintenance and P.O.L. charges and other miscellaneous supply/replacement required for smooth running of vehicle will be born by the owner of the tractor with in all leads and lifts to the entire satisfaction of Engineer-in-Charge. The payment will be made on the submission of the copy of Log Book duly signed/checked by the concerned Engineer-in-Charge. The rate is inclusive of all taxes including GST levy by the Govt time to time. | 38.00 |           |          | Per working day |        |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |       |           |          |                 |        |

  
 Executive Engineer,  
 B&R Sub Division,  
 HP PWD Joginder Nagar.