Office of
Executive Engineer B&R Division HP.PWD. Joginder Nagar
Himachal Pradesh Public Works Department, Mandi-175015
Phone & Fax No. 01908-222033 E-Mail:- ee-jog-hp@nic.in

"NOTICE INVITING TENDER"

Sealed item rate tender for the following works are hereby invited by the Executive Engineer, B&R Division HP.PWD., Joginder Nagar District Mandi (H.P) from the eligible contractors of the appropriate class registered in HP.PWD. as per revised enlistment rules so as to reach in the office of under signed on 27.06.2025 up to 11:30 A.M. and will be opened on the same day at (12:00 noon) in the presence of intending contractors. The tender application will be received in this office on 25.06.2025 up to 10.00 A.M. to 12:00 P.M. and tender form can be had from this office on 26.06.2025 from 2.00 P.M. to 5.00 Pm. The earnest money as shown against each in the shape of F.D.R of any bank in Himachal Pradesh duly pledged in the name of the under signed must accompany with each tender. The tender form will be issued to contractor giving proof of enlistment, GST. Conditional tender and tender received without earnest money will be out rightly rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all the tenders without assigning any reasons.

The draft NIT and other specifications and conditions of the tender can be seen by the contractors in the office of the under signed on any working day during the office hours.

	Name of work	Amount put to tender/ Estimated cost	Earnest Money	Cost of tender form	Eligible Class of Contractor	Time
1	Construction & M/T of link road from Galu Bhatwar to Village Badan & Chhanang Dhar km 0/0 to 3/0 in GP Ropa Padha (Sub Head: - Formation cutting in km 0/810 to 0/857). Under Deposit SID:BSP/2024/803	Rs. 99,336/-	Rs. 2,000/-	Rs. 350/	Class "D"	Two months
2	Construction of Retaining wall at Bagdena road near house of Amar singh Khadihar GP Khadiar km. 0/0 to 0/700 (Sub Head : Filling Behind Retaining wall at km 0/585 to 0/604.50). under deposit SID:SDP/2021/160	Rs. 53,322/-	Rs. 1,100/-	Rs. 350/	Class "D"	Two months
3	Construction of link road upper Gharoun Mohal km 0/0 to 1/500. (Sub Head: -Formation Cutting in km 0/125 to 0/167) under BASP Deposit SID ; BSP/2024/647).	Rs. 81,090/-	Rs. 1,600/-	Rs. 350/	Class "D"	Two months
4	Construction & M/T of link road from Galu Bhatwar to Village Badan & Chhanang Dhar km 0/0 to 3/0 in GP Ropa Padha (Sub Head: - Formation cutting in km 1/195 to 1/258). Under Deposit SID:BSP/2024/803	Rs. 99,123/-	Rs. 2,000/-	Rs. 350/	Class "D"	Two months
5	Construction of link road Upper Bhatwar to Khai Mohal km 0/0 to 1/500 (Sub Head: - Formation Cutting from km 0/112 to 0/146. under BASP Deposit SID ; BSP/2024/648).	Rs. 82,816/-	Rs. 1,600/-	Rs. 350/	Class "D"	Two months

Certified that tender of above works are being called of emergent nature in exigency of public interest

Terms and conditions:-

1. The contractor should produce a copy of enlistment / renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor/Firm shall have his registration and GST No, the copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer B&R Division HPPWD., Joginder Nagar & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. No tender form will be issued to the contractor without producing the work done certificate from the Executive Engineer concerned.
6. The contractor/firms are requested to insert the rate of each item in words as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reason at any stage.
7. The tender shall be issued to those contractors who have not more than two works in hand.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.
District Mandi (HP) for on behalf of
Governor of Himachal Pradesh
Ph. 01908-222033

No. PW-JND-B&R-EA-I/NIT/Press/2025-26- 3652-3701 Dated:- 27/05/2025

1. Copy to the F.C. Cum Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (MZ), HPPWD, Mandi.
4. The Superintending Engineer, Joginder Nagar Circle HPPWD, Joginder Nagar.
5. All the Assistant Engineer working under this Division.
6. All the Contractor working under this Division.
7. Drawing Branch in this office.
8. Account Branch in this office.
9. Notice Board.
10. The Computer Cell office of the Engineer-in-Chief, HPPWD, Shimla for uploading the NIT on the Departmental website.

Executive Engineer,
B&R Division HP PWD.,
Joginder Nagar.

Job-1

SCHEDULE OF QUANTITY

Name of Work:Construction & M/T of link road from Galu Bhatwari road to Village Badan & Chhanang Dhar km.0/0 to 3/0 in GP Ropa Padhar.(Sh:-Formation cutting in km.0/810 to 0/857) under deposit SID:BSP/2024/803

Estimate Cost: 99,336.00
Earnest Money: 2,000.00
Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of 31.09cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	432.46	Per cubic metre			
	Total					

Executive Engineer
B & R Division HP.PWD,
Jogindder Nagar

Job - 2

SCHEDULE OF QUANTITY

Name of Work : Construction of retaining wall at Bagdena road near house of Amar Singh Khadihar GP Khadiar km. 0/0 to 0/700 (SH :- Filling behind retaining wall at km. 0/585 to 0/604.50 under deposit SID:SDP/2021/160)						Estimate Cost: 53,322.00 Earnest Money: 1,100.00 Time Limit : Two Months
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Filling earth in foundation trenches, behind retaining/ breast wall with marshy soil as per drawing and technical specification clause 305.3.9. complete within all leads, lifts, carriage of material and other incidentials. The rate is inclusive all taxes levy by the government time to time excluding GST.	160.68	Per cubic metre			
	Total					

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job - 3

SCHEDULE OF QUANTITY

Name of Work:Construction of link road upper Gharoun Mohal km.0/0 to 1/500 (Sub Head:-Formation cutting from km. 0/125 to 0/167 under BASP Deposit SID: BSP/2024/647)				Estimate Cost: 81,090.00 Earnest Money: 1,600.00 Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of ~~26.87~~ 72.77 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	369.60	Per cubic metre			
	Total					

Executive Engineer
B & R Division HP.PWD,
Joginder Nagar

Job-4

SCHEDULE OF QUANTITY

Name of Work:Construction & M/T of link road from Galu Bhatwari road to Village Badan & Chhanang Dhar km.0/0 to 3/0 in GP Ropa Padhar.(Sh:-Formation cutting in km.1/195 to 1/258) under deposit SID:BSP/2024/803				Estimate Cost: 99,123.00 Earnest Money: 2,000.00 Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of ~~37.99~~ 38.19 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	401.96	Per cubic metre			
	Total					

Executive Engineer
B & R Division HP.PWD,
Jogindder Nagar

Job - 5

SCHEDULE OF QUANTITY

Name of Work:Construction of link road upper Bhatwar to Kahi Mohal km.0/0 to 1/500 (Sub Head:-Formation cutting from km. 0/112 to 0/146 under BASP Deposit SID: BSP/2024/648)				Estimate Cost: 81,370.00 Earnest Money: 1,600.00 Time Limit : Two Months		
Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT
				Figures	Words	Rs. P
1	Excavation in soil in hilly area in all heights and depths and in all kind of soil by all means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 1000 & 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material at approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for usefull stone of ~~34.74~~ 94.39 cum @ 300/- per cum shall be effected from the contractor bill on pro-rata basis for the quality of cutting in earth work executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him at his own cost. The rate is inclusive all taxes levy by the government time to time excluding GST.	347.44	Per cubic metre			
	Total					

Executive Engineer
B & R Division HP.PWD,
Jogindar Nagar