

Himachal Pradesh  
Public Works Department

No. PW-SD-I-CTR- Tender-NIT/2024-2025- 4958-59 Dated:- 26/6/25

To


The Executive Engineer (IT Cell)  
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.

  
Executive Engineer,  
Shimla Division No-1.,  
HPPWD, Shimla-3.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4<sup>th</sup> Circle HPPWD Shimla .

  
Executive Engineer,  
Shimla Division No-1.,  
HPPWD, Shimla-3.

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDERS**

Executive Engineer B&R Division No-I HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

- |  |                                   |
|--|-----------------------------------|
| 1. Date of receipt of application for tender forms:- | 05-07-2025 10:00 AM upto 12:00 PM |
| 2. Dated of Issue /sale of tender forms:-            | 05-07-2025 12:00 PM upto 4:00 PM  |
| 3. Date of receipt of tender:-                       | 07-07-2025 upto 10:30 AM          |
| 4. Date of opening of tender:-                       | 07-07-2025 upto 11:00 AM          |

Sr. No.	Name of Work	Estimated cost	EMD(Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	A/R & M/O various Residential Building at 1 to VI qtrs at Mehli Shimla (SH:- Providing and fixing kitchen accessories curtain rod, and main hole set No.9 type-VI at mehli Shimla (Balance work).	96032/-	1900/-	350/-	30 days	Class-D
2	A/R & M/O to various Type-I to Type-VI Qtrs of Gad at kasumpti Shimla-9 (SH:- Providing and Fixing cupboard in type-III set no.136 under kasumpti Shimla).	96973/-	1900/-	350/-	30 days	Class-D
3	Improvement of Charabra to Kalyani Helipad road in km. 0/00 to 1/200 (SH:- Maintenance of drain, Trimming of grass, white washing etc in km. 0/00 to 1/200 and Terminal building at kalyani Helipad).	65180/-	1300/-	350/-	30 Days	Class-D
4	Improvement of sadhora to Mohanpur road km. 0/00 to 6/525 (SH:- Maintenance of drain Bush Cutting, White washing & Earthen shoulder in km. 0/00 to 4/500).	99885/-	2000/-	350/-	30 Days	Class-D
5	Improvement of Mashobra to Ramnagari road km. 0/00 to 5/300 (SH:- Maintenance of drain, Bush cutting, White washing in km. 0/000 to 5/300).	99746/-	2000/-	350/-	30 days	Class-D
6	A/R & M/O Kasumpti to Basant Vihar road km. 0/00 to 0/550 (SH:- C/O B/wall between at Rd. 0/313 to 0/315.50 under Parimahal section).	97663/-	1900/-	350/-	30 days	30 Days
7	Providing Staff for maintenance of Shoghi Mehli Junga road in km. 12/375 to 48/925 under junga section for the year 2025-2026 w.e.f.01-07-2025 to 31-07-2025)	99688/-	2000/-	350/-	30 days	30 Days
8	Providing Staff for maintenance of old kasumpti junga road , Rajhana Savi road Rajhana Badagaon road and RajahanBird colony road under junga section for the year 2025-2026 w.e.f.01-07-2025 to 31-07-2025).	99688/-	2000/-	350/-	30 Days	Class-D
9	Improvement of Shimla to Mandi road in km. 6/00 to 22/00 (SH:- Maintenance of Earthen shoulder of drain ,Trimming of grass between Rd. 15/00 to 18/00).	99446/-	2000/-	350/-	30 Days	Class-D
10	Improvement of Shimla to Mandi road in km. 6/00 to 22/00 (SH:- Maintenance of Earthen shoulder of drain ,Trimming of grass between Rd. 18/00 to 22/00).	99860/-	2000/-	350/-	30 Days	Class-D
11	Preparation of Detailed project Report of Construction of kemu ka Khet to Kinkuti road km. 0/00 to 2/315 under junga sub Division in Distt. Shimla (HP).	99025/-	2000/-	350/-	30 Days	Class-D
12	Restoation of Rain Damages on Various roads under janedghat section (SH:- Hiring of Excator cum loader for removal of salips in various RDs).	99750/-	2000/-	350/-	30 Days	Class-D
13	Restoration of rain Damages on various roads under junga section (SH:- Hiring of Excavator cum loader for removal of slips in various RDs).	99750/-	2000/-	350/-	30 Days	Class-D
14	Restoration of rain Damages on various roads under Challanda section (SH:- Hiring of Excavator cum loader for removal of slips in various RDs).	99750/-	2000/-	350/-	30 Days	Class-D
15	Restoration of rain Damages on various roads under Beolia section (SH:- Hiring of Excavator cum loader for removal of slips in various RDs).	99750/-	2000/-	350/-	30 Days	Class-D
16	A/R & M/O various Type-I to Type-VI qtr of GAD at kasumpti Shimla (SH:- Providing white washing Distemping in out house No.3,4,5 and repair of roof in type-III-165 under kasumpti section).	96243/-	1900/-	350/-	30 Days	Class-D
17	A/R & M/O various Type -I to Type-VI Gad residential qtrs at kasumpti Shimla-9 (SH:- Providing and fixing polycarbonate in type-VI set nO.2 & Type-IV set no.58 and steel work in type-IV set nO.58 in kasumpti Shimla-9).	99120/-	2000/-	350/-	30 Days	Class-D
18	A/R & M/O various type-I to type-VI qtr of Gad at kasumpti Shimla (SH:- Providing and fixing tiles in type-III 165 and repair work in o/o Electrical division under kasumpti section).	98255/-	1900/-	350/-	30 Days	Class-D
19	A/R & M/O various residential at kasumpti Shimla (SH:- painting and Distemping in type-III 100 and sets on vacation /on due kasumpti Shimla).	99090/-	2000/-	350/-	30 Days	Class-D
20	A/R & M/O to type-VI qtrs at mehli Shimla (SH:- Providing and fixing cup board & Bed Box in set No.17VI at mehli Shimla).	99985/-	2000/-	350/-	30 Days	Class-D
21	A/R & M/O various type-I to type-VI Gad Residential qtrs at kasumpti Shimla -9 (SH:- Providing and laying sewer line in type-II Block No.28 New Shimla under kasumpti Section).	99116/-	2000/-	350/-	30 Days	Class-D
22	A/R & M/O kasumpti to Besant Vihar road km. 0/00 to 0/550 (SH:- C/O B/wall between Rd. 0/337 to 0/340 under Parimahal section).	97446/-	2000/-	350/-	30 Days	Class-D
23	A/R & M/O kasumpti to Basant vihar road km. 0/00 to 0/550 (SH:- C/O B/wall between Rd. 0/332.50 to 0/335 under Parimahal section).	96396/-	1800/-	350/-	30 Days	Class-D
24	A/R & M/O to Type-I Qtrs Windsor cottage near Rani Ground kasumpti Shimla (SH:- Renovation of Toilet & kitchen set No.8 type-I Windsor cottage kasumpti Shimla).	99171/-	2000/-	350/-	30 Days	Class-D
25	A/R & M/O various type-I to Type-VI Gad Residential qtrs at kasumpti Shimla (SH:- C/O B/wall below type-IV 22 to 27 at Rd. 0/02.50 to 0/05.00 under Mehli Section).	97938/-	2000/-	350/-	30 Days	Class-D
26	A/R & M/O to Type-I Qtrs Windsor cottage Kasumpti Shimla (SH:- Renovation/Addition of Type-I Qtrs set No.8 kasumpti Shimla).	99498/-	2000/-	350/-	30 Days	Class-D
27	A/R & M/O to various Type-I to Type-VI Qtrs of GAD at kasumpti Shimla-9 (SH:- Providing and Fixing G-I water pipeline at SDA Complex parking and providing and fixing accessories in various sets under Parimahal section).	94567/-	1900/-	350/-	30 Days	Class-D
28	A/R & M/OI various Type-I to qtrs of GAD at kasumpti Shimla (SH:- providing and fixing tiles in type-III 166 to 171 under kasumpti Section).	97502/-	1900/-	350/-	30 Days	Class-D

29	A/R & M/O to Type-I to VI Qtrs of Gad at kasumpti Shimla-9 (SH:- Providing and fixing of wood work type-IV set No.58 in kasumpti Shimla (HP).	98294/-	2000/-	350/-	30 Days	Class-D
30	A/R & M/O various type-I to type-VI qtr of GAD at kasumpti Shimla (SH:- Providing and fixing PVC flooring in type-III 165, Type-I-03 fixing accessories in type-III 132 under kasumpti Section).	98323/-	1900/-	350/-	30 Days	Class-D
31	A/R & M/O various Type-III to Type-IV Qtrs of Gad at Parimahal kasumpti Shimla-9 (SH:- Repair work in Bathroom, kitchen and Toilet etc type-III set NO.64 under Parimahal section).	96080/-	1900/-	350/-	30 Days	Class-D
32	A/R & M/O to Type-I to VI Qtrs of GAD at kasumpti Shimla -9 (SH:- Providing and Fixing Cup boards in type-III set nO.142,137 under kasumpti Section).	97073/-	2000/-	350/-	30 Days	Class-D
33	A/R & M/O various Type-I to Type-VI Qtrs of GAD at kasumpti Shimla-9 (SH:- Repair work in kitchen, providing and fixing accessories etc in type-III set nO.110 and Type-III 64 under kasumpti Sub Division).	98776/-	2000/-	350/-	30 Days	Class-D
34	Special Repair to Atal institute of Medical super specialties Shimla-6 at Chamayana (SH:- Providing and Fixing Flashing, Base frame work etc on Roof top of Hospital Building over corridor/badminton court portion and repairs to roofing).	99762/-	2000/-	350/-	30 Days	Class-D
35	A/R & M/O to various Residential Building at kasumpti Shimla-9 (SH:- Providing and fixing of PVC flooring in type-IV set nO.40 at kasumpti Shimla-9).	99973/-	2000/-	350/-	30 Days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.  
The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

1. The valid enlistment/Registration of contractor in Appropriate Class.
2. Permanent account No. (PAN NO).
3. G.S.T No.
4. Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Shimla Division No-I HPPWD Shimla.
5. The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form . The application received without earnest money & cost of tender form shall summarily be rejected.
6. The officer of the tender shall remain valid up to 75 days after the opening of tender.
7. Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
8. Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
9. If the date given above happens to be holiday the same shall be processed on next working day.
10. The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
11. The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12. One contractor shall not have more than two major works in hand at a time.
13. Work should be completed by the contractor within stipulated period.

No.PW-SD-I/CB-Tender/2025-2026-  
Copy forwarded to :-

1. Copy to the Deputy Commissioner Shimla Distt. Shimla.
2. Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
3. Copy to the Sub Divisional Magistrate (U) Shimla.
4. Copy to the Sub Divisional Magistrate (R) Shimla.
5. Copy to Municipal committee Shimla Distt. Shimla.
6. Copy to Block Development officer Mashobra Distt. Shimla.
7. All the Assistant Engineers under this Division, HPPWD Shimla-3.
8. Superintendent / HDM /DAO.
9. Notice Board.

Executive Engineer,  
Shimla Division No-I.,  
HPPWD,,Shimla-3.  
Dated :- 26/6/25

Executive Engineer,  
Shimla Division No-I.,  
HPPWD Shimla.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:-96032=00		
Name of Work :-A/R & M/O various Residential Building at 1 to VI qtrs at Mehli Shimla. (SH:-					Earnest Money :1900=00		
Providing and fixing kitchen accessories curtain rod , and main hole set No 9 type - VI at Mehli Shimla					Time:- One Month.		
( Balance work )							
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Chequerred precast cement concrete tiles 20 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc complete, on 20 mm thick bed of cement mortar 1:4 (One cement: Four coarse sand)including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(i)Light shade pigment using white cement.	10.40	Sqm	1050.00	Rupees One Thousand Fifty Only	Per Square Metre	10920.00
2	Construction of man hole size 50x50x75 cm inside in brick work in cm 1:4 ( i ) with common burnt clay FPS ( Non modular ) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.00	Nos	7500.00	Rupees Seven Thousand Five Hundred Only	Each	15000.00
3	Providing and fixing stainless steel curtain rod including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	27.00	Rmt	275.00	Rupees Two Hundred Seventy Five Only	Per Running Metre	7425.00
4	Providing and fixing stainless Litchi trim double curtain system including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	26.00	Nos	500.00	Rupees Five Hundred Only	Each	13000.00
5	Providing and fixing SS wall to wall finial for curtain rod including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	20.00	Nos	150.00	Rupees One Hundred Fifty Only	Each	3000.00
6	Providing and fixing SS finial for curtain rod including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	24.00	Nos	120.00	Rupees One Hundred Twenty Only	Each	2880.00
7	Providing and fixing SSC DISH Rock henc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.00	Nos	2500.00	Rupees Two Thousand Five Hundred Only	Each	5000.00
8	Providing CPC Cross pipe cutlery including carriage of materials in all as per directions of the Engineer-in-Charge. leads	2.00	Nos	3000.00	Rupees Three Thousand Only	Each	6000.00

9	Steel work welded in built up sections, and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In beams joists channels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like.	200.00	Kgs	37.00	Rupees Thirty Seven Only	Per Kilo- gram.	7400.00
10	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	59.95	Sqm	10.00	Rupees Ten Only	Per Square Metre	600.00
11	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	59.95	Sqm	55.00	Rupees Fifty Five Only	Per Square Metre	3297.00
12	Distempering with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade. Old work (one or more coats). including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	59.95	Sqm	55.00	Rupees Fifty Five Only	Per Square Metre	3297.00
13	Painting one coats(excluding priming coat) on <b>previously painted wood and wood based</b> surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matters sand papering and stopping . including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) With white enamel paint	50.00	Sqm	65.00	Rupees Sixty Five Only	Per Square Metre	3250.00
14	Providing and fixing vitreous china wash down water closet (European type W.C. pan) with integral P or S trap including jointing the trap with soil pipe in cement mortar 1:1 (One cement:one sand) (seat and cover to be measured and paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Ordinary closet.	1.00	Nos	2620.00	Rupees Two Thousand Six Hundred Twenty Only	Each	2620.00

15	Providing and fixing C.P Jet including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	350.00	Rupees Three Hundred Fifty Only	Each	350.00
16	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm(three hundred into three hundred millimetre) or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm (twenty millimetre)thick cement mortar 1:4 (one Cement: four Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	10.52	Sqm	1140.00	Rupees One Thousand One Hundred Forty Only	Per Square Metre	11993.00
	Quated rates Percentage in figures					Total	96032.00
	Quoted rates Percentage in words						
saw						G.Total	

TIS No. 4655-56 Dt- 23-06-23

Amount = 98,913/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

**Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.**

**Estimated Cost:- 96,973.00**

**NAME OF WORK:- A/R & M/O to various Type-I to Type-VI Qtrs. Of GAD at Kasumpti Shimla-9.**

**Earnest Money :- 1,900.00**

**(SH:- Providing and Fixing cupboard in Type-III Set No. 136 under Kasumpti Section).**

**Time:- One Month.**

Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 19mm thick water proof commercial board in shelves/shutters box for cup board with butt joints & fixing with nails & screws etc complete) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	42.03	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square Meter	56741.00
2	Providing and fixing 0.80mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	12.96	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square meter	11016.00
3	Providing and fixing ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) 6mm (six milimetre)thick	14.96	Sqm	600.00	Rupees Six Hundred Only	Per Square Meter	8976.00
4	Providing and fixing square edges cover fillets (beading) 19mmx6mm(Nineteen milimetre into six milimetre) section i/c mitring at junctions with wood screws and nails complete including carriage of matrials in all leads and lifts as per directions of the Engineer-In-Charge.(i) 1st class deodar wood.	48.60	Rmt	65.00	Rupees Sixty Five Only	Per Running Meter	3159.00
5	Providing and fixing bright finished brass ball catcher 10 mm dia including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	34.00	Nos	50.00	Rupees Fifty Only	Each	1700.00
6	Providing and fixing bright finished Stainless steel handles with screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 125mm	34.00	Nos	150.00	Rupees One Hundred Fifty Only	Each	5100.00
7	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) 2nd class Pine wood.	0.035	Cum	92000.00	Rupees Ninety Two Thousand Only	Per Cubic Metre	3220.00
8	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth including carriage of materials in all leads as per directions of the Engineer-in-Charge.	42.03	Sqm	60.00	Rupees Sixty Only	Per Square Meter	2522.00

9	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil,grease,dirt and other foreign matter) sand papering and knotting including carriage of materials in all leads as per directions of the Engineer-in-Charge.	42.03	Sqm	38.00	Rupees Thirty Eight Only	Per Square Meter	1597.00
10	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping including carriage of materials in all leads as per directions of the Engineer-in-Charge.(i) With white enemal paint.	42.03	Sqm	70.00	Rupees Seventy Only	Per Square Meter	2942.00
	Quated rates Percentage in figures					<b>Total</b>	<b>96973.00</b>
	Quoted rates Percentage in words						
						<b>G.Total</b>	

TIS No. 4657-58 Dt-23-01-25  
Amount = 99,882/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer  
Shimla Division No.1,  
HP PWD Shimla-3.



SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 65,180.00	
NAME OF WORK:- Improvement of Charabra to Kalyani Helipad road in Km. 0/00 to 1/200. (SH:-						Earnest Money :- 1,300.00	
Maintenance of drain, Trimming of grass, White washing etc in Km. 0/00 to 1/200 and Terminal building at Kalyani Helipad).						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	White washing two coats on parapets wall and tree trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	609.00	Sqm	29.40	Rupees Twenty Nine and Paise Forty Only	Per Square Meter	17905.00
2	Maintenance of drain including erosion, repair, cleaning, reshaping, regarding, deepening of side drain as well as per Technical specification Clause 1907 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	1200.00	Rmt	4.60	Rupees Four and Paise Sixty Only	Per Running Meter	5520.00
3	Trimming of grass and weeds from the shoulders/ berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2400.00	Sqm	4.08	Rupees Four and Paise Eight Only	Per Square Meter	9792.00
4	Finishing wall with weather proof exterior grade emulsion of approved design (Apexultima) or its equalied on undecorated wall surfaces (One or more coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth including carriage of materials in all leads as per directions of the Engineer-in-Charge.	255.70	Sqm	65.00	Rupees Sixty Five Only	Per Square Meter	16621.00
5	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	255.70	Sqm	60.00	Rupees Sixty Only	Per Square Metre	15342.00
						<b>Total</b>	<b>65180.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

CT IS NO. 4653-54 Dt - 23-06-25 Amount = 67,186/-

### CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,885.00	
Name of Work :- Improvement of Sadhora to Mohanpur road Km 0/000 to 6/525. (SH:- Maintenance of drain, Bush Cutting, White Washing & Earthen shoulder in Km. 0/000 to 4/500).						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Maintenance of drain including erosion, repair, cleaning, reshaping, regarding, deepening of side drain as well as per Technical specification Clause 1907 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	4250.00	Rmt	4.60	Rupees Four and Paise Sixty Only	Per Running Meter	19550.00
2	Trimming of grass bushes complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge.	7950.00	Sqm.	4.08	Rupees Four and Paise Eight Only	Per Square Metre	32436.00
3	White washing two coats on parapets wall and tree trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	910.00	Sqm	29.40	Rupees Twenty Nine and Paise Forty Only	Per Square Meter	26754.00
4	Maintenance of Earthen Shoulder (Filling with fresh selected soil) Making un loose Material/ Irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 metre as per technical specification Clause 1603 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	500	Sqm	42.29	Rupees Forty Two and Paise Twenty Nine Only	Per Square Meter	21145.00
						Total	99885.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

TIS No. 4647-48 Dt-23-06-25 Amount = 1,02,882/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of Indian standards.

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,746.00	
Name of Work :- Improvement of Mashobra to Ramnagari road Km 0/000 to 5/300. (SH:- Maintenance of drain, Bush Cutting, White Washing in Km. 0/000 to 5/300).						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Maintenance of drain including erosion, repair, cleaning, reshaping, regarding, deepening of side drain as well as per Technical specification Clause 1907 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	5200.00	Rmt	4.60	Rupees Four and Paise Sixty Only	Per Running Meter	23920.00
2	Trimming of grass bushes complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge.	10925.00	Sqm.	4.08	Rupees Four and Paise Eight Only	Per Square Metre	44574.00
3	White washing two coats on parapets wall and tree trunks including preparation of surface by cleaning scraping etc. as per technical specification clause 1915 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	1063.00	Sqm	29.40	Rupees Twenty Nine and Paise Forty Only	Per Square Meter	31252.00
						Total	99746.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

TIS No. 4646-46 D+ = 23-06-26 Amount  
= 1,02,738/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:-97663.00		
Name of Work :-A/R &M/O Kasumpti to Basant vihar road km 0/00 to 0/550 ( SH: - C/O B/wall between Rd 0/313 to 0/315.50 under parimahal section )					Earnest Money :- 1900.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting in Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (ten Square Metre) on plan) including getting out and disposal of excavated earth all lead and lift as directed by Engineer-in-charge and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour ( if required ) Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges. (i)All kinds of soil.	13.88	Cum	350.00	Rupees Three Hundred Fifty Only	Per Cubic Metre	4858.00

2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (ten Square Metre) on plan) including getting out and disposal of excavated earth all lead and lift as directed by Engineer-in-charge and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour ( if required ) Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges. (i) Ordinary rock.	2.63	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	1052.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:5:10 (One cement : five coarse sand) : ten graded stone aggregate 40 mm(forty milimetre) nominal size)	1.04	Cum	3800.00	Rupees Three Thousand Eight Hundred Only	Per Cubic Metre	3952.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:3:6(1cement:3sand:6graded stone agg.20mm nominal size).	8.01	Cum	5700.00	Rupees Five Thousand Seven Hundred Only	Per Cubic Meter	45657.00
5	Providing weapholes in stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	15.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	2700.00

6	Backfilling behind Retaining / Breast wall , wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	1.76	Cum	1050.00	Rupees One Thousand Fifty Only	Per Cubic Metre	1848.00
7	Disposal of excavated earth up to site approved by MC up to all leads and lifts as per directions of the Engineer-in-charge.	10.11	Cum	600.00	Rupees Six Hundred Only	Per Cubic Meter	6066.00
8	Square rubble masonry/polygonal rubble masonry(un-coursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (One cement:Six sand:twelve graded stone aggregate 20mm (twenty milimetre)nominal size) in cement mortar 1:6 (One cement: Six sand) in breast wall and retaining walls including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.38	Cum	6000.00	Rupees Six Thousand Only	Per Cubic Metre	26280.00
9	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge. (i) Mild steel and Medium Tensile steel bars	50.00	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilo-gram	5250.00
ash						<b>Total</b>	<b>97663.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No 4583-88 dated 23-06-25 Amounting to Rs. 1,00,592/-

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,688.00	
Name of Work :- Providing Staff for maintenance of Shoghi Mehli Junga road in Km. 12/375 to 48/925 Under Junga Section for the year 2025-26 w.e.f 01.07.2025 to 31.07.2025).						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Engagement of 5 Nos. Beldar for any of duties assigned by Junior Engineer unskilled jobs such as earth work, carriage of material cleaning and washing of areas, assisting plumber carpenter etc cutting of grass and other misclenious works assigned by Junior Engineer. (Five Nos. Beldar for One month)	148.00	Days	548.00	Rupees Five Hundred Forty Eight Only	Per Days	81104.00
2	Engagement of 1Nos. mason for any of duties assigned by Junior Engineer unskilled jobs such as earth work, carriage of material cleaning and washing of areas, assisting plumber carpenter etc cutting of grass and other misclenious works assigned by Junior Engineer. (One No. Mason for One month)	30.00	Days	619.48	Rupees Six Hundred Nineteen and Paise Forty Eight Only	Per Days	18584.00
						<b>Total</b>	<b>99688.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words					<b>G.Total</b>	

TIS No. 4643-44 D + = 23-06-25 Amount = 1,02,679/-

#### CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.
3. Agency has to provide all T&P as required for day to day maintenance of Shoghi Mehli Junga road in Km. 12/375 to 48/925 Under Junga Section & its compus along with safety tools and do take care of all safety measures to the inforstructure, workers, execution of work. Agency has to provide all safety equipments, tools, dress, etc as required for each job work fo maintenance.


Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,688.00	
Name of Work :- Providing Staff for maintenance of Old Kasumpti Junga road, Rajhana Savi road, Rajhana Badagaon road and Rajahana Bird Colony road Under Junga Section for the year 2025-26 w.e.f 01.07.2025 to 31.07.2025).						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Engagement of 5 Nos. Beldar for any of duties assigned by Junior Engineer unskilled jobs such as earth work, carriage of material cleaning and washing of areas, assisting plumber carpenter etc cutting of grass and other misclenious works assigned by Junior Engineer. (Five Nos. Beldar for One month)	148.00	Days	548.00	Rupees Five Hundred Forty Eight Only	Per Days	81104.00
2	Engagement of 1Nos. mason for any of duties assigned by Junior Engineer unskilled jobs such as earth work, carriage of material cleaning and washing of areas, assisting plumber carpenter etc cutting of grass and other misclenious works assigned by Junior Engineer. (One No. Mason for One month)	30.00	Days	619.48	Rupees Six Hundred Nineteen and Paise Forty Eight Only	Per Days	18584.00
	Quated rates Percentage in figures					Total	99688.00
	Quoted rates Percentage in words						
						G.Total	

TIS No- 4624-25 Dt- 23-06-25 Amount= 1,02,679/-

#### CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.
3. Agency has to provide all T&P as required for day to day maintenance of Old Kasumpti Junga road, Rajhana Savi road, Rajhana Badagaon road and Rajahana Bird Colony road Under Junga Section & its compus along with safety tools and do take care of all safety measures to the inforstructure, workers, execution of work. Agency has to provide all safety equipments, tools, dress, etc as required for each job work fo maintenance.

  
Executive Engineer  
Shimla Division No.I,  
HP PWD Shimla-3.




## SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-99,446.00	
Name of Work :-Improvement of Shimla to Mandi road in Km. 6/00 to 22/000 (SH:- Maintenance of Earthen Shoulder, Maintenance of drain ,Trimming of grass between Rd. 15/00 to 18/00.)						Earnest Money :- 2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In	In words		
1	Maintenance of Earthen Shoulder (Filling with fresh selected soil) Making un loose Material/ Irregullarties on shoulders to the desion level by adding fresh approved slected soil and compacting it with approproese equipment at OMC upto a lead of 1000 metre as per technical specification Clause 1603 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	1620.00	Sqm	42.29	Rupees Forty Two and Paise Twenty Nine Only	Per Cubic Metre	68510.00
2	Mainteance of drain including erosion, reoair, cleaning, reshaping, regarding , deepening of side drain as well as per Technical specification Clause 1907 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	3000.00	Rmt	4.60	Rupees Four and Paise Sixty Only	Per Runnin g Meter	13800.00
3	Trimming of grass and weeds from the shoulders/ berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4200.00	Sqm	4.08	Rupees Four and Paise Eight Only	Per Square Meter	17136.00
	Quated rates Percentage in figures					Total	99446.00
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

T/S No. 4649-50 Dt-23-06-25 Amount = 1,02,429/-


  
 Executive Engineer  
 Shimla Division No.I,  
 HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.							
Name of Work :-Improvement of Shimla to Mandi road in Km. 6/00 to 22/000 (SH:- Maintenance of Earthen Shoulder, Maintenance of drain, Trimming of grass between Rd. 18/00 to 22/00.)						Estimated Cost:-99,860.00	
						Earnest Money :- 2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Maintenance of Earthen Shoulder (Filling with fresh selected soil) Making un loose Material/ Irregullarties on shoulders to the desion level by adding fresh approved slected soil and compacting it with approproese equipment at OMC upto a lead of 1000 metre as per technical specification Clause 1603 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	1380.00	Sqm	42.29	Rupees Forty Two and Paise Twenty Nine Only	Per Cubic Metre	58360.00
2	Mainteance of drain including erosion, rcoair, cleaning, reshaping, regarding , deepening of side drain as well as per Technical specification Clause 1907 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	3700.00	Rmt	4.60	Rupees Four and Paise Sixty Only	Per Running Meter	17020.00
3	Trimming of grass and weeds from the shoulders/ berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	6000.00	Sqm	4.08	Rupees Four and Paise Eight Only	Per Square Meter	24480.00
	Quated rates Percentage in figures					Total	99860.00
	Quoted rates Percentage in words						
						G.Total	

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


  
 Executive Engineer,  
 Shimla Division No.I,  
 HP PWD Shimla-3

TIS No. 4657-58 Pt = 23-06-76 Amount = 1,02,856/-

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,025.00	
Name of Work :- Preparation of Detailed Project Report of Construction of Kemu ka Khet to Binkuti road. Km						Earnest Money :- 2,000.00	
0/00 to 2/315 under Junga Sub Division in Distt. Shimla (H.P)						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Preparation of Detailed Project Report of which includes following provision as mentioned below :- i) Topography survey by digital total station with two second accuracy showing all features on survey plan like trees, culverts, bridges, electric poles, telephone poles, hand pumps, school, Habitants villages etc. ii) Draw cross-sections at 15m intervals, L-sections and calculate the quantity of earthwork in standard format of autocad showing all layers of pavement components as applicable. iii) Preparation of survey plan showing all details as per MORD guidelines and specifications. If any correction/amendment will be desired by the office the same may be corrected as desired and directed by the Engineer-In-Charge complete in all respect. After approval of the same from the head office the same should be submitted in three fair copies and soft copy as per the requirement of this office and upto entire satisfaction of Engineer-In-Charge including all type of incidental charges.	2.315	Per Km	35000.00	Rupees Thirty Five Thousand Only	Pe Kilometre	81025.00
2	CBR test including gain size analysis, atterbergs limit, proctor compaction and CBR value upto the entire satisfaction of Engineer-In-Charge including all type of incidental charges.	6	Per Sample	3000.00	Rupees Three Thousand Only	Per Sample	18000.00
						Total	99025.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

T/S No - 4641-42 D + - 23-06-25 Amount = 1,01,996/-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
Executive Engineer,  
Shimla Division No.1,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 99,750.00		
Name of Work :- Restoration of Rain Damages on various roads under Janedghat Section. (SH:-					Earnest Money :- 2,000.00		
Hiring of Excavator cum loader for removal of slips in various RDs).					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, machinery of any minor or major accidents and other damages to private and Govt. property occur during working hour is the whole responsibility of contractor, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. Removal of slips, Debries with minimum capacity of 45.00 Cum. Per Hour, Minium Six hours per day. The disposal of this un-serviceable materials has to be done in the required width of the road to avoid damaged to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged materials such quarried stone shall belong to the department and maximun usefull quantities of stone from removal of slips shall have to be neatly stacked along road side on road burms, minium 30.00 Cubic metre of cutting earth work. Minimum 150.00 cubic metre of removal of slips and 300.00 cubic metre removal of snow shall be done by the machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	95.00	Hour	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00
						Total	99750.00

+15 No - 4639-40 Dt - 23-06-25 Amount = 1,02,742/-

#### CONDITION:

1. All the P.O.L. Charges shall be borne by the contractor.
2. All the repair /maintenance of machineries shall be borne by the contractor.
3. For any minor /Major repair or any accident /damaged shall be the whole responsibility of contractor.
4. Any damages or loss to Govt./Private property during course of work shall have to be make good by the contractor.


Executive Engineer,  
Shimla Division No. I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,750.00	
Name of Work :- Restoration of Rain Damages on various roads under Junga Section. (SH:-						Earnest Money :- 2,000.00	
Hiring of Excavator cum loader for removal of slips in various RDs).						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, machinery of any minor or major accidents and other damages to private and Govt. property occur during working hour is the whole responsibility of contractor, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. Removal of slips, Debries with minimum capacity of 45.00 Cum. Per Hour, Minium Six hours per day. The disposal of this un-serviceable materials has to be done in the required width of the road to avoid damaged to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged materials such quarried stone shall belong to the department and maximum usefull quantities of stone from removal of slips shall have to be neatly stacked along road side on road burms. minimum 30.00 Cubic metre of cutting earth work. Minimum 150.00 cubic metre of removal of slips and 300.00 cubic metre removal of snow shall be done by the machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	95.00	Hour	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00
						Total	99750.00

TLS No - 4637-38 D + - 23-06-25 Amount = 1,02,742/-

**CONDITION:**

1. All the P.O.L. Charges shall be borne by the contractor.
2. All the repair /maintenance of machineries shall be borne by the contractor.
3. For any minor /Major repair or any accident /damaged shall be the whole responsibility of contractor.
4. Any damages or loss to Govt./Private property during course of work shall have to be make good by the contractor.

  
Executive Engineer,  
Shimla Division No. I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,750.00	
Name of Work :- Restoration of Rain Damages on various roads under Challanda Section. (SH:-						Earnest Money :- 2,000.00	
Hiring of Excavator cum loader for removal of slips in various RDs).						Time:- One Month	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, machinery of any minor or major accidents and other damages to private and Govt. property occur during working hour is the whole responsibility of contractor, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. Removal of slips, Debries with minimum capacity of 45.00 Cum. Per Hour, Minimum Six hours per day. The disposal of this un-serviceable materials has to be done in the required width of the road to avoid damaged to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged materials such quarried stone shall belong to the department and maximum usefull quantities of stone from removal of slips shall have to be neatly stacked along road side on road burms, minimum 30.00 Cubic metre of cutting earth work. Minimum 150.00 cubic metre of removal of slips and 300.00 cubic metre removal of snow shall be done by the machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	95.00	Hour	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00
						Total	99750.00

#### CONDITION:

1. All the P.O.L. Charges shall be borne by the contractor.
2. All the repair /maintenance of machineries shall be borne by the contractor.
3. For any minor /Major repair or any accident /damaged shall be the whole responsibility of contractor.
4. Any damages or loss to Govt./Private property during course of work shall have to be made good by the contractor.

Executive Engineer,  
Shimla Division No. I,  
HP PWD Shimla-3.

+16 NO- 4635-36 Dt-23-06-25 Amount = 1,02,742/-

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,750.00	
Name of Work :- Restoration of Rain Damages on various roads under Beolia Section. (SH:-						Earnest Money :- 2,000.00	
Hiring of Excavator cum loader for removal of slips in various RDs).						Time:- One Month	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB excavator-cum-loader (JCB) including P.O.L charges, machinery of any minor or major accidents and other damages to private and Govt. property occur during working hour is the whole responsibility of contractor, shifting charges and other ancillary equipments as required at site of work for removal of slips/snow in all heights in all kind of soil such as kankar, mooram shingle, boulders decomposed or soft variety of soil such as spade work, jumper work, soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary. Removal of slips, Debris with minimum capacity of 45.00 Cum. Per Hour, Minimum Six hours per day. The disposal of this un-serviceable materials has to be done in the required width of the road to avoid damaged to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged materials such as quarried stone shall belong to the department and maximum useful quantities of stone from removal of slips shall have to be neatly stacked along road side on road burms, minimum 30.00 Cubic metre of cutting earth work. Minimum 150.00 cubic metre of removal of slips and 300.00 cubic metre removal of snow shall be done by the machine in one hour, other wise number of hour shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instructions/ direction of the Engineer-in-Charge.	95.00	Hour	1050.00	Rupees One Thousand Fifty Only	Per Hours	99750.00
						<b>Total</b>	<b>99750.00</b>

TIS No - 4633-34 Dt - 23-06-25 Amount = 1,02,742/-

1. All the P.O.L. Charges shall be borne by the contractor.

2. All the repair /maintenance of machineries shall be borne by the contractor.
3. For any minor /Major repair or any accident /damaged shall be the whole responsibility of contractor.
4. Any damages or loss to Govt./Private property during course of work shall have to be make good by the contractor.

Executive Engineer,  
Shimla Division No. 1,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-96243=00	
Name of Work :- A/R & M/O various Type -I to type VI qtr of GAD at Kasumpti Shimla ( SH:- Providing White washing / Distemping in out house No 3,4,5 and repair of roof in Type - III -165 under Kasumpti section )						Earnest Money :-1900=00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded built up sections / framed work including cutting hoisting , fixing in position and applying a priming cost of approved stel primer using structural steel etc as required ( i) in stringers , treads landing etc of stair cases including use of chequered plate wherever required all complete as per directions of the Engineer-in-Charge	62.27	Kg	105.00	Rupees One Hundred Five Only	Per Kilo gram	6538.35
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.Cement mortar 1:4 (one cement :four coarse sqm sand) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	5.61	Sqm	1020.00	Rupees One Thousand Twenty Only	Per Square Metre	5722.00
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	600.00	Sqm	12.00	Rupees Twelve Only	Per Square Metre	7200.00
4	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	300.00	300	55.00	Rupees Fifty Five Only	Per Square Metre	16500.00
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) One or more coats on old work.	250.00	Sqm	70.00	Rupees Seventy Only	Per Square Meter	17500.00
6	Finishing wall with weather proof exterior grade emulsion of approved design Apexultima) or its equarled on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth including carriage of materials in all leads as per directions of the Engineer-in-Charge.	300.00	Sqm	75.00	Rupees Seventy Five Only	Per Square Meter	22500.00
7	15mm cement plaster in single coat on rough side of brick/ concrete /stone walls for interior plastering up to all floor level /heights i/c arises internal rounded angles, chamfers and / or rounded angles not exceeding 80mm in girth and finished even and smooth including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement mortar 1:6(One cement; six sand).	5.61	Sqm.	270.00	Rupees Two Hundred Seventy Only	Per Square Metre	1515.00



8	supplying and fixing welded mesh 225x25x3mm to wood or steel members in partitions etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.21	Sqm	650.00	Rupees Six Hundred Fifty Only	Per square metre	2737.00
9	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 0.63 mm thick sheet. make TATA	9.80	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square Meter	13230.00
10	Wall painting (One coat) with plastic emulsion paint of approved brand and manufacture on undecorated wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for making the surface including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	20.00	Sqm	70.00	Rupees Seventy Only	Per Square Metre	1400.00
11	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) One or more coats on old work	20.00	Sqm	70.00	Rupees Seventy Only	Per Square Meter	1400.00
	Quoted rates Percentage in figures						
vis	Quoted rates Percentage in words						
						G.Total	96242.35

T/s No 4695-86 dated 23-06-25 Amounting to Rs. 99,130/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

Executive Engineer  
Shimla Division No.1,  
HP PWD Shimla-3.


SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-99120.00	
Name of Work :- A/R & M/O various Type - I TO Type - VI GAD Residential qtrs at Kasumpti Shimla - 9 ( SH:-						Earnest Money :- 2000.00	
Providing and fixing polycarbonate in type VI set no 2 & type - IV set No 58 and steel work in type IV set No 58 in Kasumpti shimla -9 )						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing magnetic Catchers ISI marked with necessary screws etc complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	30.00	Nos	50.00	Rupees Fifty Only	Each	1500.00
2	Polishing two coats with P.U. polish of required shade on new wood and wood based surfaces to give an even surface including cleaning the surface of all dirt, dust and sand papered smooth and including a coat of wood filler including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	39.84	Sqm	325.00	Rupees Three Hundred Twenty Five Only	Per Square Meter	12948.00
3	Applying sealer on wood and wood based surfaces to given an even surfaces including cleaning the surfaces of all dirt,dust and sand papering so as to produce a smooth dry and matt surface including stopping & knotting including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	39.84	Sqm	290.00	Rupees Two Hundred Ninety Only	Per Square Meter	11554.00
4	Providing and laying Granite work (table rubbed and polished) with semi round nosing in flooring laid over 20mm (Twenty milimetres) thick base in 1:3 (One cement: three sand) including jointed with cement mortar 1:2 (one white cement: two marble dust) with an admixture of pigment to match the shade of marble 20mm (Twenty milimetres) thick Green marble with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.10	Sqm	5500.00	Rupees Five Thousand Five Hundred Only	Per Square Metre	22550.00
4	Extra for making moulded nosing in terrazzo including returned ends and angles to moulding including carriage of materials in all leads and lifts.	18.54	Rmt	250.00	Rupees Two Hundred Fifty Only	per Running metre	4635.00
5	Steel work welded in Hollow sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	96.39	Kgs	115.00	Rupees One Hundred Fifteen Only	Per KilogramMetre	11085.00

6	Providing and fixing C.G.I corrugated polycarbonated sheet 2.00mm thick including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	14.52	Sqm.	2400.00	Rupees Two Thousand Four Hundred Only	Per Square Metre	34848.00
bd						Total	99120.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						

TIS No. 4683-84 DT-23-06-25 Amount to Rs. 1,02,000/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.


SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:-98255=00		
Name of Work :- A/R & M/O various Type -1 to type VI qtr of GAD at Kasumpti Shimla ( SH:- Providing and fixing tiles in Type - III 165 and repair work in O/O Electrial division under Kasumpti section )					Earnest Money :-1900=00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i)Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	4.90	Cum	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Cubic Metre	5635.00
2	Dismantling tiles work in floors and roofs laid in cement mortar including stacking material within 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)For thickness of tiles 10 mm to 25 mm	5.60	Sqm	50.00	Rupees Fifty Only	Per Square Meter	280.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)1:5:10(one cement : sandcoarse sand) : 10graded stone aggregate 20 mm (twenty milimetre) nominal size)	0.95	Cum	4500.00	Rupees Four Thousand Five Hundred Only	Per Cubic Metre	4275.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:3:6(One cement:Four sand:Eight graded stone aggregate 20mm(Twenty milimetre) nominal size).	4.90	Cum	5400.00	Rupees Five Thousand Four Hundred Only	Per Cubic Metre	26460.00

5	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	53.57	Sqm	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Square Meter	61605.50
	Quoted rates Percentage in figures						
vis	Quoted rates Percentage in words					G.Total	98255.50

T/s No 4681-82 dated 23-6-25 Amounting to Rs. 1,01,203/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

  
Executive Engineer,  
Shimla Division No.1,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:-99090=00		
Name of Work :- A/R & M/O various residential at Kasumpti Shimla (SH:- Painting and Distempereing in Type -III 100 and sets on vacation / on due kasumpti Shimla .					Earnest Money :-2000=00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Distempereing with oil bound washable distemper of approved brand and manufacture and of required shade on undecorated wall surfaces to give an even shade. Old work (one or more coats). including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	519.45	Sqm	55.00	Rupees Fifty Five Only	Per Square Metre	28570.00
2	Wall painting (One coat) with plastic emulsion paint of approved brand and manufacture on undecorated wall surfaces to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for making the surface including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	305.08	Sqm	75.00	Rupees Seventy Five Only	Per Square Metre	22881.00
3	Removing dry or oil bound distemper, water proofing cement paint and the like by scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	412.27	Sqm	12.00	Rupees Twelve Only	Per Square Metre	4947.00
4	Applying Birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	138.93	Sqm	55.00	Rupees Fifty Five Only	Per Square Metre	7641.00
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) One or more coats on old work	376.93	Sqm	70.00	Rupees Seventy Only	Per Square Meter	26385.00
6	Finishing wall with weather proof exterior grade emulsion of approved design Apexultima) or its equarlised on undecorated wall surfaces (two coats) to give an even shade and final finish after thoroughly cleaning the surface to remove all dirt, dust and other foreign matter etc including sand paper smooth including carriage of materials in all leads as per directions of the Engineer-in-Charge.	100.00	Sqm	75.00	Rupees Seventy Five Only	Per Square Meter	7500.00
7	Repair to plaster in patches of 2.50 square meter under and upto 10 to 15mm thick including cutting the patch in proper shape and re-plastering the surface of wall including disposal to the dumping ground with a lead of 20 metres with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Cement Mortar 1:5(One cement: Five sand).	1.44	Sqm	280.00	Rupees Two Hundred Eighty Only	Per Square Meter	403.00

8	Providing and fixing chicken mesh in wall with wood screws and nails including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.44	Sqm	250.00	Rupees Two Hundred Fifty Only	Per Square Metre	360.00
9	Providing Dubbing out an old irregular walls average 10mm thick with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) cement mortar 1:5 (One cement: Five sand).	1.44	Sqm.	280.00	Rupees Two Hundred Eighty Only	Per Square Metre	403.00
						Total	99090.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words					G.Total	
Kol							

T/S No. 4674-80 Dt. 23-6-25 Amount = 1,02,063/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance


Executive Engineer,  
Shimla Division No.1,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:-99985=00		
Name of Work :- A/R & M/O TO Type - VI qtrs at Melhi Shimla ( SH: Providing and fixing cup board & ^ Bed Box in set No 17- VI at Melhi Shimla					Earnest Money :-2000=00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 19 mm thick HDMR laminated water proof commercial board in shelves/box for cup board with butt joints & fixing with nails & screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.						
	(ii) 19mm thick	44.30	Sqm	2257.00	Rs Two thousand two hundred fifty seven only	Per Square meter	99985.100
	Quated rates Percentage in figures					Total	99985.10
	Quoted rates Percentage in words						
bd						G.Total	

T/S No. 4677-78 Dt- 23-06-25 Amount = 1,02,985/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

  
 Executive Engineer,  
 Shimla Division No.I,  
 H.P.W.D Shimla-3.



SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:-99116=00		
Name of Work :- A/R & M/O various Type - I TO Type - VI GAD Residential qtrs at Kasumpti Shimla - 9 ( SH:-					Earnest Money :-2000=00		
Providing and laying sewer line in Type - II Block No 28 New shimla under Kasumpti section ) )					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 90 mm dia.	10.00	Rmt	300.00	Rupees Three Hundred Only	Per Running Meter	3000.00
	(ii) 110mm	10.00	Rmt	375.00	Rupees Three Hundred Seventy Five Only	Per Running Meter	3750.00
	(iii) 150mm	10.00	Rmt	550.00	Rupees Five Hundred Fifty Only	Per Running Meter	5500.00
2	Providing and fixing PVC single equal branch plain ISI marked including fixing with approved adhesive etc. complete. (i) 90 mm dia.	2.00	Nos.	220.00	Rupees Two Hundred Twenty Only	Each	440.00
	(ii) 110 mm dia	2.00	Nos.	275.00	Rupees Two Hundred Seventy Five Only	Each	550.00
	(iii) 150mm	2.00	Nos.	500.00	Rupees Five Hundred Only		1000.00
3	Providing and fixing PVC collars ISI marked including fixing with approved adhesive etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 90 mm dia.	5.00	Nos.	220.00	Rupees Two Hundred Twenty Only	Each	1100.00
	(ii )110mm	5.00	Nos.	285.00	Rupees Two Hundred Eighty Five Only	Each	1425.00
	(iii) 150mm	5.00	Nos.	350.00	Rupees Three Hundred Fifty Only	Each	1750.00
4	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 90 mm dia.	2.00	Nos.	275.00	Rupees Two Hundred Seventy Five Only	Each	550.00
	(ii)110mm dia	2.00	Nos.	325.00	Rupees Three Hundred Twenty Five Only	Each	650.00
	(iii) 150mm	2.00	Nos.	500.00	Rupees Five Hundred Only		1000.00

5	Providing and fixing PVC door bend with oval access door, insertion rubber washer 3 mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) 90 mm dia.	2.00	Nos.	200.00	Rupees Two Hundred Only	Each	400.00
	(ii) 110 mm dia.	2.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	500.00
	(iii) 150mm dia.	2.00	Nos.	500.00	Rupees Five Hundred Only	Each	1000.00
6	Providing and fixing PVC offset 45 degree ISI marked including with approved adhesive etc complete including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) 90 mm dia.	2.00	Nos.	200.00	Rupees Two Hundred Only	Each	400.00
	(ii) 110 mm dia.	2.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	500.00
	(iii) 150mm dia.	2.00	Nos.	325.00	Rupees Three Hundred Twenty Five Only	Each	650.00
7	Dismantling tiled floors laid in mortar upto all floor two level including stacking of serviceable materials and disposal of un-serviceable materials with in 20 mtrs.(Twenty metres) lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) For thickness of tiles upto 25mm(Twenty milimetre)	15.00	Sqm	50.00	Rupees Fifty Only	Per Square Metre	750.00
8	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (ten Square Metre) on plan) including getting out and disposal of excavated earth all lead and lift as directed by Engineer-in-charge and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour ( if required ) Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges. (i)All kinds of soil.	16.44	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	6576.00


9	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i)Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	1.50	Cum	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Cubic Metre	1725.00
10	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:3:6(One cement:Four sand:Eight graded stone aggregate 20mm(Twenty milimetre) nominal size).	1.50	Cum	5600.00	Rupees Five Thousand Six Hundred Only	Per Cubic Metre	8400.00
11	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:5:10 (One cement : five coarse sand) : ten graded stone aggregate 40 mm(forty milimetre) nominal size)	1.50	Cum	3800.00	Rupees Three Thousand Eight Hundred Only	Per Cubic Metre	5700.00
12	Chequerred precast cement concrete tiles 20 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc complete, on 20 mm thick bed of cement mortar 1:4 (One cement: Four coarse sand)including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(i)Light shade pigment using white cement.	18.00	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square Metre	24300.00
13	Constructing Brick masonry manhole with R.C.C. top slab in 1:2:4 mix (one cement : two sand : four graded stone aggregate 20mm(twenty milimetre) nominal size), foundation concrete 1:4:8 (one cement : four sand : eight graded stone aggregate 40 mm(forty milimetre) nominal size), inside plastering 15mm (fifteen milimetre)thick with cement mortar 1:3 (one cement : three sand) and finished with floating coat of neat cement and making channels in cement concrete 1:2:4 mix (one cement : two sand : four graded stone aggregate 20mm(twenty milimetre) nominal size) finished smooth complete including curing and testing including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a)Inside size 455mmx610mm and 500mm(eight hundred milimetre into eight hundred milimetre and five hundred milimetre) deep including precast reinforced Cement concrete manhole Cover (Medium Duty) with frame 600 mm (six hundred milimetre) dia Total weight of cover and frame to be notge less than 38Kg. :- (i) with 200mm (two hundred milimetre) thick walls of brick masonry using common burnt clay building bricks in cement mortar 1:3 (one cement : three sand) :-	2.00	Nos	12500.00	Rupees Twelve Thousand Five Hundred Only	Each	25000.00

14	Constructing brick masonry in road gully chamber 500x450x600 cm with bricks in cement mortar 1:5 (One cement : Five coarse sand) including 500x450 mm C.I horizontal grating with frame complete as per standard design :	1.00	Nos	2500.00	Rupees Two Thousand Five Hundred Only	Each	2500.00
	Quoted rates Percentage in figures						
Raj	Quoted rates Percentage in words						
						G.Total	99116.00

TIS No. 4675-76 Dt - 23-06-25 Amount = 1,02,090/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-1, H.P.P.W.D., SHIMLA-3.					Estimated Cost:-97446.00		
Name of Work :- A/R & M/O Kasumpti to Basant vihar road Km 0/00 to 0/550 ( SH:- C/O B/wall					Earnest Money :- 2000.00		
between Rd 0/337.50 to 0/340 under parimahal section )					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour ( if required ). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	12.38	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	4023.50

2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	2.63	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	1052.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:5:10 (1cement:5sand:10graded stone agg.40mm nominal size).	1.04	Cum	3900.00	Rupees Three Thousand Nine Hundred Only	Per Cubic Metre	4056.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:3:6(1cement:3sand:6graded stone agg.20mm nominal size).	8.01	Cum	5600.00	Rupees Five Thousand Six Hundred Only	Per Cubic Meter	44856.00

5	Providing weapholes in stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	6.25	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	1125.00
6	Backfilling behind Retaining / Breast wall , wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	1.76	Cum	1200.00	Rupees One Thousand Two Hundred Only	Per Cubic Metre	2112.00
7	Disposal of excavated earth up to site approved by MC up to all leads and lifts as per directions of the Engineer-in-charge.	10.11	Cum	600.00	Rupees Six Hundred Only	Per Cubic Meter	6066.00
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge. (i) Mild steel and Medium Tensile steel bars	55.00	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilo- gram	5775.00
9	Square rubble masonry/polygonal rubble masonry(un-coursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (One cement:Six sand:twelve graded stone aggregate 20mm (twenty milimetre)nominal size) in cement mortar 1:6 (One cement: Six sand) in breast wall and retaining walls including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.73	Cum	6000.00	Rupees Six Thousand Only	Per Cubic Metre	28380.00
ash						Total	97445.50
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No 4673-74 dated 23-06-25 Amounting to Rs. 1,00,269/-

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:96396.00	
Name of Work :- A/R & M/O Kasumpti to Basant vihar road Km 0/00 to 0/550 ( SH:- C/O B/wall between Rd 0/332.50 to 0/335 under parimahal section )						Earnest Money :-1800.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour ( if required ). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	12.38	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	4024.00



2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	2.63	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	1052.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:5:10 (1cement:5sand:10graded stone agg.40mm nominal size).	1.04	Cum	3900.00	Rupees Three Thousand Nine Hundred Only	Per Cubic Metre	4056.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:3:6(1cement:3sand:6graded stone agg.20mm nominal size).	8.01	Cum	5600.00	Rupees Five Thousand Six Hundred Only	Per Cubic Meter	44856.00

5	Providing weapholes in stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	15.00	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	2700.00
6	Backfilling behind Retaining / Breast wall , wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	1.76	Cum	1200.00	Rupees One Thousand Two Hundred Only	Per Cubic Metre	2112.00
7	Disposal of excavated earth up to site approved by MC up to all leads and lifts as per directions of the Engineer-in-charge.	10.11	Cum	600.00	Rupees Six Hundred Only	Per Cubic Meter	6066.00
8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge. (i) Mild steel and Medium Tensile steel bars	50.00	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilo- gram	5250.00
9	Square rubble masonry/polygonal rubble masonry(un-coursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (One cement:Six sand:twelve graded stone aggregate 20mm (twenty milimetre)nominal size) in cement mortar 1:6 (One cement: Six sand) in breast wall and retaining walls including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	4.38	Cum	6000.00	Rupees Six Thousand Only	Per Cubic Metre	26280.00
ash						Total	96396.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

T/s No 4671-72 dated 23-06-25 Amounting to Rs. 99,287/-

Executive Engineer,  
Shimla Division No.1,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,171.00	
Name of Work :- A/R & M/O to Type-I Qtrs. Windsor Cottage near Rani Ground Kasumpti Shimla. (SH:-						Earnest Money :- 2,000.00	
Renovation of Toilet & Kitchen Set No. 8 Type-I Windsor Cottage Kasumpti Shimla).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i) Nominal concrete 1:3:6 or leaner mix (i/c equivalent design mix)	0.91	Cum	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Cubic Metre	1047.00
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) For thickness of tiles 10 mm to 25 mm	11.52	Sqm	45.00	Rupees Forty Five Only	Per Square Meter	518.00
3	Providing and fixing PVC floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110mm x 75mm (one hundred ten milimetre into Seventy five millimetre) nominal size.	2.00	Nos.	350.00	Rupees Three Hundred Fifty Only	Each	700.00
4	Providing and fixing PVC Sewerage pipe including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110mm dia.	2.00	Rmt	650.00	Rupees Six Hundred Fifty Only	Per Running Meter	1300.00
	(ii) 75mm dia.	3.00	Rmt	500.00	Rupees Five Hundred Only	Per Running Meter	1500.00
5	Providing and fixing PVC door bend with oval access door, insertion rubber washer 3 mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) 110 mm dia.	1.00	Nos.	300.00	Rupees Three Hundred Only	Each	300.00
	(b) 75mm diameter.	1.00	Nos	250.00	Rupees Two Hundred Fifty Only	Each	250.00
6	Providing and fixing PVC collars ISI marked including fixing with approved adhesive etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110 mm dia.	2.00	Nos.	275.00	Rupees Two Hundred Seventy Five Only	Each	550.00
	(b) 75mm diameter.	3.00	Nos.	185.00	Rupees One Hundred Eighty Five Only	Each	555.00


7	Providing and laying in position cement concrete of specified grade including the cost of centering and Shuttering All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:2:4 (One cement :Two coarse sand): four graded stone aggregate 20mm (Twenty millimeter) nominal size).	1.00	Cum	6400.00	Rupees Six Thousand Four Hundred Only	Per Cubic Metre	6400.00
8	Providing and laying 1st quality Ceramic glazed wall tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:3 (1 Cement : 3 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	26.50	Sqm	1200.00	Rupees One Thousand Two Hundred Only	Per Square Meter	31800.00
9	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	7.11	Sqm	1140.00	Rupees One Thousand One Hundred Forty Only	Per Square Meter	8105.00
10	Providing and fixing Angle iron frames for doors windows & ventilators of mild steel angle sanction of size 35x35x5mm joints including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	62.92	Kgs	105.00	Rupees One Hundred Five Only	Per Kilogram	6607.00
11	Providing and fixing glass panes with putty and nails including removal of broken glass panes wherever necessary including carriage of material within all leads and lifts as per direction of Engineer-in-charge. (a) Plain Glass: 4mm thick.	3.42	Sqm	900.00	Rupees Nine Hundred Only	Per square metre	3078.00
12	Providing and fixing vitreous China wash down, water closet (European type. W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1(1 cement : 1 sand) (Seat and over to be measured and paid for separately) including carriage of materials in all leads as per directions of the Engineer-in-Charge (i) ordinary closet	1.00	Nos.	2800.00	Rupees Two Thousand Eight Hundred Only	Each	2800.00
13	Providing and fixing 100 mm sand cast Iron grating for gully trap including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.00	Nos.	200.00	Rupees Two Hundred Only	Each	400.00
14	Providing and fixing plastic seat (Solid / Hollow type) and cover for wash down water closet with C.P. Brass hinges and rubber buffers including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (1)SOLID TYPE (a) White plastic seat and cover. <b>Make Inglo</b>	1.00	Nos	850.00	Rupees Eight Hundred Fifty Only	Each	850.00
15	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 10 litre capacity - White <b>Make Ess</b>	1.00	Nos.	2473.40	Rupees Two Thousand Four Hundred Seventy Three and Paise Forty Only	Each	2473.00

16	Providing and fixing 8.00mm C.P jet spray of approved quality and colour with 1.50 meter tube including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos	450.00	Rupees Four Hundred Fifty Only	Each	450.00
17	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) 510x1040 mm bowl depth 250 mm	1.00	Nos.	3800.00	Rupees Three Thousand Eight Hundred Only	Each	3800.00
18	Providing and fixing 15mm mixer for kitchen sink with top / bottom swinging spout. including carriage of materials in all leads as per directions of the Engineer-in-Charge. <b>MAKE ESS ESS</b>	1.00	Nos.	4000.00	Rupees Four Thousand Only	Each	4000.00
19	Providing and fixing chromium plated brass soap dish with C.P. Brass brackets fixed to wooden plug with C.P. Brass screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.00	Nos	550.00	Rupees Five Hundred Fifty Only	Each	1100.00
20	Providing and fixing 0.60mm(zero point six zero milimetre) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyster of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 8mm dia metre with prepainted limpet and bitumen washers complete with all accesories as required as per the direction of Engineer-in-charge. <b>(MAKE TATA)</b>	15.25	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square Metre	20588.00
						<b>Total</b>	<b>99171.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words					<b>G.Total</b>	

### CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

(T/S No. 4669-70 Dated 23-06-25 Amount to  
Rs. 4,92,146/-).

  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-97938.00	
Name of Work :- A/R & M/O various Type - 1 to Type - VI GAD residential qtrs at Kasumpti Shimla (SH:-C/O B/wall below Type - IV 22 to 27 at Rd 0/02.50 to 0/05.00 under Melhi section )						Earnest Money :- 2000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour ( if required ). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	18.91	Cum	325.00	Rupees Three Hundred Twenty Five Only	Per Cubic Metre	6146.00

2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	3.60	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	1440.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:5:10 (1cement:5sand:10graded stone agg.40mm nominal size).	0.86	Cum	3800.00	Rupees Three Thousand Eight Hundred Only	Per Cubic Metre	3268.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:3:6(1cement:3sand:6graded stone agg.20mm nominal size).	7.88	Cum	5600.00	Rupees Five Thousand Six Hundred Only	Per Cubic Meter	44128.00
5	Providing weapholes in stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	14.40	Rmt	180.00	Rupees One Hundred Eighty Only	Per Running meter	2592.00
6	Backfilling behind Retaining / Breast wall , wing wall and return wall complete as per drawings and technical specification clause 1204:3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material.	2.25	Cum	1200.00	Rupees One Thousand Two Hundred Only	Per Cubic Metre	2700.00
7	Disposal of excavated earth up to site approved by MC up to all leads and lifts as per directions of the Engineer-in-charge.	11.34	Cum	600.00	Rupees Six Hundred Only	Per Cubic Meter	6804.00

8	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge. (i) Mild steel and Medium Tensile steel bars	50.00	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilo- gram	5250.00
9	Square rubble masonry/polygonal rubble masonry(un-coursed/brought to courses) with hard stone of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (One cement:Six sand:twelve graded stone aggregate 20mm (twenty milimetre)nominal size) in cement mortar 1:6 (One cement: Six sand) in breast wall and retaining walls including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	3.94	Cum	6500.00	Rupees Six Thousand Five Hundred Only	Per Cubic Metre	25610.00
						<b>Total</b>	<b>97938.00</b>
d							
DP	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

T/s No 4689-90 dated 22-06-25 Amounting to Rs. 1,00,876/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.




DRAFT SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 99,498.00		
NAME OF WORK:- A/R & M/O to Type-I Qtrs. Windsor Cottage Kasumpti Shimla. (SH:-					Earnest Money :- 2,000.00		
Renovation/Addition of Type-I Qtrs. Set No. 8 Kasumpti Shimla).					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Structure steel work welded in built up ( M.S Hollow pipe) trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	865.20	Kgs.	115.00	Rupees One Hundred Fifteen Only	Per Kilogram	99498.00
						Total	99498.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words					G.Total	

and for Rs. 99 498/- Only (Rupees Ninety nine Thousand Four

DNIT approved for Rs. 99,498/- Only (Rupees Ninety nine Thousand Four Hundred Ninety eight only ) vide DNIT Register Sr.No..... the financial year 2025-26. (T/S No. 1147-18.. Dated 23.08.25... Amount to Rs. 99,498/-).

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 94,567.00	
NAME OF WORK:- A/R & M/O to various Type-I to Type-VI Qtrs. Of GAD at Kasumpti Shimla-9.						Earnest Money :- 1,900.00	
(SH:- Providing and Fixing G.I water pipeline at SDA Complex parking and Providing and fixing accessories in various sets under Parimahal Section).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing G.I pipes complete with G.I fittings and clamps including cutting chases and making good the all including carriage of materials within all leads and lifts and as per the direction of Engineer-in-Charge. (i) 50mm dia.	54.40	Rmt	927.70	Rupees Nine Hundred Twenty Seven and Paise Seventy Only	Per Running Meter	50467.00
	(ii) 15mm dia.	6.00	Rmt	350.00	Rupees Three Hundred Fifty Only	Per Running Meter	2100.00
2	Providing and fixing G.I union in G.I pipe including cutting and threading the pipe and making long screws complete (New work) including carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge. (i) 50mm dia.	2.00	Nos.	550.00	Rupees Five Hundred Fifty Only	Each	1100.00
	(ii) 15mm dia.	2.00	Nos.	150.00	Rupees One Hundred Fifty Only	Each	300.00
3	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but with out fittings and the base support for tank including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1000.00	Ltrs.	8.50	Rupees Eight and Paise Fifty Only	Per Ltrs.	8500.00

4	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges.	18.00	Cum	400.00	Rupees Four Hundred Only	Per Cubic Metre	7200.00
5	Providing and fixing vitreous China wash down, water closet (European type. W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1(1 cement : 1 sand) (Seat and over to be measured and paid for separately) including carriage of materials in all leads as per directions of the Engineer-in-Charge (i) ordinary closet MAKE ESS ESS or Equivalent	1.00	Nos.	2800.00	Rupees Two Thousand Eight Hundred Only	Each	2800.00
6	Providing and fixing plastic seat (Solid / Hollow type) and cover for wash down water closet with C.P. Brass hinges and rubber buffers including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (1)SOLID TYPE (a) White plastic seat and cover. MAKE ESS ESS or Equivalent	1.00	Nos	600.00	Rupees Six Hundred Only	Each	600.00
7	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 10 litre capacity - White MAKE ESS ESS or Equivalent	1.00	Nos.	1250.00	Rupees One Thousand Two Hundred Fifty Only	Each	1250.00
8	Providing and fixing hand faucet including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	550.00	Rupees Five Hundred Fifty Only	Each	550.00
9	Providing and fixing 100 mm sand cast Iron grating for gully trap including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	200.00	Rupees Two Hundred Only	Each	200.00


10	Providing and fixing C.P. Brass Towel rail complete with C.P. Brass brackets fixed to wooden plugs with C.P. Brass screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms.	1.00	Nos.	600.00	Rupees Six Hundred Only	Each	600.00
11	Providing and fixing PTMT towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved quality and colour, weighing not less than 88 gms including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	550.00	Rupees Five Hundred Fifty Only	Each	550.00
12	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	1050.00	Rupees One Thousand Fifty Only	Each	1050.00
13	Providing and fixing chromium plated brass soap dish with C.P. Brass brackets fixed to wooden plug with C.P. Brass screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (E.S) <b>Make ESS ESS</b>	1.00	Nos	550.00	Rupees Five Hundred Fifty Only	Each	550.00
14	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15 mm nominal bore <b>Make ESS ESS</b>	1.00	Nos.	850.00	Rupees Eight Hundred Fifty Only	Each	850.00
15	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15 mm nominal bore with 45 cm length	1.00	Nos.	150.00	Rupees One Hundred Fifty Only	Each	150.00
16	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Flexible pipe (a) 32 mm dia	1.00	Nos.	200.00	Rupees Two Hundred Only	Each	200.00
17	Providing and fixing 600x120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	650.00	Rupees Six Hundred Fifty Only	Each	650.00
18	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15mm nominal bore <b>MAKE ESS ESS</b>	1.00	Nos.	850.00	Rupees Eight Hundred Fifty Only	Each	850.00
19	Providing and fixing vitreous China wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings with pedestal complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Flat back (i) 550 x 400mm.	1.00	Nos	2600.00	Rupees Two Thousand Six Hundred Only	Each	2600.00
20	Providing and fixing 32 mm (thirty two millimetre) dia C.P. brass waste for wash basin or sink complete within all leads, lifts of materials and other incidentals. including carriage of materials in all leads as per directions of the Engineer-in-Charge.	1.00	Nos.	450.00	Rupees Four Hundred Fifty Only	Each	450.00

21	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	3000.00	Rupees Three Thousand Only	Each	3000.00
22	Providing and fixing 15mm mixer for kitchen sink with top / bottom swinging spout. including carriage of materials in all leads as per directions of the Engineer-in-Charge. <b>MAKE ESS ESS</b>	1.00	Nos.	4000.00	Rupees Four Thousand Only	Each	4000.00
23	Providing and fixing wall mixing faucet including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. <b>MAKE ESS ESS</b>	1.00	Nos.	4000.00	Rupees Four Thousand Only	Each	4000.00
	Quoted rates Percentage in figures					<b>Total</b>	<b>94567.00</b>
	Quoted rates Percentage in words						
						<b>G.Total</b>	

T/S No. 4665-66 Dt 23-06-25 Amount = 97,404/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
 Executive Engineer.  
 Shimla Division No.I,  
 HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-97502=00	
Name of Work :- A/R & M/O various Type -I to type VI qtr of GAD at Kasumpti Shimla (SH:- Providing and fixing tiles in						Earnest Money :-1900=00	
Type - III 166 to 171 under kasumpti section )						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	31.81	Sqm	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Square Meter	36581.50
2	Tile work in skirting, risers of steps and dado up to 2 m (two metre) height over 12 mm(twelve milimetre) thick bed of cement mortar 1:3 (One cement :three coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge. (i) 8 mm(eight milimetre) thick	39.52	Sqm	1170.00	Rupees One Thousand One Hundred Seventy Only	Per Square Metre	46238.00
3	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings, framed guards bars ladders, railing, brackets and similar work.	139.84	Kgs	105.00	Rupees One Hundred Five Only	Per KilogramMetre	14683.00
	Quated rates Percentage in figures						
vis	Quoted rates Percentage in words						
						G.Total	97502.50

T/s No 4663-64 dated 27-06-25 Amounting to Rs. 1,00,427/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

Executive Engineer  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- Rs -98294=00		
Name of Work :- A/R & M/O to Type - I to VI Qtrs of GAD at Kasumpti Shimla -9 ( SH:- Providing and fixing of wood work Type-IV set No 58 in Kasumpti Shimla ( H.P)					Earnest Money :Rs:-2000=00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 32 mm dia CP Brass waste for wash basin or sink complete with in all leads lifts of materials and other incidentals .	2.00	Nos	500.00	Rupees Five Hundred Only	Each	1000.00
2	Providing and fixing one piece water closet oval shaped white including carriage of materials in all leads and lifts as per directions of the Engineer- in - charge make Hindware for equivlents .	2.00	Nos	19600.00	Rupees Nineteen Thousand Six Hundred Only	Each	39200.00
3	Providing and fixing 19mm thick Commercial Board water proof shutters for up boards i/c fixing with nickel plated piano hinges with screws etc complete) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	42.25	Sqm	1375.00	Rupees One Thousand Three Hundred Seventy Five Only	Per Square Meter	58094.00
b							98294.00

T/S No. 4661-62 Dt - 23-06-25 Amount Rs. 9,01,243/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:-98323=00	
Name of Work :- A/R & M/O various Type -I to type VI qtr of GAD at Kasumpti Shimla ( SH:- Providing and fixingPVC Flooring in Type - III 165, Type - I- 03 fixing accessories in Type - III 132 under Kasumpti section )						Earnest Money :-1900=00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 1.50mm(One point Fifty milimetre) thick PVC antistatic vinyl Flooring plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	65.16	Sqm	950.00	Rupees Nine Hundred Fifty Only	Per Square Metre	61902.00
2	Providing and fixing ply wood lining with but jointing and nails (frame work and cover fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 6mm thick	35.85	Sqm	600.00	Rupees Six Hundred Only	Per Square Meter	21510.00
3	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15 mm nominal bore MAKE ESS ESS	1.00	Nos.	950.00	Rupees Nine Hundred Fifty Only	Each	950.00
4	Providing and fixing C.P.brass angle valve without nuts and pipe including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charges.(i)15mm(fifteen milimetre) dia.	9.00	Nos	850.00	Rupees Eight Hundred Fifty Only	Each	7650.00
5	Providing and fixing C.P. Brass extension nipple (size 15mmx50mm) of approved make and quality as per direction of Engineer-in-charge	8.00	Nos.	80.00	Rupees Eighty Only	Each	640.00
6	Providing and fixing toilet paper holder of approved quality and Stainless steel screws and rawal plugs etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge	1.00	Nos	750.00	Rupees Seven Hundred Fifty Only	Each	750.00
7	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)1:2:4 (one cement : two coarse sand) : four graded stone aggregate 20 mm (twenty milimetre) nominal size)	0.26	Cum	6400.00	Rupees Six Thousand Four Hundred Only	Per Cubic Metre	1664.00




8	Steel Reinforcement for RCC work including straightening cutting, bending placing in position and binding all complete up to plinth level (i) thermo mechanically treated bars of grade Fe -500 D or more.	20.00	Kg	105.00	Rupees One Hundred Five Only	per Kilogram	2100.00
9	Centering and shuttering including strutting, propping etc. and removal of form work for including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.	2.57	Sqm	450.00	Rupees Four Hundred Fifty Only	Per Square Metre	1157.00
	Quated rates Percentage in figures						
vis	Quoted rates Percentage in words						
						G.Total	98323.00

T/s No 4659-40 dated 23-06-25 Amounting to Rs. 1,01,273/-

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance

  
Executive Engineer  
Shimla Division No.I,  
HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 96,080.00	
Name of Work :- A/R & M/O various Type-III to Type-IV Qtrs. of GAD at Parimahal Kasumpti Shimla-9.						Earnest Money :- 1,900.00	
(SH:- Repair work in Bathroom, Kitchen and Toilet etc Type-III Set No. 64 Under Parimahal Section).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i) Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	0.44	Cum	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Cubic Metre	506.00
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) For thickness of tiles 10 mm to 25 mm	23.18	Sqm	45.00	Rupees Forty Five Only	Per Square Meter	1043.00
3	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Of area 3 sq. metres and below	2.00	Nos	250.00	Rupees Two Hundred Fifty Only	Each	500.00
4	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:3:6 (One cement : Three coarse sand) : Six graded stone aggregate 20 mm nominal size)	1.20	Cum	5400.00	Rupees Five Thousand Four Hundred Only	Per Cubic Metre	6480.00
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Nominal mix 1:2:4 (One cement : Two coarse sand) : Four graded stone aggregate 20 mm nominal size)	0.16	Cum	6500.00	Rupees Six Thousand Five Hundred Only	Per Cubic Metre	1040.00

6	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	6.68	Sqm	1140.00	Rupees One Thousand One Hundred Forty Only	Per Square Meter	7615.00
7	Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	35.15	Sqm	1140.00	Rupees One Thousand One Hundred Forty Only	Per Square Meter	40071.00
8	Providing and fixing vitreous China wash down, water closet (European type, W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1 (1 cement : 1 sand) (Seat and over to be measured and paid for separately) including carriage of materials in all leads as per directions of the Engineer-in-Charge (i) ordinary closet <b>MAKE ESS ESS or Equivalent.</b>	1.00	Nos.	2800.00	Rupees Two Thousand Eight Hundred Only	Each	2800.00
9	Providing and fixing plastic seat (Solid / Hollow type) and cover for wash down water closet with C.P. Brass hinges and rubber buffers including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (1) SOLID TYPE (a) White plastic seat and cover. <b>Make ESS ESS</b>	1.00	Nos	1049.36	Rupees One Thousand Forty Nine and Paise Thirty Six Only	Each	1049.00
10	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle/lever) conforming to IS : 7231, with all fittings and fixtures including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 10 litre capacity - White <b>MAKE ESS ESS</b>	1.00	Nos.	2473.40	Rupees Two Thousand Four Hundred Seventy Three and Paise Forty Only	Each	2473.00
11	Providing and fixing hand faucet including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. <b>MAKE ESS ESS</b>	1.00	Nos.	875.44	Rupees Eight Hundred Seventy Five and Paise Forty Four Only	Each	875.00
12	Providing and fixing 100 mm sand cast Iron grating for gully trap including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.00	Nos.	200.00	Rupees Two Hundred Only	Each	400.00

13	Providing and fixing C.P. Brass Towel rail complete with C.P. Brass brackets fixed to wooden plugs with C.P. Brass screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms. <b>MAKE ESS ESS</b>	1.00	Nos.	1074.00	Rupees One Thousand Seventy Four Only	Each	1074.00
14	Providing and fixing PTMT towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved quality and colour, weighing not less than 88 gms including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. <b>MAKE ESS ESS</b>	1.00	Nos.	968.82	Rupees Nine Hundred Sixty Eight and Paise Eighty Two Only	Each	969.00
15	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	1050.00	Rupees One Thousand Fifty Only	Each	1050.00
16	Providing and fixing chromium plated brass soap dish with C.P. Brass brackets fixed to wooden plug with C.P. Brass screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (E.S) <b>Make ESS ESS or Equivalent.</b>	1.00	Nos	650.00	Rupees Six Hundred Fifty Only	Each	650.00
17	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15 mm nominal bore <b>Make ESS ESS</b>	1.00	Nos.	850.00	Rupees Eight Hundred Fifty Only	Each	850.00
18	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15 mm nominal bore with 45 cm length	2.00	Nos.	150.00	Rupees One Hundred Fifty Only	Each	300.00
19	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Flexible pipe (a) 32 mm dia	1.00	Nos.	200.00	Rupees Two Hundred Only	Each	200.00
20	Providing and fixing 600x120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	650.00	Rupees Six Hundred Fifty Only	Each	650.00
21	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15mm nominal bore <b>MAKE ESS ESS</b>	1.00	Nos.	850.00	Rupees Eight Hundred Fifty Only	Each	850.00

22	Providing and fixing G.I pipes complete with G.I fittings and clamps including cutting chases and making good the all including carriage of materials within all leads and lifts and as per the direction of Engineer-in-Charge. (i) 15mm (Fifteen millimeters) nominal bore	6.00	Rmt	350.00	Rupees Three Hundred Fifty Only	Per Running Meter	2100.00
23	Providing and fixing G.I union in G.I pipe including cutting and threading the pipe and making long screws complete (New work) including carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge. (i) 15mm (Fifteen millimeters) nominal bore	1.00	Nos.	150.00	Rupees One Hundred Fifty Only	Each	150.00
24	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110 mm dia.	1.00	Rmt	350.00	Rupees Three Hundred Fifty Only	Per Running Meter	350.00
	(ii) 90 mm dia.	1.00	Rmt	250.00	Rupees Two Hundred Fifty Only	Per Running Meter	250.00
25	Providing and fixing PVC single equal branch plain ISI marked including fixing with approved adhesive etc. complete. (i) 110 mm dia.	1.00	Nos.	350.00	Rupees Three Hundred Fifty Only	Each	350.00
	(ii) 90 mm dia	1.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	250.00
26	Providing and fixing PVC collars ISI marked including fixing with approved adhesive etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110 mm dia.	1.00	Nos.	275.00	Rupees Two Hundred Seventy Five Only	Each	275.00
	(ii) 90 mm dia.	1.00	Nos.	220.00	Rupees Two Hundred Twenty Only	Each	220.00
27	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110 mm dia.	1.00	Nos.	300.00	Rupees Three Hundred Only	Each	300.00
	(ii) 90 mm dia.	1.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	250.00
28	Providing and fixing PVC reducer ISI marked including jointing with approved adhesive etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110mmx90 mm dia	1.00	Nos	300.00	Rupees Three Hundred Only	Each	300.00

29	Providing and fixing PVC floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110mm x 90mm (one hundred ten millimetre into ninety millimetre) nominal size.	1.00	Nos.	350.00	Rupees Three Hundred Fifty Only	Each	350.00
30	Providing and fixing PVC single equal branch with oval access door, ISI marked insertion rubber washer 3 mm thick bolts and nuts complete including fixing with approved adhesive etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110 mm dia.	1.00	Nos.	300.00	Rupees Three Hundred Only	Each	300.00
	(ii) 90 mm dia	1.00	Nos.	270.00	Rupees Two Hundred Seventy Only	Each	270.00
31	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 40mm thick (i) 2nd class deodar wood.	0.52	Sqm	4800.00	Rupees Four Thousand Eight Hundred Only	Per Square Metre	2496.00
32	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. with wire of dia 0.56 mm. for doors windows and clerestory windows including bright finished black enamelled iron hinges with necessary screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 40mm thick 2nd class deodar wood	0.52	Sqm	4500.00	Rupees Four Thousand Five Hundred Only	Per Square Metre	2340.00
33	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 150x10mm	1.00	Nos.	80.00	Rupees Eighty Only	Each	80.00
	(ii) 200x10 mm	1.00	Nos.	100.00	Rupees One Hundred Only	Each	100.00
34	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 125 mm	1.00	Nos.	75.00	Rupees Seventy Five Only	Each	75.00
35	Providing and fixing bright finished brass hard drawn hooks and eyes including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 200 mm	1.00	Nos.	60.00	Rupees Sixty Only	Each	60.00
36	Providing and fixing C.P. Brass extension nipple (size 15mmx50mm) of approved make and quality as per direction of Engineer-in-charge	1.00	Nos.	80.00	Rupees Eighty Only	Each	80.00

37	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.08	Cum	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Cubic Metre	92.00
38	Centering and shuttering including strutting, propping etc. and removal of form work for including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.	0.75	Sqm	450.00	Rupees Four Hundred Fifty Only	Per Square Metre	338.00
39	Marble work (table rubbed and polished for walls lining) Veneer work 2.50cm. thick in cement mortar 1:3 (1 cement:3 sand) including pointing with white cement mortar 1:2 (1 white cement: 2 marble dust) with an admixture of pigment to match the marble shade including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) Baroda Green Marble	0.90	Sqm	4000.00	Rupees Four Thousand Only	Per Square Metre	3600.00
40	Providing and fixing PVC door bend with oval access door, insertion rubber washer 3 mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) 110 mm dia.	1.00	Nos.	350.00	Rupees Three Hundred Fifty Only	Each	350.00
	(iii) 90 mm dia.	1.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	250.00
41	Providing and fixing C.P. Brass waste for wash basin or sink including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 32mm dia.	1.00	Nos	550.00	Rupees Five Hundred Fifty Only	Each	550.00
42	Repair to plaster in patches of 2.50 square meter under and upto 10 to 15mm thick including cutting the patch in proper shape and re-plastering the surface of wall including disposal to the dumping ground with a lead of 20 metres with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Cement Mortar 1:5 (One cement: Five sand).	2.00	Sqm	250.00	Rupees Two Hundred Fifty Only	Per Square Meter	500.00
43	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in - Charge.	0.09	Cum	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Cubic Metre	122.00
44	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge. (i) Mild steel and Medium Tensile steel bars.	20.00	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilo-gram	2100.00

45	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (one cement :four coarse sqm sand) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.02	Sqm	1020.00	Rupees One Thousand Twenty Only	Per Square Meter	1040.00
46	Providing and fixing chicken mesh in wall surface screws and nails including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	9.89	Sqm	200.00	Rupees Two Hundred Only	Per Square Metre	1978.00
47	Dubbing out an old irregular walls average 10mm thick with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) cement mortar 1:5 (One cement: Five sand).	9.89	Sqm.	280.00	Rupees Two Hundred Eighty Only	Per Square Metre	2769.00
						<b>Total</b>	<b>96080.00</b>
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

**CONDITION:-**

(T/S No. 4737-78 Dated 24-4-25 Amount to Rs. 96,962/-).

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.



## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 97,073.00	
Name of Work :- A/R & M/O to Type-I to VI Qtrs. Of GAD at Kasumpti Shimla-9. (SH:- Providing and						Earnest Money :- 2,000.00	
Fixing Cup boards in Type-III Set No. 142,137 under Kasumpti Section).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 19mm thick water proof commercial board in shelves/shutters box for cup board with butt joints & fixing with nails & screws etc complete) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	42.03	Sqm	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Square Meter	56741.00
2	Providing and fixing 0.80mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	12.96	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square meter	11016.00
3	Providing and fixing ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) 6mm (Six milimetre)thick	14.96	Sqm	600.00	Rupees Six Hundred Only	Per Square Meter	8976.00
4	Providing and fixing square edges cover fillets (beading) 19mmx6mm(Nineteen milimetre into six milimetre) section i/c mitring at junctions with wood screws and nails complete including carriage of matrials in all leads and lifts as per directions of the Engineer-In-Charge.(i)1st class deodar wood.	48.60	Rmt	65.00	Rupees Sixty Five Only	Per Running Meter	3159.00
5	Providing and fixing bright finished brass ball catcher 10 mm dia including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	36.00	Nos	50.00	Rupees Fifty Only	Each	1800.00
6	Providing and fixing bright finished Stainless steel handles with screws etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 125mm	34.00	Nos	150.00	Rupees One Hundred Fifty Only	Each	5100.00
7	Providing wood work in frames of false ceiling, partitions etc. sawn and fixed in position with necessary stainless steel screws etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) 2nd class Pine wood.	0.035	Cum	92000.00	Rupees Ninety Two Thousand Only	Per Cubic Metre	3220.00
8	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth including carriage of materials in all leads as per directions of the Engineer-in-Charge.	42.03	Sqm	60.00	Rupees Sixty Only	Per Square Meter	2522.00

9	Applying priming coat over new wood and wood based surfaces after and including prepering the surface by thoroughly cleaning oil,grease,dirt and other foreign matter) sand papering and knotting including carriage of materials in all leads as per directions of the Engineer-in-Charge.	42.03	Sqm	38.00	Rupees Thirty Eight Only	Per Square Meter	1597.00
10	Painting two coats(excluding coat) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping including carriage of materials in all leads as per directions of the Engineer-in-Charge.(i) With white enemal paint.	42.03	Sqm	70.00	Rupees Seventy Only	Per Square Meter	2942.00
						<b>Total</b>	<b>97073.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words					<b>G.Total</b>	

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

(T/S No. 4781-82 Dated 24-06-2025 Amount to Rs. .... 99,985/-).

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 98,776.00	
Name of Work :- A/R & M/O various Type-I to Type-VI Qtrs. of GAD at Kasumpti Shimla-9. (SH:- Repair work in Kitchen, Providing and Fixing accessories etc in Type-III Set No. 110 and Type-III 64 Under Kasumpti Sub Division).						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i) Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	0.07	Cum	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Cubic Metre	81.00
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) For thickness of tiles 10 mm to 25 mm	23.18	Sqm	45.00	Rupees Forty Five Only	Per Square Meter	1043.00
3	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Of area 3 sq. metres and below	2.00	Nos	250.00	Rupees Two Hundred Fifty Only	Each	500.00
4	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 1:3:6 (One cement : Three coarse sand) : Six graded stone aggregate 20 mm nominal size)	0.44	Cum	5400.00	Rupees Five Thousand Four Hundred Only	Per Cubic Metre	2376.00
5	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Nominal mix 1:2:4 (One cement : Two coarse sand) : Four graded stone aggregate 20 mm nominal size)	0.15	Cum	6500.00	Rupees Six Thousand Five Hundred Only	Per Cubic Metre	975.00
6	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including pointing the joints with white cement and matching pigments etc., including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	2.80	Sqm	1140.00	Rupees One Thousand One Hundred Forty Only	Per Square Meter	3192.00

7	Tile work in skirting, risers of steps and dado up to 2 m height over 12 mm thick bed of cement mortar 1:3 (1 cement :3 coarse sand) and jointed with grey cement slurry @ 3.3 kg/sqm, including pointing in white cement mixed with pigment of matching shade including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	18.32	Sqm	1140.00	Rupees One Thousand One Hundred Forty Only	Per Square Meter	20885.00
8	Providing and fixing vitreous China wash down, water closet (European type. W.C. pan) with integral 'P' or 'S' trap including jointing the trap with soil pipe in cement mortar 1:1 (1 cement : 1 sand) (Seat and over to be measured and paid for separately) including carriage of materials in all leads as per directions of the Engineer-in-Charge (i) ordinary closet <b>MAKE ESS ESS or Equivalent.</b>	1.00	Nos.	2800.00	Rupees Two Thousand Eight Hundred Only	Each	2800.00
9	Providing and fixing plastic seat (Solid / Hollow type) and cover for wash down water closet with C.P. Brass hinges and rubber buffers including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (1) SOLID TYPE (a) White plastic seat and cover. <b>MAKE ESS ESS or Equivalent</b>	1.00	Nos	1049.36	Rupees One Thousand Forty Nine and Paise Thirty Six Only	Each	1049.00
10	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 10 litre capacity - White <b>MAKE ESS ESS</b>	1.00	Nos.	2473.40	Rupees Two Thousand Four Hundred Seventy Three	Each	2473.00
11	Providing and fixing hand faucet including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. <b>MAKE ESS ESS</b>	1.00	Nos.	875.44	Rupees Eight Hundred Seventy Five	Each	875.00
12	Providing and fixing 100 mm sand cast Iron grating for gully trap including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	200.00	Rupees Two Hundred Only	Each	200.00
13	Providing and fixing C.P. Brass Towel rail complete with C.P. Brass brackets fixed to wooden plugs with C.P. Brass screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190 gms. <b>MAKE ESS ESS</b>	1.00	Nos.	1074.00	Rupees One Thousand Seventy Four Only	Each	1074.00
14	Providing and fixing PTMT towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved quality and colour, weighing not less than 88 gms including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. <b>MAKE ESS ESS</b>	1.00	Nos.	968.82	Rupees Nine Hundred Sixty Eight and Paise Eighty Two Only	Each	969.00

15	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	1050.00	Rupees One Thousand Fifty Only	Each	1050.00
16	Providing and fixing chromium plated brass soap dish with C.P. Brass brackets fixed to wooden plug with C.P. Brass screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (E.S) <b>Make ESS ESS or Equivalent.</b>	1.00	Nos	650.00	Rupees Six Hundred Fifty Only	Each	650.00
17	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15 mm nominal bore <b>Make ESS ESS</b>	1.00	Nos.	850.00	Rupees Eight Hundred Fifty Only	Each	850.00
18	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15 mm nominal bore with 45 cm length	1.00	Nos.	150.00	Rupees One Hundred Fifty Only	Each	150.00
19	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Flexible pipe (a) 32 mm dia	1.00	Nos.	200.00	Rupees Two Hundred Only	Each	200.00
20	Providing and fixing 600x120x5 mm glass shelf with edges round off, supported on anodised aluminium angle frame with C.P. brass brackets and guard rail complete fixed with 40 mm long screws, rawl plugs etc., including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	650.00	Rupees Six Hundred Fifty Only	Each	650.00
21	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 15mm nominal bore <b>MAKE ESS ESS</b>	1.00	Nos.	850.00	Rupees Eight Hundred Fifty Only	Each	850.00
22	Providing and fixing G.I pipes complete with G.I fittings and clamps including cutting chases and making good the all including carriage of materials within all leads and lifts and as per the direction of Engineer-in-Charge. (i) 15mm (Fifteen millimeters) nominal bore	6.00	Rmt	350.00	Rupees Three Hundred Fifty Only	Per Running Meter	2100.00
23	Providing and fixing G.I union in G.I pipe including cutting and threading the pipe and making long screws complete (New work) including carriage of materials in all leads and lifts as per direction of the Engineer-in-Charge. (i) 15mm (Fifteen millimeters) nominal bore	1.00	Nos.	150.00	Rupees One Hundred Fifty Only	Each	150.00
24	Providing and fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110 mm dia.	1.00	Rmt	350.00	Rupees Three Hundred Fifty Only	Per Running Meter	350.00
	(ii) 90 mm dia.	1.00	Rmt	250.00	Rupees Two Hundred Fifty Only	Per Running Meter	250.00

25	Providing and fixing PVC single equal branch plain ISI marked including fixing with approved adhesive etc. complete. (i) 110 mm dia.	1.00	Nos.	350.00	Rupees Three Hundred Fifty Only	Each	350.00
	(ii) 90 mm dia	1.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	250.00
26	Providing and fixing PVC collars ISI marked including fixing with approved adhesive etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110 mm dia.	1.00	Nos.	275.00	Rupees Two Hundred Seventy Five Only	Each	275.00
	(ii) 90 mm dia.	1.00	Nos.	220.00	Rupees Two Hundred Twenty Only	Each	220.00
27	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110 mm dia.	1.00	Nos.	300.00	Rupees Three Hundred Only	Each	300.00
	(ii) 90 mm dia.	1.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	250.00
28	Providing and fixing PVC reducer ISI marked including jointing with approved adhesive etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110mmx90 mm dia	1.00	Nos.	300.00	Rupees Three Hundred Only	Each	300.00
29	Providing and fixing PVC floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110mm x 90mm (one hundred ten milimetre into ninety millimetre) nominal size.	1.00	Nos.	350.00	Rupees Three Hundred Fifty Only	Each	350.00
30	Providing and fixing PVC single equal branch with oval access door, ISI marked insertion rubber washer 3 mm thick bolts and nuts complete including fixing with approved adhesive etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 110 mm dia.	1.00	Nos.	300.00	Rupees Three Hundred Only	Each	300.00
	(ii) 90 mm dia	1.00	Nos.	270.00	Rupees Two Hundred Seventy Only	Each	270.00
31	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 40mm thick (i) 2nd class deodar wood.	0.52	Sqm	4800.00	Rupees Four Thousand Eight Hundred Only	Per Square Metre	2496.00

32	Providing and fixing wire gauge shutters using galvanised M.S. wire gauge of I.S. gauge designation 85 G. with wire of dia 0.56 mm for doors windows and clerestorey windows including bright finished black enamelled iron hinges with necessary screws including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)40mm thick 2nd class deodar wood	0.52	Sqm	4500.00	Rupees Four Thousand Five Hundred Only	Per Square Metre	2340.00
33	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 150x10mm	1.00	Nos.	80.00	Rupees Eighty Only	Each	80.00
	(ii) 200x10 mm	1.00	Nos.	100.00	Rupees One Hundred Only	Each	100.00
34	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 125 mm	1.00	Nos.	75.00	Rupees Seventy Five Only	Each	75.00
35	Providing and fixing bright finished brass hard drawn hooks and eyes including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 200 mm	1.00	Nos.	60.00	Rupees Sixty Only	Each	60.00
36	Providing and fixing C.P. Brass extension nipple (size 15mmx50mm) of approved make and quality as per direction of Engineer-in-charge	1.00	Nos.	80.00	Rupees Eighty Only	Each	80.00
37	Providing and fixing 15mm mixer for kitchen sink with top / bottom swinging spout. including carriage of materials in all leads as per directions of the Engineer-in-Charge. <b>MAKE ESS ESS</b>	2.00	Nos.	4000.00	Rupees Four Thousand Only	Each	8000.00
38	Providing and fixing one hole basin mixing Faucet including carriage of materials in all leads as per directions of the Engineer-in-Charge. <b>MAKE ESS ESS</b>	2.00	Nos.	4000.00	Rupees Four Thousand Only	Each	8000.00
39	Providing and fixing wall mixing faucet including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. <b>MAKE ESS ESS</b>	2.00	Nos.	4000.00	Rupees Four Thousand Only	Each	8000.00
40	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. (i) Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.08	Cum	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Cubic Metre	92.00
41	Centering and shuttering including strutting, propping etc. and removal of form work for including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i)Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc.	0.75	Sqm	450.00	Rupees Four Hundred Fifty Only	Per Square Metre	338.00

42	Marble work (table rubbed and polished for walls lining) Veneer work 2.50cm. thick in cement mortar 1:3 (1 cement:3 sand) including pointing with white cement mortar 1:2 (1 white cement: 2 marble dust) with an admixture of pigment to match the marble shade including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) Baroda Green Marble	0.40	Sqm	4000.00	Rupees Four Thousand Only	Per Square Metre	1600.00
43	Providing and fixing PVC door bend with oval access door, insertion rubber washer 3 mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc. including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) 110 mm dia.	1.00	Nos.	350.00	Rupees Three Hundred Fifty Only	Each	350.00
	(iii) 90 mm dia.	1.00	Nos.	250.00	Rupees Two Hundred Fifty Only	Each	250.00
44	Providing and fixing vitreous China Hind ware IS marked IS No.2556 or equivalent wash basin with single hole for pillar tap with C.I. or M.S. brackets painted white including cutting holes and making good the same but excluding fittings with pedestal complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Flat back (i)550 x400mm.	1.00	Nos	2600.00	Rupees Two Thousand Six Hundred Only	Each	2600.00
45	Providing and fixing C.P. Brass waste for wash basin or sink including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) 32mm dia.	1.00	Nos	550.00	Rupees Five Hundred Fifty Only	Each	550.00
46	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) 510x1040 mm bowl depth 250 mm	1.00	Nos.	3800.00	Rupees Three Thousand Eight Hundred Only	Each	3800.00
47	Providing and fixing white vitreous china pedestal for wash basin completely recessed at the back for the reception of pipes and fittings including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.00	Nos.	3000.00	Rupees Three Thousand Only	Each	3000.00
48	Repair to plaster in patches of 2.50 square meter under and upto 10 to 15mm thick including cutting the patch in proper shape and re-plastering the surface of wall including disposal to the dumping ground with a lead of 20 metres with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Cement Mortar 1:5(One cement: Five sand).	2.00	Sqm	250.00	Rupees Two Hundred Fifty Only	Per Square Meter	500.00
49	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- Charge.	0.09	Cum	1350.00	Rupees One Thousand Three Hundred Fifty Only	Per Cubic Metre	122.00



50	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level including carriage of materials in all leads and lifts as per directions of the Engineer-in-charge. (i) Mild steel and Medium Tensile steel bars.	20.00	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilo-gram	2100.00
51	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.Cement mortar 1:4 (one cement :four coarse sqm sand) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	1.53	Sqm	1020.00	Rupees One Thousand Twenty Only	Per Square Meter	1561.00
52	Providing and fixing chicken mesh in wall surface screws and nails including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	8.49	Sqm	200.00	Rupees Two Hundred Only	Per Square Metre	1698.00
53	Dubbing out an old irregular walls average 10mm thick with including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) cement mortar 1:5 (One cement: Five sand).	8.49	Sqm.	280.00	Rupees Two Hundred Eighty Only	Per Square Metre	2377.00
						<b>Total</b>	<b>98776.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

**CONDITION:-**

(T/S No. 47.83.8.1 Dated 24.01.2025 Amount to Rs. 1,01,73.94.00).

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

## SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,762.00	
Name of Work :- Special Repair to Atal Institute of Medical Super Specialties Shimla-6 at Chamayana.						Earnest Money :- 2,000.00	
(SH:- Providing and Fixing Flashing, Base frame work etc on Roof top of Hospital Building over corridor/bedminton court portion and repairs to roofing).						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No. of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (Agency has to take all safety measures for workers and public below during execution and nothing shall be paid extra for any)	54.00	Kgs.	105.00	Rupees One Hundred Five Only	Per Kilogram	5670.00
2	Steel work in built up tubular (round, square or rectangular hollow tubes trusses etc), including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(Agency has to take all safety measures for workers and public below during execution and nothing shall be paid extra for any) (MAKE TATA)	592.41	Kgs	115.00	Rupees One Hundred Fifteen Only	Per Kilogram	68127.00
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade over an under coat of suitable shade with ordinary paint to approved brand and manufacture including carriage of materials in all leads as per directions of the Engineer-in-Charge. (i) Two or more coats on New work (Agency has to take all safety measures for workers and public below during execution and nothing shall be paid extra for any)	15.00	Sqm	75.00	Rupees Seventy Five Only	Per Square Meter	1125.00

4	Providing and fixing 0.48mm(zero point Forty eight milimetre) thick preapainted G.I. Sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyster of 5 microns over 5 microns primer coating i/c fixing with preapainted iron J or L hooks, bolts and nuts 6mm dia metre with preapainted limpet and bitumen washers complete with all accesoriees as required as per the direction of Engineer-in-charge. (Agency has to take all safety measures for workers and public below during execution and nothing shall be paid extra for any)	21.60	Sqm	1150.00	Rupees One Thousand One Hundred Fifty Only	Per Square Metre	24840.00
						<b>Total</b>	<b>99762.00</b>
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						<b>G.Total</b>	

(T/S No. 4787-19 Dated 24-06-2025 Amount to Rs. 1,02,755/-).

**CONDITION:-**

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 99,973.00	
NAME OF WORK:- A/R & M/O to various Residential Building at Kasumpti Shimla-9. (SH:- Providing and fixing of PVC Flooring in Type-IV Set No. 40 at Kasumpti Shimla-9).						Earnest Money :- 2,000.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 1.50mm(One point Fifty milimetre) thick PVC antistatic vinyl Flooring plain or coloured, carbed or mosaic/metalled finish laid with approved adhesive on sub-floor (damp proofing treatment to be paid for separately) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.	90.38	Sqm	950.00	Rupees Nine Hundred Fifty Only	Per Square Metre	85861.00
2	Providing and fixing 12mm thick water proof shuttering ply for up boards including fixing with nickel plated piano hinges with screws etc carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.	12.60	Sqm	1120.00	Rupees One Thousand One Hundred Twenty Only	Per Square Meter	14112.00
	Quoted rates Percentage in figures					Total	99973.00
	Quoted rates Percentage in words						
						G.Total	

CTIS No - 4791-92. D + E 24-06-2025 Amount = 1,02,972

#### CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

  
Executive Engineer,  
Shimla Division No.I,  
HP PWD Shimla-3.