

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-SRDD-CB-CTR-NIT-2025-26- 5521-45

Dated:- 31-07-2025

To

The Executive Engineer (IT Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- **Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) A (3)1/2024 dated Shimla-2 the 03-01-2024 as the works mentioned in the tender Notice are urgent in nature and in public interest.

Encl:-Copy of NIT

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. Dharni on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.P.W.D. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **08.08.2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 P.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **07.08.2025 up to 4.30 PM** and the application for issue of tender form shall be received on **06.08.2025 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dharni must be accompanied with the application for tender documents. Please note any exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD	Time	Cost of Form
1	R/R damages on various roads under Totu section (SH: Hiring of JCB & Tipper for clearance of landslide).	99080/-	2000/-	One Month	Rs.350 -
2	R/R damages on various roads in Ghanahatti section under Jutogh Sub Division (SH: Hiring of JCB for removal of slips on various roads).	98550/-	2000/-	One Month	Rs.350 -
3	R/R damages on Shal Chanog road Km. 0/00 to 7/330 (SH: Hiring of JCB for removal of slips).	98550/-	2000/-	One Month	Rs.350 -
4	R/R damages on Banuti Pahar road via Nehwat in Km. 0/00 to 17/105 (SH: Hiring of JCB for removal of slips, clearing of drain, dressing of shoulder & catch pit/pot hole etc. in Km. 0/00 to 6/00).	98550/-	2000/-	One Month	Rs.350 -
5	R/R damages on Chauri Ki Ghatti to Yan via Bhad road in Km. 0/00 to 8/500 (SH: Removal of slips at various Rds.).	99910/-	2000/-	One Month	Rs.350 -
6	R/R damages on Shoghi goro Kanawan to Kanhechi road in Km. 0/00 to 8/300 (SH: Removal of slips at various Rds.).	99731/-	2000/-	One Month	Rs.350 -
7	R/R damages on Shoghi Salana Sari road in Km. 0/00 to 12/200 (SH: Removal of slips at various Rds.).	99294/-	2000/-	One Month	Rs.350 -
8	R/R damages on Shoghi Mehli road in Km. 0/00 to 12/375 (SH: Removal of slips at various Rds.).	99860/-	2000/-	One Month	Rs.350 -

9	R/R damages on Taradevi Gamber road in Km. 0/00 to 11/550 (SH: Removal of slips at various Rds.).	99616/-	2000/-	One Month	Rs.350/-
10	R/R damages on (1) Bag to Kayalu road Km. 0/00 to 10/500, (2) Dhanpar to Sandea Gallah Saraiya road Km. 0/99 to 8/100 (SH: Hiring of JCB for removal of slips and debris, cleaning of drain, dressing of berms at various Rds. in various roads).	99645/-	2000/-	One Month	Rs.350/-
11	R/R damages on (1) Sal to Karyali road Km. 0/00 to 3/00 (2) Kadharghat to Domehar road Km. 0/00 to 5/00 (SH: Removal of slips, carriage of debris, cleaning of drain, dressing of berms at various Rds. in various roads).	99645/-	2000/-	One Month	Rs.350/-
12	R/R damages on Slapper Tatapani Suni Luhri road portion road Km. 86/00 to 104/00 (SH: Hiring of JCB for removal of slips and debris, cleaning of drain, dressing of berms at various Rds. in various roads).	99645/-	2000/-	One Month	Rs.350/-
13	R/R damages on various roads under Suni Sub Division (SH: Hiring of JCB for removal of slips on various roads under section Sunni-I & Sunni-II).	98550/-	2000/-	One Month	Rs.350/-
14	R/R damages on various roads under Suni Sub Division (SH: Hiring of JCB for removal of slips on various roads under Thaila section).	98550/-	2000/-	One Month	Rs.350/-
15	R/R damages on various roads under Suni Sub Division (SH: Hiring of JCB for removal of slips on various roads under Badmain section).	98550/-	2000/-	One Month	Rs.350/-
16	A/R & M/O on Tattapani Sunni Luhri road Km. 72/00 to 104/00 (SH: Trimming of grass, Maintenance of shoulder, Maintenance of drains Km. 72/00 to 86/00).	99929/-	2000/-	One Month	Rs.350/-
17	A/R & M/O on Tattapani Sunni Luhri road Km. 72/00 to 104/00 (SH: Trimming of grass, Maintenance of shoulder, Maintenance of drains Km. 86/00 to 104/00).	99929/-	2000/-	One Month	Rs.350/-
18	A/R & M/O Bathora to Panewat road Km. 0/00 to 3/500 (SH: Hiring of JCB rock Breaker for breaking/removal of Rock/boulder at various Rds. in Km. 0/00 to 3/500).	99000/-	2000/-	One Month	Rs.350/-
19	A/R & M/O Slapper Tattapani Suni Luhri road portion Km. 86/00 to 104/000 (SH: Hiring of JCB Rock Breaker for breaking/removal of Rock/boulder from slips at various Rds. in Km. 86/00 to 104/000).	99000/-	2000/-	One Month	Rs.350/-
20	A/R & M/O Malgipul to Dharogra road Km. 0/00 to 8/100 (SH: Hiring of JCB Rock Breaker for breaking/removal of Rock/boulder at various Rds. in Km. 0/00 to 8/100).	99000/-	2000/-	One Month	Rs.350/-
21	A/R & M/O link road Jamog to Junni Km. 0/00 to 2/850 (SH: Trimming of grass, maintenance of earthen shoulder and maintenance of drain in Km. 0/00 to 2/850).	99780/-	2000/-	One Month	Rs.350/-
22	A/R & M/O 16 Mile Sedan road Km.0/00 to 2/600 (SH: Removal of slips at various RDs.).	95232/-	2000/-	One Month	Rs.350/-
23	A/R & M/O Ghanahatti Nehra Bhukoo road Km.0/00 to 8/00 (SH: Removal of slips at various RDs.).	96016/-	400/-	One Month	Rs.350/-
24	R/R damages on Okhroo Nehra via Keru road Km.0/00 to 2/00 (SH: Removal of slips at various Rds.).	98658/-	2000/-	One Month	Rs.350/-
25	R/R damages on Galog Nehra Okroo road Km.0/00 to 11/135 (SH: Removal of slips at various Rds.).	98594/-	2000/-	One Month	Rs.350/-
26	R/R damages on Thachi Rehana road Km.0/00 to 2/500 (ii) Link road to village Bashol Km. 0/00 to 1/300 (SH: Removal of slips at various Rds.).	98852/-	2000/-	One Month	Rs.350/-

27	R/R damages on (i) Dargi Macharyana road Km.0/00 to 11/900 (ii) Banjanghatti Chanawag road Km. 2/225 to 4/500 (SH: Removal of slips at various Rds.).	99527/-	2000/-	One Month	Rs.350/-
28	R/R damages on (i) Thachi Seri Shali road Km.0/00 to 3/00 (ii) Khel Ka Chaura Baggi road Km. 10/00 to 12/225 (SH: Removal of slips at various Rds.).	99916/-	2000/-	One Month	Rs.350/-
29	R/R damages on (i) Simloh Mandhorghat Dargi road Km.0/00 to 2/825 (ii) Dargi Dishti road Km. 0/00 to 3/00 (SH: Removal of slips at various Rds.).	99074/-	2000/-	One Month	Rs.350/-
30	R/R damages on Devnagar Moolbari road Km. 0/00 to 1/200 (SH: Removal of slips in various Rds. In Km. 0/00 to 1/200, Berm filling, Dressing of shoulder and clearing of drain).	99660/-	2000/-	One Month	Rs.350/-
31	A/R & M/O Shakrah Sedan road Km.0/00 to 5/700 (SH: Removal of slips at various RDs.).	95965/-	2000/-	One month	Rs.350/-
32	A/R & M/O Nehra Shaltu Dargot road Km.0/00 to 5/350 (SH: Removal of slips at various RDs.).	96276/-	2000/-	One Month	Rs.350/-
33	A/R & M/O Gharog Nalta road Km.0/00 to 7/00 (SH: Removal of slips at various RDs.).	97069/-	2000/-	One Month	Rs.350/-
34	R/R damages on various roads in Karyali section under sub division Jalog (SH: Hiring of JCB for removal of slips and debris, cleaning of drain, dressing of berms on various road at various Rds.).	99645/-	2000/-	One Month	Rs.350/-

Followings documents should be attached with the application for tenders:-

- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dharni

Certificate


Certified that the tenders called vide this notice inviting tender for 34 (Thirty four) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dharni.

Schedule Of Quantity

Name of Work :- Restoration of rain Damages on various roads in Ghanahatti		Estimated Cost:- 98,550.00
Section Under Jutogh sub Division (SH:--Hiring of JCB for removal of slips on various roads).		Earnest Money:- 2000.00
		Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate	In words	Unit	Amount
		3	4				
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost .including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	90.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	98550
Total Rs.							98550
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharm


SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Shal Changog Road Km. 0/00 to 7/330 (Sh: Hiring of JCB for removal of Slips)

Estimated Cost: - Rs 98550 /- only
Earnest Money : - Rs. 2000 /-only

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	Time: -		
1	Hiring of excavator Cum loader for removal of slips including cost of fuel oil lubricants, wages of operational staff any repair during operation will be carried out at his own risk, cost including carriage of machinery from one place to another at required location. Actual working hours will be accounted for payment and proper disposal of slips will be insured by the contractor and including all leads and lifts & work shall be executed as per the direction of Engineer-in-Charge.	90.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	98550.00
0					Total:	98550.00

Amount Quoted by the Contractor in Percentage

Rs.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharmi

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Banuti Pahar road via Nahwat in Km. 0/00 to 17/105(Sh: Hiring of JCB for removal of slips, clearing of drain, dressing of shoulder & catch pit / pot hole etc. in Km. 0/00 to 6/00	Estimated Cost: - Rs 98550 / - only Earnest Money : - Rs. 2000 /-only
--	--

Estimated Cost: - Rs 98550 /- only
Earnest Money: - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate in		Unit	Amount	
			3	4			figures
1.00	Hiring of excavator Cum loader for removal of slips including cost of fuel oil lubricants, wages of operational staff any repair during operation will be carried out at his own risk, cost including carriage of machinery from one place to another at required location. Actual working hours will be accounted for payment and proper disposal of slips will be insured by the contractor and including all leads and lifts & work shall be executed as per the direction of Engineer-in-Charge.	90.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	98550.00
						Total:	98550.00

Note : (i) All the material will procured by the contractor him self.

Draft Schedule of Quantity approved for Rs.98550/- only (Rupees
Ninety Eight Thousand Five Hundred Fifty Only) At Sr.
No. 86 year 2025-26

Executive Engineer,
Shimla Rural Division
HPPWD, Dhami

Schedule Of Quantity

Name of Work :- Restoration of Rain damage on Chauri ki Ghatti to Yan via Bhad road km. 0/00 to 8/500 (SH:- Removal of Slips at Various Rds)

Estimated Cost:- 99,910.00
Earnest Money:- 2000.00
Time:- One Month.

S.No	Description of Work	No. of Qty.		Rate In figures	In words	Unit	Amount
		3	4				
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. The rate including octroi, royalty, Malkana toll tax, GST or any other taxes inputfor or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1110.11	Cum	90.00	Rupees Ninety Only	Per cubic metre	99910
Total Rs.							99910
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharmi

Schedule Of Quantity							
Name of Work :- R/R Damages on Shoghi Goro Kanawan to Kanhechi road km.							Estimated Cost:- 99,731.00
0/00 to 8/300 (SH:- Removal of Slips at various Rds)							Earnest Money:- 2,000.00
							Time:- One Months.
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2					7	8
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. The rate including octroi, royalty, Malkana toll tax, GST or any other taxes inputor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	1108.12	Cum	90.00	Rupees Ninety Only	Per cubic metre	99731
Total Rs.							99731
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharmi. 18/02

Schedule Of Quantity

Name of Work :- R/R Damages on Shoghi Salana Sari road km. 0/00 to 12/200 (SH:-

Estimated Cost:- 99,294.00

Removal of Slips at various Rds)

Earnest Money:- 2,000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. The rate including octroi, royalty, Malkana toll tax, GST or any other taxes inputtor or output by this contract shall be payable by the contractor and Government shall not entetain any claim whatsoever in this respect of the same.	1103.27	Cum	90.00	Rupees Ninety Only	Per cubic metre	99294
	Total Rs.						99294
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will,procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharmu

Schedule Of Quantity

Estimated Cost:- 99,860.00

Name of Work :- Restoration of Rain damage on Shoghi Mehli road km. 0/00 to 12/375 (SH:- Removal of Slips at Various Rds)

Earnest Money:- 2000.00
Time:- One Month:-

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2					6	7
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 16.1. The rate including octroi, royalty, Malkana toll tax, GST or any other taxes inputtor or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1109.55	Cum	90.00	Rupees Ninety Only	Per cubic metre	99860
Total Rs.							99860
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharmi. 

Schedule Of Quantity

Name of Work :- Restoration of Rain damage on Tara Devi Gumber road km. 0/00 to 11/550 (SH:- Removal of Slips at Various Rds)	Estimated Cost:- 99,616.00
	Earnest Money:- 2000.00
	Time:- One Month.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	5	6		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. The rate including octroi, royalty, Malkana toll tax, GST or any other taxes Inputtor or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	1106.84	Cum	90.00	Rupees Ninety Only	Per cubic metre	99616
Total Rs.							99616
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dhami. *[Signature]*

Schedule Of Quantity							Estimated Cost:- 99,645.00
Name of Work :- Restoration of Rain damage on (1)Bag to Kayalu road km. 0/00 to 10/500. (2)Dhanpar to Sandoa Gallah Saraiya road km 0/00 to 8/100 (SH:- Hiring of JCB for removal of slips and debris ,cleaining of drain , dressing of berms at various Rd,s in various roads)							Earnest Money:- 2000.00
							Time:- One Months.
S No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5		6/7	8
1	Hiring of JCB-Excavator cum loader for removal of Land slides slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	91.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	99645
Total Rs.							99645
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhami. 

Schedule Of Quantity

Name of Work :- Restoration of Rain damage on (1) Sal to Karyali road km 0/00 to 3/00 (2) Kadharghat to Domehar road km 0/00 to 5/00(SH:- Removal of slips , carriage of debris,cleaining of drain , dressing of berms at various Rd,s in various roads.)							Estimated Cost:- 99,645.00
							Earnest Money:- 2000.00
							Time:- One Months.
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5		6	7
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	91.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	99645
Total Rs.							99645
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharmi, Him

Schedule Of Quantity

Name of Work :- Restoration of Rain damage on Slapper Tattapani Sunni Luhri Portion road km. 86/00 to 104/00 (SH:- Hiring of JCB for removal of slips and debris ,cleaning of drain , dressing of berms at various Rd,s in km 86/00 to 104/00.)

Estimated Cost:- 99,645.00
Earnest Money:- 2000.00
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5		6	7
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff. any repair during operation will be carried out at his risk and cost .including carriage of Machinery from one place to another at required location.actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	91.00	Hour	1095.00	Rupees One Thousand Niney Five Only	Per Hour	99645
Total Rs.							99645
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharmu.

Schedule Of Quantity

Name of Work :- Restoration of rain Damages on various roads under Sunni Sub-division (SH:--Hiring of JCB for removal of slips on various roads under Section Sunni-I & Sunni-II).

Estimated Cost:- 98,550.00
Earnest Money:- 2000.00
Time:- One Month

S.No	Description of Work	No. of Qty.		Rate	In words	Unit	Amount
		3	4	In figures			
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost .including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow/.slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	90.00	Hour	1095.00	Rupees One Thousand and Ninety Five Only	Per Hour	98550
Total Rs.							98550
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharti.

Schedule Of Quantity

Name of Work :- Restoration of rain Damages on various roads under Sunni Sub-division (SH:--Hiring of JCB for removal of slips on various roads under Thaila Section).

Estimated Cost:- 98,550.00
Earnest Money:- 2000.00
Time:- One Month

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	5	In words		
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	90.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	98550
Total Rs.							98550
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
 Shimla Rural Division,
 HP PWD, Dharti

Schedule Of Quantity

Name of Work :- Restoration of rain Damages on various roads under Sunni Sub-division (SH:--Hiring of JCB for removal of slips on various roads under Badmain Section).						Estimated Cost:- 98,550.00
						Earnest Money:- 2000.00
						Time:- One Month

S.No	Description of Work	No. of Qty.		Rate In figures	In words	Unit	Amount
		3	4				
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost .including carriage of Machinery from one place to another at required location.actual working will be accounted for payment and proper disposal of snow./slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	90.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	98550
Total Rs.							98550
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP.PWD, Dhargi

Schedule Of Quantity

Name of Work :- Annual Repair & Maintenance on Tattapani Sunni Luhri road						Estimated Cost:- 99,929.00
km.72/00 to 104/00 (SH:- Trimming of grass, Maintenance of Shoulder,Maintenance of drains km. 72/00 to 86/00)						Earnest Money:- 2,000.00
						Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2						
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	7500	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	33750
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2163.00	Sqm	24.50	Rupees Twenty Four and Paise Fifty Only	Per Square metre	52994
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2930.00	Rmt.	4.50	Rupees Four and Paise Fifty Only	Per Running Metre	13185
	Total Rs.						99929
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhari

Schedule Of Quantity

Name of Work :- Annual Repair & Maintenance on Tattapani Sunni Luhri road km.72/00 to 104/00 (SH:- Trimming of grass, Maintenance of Shoulder, Maintenance of drains km. 86/00 to 104/00)

Estimated Cost:- 99,929.00
Earnest Money:- 2,000.00
Time:- One Months.

S.No	Description of Work	No. of Qty.			Rate		Unit	Amount
		3	4	5	In figures	In words		
1	2							
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	7500	Sqm	4.50		Rupees Four and Paise Fifty Only	Per Square metre	33750
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2163.00	Sqm	24.50		Rupees Twenty Four and Paise Fifty Only	Per Square metre	52994
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2930.00	Rmt	4.50		Rupees Four and Paise Fifty Only	Per Running Metre	13185
	Total Rs.							99929
	Amount Quoted by the Contractor in Percentage							
	Note :- All the material will procured by the contractor him self							

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dhara

Schedule Of Quantity

Name of Work :- A/R & M/O Bathora to Panewat road km. 0/00 to 3/500 (SH:- Hiring of JCB Rock Breaker for breaking/ removal of Rock/ boulder at various Rds in km. 0/00 to 3/500)

Estimated Cost:- 99,000.00
Earnest Money:- 2,000.00
Time:- One Months.

S No	Description of Work	No. of Qty.		Rate		In words		Unit	Amount
		3	4	5	6	7	8		
1	Hiring of Excavator- cum- Loader for removal of rock /boulders including cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk & cost, including carriage of machinery from one place to another at required location. Actual working will be accounted for payment & proper disposal of snow, slips will be insured by the contractor & including all leads & lifts & work will be executed as per direction of Engineer- in - Charge average Quantity lifts (47.05 cum/hour)	55.00	Hour	1800.00	Rupees One Thousand Eight Hundred Only	Per Hour	99000		
Total Rs									99000
Amount Quoted by the Contractor in Percentage									
Note :- All the material will procured by the contractor him self									

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhamai 

Schedule Of Quantity

Name of Work :- A/R & M/O Slapper Tattapni Suni Luhri road portion km. 86/00 to 104/000 (SH:- Hiring of JCB Rock Breaker for breaking/removal of Rock /boulder from Slips at various Rds in Km. 86/00 to 104/000)							Estimated Cost:- 99000.00
							Earnest Money:- 2,000.00
							Time:- One Months.
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	5	6		
				In figures	In words		
1	2					7	8
1	Hiring of Excavator- cum- Loader for removal of rock /boulders including cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk & cost, including carriage of machinery from one place to another at required location. Actual working will be accounted for payment & proper disposal of snow, slips will be insured by the contractor & including all leads & lifts & work will be executed as per direction of Engineer- in - Charge average Quintity lifts (47.05 cum/hour)	55.00	Hour	1800.00	Rupees One Thousand Eight Hundred Only	Per Hour	99000
Total Rs							99000
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharmu 

Schedule Of Quantity

Name of Work :- A/R & M/O Malgipul to Dharogra road km. 0/00 to 8/100 (SH:- Hiring of JCB Rock Breaker for breaking/ removal of Rock/ boulder at various Rds in km. 0/00 to 8/100)

Estimated Cost:- 99,000.00
Earnest Money:- 2,000.00
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Hiring of Excavator- cum- Loader for removal of rock /boulders including cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk & cost, including carriage of machinery from one place to another at required location. Actual working will be accounted for payment & proper disposal of snow, slips will be insured by the contractor & including all leads & lifts & work will be executed as per direction of Engineer- in - Charge average Quintity lifts (47.05 cum/hour)	55.00	Hour	1800.00	Rupees One Thousand Eight Hundred Only	Per Hour	99000
	Total Rs						99000
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dharmi


Schedule Of Quantity

Name of Work :- A/R & M/O link road Jamog to Junni km. 0/00 to 2/850. (SH:-
Trimming of grass, Maintenance of Earthen Shoulder and Maintenance of Drain in
km. 0/00 to 2/850)

Estimated Cost:- 99,780.00
Earnest Money:- 2,000.00
Time:- One Months.

S No	Description of Work	No of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	3250	Sqm	4 50	Rupees Four and Paise Fifty Only	Per Square metre	14625
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	3250.00	Sqm	24 00	Rupees Twenty Four Only	Per Square metre	78000
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	1590.00	Rmt.	4 50	Rupees Four and Paise Fifty Only	Per running metre	7155
Total Rs							99780
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dharti.

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance of 16 Mile Sedan Road Km. 0/00. to 2/600 (Sh: Removal of Slips at various RDs.)

Estimated Cost :- Rs 95232/- only
Earnest Money :- Rs. 2000/- only

Time :-

One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			Figures	Figures		
1	Removal of land slides slip clearance Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3.5 and 1611 as per the directions of Engineer-in-Charge.	971.75	Cum	98.00	Per Cubic Meter	95232.00
0					Total:	95232.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla/Rural Division,
HPPWD, Dharmi

Name of Work:- Annual Repair & Maintenance of Ghanahatti Nehra Bhukho Road Km. 0/00 to 8/00 (Sh: Removal of Slips at various RDs.

Name of Work:- Annual Repair & Maintenance of Ghanahatti Nehra Bhukho Road Km. 0/00 to 8/00 (Sh: Removal of Slips at various RDs.

Estimated Cost: - Rs 96016 /- only

Earnest Money :- - Rs. 2000 /-only

Time: -

One Month

Rate in figures

Unit

Amount:

S No	Sub head and items of work	Dty.		Rate in figures	Unit	Amount
1	Removal of land slides slip clearance Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3.5 and 1611 as per the directions of Engineer-in-Charge.	3	Cum	98.00	Rupees Ninety Eight Only Per Cubic Meter	96016.00
Total:						96016.00

Note : (i) All the material will procured by the contractor him self.

Draft Schedule of Quantity approved for Rs.96016/- only (Rupees
Ninety Six Thousand Sixteen Only) At Sr. No. 2 year 2025-26

~~Executive Engineer,~~
Shimla Rural Division
HPPWD, Dharni

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain damages on Okhroo Nehra via Keru Road Km. 0/00 to 2/000 (Sh:- Removal of slips at various RDs.)

Estimated Cost: - Rs 98658 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	5		
1	2	3	4	5	6	7
1	Removal of land slide slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	1038.50 Cum	95.00	Rupees Ninety Five Only	Per cubic metre	98658.00
0					Total:	98658.00

Amount Quoted by the Contractor in Percentage

Rs.


Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain damages on Galog Nehra Okhroo Road Km. 0/00 to 11/135 (Sh:- Removal of slips at various RDs.)

Estimated Cost: - Rs 98594 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount
			figures	5		7
1	2	3	4	5	6	7
1	Removal of land slide slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in lift upto all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	1037.83 Cum	95.00	Rupees Ninety Five Only	Per cubic metre	98594.00
0					Total:	98594.00

Amount Quoted by the Contractor in Percentage

Rs.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharmi

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain damages on Thachi Rehana Road Km. 0/00 to 2/500 (ii) Link Road to village Bashol Km. 0/00 to 1/300 (Sh:- Removal of slips at various RDs.)

Estimated Cost :- Rs 98852/- only
Earnest Money :- Rs. 2000/- only

Time :- One Month

S. No.	Sub head and items of work	Qty.	Rate		One Month		
			Unit	Amount	Unit	Amount	
1	2	3	4	5	6	7	
1	Removal of land slide slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	1040.55	Cum	95.00	Rupees Ninety Five Only	Per cubic metre	98852.00
0							Total: 98852.00

Amount Quoted by the Contractor in Percentage

Rs.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharmi

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain damages (i) Dargi Macharyana Juddoo Road Km. 0/00 to 11/900 (ii) Banjanghatti Chanawag Road Km. 2/225 to 4/500 (Sh:- Removal of slips at various RDs.)

Estimated Cost :- Rs. 99527 /- only
Earnest Money :- Rs. 2000 /- only

Time :- One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount	
			figures	5			
1	Removal of land slide slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	1047.65	Cum	95.00	Rupees Ninety Five Only	Per cubic metre	99527.00
0							Total: 99527.00

Amount Quoted by the Contractor in Percentage

Rs.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain damages on (i) Thachi Seri Shaili Road Km. 0/00 to 3/00 (ii) Khel Ka Chaura Baggi Road Km. 10/00 to 12/225 (Sh:- Removal of slips at various RDs.)

Estimated Cost :- Rs 99916 /- only
Earnest Money :- Rs. 2000 /-only

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	Time :-		
1	2	3	4	5	6	7
1	Removal of land slide slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	1051.75 Cum	95.00	Rupees Ninety Five Only	Per cubic metre	99916.00
0					Total:	99916.00

Amount Quoted by the Contractor in Percentage

Rs.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharampur

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain damages (i) Simloh Mandhorphat Dargi Via Nagar Road Km. 0/00 to 2/825 (ii) Dargi Dishti Road Km. 0/00 to 3/00 (Sh:- Removal of slips at various RDs.)

Estimated Cost: - Rs 99074 /- only
Earnest Money : - Rs. 2000 /- only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	5		
1	2	3	4	5	6	7
1	Removal of land slide slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in lift upto all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	1042.88	Cum	95.00	Rupees Ninety Five Only	Per cubic metre
0						
					Total:	99074.00

Amount Quoted by the Contractor in Percentage

Rs.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharni

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Devnagar Moolbari Road Km. 0/00 to 1/200 (Sh: Removal of Slips in various Rds. in Km. 0/00 to 1/200, Berm filling, Dressing of Shoulder, Clearing of drain)

Estimated Cost - Rs 99660 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount	
			figures				
1	Removal of land slides slip clearance Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3.5 and 1611 as per the directions of Engineer-in-Charge.	840.75	Cum	80.00	Rupees Eighty Only	Per cubic metre	67260.00
2	Maintenance of Earthen shoulder (stripping of excess soil) , Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 as per the direction of Engineer-in-Charge.	1944.00	Sqm	15.00	Rupees Fifteen Only	Per Square Meter	29160.00
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of material upto all leads and lifts as per the direction of Engineer-in-charge.	1080.00	Rmt.	3.00	Rupees Three Only	Per Running Meter	3240.00
0						Total:	99660.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharmi

Name of Work:- Annual Repair & Maintenance of Shakrah Sedan Road Km. 0/00 to 5/700 (Sh: Removal of Slips at various RDs.)

Estimated Cost: - Rs 95965 /- only
Earnest Money : - Rs. 2000 /-only

S. No.	Sub head and Items of work	Qty.	Time: -		One Month		
			Rate	Unit	Amount		
1	2	3	4	5	6	7	
			Figures				
1	Removal of land slides slip clearance Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3.5 and 1611 as per the directions of Engineer-in-Charge.	979.23	Cum	98.00	Rupees Ninety Eight Only	Per Cubic Meter	95965.00
0						Total:	95965.00

Amount Quoted by the Contractor in Percentage

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharam
Dharam

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance of Nehra Shattu Dargot Road Km. 0/00 to 5/350 (Sh: Removal of Slips at various RDs.)

Estimated Cost:- Rs 96276/- only
Earnest Money :- Rs. 2000/-only

Time:-

One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount	
			figures	figures			
1	Removal of land slides slip clearance Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3.5 and 1611 as per the directions of Enigneer-in-Charge.	982.41	Cum	98.00	Rupees Ninety Eight Only	Per Cubic Meter	96276.00
0						Total:	96276.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division,
HPPWD, Dhama

SCHEDULE OF QUANTITY

Name of Work:- Annual Repair & Maintenance of Gharog Nalta Km. 0/00 to 7/00 (Sh: Removal of slips at various RDs)

Estimated Cost:- Rs 97069 /- only
Earnest Money :- Rs. 2000 /-only
Time:- One Month

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount
			3	4		
1	Removal of land slides slip clearance Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3.5 and 1611 as per the directions of Engineer-in-Charge.	990.50	Cum	98.00	Per Cubic Meter	97069.00
0					Total:	97069.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharmi

Schedule Of Quantity

Name of Work :- Restoration of rain Damages on various roads in Karyali Section Under Sub Division Jalog (SH:- Hiring of JCB for removal of slips and debris, Cleaning of drain, dressing of berms on various road at various Rds)

Estimated Cost:- 99,645.00
Earnest Money:- 2000.00
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	5	In words		
1	Hiring of JCB Excavator cum loader for removal of Land slides / slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow, slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	91.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	99645
Total Rs.							99645
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dhamai *Sharma*