

Dated:- 08-07-2025


To

The Executive Engineer (IT Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- **Notice Inviting Tender for uploading the same on departmental website.**


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) A (3)1/2024 dated Shimla-2 the 03-01-2024 as the works mentioned in the tender Notice are urgent in nature and in public interest.

Encl:-Copy of NIT


Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.


Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. Dhami on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **17.07.2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 P.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **16.07.2025 up to 4.30 PM** and the application for issue of tender form shall be received on **15.07.2025 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dhami must be accompanied with the application for tender documents. Please not any exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD	Time	Cost of Form
1	Special repair to Govt. S.S.S. at Kaina-1 Tehsil & Distt. Shimla (SH: C/O R/Wall in school campus) Deposit work.	99367/-	2000/-	One Month	Rs.350/-
2	C/O Jawahar Lal govt. College of fine Arts at Loharav, Distt. Shimla (SH: Providing fixing aluminium door, window & flooring for canteen for students).	93630/-	2000/-	One Month	Rs.350/-
3	Geological investigation for construction of bridge at Khaira on Slapper Tatapani Suni Luhri road Km. 72/00 to 86/000. Job No.2.	98185/-	2000/-	One Month	Rs.350/-
4	Geological investigation for construction of bridge at near Chaba on Slapper Tatapani Suni Luhri road Km. 72/00 to 86/000. Job No.1.	98550/-	2000/-	One Month	Rs.350/-
5	A/R & M/O link road to village Khatnol Km. 0/00 to 10/00 (SH: Trimming of grass and maintenance of earthen shoulder, maintenance of drain in Km. 5/500 to 8/00).	99915/-	2000/-	One Month	350/-
6	Geological investigation for construction of Liabrary at Hanuman Parisar at Suni Tehsil Suni, Distt. Shimla H.P. Job No.2.	94900/-	2000/-	One Month	Rs.350/-

7	Geological investigation for construction of Govt. Polytechnic at Basantpur Tehsil Suni Distt. Shimla, H.P. Job No.1.	98550/-	2000/-	One Month	Rs.350/-
---	---	---------	--------	-----------	----------

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dhamsi

Certificate

Certified that the tenders called vide this notice inviting tender for 7 (Seven) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dhamsi.



SCHEDULE OF QUANTITY

Name of Work:- Special Repair to Govt. Senior Sec. School at Kaina-1 Tehsil & District Shimla (Sh: Construction of Retaining Wall in School Campus) Deposit Work

Estimated Cost - Rs 99367 /- only
Earnest Money - Rs 2000 /- only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Time :-			One Month	
			Rate	figures	Unit	Amount	
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORDD specification directed by Engineer-in Charge.	2.99	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	698.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORDD specification directed by Engineer-in-Charge.	6.84	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2438.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm (Twenty millimeter) nominal mix including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	19.78	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	90988.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (i) Granular material, including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	4.31	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	3628.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	9.50	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	1615.00
0	Total:						99367.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dhami

SCHEDULE OF QUANTITY

Name of Work:- Construction of Jawahar Lal Govt. College of Fine Arts at Loharav, District Shimla (Sh: Providing fixing aluminium door,window & flooring for canteen for students)

Estimated Cost: - Rs 93630 /- only
Earnest Money : - Rs. 2000 /-only
Time: - One Month

Sub head and items of work	Qty.	Rate		Unit	Amount
		4	5		
2	3	4	5	6	7
Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-incharge. (Glazing, paneling and dash fasteners to be paid for separately) : Powder coated aluminium (minimum thickness of powder coating 50 micron) including carriage of material upto all leads & lifts as per the direction of Engineer in Charge.	72.78 kg.	420.45	Rupees Four Hundred Twenty and Paise Forty Five Only	Per Kilogramme	30600.00
Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-incharge. (Glazing, paneling and dash fasteners to be paid for separately) : Powder coated aluminium (minimum thickness of powder coating 50 micron) For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) including carriage of material upto all leads & lifts as per the direction of Engineer in Charge.	56.77 kg.	482.40	Rupees Four Hundred Eighty Two and Paise Forty Only	Per Kilogramme	27386.00
3 Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : including carriage of material in all leads and lifts as per direction of the Engineer in Charge. 300x16 mm	2.00 No.	239.60	Rupees Two Hundred Thirty Nine and Paise Sixty Only	Each	479.00
4 Providing and fixing aluminium tower bolts, ISI marked,anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : including carriage of material in all leads and lifts as per direction of the Engineer in Charge. 200x10 mm	4.00 No.	85.60	Rupees Eighty Five and Paise Sixty Only	Each	342.00
5 Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : including carriage of material in all leads and lifts as per direction of the Engineer in Charge. 125 mm	4.00 No.	57.55	Rupees Fifty Seven and Paise Fifty Five Only	Each	230.00



Providing & fixing ACP Sheet (excluding the cost of frame work)	31.80	Sqm	650.00	Rupees Six Hundred Fifty Only	Per Square Meter	20670.00
Providing and fixing PVC flooring 1.50 mm thick including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	16.38	Sqm	850.00	Rupees Eight Hundred Fifty Only	Per Square Meter	13923.00
					Total:	93630.00

Amount Quoted by the Contractor in Percentage	Rs.
--	------------

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,
Shimla Rural Division,
HPPWD, Dharam



Schedule Of Quantity						Estimated Cost:- 98,185.00	
Name of Work :- Geological Investigation for Construction of bridge at Khaira on Slapper Tatapani Suni Luhri road km. 72/000 to 86/000 (Job No.2)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia for investigation of soil rock conditions at site of work including mobilization and demobilization for drilling shifting of machinery to bore site making platform and water arrangement for drilling. The scope of work includes preservation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of materials within all leads and lift as per the direction of Engineer-in Charge.	13.45	Rmt.	7300.00	Rupees Seven Thousand Three Hundred Only	Per running metre	98185
	Total Rs.						98185
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhadi.



Schedule Of Quantity						Estimated Cost:- 98,550.00	
Name of Work :- Geological Investigation for Construction of bridge at Near Chaba on Slapper Tatapani Suni Luhri road km. 72/000 to 86/000 (Job No.1)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
1	2	3	4	In figures	In words		
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia for investigation of soil rock conditions at site of work including mobilization and demobilization for drilling shifting of machinery to bore site making platform and water arrangement for drilling. The scope of work includes preservation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of materials within all leads and lift as per the direction of Engineer-in Charge.	13.50	Rmt.	7300.00	Rupees Seven Thousand Three Hundred Only	Per running metre	98550
	Total Rs.						98550
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhamsi.



Schedule Of Quantity						Estimated Cost:- 99,915.00	
Name of Work :- A/R & M/O link road to Village Khatnol km. 0/00 to 10/00. (SH:- Trimming of grass and Maintenance of Earthen Shoulder , Maintenance of Drain in km. 5/500 to 8/00)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3250	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	14625
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3250.00	Sqm	24.00	Rupees Twenty Four Only	Per Square metre	78000
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	1620.00	Rmt.	4.50	Rupees Four and Paise Fifty Only	Per running metre	7290
	Total Rs						99915
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dhani.



Schedule Of Quantity						Estimated Cost:- 94,900.00	
Name of Work :- Geological Investigation for Construction of Library at Hanuman Parisar at Suni Tehsil Suni, Distt Shimla . HP. Job No.2						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia for investigation of soil rock conditions at site of work including mobilization and de- mobilization for drilling shifting of machinery to bore site making platform and water arrangement for drilling. The scope of work includes preservation of core including relevant tests and submission of geotechnical report of complex site of work including carriage of materials within all leads and lift as per the direction of Engineer-in Charge.	13.00	Rmt.	7300.00	Rupees Seven Thousand Three Hundred Only	Per running metre	94900
Total Rs.							94900
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharm.



Schedule Of Quantity						Estimated Cost:- 98,550.00	
Name of Work :- Geological Investigation for Construction of Govt. Polytechnic at Basantpur Tehsil Suni Distt Shimla , HP (Job No.1)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Sub Soil Investigation in all type of soil/strata by drilling of bore holes of Nx Size 75 mm dia for investigation of soil rock conditions at site of work including moblization and de-mobiization for drilling shifting of machinery to bore site making platform and water arrangement for drilling. The scope of work includes preservation of core including relevant tests and submission of geotechnical report of comlex site of work including carriage of materials within all leads and lift as per the direction of Engineer-in Charge.	13.50	Rmt.	7300.00	Rupees Seven Thousand Three Hundred Only	Per running metre	98550
Total Rs.							98550
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP,PWD, Dharm,

