



O/o the Executive Engineer, Karchham Division, HP.PWD., Bhabanagar-172115.

Web: www.hp.pwd.gov.in, e-mail: ee-karc-hp@ntc.in DDO 16 NR04-651 Phone No-01786-292897

No:- PW- BHNR-B&R-EA-I-Tender Notice/2025-26- 3905

Registered
Dated:- 18-7-025

To

The Executive Engineer (IT Cell),
Nigam Bihar, Himachal Pradesh Shimla-2.

Subject:-


Publication of Notice Inviting Tender.

Sir,

I am enclosing herewith the "Notice Inviting Tender" alongwith "Schedule of Quantity" for favour of information and necessary action. The work attached in list is very urgent nature. It is requested that the same may kindly be got published.

DA: - Notice Inviting Tender/Schedule of Quantity.

Yours Faithfully


Executive Engineer,
Karchham Division,
HP.PWD., Bhabanagar.



O/o the Executive Engineer, Karchham Division, HP.PWD. Bhabanagar
Web: www.hppwd.gov.in, Email: ee-karc-hp@nic.in Phone No.-01786-292897

NOTICE INVITING TENDER


Sealed percentage rate tender(s) on PWD form No.6 &8 are hereby invited by the Executive Engineer, Karchham Division, HP.PWD., Bhabanagar District Kinnaur (H.P) on behalf of the Governor of H.P for the following works from the registered contractors in HP.PWD., in appropriate class to reach in this office on **30.07.2025** up to 11.00 A.M. and will be opened on the same day at 11.30A.M. in the presence of Contractors or their authorized representative who wish to be present at that time. The application for obtaining the tender form will be received on **29.07.2025** i.e. 11.00 A.M. to 2.00 P.M. and the tender form can be had from this office against this cash payment (Non- refundable) on the same day from 2.00 P.M. to 5.00 P.M. No application shall be entertained without earnest money or through FAX.

Earnest money shall be in shape of NSC/FDR duly pledged in favour of Executive Engineer, Karchham Division, HP.PWD., Bhabanagar District Kinnaur, H.P. Ambiguous/ Telegraphically/conditional tenders or tender through FAX shall not be entertained/ considered in any case.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Cost of Form	Eligible class of contractor	Time Period
1	C/o link road from Palingche to Shong Km. 0/00 to 2/600 (SH:-complete Geotechnical Investigation for construction of bridge on bore hole "B" of right side abutment).	99,400/-	2000/-	350/-	Class-D	15 Days
2	C/o link road from Palingche to Shong Km. 0/00 to 2/600 (SH:-complete Geotechnical Investigation for construction of bridge on bore hole "B" of left side abutment).	92,300/-	2000/-	350/-	Class-D	15 Days
3	Dismantling of old building of Bee Keeping Center at Urni Distt. Kinnaur HP (SH:- Dismantling of roofs door & window and stone masonry)	63,284/-	1300/-	350/-	Class-D	One Month
4	Preparation of detailed estimate of construction of Eklavya Model Residential School at Nichar Distt. Kinnaur HP for Staff Quarter No.3	95,000/-	2000/-	350/-	Class-D	One Month
5	Preparation of detailed estimate of construction of Eklavya Model Residential School at Nichar Distt. Kinnaur HP for Principal residence.	95,000/-	2000/-	350/-	Class-D	One Month
6	R/R damages on various roads under Karchham Division. (SH:-Hiring of Excavator cum loader in working condition for removal of slips/boulders/debris on Palingi to Nichar road Km. 0/00 to 16/00, Ponda to Bari road Km. 0/00 to 5/200 and Nichar to Wangtoo road Km. 0/00 to 4/240).	98,750/-	2000/-	350/-	Class-D	15 Days

SPECIAL CONDITIONS:-


1. The material shall be arranged by the contractor himself.
2. The detail of documents to be attached with the application is given below.
 - i Latest copy of enlistment/ renewal.
 - ii Copy of Pan Card.
 - iii Copy of GST No.
3. The offer of the tender shall be kept open for 90 days
4. Tender received after the specified time/date shall not be opened.
5. Executive Engineer, Karchham Division, HP.PWD, Bhabanagar District Kinnaur H.P. reserves the right to reject any or all tender/s without assigning any reasons.
6. If due to any unforeseen reasons the office of the Executive Engineer, Karchham Division, HP.PWD, Bhabanagar District Kinnaur remain closed on the notified date of sale and receipt of tender, tender will be sold and received/opened the next working day of same specified time.
7. Tenderers may contact the Executive Engineer for any further information they may require during the working day/ office hours.
8. The contractors are requested to insert the rate of each in words as well as in figures failing which Executive Engineer reserves the right to reject any or all tenders.
9. The labour cess shall allow/ deduction @ 2% TDS amount of GST (1% CGST and 1% SGST).
10. The labour cess @ 1% will be deducted from the gross amount of the bill
11. All the works are of urgent nature hence the contractor already having two works are not eligible to participate for the tendering.
12. A contractors enlisted in a particular class shall be eligible to tender for his own class and one step below as per Govt. notification.
13. The Contractor will have to submit the proof of registration under Employees Provident Funds & Miscellaneous Provision Act, 1952 before award of work.
14. Cement should be purchased from H.P. State Civil Supply Corporation.
15. GST will be deducted from each bill as per latest instruction of the Government.
- 16. The rates beyond over +5% will be rejected. Besides this the additional performance security will to borne @ 20% and 30% for unbalanced bid in case rates is lower than 10% but upto 20% and lower than 20% upto 30% respectively. The tender beyond the limit of -30% will also be accepted.**


Executive Engineer,
Karchham Division,
HP.PWD., Bhabanagar.

No.PW/BHNR/B&R/EA-I-Tender Notice/2025-26- 3896-3904 Dated:- 18 /07/2025

Copy forwarded the following for information to the:-

1. The Engineer-in-Chief, HP.PWD, Shimla.
2. The Chief Engineer (SZ) HP.PWD, Shimla-1.
3. The Superintending Engineer, 11th Circle, HP.PWD, Rampur.
4. All the Assistant Engineer working under this division.
5. A/B & D/B in this office.
6. Notice board of this office.


Executive Engineer,
Karchham Division,
HP.PWD., Bhabanagar.



O/o the Executive Engineer, Karchham Division, HP.PWD., Bhabanagar-172115.

Web: www.hppwd.gov.in e-mail: ee-karc-hpx@nic.in DDO KNR04-651 Phone No-01786-292897

Certificate

Certified that the tenders of the works invited vide this office
NIT No.PW/BIENR/B&R/EA-1-Tender Notice/2025-26- 3896-3904 Dated:- 18/7/25
is urgent nature in exigency of Public interest.

**Executive Engineer,
Karchham Division,
HP.PWD., Bhabanagar.**

345

Draft Schedule of Quantity

Estimated Cost:-
Earnest Money:-
Time:-

99400.00
2000
15 Days

Name of work - C/O Link road from Palingche to Shong KM 0/00 to 2/600

Job No:-1

Sub Head:- Complete Geotechnical Investigation for Construction of Bridge on bore hole "B" of Right side abutment

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Sub soil investigation in all type of soil/ strata by drilling of bore holes of Nx size 75 mm dia for investigation of soil rock conditions at site of work determination of silt factor including mobilization for drilling shifting of machinery to bore site making platform and water arrangement for drilling The scope of work includes relevant tests and submission of Geotechnical report of complex site of work including carriage of materials within all leads lift as per the direction of engineer-in-Charge	14.00	7100.00	Rupees Seven Thousand One Hundred Only	Per running meter	99400.00
					Total	99400.00

Executive Engineer
Karghnam Division,
HPPWD, at Bhaba Nagar

Draft Schedule of Quantity

Estimated Cost:-
Earnest Money -
Time:-


92300.00
2000
15 Days

Name of work - C/O Link road from Palingche to Shong KM 0/00 to 2/600

Sub Head:- Complete Geotechnical Investigation for Construction of Bridge on bore hole "B" of left side abutment

Job No:-2

Sr No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Sub soil investigation in all type of soil/ strata by drilling of bore holes of Nx size 75 mm dia for investigation of soil rock conditions at site of work, determination of silt factor including mobilization for drilling shifting of machinery to bore site making platofrm and water arrangement for drilling The scope of work includes relevant tests and submission of Geotechnical report of complex site of work including carriage of materials within all leads lift as per the direction of engineer-in-Charge	13.00	7100.00	Rupees Seven Thousand One Hundred Only	Per running meter	92300.00
					Total	92300.00


Executive Engineer,
Karcham-Division,
HPPWD, at Bhaba Nagar

Draft Schedule of Quantity

Estimated Cost:-
Earnest Money:-
Time :-

63284.00
1300
One Month

28

Name of work:- Dismantling of old building of Bee Keeping Center at Urni Distt. Kinnaur HP
Sub Head:- Dismantling of roofs door & window and stone masonry

Job No-3

Sr No.	Description of item	Qty	Rate		Unit	Amount
			In Figure	In Words		
1	Dismantling roofing including ridges, hips, valleys and gutters etc. and stacking the material within 50 metres lead of G.S. Sheet including carriage of material, labour, tool and plants through all modes of transportation within all leads and lifts as per PWD specification and as per the direction of the Engineer-in-charge.	90.32	131.80	Rupees One Hundred Thirty One and Eighty Paise Only	Per square metre	11904.00
2	Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead of sectional area 40 square centimetres and above including carriage of material, labour, tool and plants through all modes of transportation within all leads and lifts as per PWD specification and as per the direction of the Engineer-in-charge.	2.17	3573.35	Rupees Three Thousand Five Hundred Seventy Three and Thirty Five Paise Only	Per Cubic meter	7754.00
3	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead including carriage of material, labour, tool and plants through all modes of transportation within all leads and lifts as per PWD specification and as per the direction of the Engineer-in-charge.	45.90	918.40	Rupees Nine Hundred Eighteen and Forty Paise Only	Per Cubic meter	42155.00
4	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead of area 3 sq. metres and below including carriage of material, labour, tool and plants through all modes of transportation within all leads and lifts as per PWD specification and as per the direction of the Engineer-in-charge.	5.00	294.10	Rupees Two Hundred Ninety Four and Ten Paise Only	Each	1471.00
TOTAL:-						63284.00

Draft schedule of quantity approved for amounting to Rs 63,284/- only

Executive Engineer
Karghram Division
HPPWD at Bhabanagar

49

Job No. 4

DRAFT SCHEDULE OF QUANTITY

Estimated Cost ₹ 95,000.00

Earnest Money 2000

Name of work:- Preparation of detailed estimate of Construction of Eklayya Model Residential School at Nichar Distt. Kinnaur HP
for Staff quarter No.3

Time One months


Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Job work for preparing of estimate of whole project as per architectural drawing for the construction of buildings in District Kinnaur (H.P.). Under the job work shall also include preparing working estimate duly supported with analysis of rates 2020 on prevailing market rates and getting the working estimate approved from the competent authority alongwith DNIT and submission of the same in this office in hard and soft copy as per direction of Engineer-in Charge.	1.00	₹ 95,000.00	Rupees sixty thousand and paise zero only	Per job	₹ 95,000.00
				Total:-		₹ 95,000.00

Terms and conditions:-

- 1 Submission of fair copy in quadruplicate duly computerized and got approved of the same from competent authority (Superintending Engineer 11th Circle Rampur / Chief Engineer (SZ) HPPWD Shimla.

Payment schedule:-

1	On submission of Detailed/Working estimate	60%
2	On approval of working estimate and DNIT	40%


Executive Engineer,
Karchham Division (B&R),
HP.PWD, Bhabanagar.

DRAFT SCHEDULE OF QUANTITY

Estimated Cost ₹ 95,000.00

Name of work:- Preparation of detailed estimate of Construction of Eklavya Model Residential School at Nichar Distt. Kinnaur HP
for Principal residence

Earnest Money 2000

Time One months

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Job work for preparing of estimate of whole project as per architectural drawing for the construction of buildings in District Kinnaur (H.P.). Under the job work shall also include preparing working estimate duly supported with analysis of rates 2020 on prevailing market rates and getting the working estimate approved from the competent authority alongwith DNIT and submission of the same in this office in hard and soft copy as per direction of Engineer-in Charge.	1.00	₹ 95,000.00	Rupees sixty thousand and paise zero only	Per job	₹ 95,000.00
				Total:-		₹ 95,000.00

Terms and conditions:-

- 1 Submission of fair copy in quadruplicate duly computerized and got approved of the same from competent authority (Superintending Engineer 11th Circle Rampur/ Chief Engineer (SZ) HPPWD Shimla.

Payment schedule:-

1	On submission of Detailed/Working estimate	60%
2	On approval of working estimate and DNIT	40%

[Signature]
Executive Engineer,
Karchham Division (B&R),
HP.PWD, Bhabanagar.

Job No:- 6

Draft Schedule of Quantity

Estimated Cost:- 98750.00
 Earnest Money:- 2000.00
 Time:- 15 Days

Name of work:- R/R damages on various roads under Karchham Division

Sub Head:- Hiring of Excavator cum loader in working condition for removal of Slips/Boulders/debris on Palingi to nichar road Km 0/00 to 16/00, Ponda to Bari road Km 0/00 to 5/200 and Nichar to Wangtoo road km 0/00 to 4/240)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Hiring of Excavator cum loader in working condition having a 1.00 (one) cubic metre bucket capacity for removal of Snow slips and debris and their loading with free of cost including P.O.L. operation staff, repair charges of machinery etc. The actual working hour shall be counted for payment. Any damages to the private/ public property during the execution shall be the absolutely responsibility of the owner. The work shall be executed as per the entire satisfaction and direction of Engineer-in-Charge with in all leads lifts complete in all respect	79.00	1250.00	Rupees one thousand two hundred fifty and paise nil only	Per hour	98750.00
					Total	98750.00

Draft Schedule of Quantity approved for Amount to Rs. 98750/only

[Signature]

Executive Engineer,
 Karchham Division,
 HPPWD Bhabanagar