OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , e-mail : ee-kar-hp@nic.in

No.PW-KSG-E-Tenders/2024- 2543 Dated:- 28/6/2025

To

The Executive Engineer (IT) Cell,
HPPWD, Nirman Bhawan, Nigam Vihar,
Shimla-2.

Subject :- Regarding publication of Tender on departmental site.

With reference to the notification issued by the Secretary(PW) to the Government of Himachal Pradesh No. PBW(B)A(3)1/2024 dated 03.01.2024 enclosed please find herewith the copy of Notice Inviting Tender for the loading on departmental web-site.

Certified that the works mentioned in the Tender Notice are urgent in nature.

Encl:- As above.

Executive Engineer,
B&R Division,
HP PWD Karsog

OFFICE OF THE EXECUTIVE ENGINEER,
HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT KARSOG
PH: 01907-222229 Fax: 222229 , E-mail : ee-kar-hp@nic.in

Notice inviting tender

Sealed item rates tender on form 6 & 8 are hereby invited by the Executive Engineer, B&R Division HPPWD Karsog on behalf of Governor of Himachal Pradesh from the approved/eligible contractors enlisted in HP,PWD for the following works so as to reach in this office on or before **09.07.2025 upto 11.00** AM and shall be opened on the same day at **12.00 AM** in presence of the contractor or their authorized representatives who may like to be present. The tender form can be obtained from this office against cash payment (Non refundable) **upto 4.00 PM on 08.07.2025** for which the application should reach in this office **upto 1.00 PM 08.07.2025**.

The earnest money in shape of National saving certificate/time deposit account/saving account in any Nationalized Bank in H.P duly pledged in favour of the Executive Engineer Karsog Division HPPWD Karsog will be received alongwith application for obtaining tenders form. The conditional tenders will summarily be rejected. The offer of the tenders shall be kept open for 51 days from the date of opening o f tender. The Executive Engineer, HP PWD, Karsog reserves the right to reject any or all tenders without assigning any reason. The contractors should append their enlistment/renewed certificates/sale Tax registration Numbers with the application for issue of tender form. If any of the date mentioned above happens to be holiday the same shall be processed on next working day.

Sr. No.	Name of work	Estimated cost	Earnest money	Time allowed	Cost of Form
1	Repair and maintenance of old building Civil Hospital Karsog Tehsil Karsog Distt. Mandi H.P. at Civil Hospital Karsog Tehsil Karsog DIstt. Mandi H.P. (SH:- Repair and maintenance of morturary house building) Job No. 3 Deposit	76,835/-	1,600/-	One mo	350/-
2	A/R & M/O Residential accommodation for Assistant District Attorney Karsog Distt. Mandi H.P. (SH;- Painting in the room repair of toilet etc)	99,008/-	2,000/-	Two month	350/-
3	R/R damages on Chamunalla to Bagshar road Km. 0/00 to 3/350 (SH:- C/o unlined drain and making of shoulders between various RDs)	99,402/-	2,000/-	Two months	350/
4	Repair and maintenance of old building Civil Hospital Karsog Tehsil Karsog Distt. Mandi H.P. at Civil Hospital Karsog Tehsil Karsog DIstt. Mandi H.P. (SH:- Repair and maintenance of morturary house building) Job No. 4 Deposit	98,609/-	2,000/-	One month	350/-
5	R/R damages on road from Shakelar to Mahog road Km. 0/00 to 10/500 (SH:- C/o R/wall at RD 8/070 to 8/071 & removal of slips at various RDs)	99,421/-	2,000/-	One month	350/-
6	R/R damages on various road under Chindi Section (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of slips at various RDs)	97,750/-	2,000/-	One month	350/-

	A/R & M/O various road under Karsog Sub-Division (SH:- Painting and writing in KM stone and sign board etc.)	99,836/-	2,000/-	One month	350/-
8	R/R damages on Punni to Naswar road Km. 0/00 to 3/00 (SH:- Hiring of JCB for removal of slips on various road)	98,900/-	2,000/-	One month	350/-

***TERMS* & CONDITIONS:-**

1. No tender form will be issued to those contractors who are not registered under HPGST Act.
2. The Contractor/firm should be registered as or dealer GST NO.
3. If any of the date mentioned above happened to be Gazetted holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/ application or all tenders without assigning any reason.
5. No tender form will be issued to those contractors who are not registered under EPF Act.
6. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
7. The earnest money for the above work should be attached with the application.
8. The intending contractors/firms shall have to produce the copy of latest enlistment and renewal enlisted in HP,PWD.
9. As per Govt. Notification **PW/CTR/32-20Genl Inst-CPWD/2020-37996-38095 dated 13-03-2023 the tenders above 5% will be summarily rejected and tenders amounts below 30% of amount put to tender will also be accepted.**

Executive Engineer
B&R Division,
HPPWD Karsog

Dated:-

No. PW-E-Tender-NIT/25-

1. All the Assistant Engineers, working under this Division.
2. Copy to Drawing & Account Branch.
3. Notice board of this office.

Executive Engineer,
B&R Division,
HP PWD Karsog

Percentage Bill of Quantity

Estimated Cost	**76835**
Earnest Money	**1600**
Time	**One Month**

Name of Work:- Repair and maintenance of old building civil hospital Karsog Tehsil Karsog Distt. Mandi H.P at Civil Hospital Karsog Tehsil Karsog Distt. Mandi H.P (Sh:- Repair and Maintenance of Morttuary House building) Job No.3 Deposit

Sr. No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	77.12	Per Square Meter	110.25	8502.00	Rupees Eight Thousand Five Hundred Two and Paise Zero Only
2	Providing and fixing of energy saving long life LED light 30 W (thirth Watt) made up of pressure die cast aluminium housing with high power LED and lens embaded PC cover with IP65 protection or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	4.00	Each	4000.00	16000.00	Rupees Sixteen Thousand and Paise Zero Only
3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately) or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	0.11	Per Cubic Meter	89285.20	9821.00	Rupees Nine Thousand Eight Hundred Twenty One and Paise Zero Only
4	Providing and fixing 40 mm (forty millimeter) thick 2nd class deodar wooden shutter panelled glazed or panelled and glazed shutters glass doors for with double , windows and clearstory windows including black enamelled iron but hinges with necessary screws or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	6.32	Per Square Meter	4142.60	26181.00	Rupees Twenty Six Thousand One Hundred Eighty One and Paise Zero Only

5	Providing and fixing of Superior quality viterous China wash basin Tango 10086, Star white with pedastal of Hindware or equivalent including cutting holes & making good or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	1.00	Each	6602.25	6602.00	Rupees Six Thousand Six Hundred Two and Paise Zero Only
6	Providing and fixing C.P. brass bib cock OPP-CHR-15037PM of jaguar/ESS-ESS or equavalent conforming to IS standard or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	3.00	Each	2275.50	6827.00	Rupees Six Thousand Eight Hundred Twenty Seven and Paise Zero Only
7	Providing and Fixing Angular stop cock with wall flange of opel prime no. OPP-15053PM jaquar or equavalent complete in all respect or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	2.00	Each	1450.80	2902.00	Rupees Two Thousand Nine Hundred Two and Paise Zero Only
Total in Figures					76835.00	
Quoted Rate in Figures			Select		**0.00**	
Quoted Rate in Words						

Bill of Quantity approved for Rs 76835 /- only.
Sr. No २ for Years 2025-26

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Bill Of Quantity

Estimated Cost 99008
Earnest Money 2000
Time Two Months

Name of Work:- A/R & M/O Residential accomodation for Assistant Distt. Attorney Karsog Tehsil Karsog Distt. Mandi (H.P.) (SH:- Painting in the room repair of toilet etc.

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all	Toatal Amount with all taxes including GST In Words
1	Providing and applying while cement based putty of average thickness 1mm,(one milemeter) of approved brand and manufacture, over the plastered wall surface to prepare the surface even and smooth complete as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	69.65	Per Squre Metre	131.55	9162.00	Rupees Nine Thousand One Hundred Sixty Two and Paise Zero Only
2	Wall Painting two coats with premium acrylic emulsion paint of interioe grade, having VOC (Volatile Oraganic Compound) content less than 50 grams/ litre of approved brand and manufacture, includiing applying additional coats wherever required to achieve even sahde and colour as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	335.72	Per Squre Metre	119.05	39967.00	Rupees Thirty Nine Thousand Nine Hundred Sixty Seven and Paise Zero Only
3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal unserviceable meterial within 50 metress lead as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	1.20	Per Cubic Metre	2257.35	2709.00	Rupees Two Thousand Seven Hundred Nine and Paise Zero Only
4	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	100.47	Per Squre Metre	98.10	9856.00	Rupees Nine Thousand Eight Hundred Fifty Six and Paise Zero Only
5	Providing and fixing PVC door bend with ovalaccess door, insertion rubber washer 3mm thick bolts and nuts ISI marked complete including fixing with approved adhesive etc as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	6.00	Each	221.15	1327.00	Rupees One Thousand Three Hundred Twenty Seven and Paise Zero Only
6	Providing and fixing PVC plain bend ISI marked including fixing with approved adhesive etc.complete as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	6.00	Each	142.40	854.00	Rupees Eight Hundred Fifty Four and Paise Zero Only
7	Providing and fixing PVC collars ISI marked including fixing with approved adhesive etc. complete as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	8.00	Each	214.25	1714.00	Rupees One Thousand Seven Hundred Fourteen and Paise Zero Only
8	Providing and fixing PVC clamps ISI marked of approved design with steel screws and rawal plugs etc. complete as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	10.00	Each	124.40	1244.00	Rupees One Thousand Two Hundred Forty Four and Paise Zero Only

9	Providing and Laying Antiskid digital Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS: 15622 of approved make in colours such as white, Ivory, Grey, Fume,Red Brown, laid on 20 mm thick cement mortar 1:4(1 Cement : 4 Coarse sand) Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement adn matching pigment etc, complete of Johnson/ Kajaria/ AGT Tiles/ RAK/ Orient Bell or its equivalent as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	4.00	Per Squre Metre	1791.15	7165.00	Rupees Seven Thousand One Hundred Sixty Five and Paise Zero Only
10	Providing and Fixing high pressure PVC spigot and socket, waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete 75 mm as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	18.00	Per Running Metre	379.65	6834.00	Rupees Six Thousand Eight Hundred Thirty Four and Paise Zero Only
11	Providing and Laying in position cement concrete of specified grade excluding the cost of centering and shuttering- All work up to plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size) as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	1.40	Per Cubic Metre	7274.15	10184.00	Rupees Ten Thousand One Hundred Eighty Four and Paise Zero Only
12	Finishing with deluxe multi surface paint system for interior and exteriors using primer as per manufactures specification: Painting Steel work with Deluxe Multi Surface Paint to give and even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand adn manufacture as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	62.22	Per Squre Metre	125.50	7809.00	Rupees Seven Thousand Eight Hundred Nine and Paise Zero Only
13	Dismantling tile work in floors and roofs laaid in cement tar includign stacking material within 50 metres lead . For thickness of tiles 10 mm to 25 mm as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	4.00	Per Squre Metre	45.85	183.00	Rupees Seven Thousand Eight Hundred Nine and Paise Zero Only
Total in Figures					**99008.00**	
Quoted Rate in Figures					**0.00**	
Quoted Rate in Words						

Bill of Quantity approved for Rs. 99008 /- only.
Sr. No 16 for Years 2025-26

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	**99402**
Earnest Money	**2000**
Time	**Two Months**

Name of Work:- R/R Damages on Chamunallah to Bagshar road km. 0/00 to 3/350 (SH:- C/O Unlined drain and making of shoulders between various RDs)

Sr. No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Construction of unlined surface drain of average cross-section area 0.20 sqm in soil specified line grade, level and dimension . Excavated material to be used to be used in embankment with a lift upto any level as per leadlift and other incidentals. As per directin of Engineer- in -charge with in all lead and lifts and other incidentals.	1000.00	Per Running Metre	27.90	27900.00	Rupees Twenty Seven Thousand Nine Hundred and Paise Zero Only
2	Maintenance of earthen shoulder (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any as per technical specification clause 1903 within all leads and lifts and other incidentals as per direction of Engineer-in Charge with in all leads and lifts and other incidentals.	2550.00	Per Square Metre	28.04	71502.00	Rupees Seventy One Thousand Five Hundred Two and Paise Zero Only
Total in Figures					99402.00	
Quoted Rate in Figures			Select		**0.00**	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Bill of Quantity

Estimated Cost	98609
Earnest Money	2000
Time	One Month

Name of Work:- Repair and maintenance of old building civil hospital Karsog Tehsil Karsog Distt. Mandi H.P at Civil Hospital Karsog Tehsil Karsog Distt. Mandi H.P (Sh:- Repair and Maintenance of Morttuary House building) Job No. 4

Sr. No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Providing and fixing MS BP sheet 1.66 mm (one point six six millimeter) to 2 mm (two millimeter) thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-In-Charge (Base members of steel work shall be measured & paid seprately) or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	33.70	Per Square Meter	2226.00	75016.00	Rupees Seventy Five Thousand Sixteen and Paise Zero Only
2	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	33.70	er Square Met	158.60	5345.00	Rupees Five Thousand Three Hundred Forty Five and Paise Zero Only
3	Half brick masonry Cement mortar 1:3 (one cement :three coarse sand) with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	2.80	Per Square Meter	1479.90	4144.00	Rupees Four Thousand One Hundred Forty Four and Paise Zero Only
4	Providing and fixing Single socketed pipes 100 mm (one hundred millimeter) dia pipe on wall face plasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	18.00	Each	473.55	8524.00	Rupees Eight Thousand Five Hundred Twenty Four and Paise Zero Only

5	Providing and fixing 100 mm (one hundred millimeter) dia pipe on wall face plasticised Coupler PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 382, leaving 10 mm gap for thermal expansion or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	6.00	Each	166.50	999.00	Rupees Nine Hundred Ninety Nine and Paise Zero Only
6	Providing and fixing 100 mm (one hundred millimeter) dia pipe unplasticised -PVC pipe clips of approved design to unplasticised -PVC rain water pipes by means of 50x50x50 mm (fifty into fifty into fifty millimeter) hard wood plugs, screwed with M.S. screws of required length, including cutting brick work and fixing in cement mortar 1:4 (one cement : four coarse sand) and making good the wall etc complete or as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.	18.00	Each	254.50	4581.00	Rupees Four Thousand Five Hundred Eighty One and Paise Zero Only
					98609.00	
Total in Figures			Select		**0.00**	
Quoted Rate in Figures						
Quoted Rate in Words						

Bill of Quantity approved for Rs 98609 /- only.
Sr. No 1 for Years 2025-26

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost 99421
Earnest Money 2000
Time One Month

Name of Work:-R/R Damages on road from Shakelar to Mahog road km 0/00 to 10/500(SH:- C/O R/Wall at RD 8/070 to 8/071 & Removal of slips at various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including	Toatal Amount with all taxes including GST In Words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction for shoring and bracing removal of stamps and other deleterious materials and desposal up to a lead of 50 mtrs dressing of side and bottom and back filling in trenches with excavated suitable materials ordinary soil upto 3mtrs depth as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.70	Per Cubic Metre	390.20	663.00	Rupees Six Hundred Sixty Three and Paise Zero Only
2	Providing and laying concrete for plain /reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803 1202 and 1203 as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals.(1:4:8)	6.94	Per Cubic Metre	5500.00	38170.00	Rupees Thirty Eight Thousand One Hundred Seventy and Paise Zero Only
3	Providing weep holes in brick masonary/stone masonary/plain reinforced concrete abutment,wing wall,return wall with 100 mm dia PVC pipe extending through the full width of structures with slope of 1(v):20 (H) towads drawing face complete as per drawing and technical specificataion clause 614,709,1204.3.7 as per direction of Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals.	3.00	Each	373.15	1119.00	Rupees One Thousand One Hundred Nineteen and Paise Zero Only
4	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	1.80	Per Cubic Metre	1200.00	2160.00	Rupees Two Thousand One Hundred Sixty and Paise Zero Only
5	Removal of land slide slip clearance:-Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materiaL with in all leads and lifts stacking the serviceable material and disposal of unserviceable material as per technical specification clause 302.3.5 and 1611 as per direction of Engineer-in-Charge with in all leads and lifts and other incidentals.	458.47	Per Cubic Metre	125.00	57309.00	Rupees Fifty Seven Thousand Three Hundred Nine and Paise Zero Only
Total in Figures					**99421.00**	
Quoted Rate in Figures					**0.00**	
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost	97750
Earnest Money	2000
Time	One Month

Name of Work:- R/R ~~Damaes on~~ Damages various road under Chindi Section (SH:- Hiring of JCB/Excavator cum loader on daily wages basis for removal of slips at various RD's)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate all taxex includingg GST (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JB/Excavator cum Loader for cutting in earth work/removal of snow/slips from road surface in all kind of soil such as pick work, jumper work, blasting work in soft and hard rock saturated soil and disposing of all excavated earth or un-serviceable materials from the road surface up to any leads and lifts and as per direction of Engineer-in-Charge. The machine/JCB should work 7 Hour daily. Any loss of public property and accident etc. the contractor is fully responsible during the execution of work. The POL and operation staff for the machine will be provided b y the owner the repair charges of machinery will be provided by the owner. The repair charges of machinery during the excution of work will be borne by the contractor. The useful material shall be stacked along the road side as epr direction of Engineer-in-Charge.	85.00	Per Hours	1150.00	97750.00	Rupees Ninety Seven Thousand Seven Hundred Fifty and Paise Zero Only
Quoted Rate in Figures			Select		97750.00	
Quoted Rate in Words			#VALUE!			

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule of Quantity

Estimated Cost	99836
Earnest Money	2000
Time	One Month

Name of Work:- A/R & M/O Various road under Karsog Sub Division (SH:- Painting and writing in Km. stone and Sign Board etc.)

Sr.No.	Sub-Head and Items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Painting two coats with epoxy paint of approved brand on concrete/steel surface after through cleaning of surface to give an even shade as per drawing and Technical specification clasue 1701 or as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	18.00	Per Square metre	152.70	2749.00	Rupees Two Thousand Seven Hundred Forty Nine and Paise Zero Only
2	Painting two coats after filling the furvace with synthetic enamel paint in all shades on new plastered/concrete surface as per drawing and technical specition or as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	33.00	Per Square metre	140.65	4641.00	Rupees Four Thousand Six Hundred Forty One and Paise Zero Only
3	Painting new letters and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade as per drawing and technical specificaiton clasue 1701 or as per direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals.	31878.00	Per Letter/Per centimeter height	2.90	92446.00	Rupees Ninety Two Thousand Four Hundred Forty Six and Paise Zero Only
Total In Figures					99836.00	
Quoted Rate In Figures						
Quoted Rate In Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.

Percentage Schedule Of Quantity

Estimated Cost	98900
Earnest Money	2000
Time	One Month

Name of Work:- R/R Damages on Punni to Naswar road km 0/00 to 3/00 (SH:- Hiring of JCB for removal of slips on various road)

Sr.No.	Sub-Head and items of works.	No. Or Qty.	Unit.	Estimated Rate (In Rs.)	Toatal Amount with all taxes including GST In Rs. P	Toatal Amount with all taxes including GST In Words
1	Hiring of JCB/excavator for removal of slips and boulder in all kinds of soil including roy portion and saturated and disposing of all excavated earth or un-serviceable materials from the road surface upto any leads and lifts as per direction of Engineer-In-Charge. The machine/JCB should work minimum 8.00 hours from 9:00 AM to 5:00 PM daily and remove at least 25.0 cum. Quantity of sllpis per hour. Any loss to the public/private property or any accident etc. should be absolute responsibility of the JCB/excavator owner which shall have to be fully compensated by him in all cases. The fuel and operational staff for excavator will be provided by the owner,the repair and spare watch and ward of excavator also be borne by the contractor/owner. The daily log book will be maintained at site which should be duly verified by Engineer-In-Charge.	86.00	Per Hours	1150.00	98900.00	Rupees Ninety Eight Thousand Nine Hundred Only
					98900.00	
Total in Figures						
Quoted Rate in Figures						
Quoted Rate in Words						

Executive Engineer,
Karsog Division,
HPPWD, Karsog.