HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

Through e-mail
eeict-pwd-shi@hp.gov.in

NO. PWP/CB/Tender Notice/2025-26- 2727-28 Dated:- 02/07/2025

To

The Executive Engineer (IT Cell),
HPPWD, Nigam Vihar, Shimla-2.
eeict-pwd-shi@hp.gov.in

Subject :- Regarding publication of Tender Notice on departmental website to be opened on 11.07.2025.

Enclosed please find herewith the tender notice alongwith schedule of quantity for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP, No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.

1. Certified that the tender mentioned in the notice is exigencies/emergency of urgent nature (upcoming rainy season) and in the public interest.

Enclosures:- Notice Inviting tender and schedule of quantity.(25 Nos.)

Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

Copy forwarded along with tender notice via e mail for information to:-

1. The Superintending Engineer Nahan 12th Circle HP.PWD Nahan for information please.

Sd/-
Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed Percentage rate tender are hereby invited by the Executive Engineer Paonta (B&R) Division HP.PWD Paonta Sahib on behalf of Governor of HP from the approved/ eligible contractor registered in HPPWD for the work, so as to reach in this office on 11.07.2025 up to 02.30 PM and shall be opened on 11.07.2025 the same day at 3.00P.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 4.00 PM on 10.07.2025 for which the applications should reach in this office up to 4.00 PM on 09.07.2025. The tender form will be issued to the contractor giving proof of registration as GST.

The earnest money in the shape of NSC / Time deposit account / Saving account in any of the Post Office in HP or FDR/CDR from nationalized bank duly pledged in the name of Executive Engineer Paonta B&R Division HP.PWD Paonta Sahib must be accompanied with the application. Conditional tender and tender received without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all tenders without assigning the reason. If there happens to be any holiday the same will be open on the next working day.

Sr. No	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form	Class
1	Restoration of rain damages to Various road under Kolar Section in HP PWD (B&R) Sub Dhaulakuan. (SH:- Hiring of JCB and Tractor with trolley for removal of slips and debris, Dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).	Rs. 99,850/-	Rs. 2000/-	Three Months.	350/-	C & D
2	Restoration of rain damages to link road Lohgarh km. 0/0 to 5/0, Jamnighat Jheelbankabara to Dhaunwala km. 0/0 to 5/020, Haripur to Jamnighat road km. 0/0 to 2/600 & Lohgarh to Banda Bahadur road km. 0/0 to 4/0. (SH:- Hiring of JCB and Tractor with trolley for removal of slips and debris, Dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).	Rs. 98,625/-	Rs. 2000/-	Three Months.	350/-	C & D
3	Restoration of rain damages to kolar Bilaspur road km. 0/0 to 12/0. (SH:- Hiring of JCB and Tractor with trolley for removal of slips and debris, Dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).	Rs. 99,850/-	Rs. 2000/-	Three Months.	350/-	C & D

4	Restoration of rain damages to Various roads under Dhaulakuan Section in HP PPWD (B&R) Sub-Division Dhaulakuan. (SH:- Hiring of JCB and Tractor with trolley for removal of slips and debris, Dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).	Rs. 99,595/-	Rs. 2000/-	Three Months.	350/-	C & D
5	Restoration of rain damages to Jamta Rajban road km. 23/0 to 43/0. (SH:- Hiring of JCB and Tractor with trolley for removal of slips and debris, Dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).	Rs. 98,540/-	Rs. 2000/-	Three Months.	350/-	C & D
6	Restoration of rain damages to Dhaulakuan to Mehat km. 0/0 to 26/0. (SH:- Hiring of JCB and Tractor with trolley for removal of slips and debris, Dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).	Rs. 98,625/-	Rs. 2000/-	Three Months.	350/-	C&D
7	Restoration of rain damages to Various road under Baila Section in HP PPWD (B&R) Sub-Division Dhaulakuan. (SH:- Hiring of JCB and Tractor with trolley for removal of slips and debris, Dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).	Rs. 99,680/-	Rs. 2000/-	Three Months.	350/-	C & D
8	Restoration of rain damages on link road Harizan Basti Kherni Palhori upto Simbalwara km. 0/00 to 5/00. (SH:- Hiring of Excavator cum Loader for dressing of berms in km. 0/0 to 5/00).	Rs. 96,940/-	Rs. 2000/-	Two Months.	350/-	C & D
9	Restoration of rain damages on link road from Salwala to Puruwala km. 0/0 to 2/0. (SH:- Hiring of JCB tractor with trolley hydraulic for removal of slips, removal of debris of Dopahria Khud from the road surface and dressing of berms in km.0/0 to 2/0).	Rs. 99,850/-	Rs. 2000/-	Two Months.	350/-	C & D
10	Restoration of rain damages on link road from NH-707 to village Chhachheti 0/0 to 14/270. (SH:- Hiring of JCB tractor with trolley for removal of slips, removal of debris of road surface and dressing of berms etc. in km. 0/0 to 2/0).	Rs. 99,850/-	Rs. 2000/-	Two Months.	350/-	C & D

11	Restoration of rain damages on link road to village Gutanpur km. 0/0 to 2/500 & link road NH-907 to Bangala Basti km. 0/0 to 0/850 of Paonta local Section and Main Kundio to Jhaba Basti km. 0/0 to 1/600 & link road Bata bridge Majra to Bias Mandir km. 0/0 to 2/340 of Jamniwala Section. (SH:- Hiring of JCB tractor with trolley hydraulic for dressing of berms).	Rs. 96,685/-	Rs. 2000/-	Two Months.	350/-	C & D
12	Restoration of rain damages to various roads under Majra Section in HP.PWD (B&R) Sub-Division Dhaulakuan. (SH:- Hiring of JCB and tractor with trolley for removal of slips and debris, dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).	Rs. 98,540/-	Rs. 2000/-	Three Months.	350/-	C & D
13	Restoration of rain damages to link road Badripur Jamniwala to Majra road km. 0/0 to 4/100, link road Harizan basti Sainwala km. 0/0 to 3/200 & link road Jagatpur Parduni road km. 0/0 to 4/0 under Majra Section in HP.PWD (B&R) Sub Dhaulakuan. (SH:- Hiring of JCB tractor with trolley for removal of slips and debris, dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).	Rs. 97,485/-	Rs. 2000/-	Three Months.	350/-	C & D
14	Repair of Bridge on Kolar Bilaspur road km. 0/0 to 12/0. (SH:- Construction of Retaining wall in wire crate in km.10/685 to 10/688.50).	Rs. 93,544/-	Rs. 2000/-	Three Months.	350/-	C & D
15	Repair of Bridge on Kolar Bilaspur road km. 0/0 to 12/0. (SH:- Construction of Retaining wall in wire crate in km.10/689.50 to 10/693).	Rs. 93,383/-	Rs. 2000/-	Three Months.	350/-	C & D
16	Construction of link road Rampur Bharapur Gunglow road km. 0/0 to 5/0. (SH:- Construction of Retaining wall in cement concrete at RD. 0/930 to 0/935 & 0/940 to 0/941). Under Deposit work.	Rs. 96,275/-	Rs. 2000/-	Three Months.	350/-	C & D
17	Construction of link road Rampur Bharapur Gunglow road km. 0/0 to 5/0. (SH:- Construction of Retaining wall in cement concrete at RD. 0/917 to 0/923). Under Deposit work.	Rs. 86,488/-	Rs. 1800/-	Three Months.	350/-	C & D

18	Construction of link road Rampur Bharapur Gunglow road km. 0/0 to 5/0. (SH:- Construction of Retaining wall in cement concrete at RD. 0/910 to 0/916). Under Deposit work.	Rs. 86,568/-	Rs. 1800/-	Three Months.	350/-	C & D
19	Construction of link road Rampur Bharapur Gunglow road km. 0/0 to 5/0. (SH:- Construction of Retaining wall in cement concrete at RD. 0/839 to 0/853). Under Deposit work.	Rs. 95,158/-	Rs. 2000/-	Three Months.	350/-	C & D
20	Improvement of curve of link road to Jamnighat km. 0/0 to 2/400. (SH:- Improvement of curve at RD. 1/340 to 1/400). Under SCSP work.	Rs. 98,272/-	Rs. 2000/-	Three Months.	350/-	C & D
21	Construction of road from Banda Bahadur road to Lambardar Basti at Lohgarh km. 0/0 to 0/255. (SH:- Formation cutting 5/7 mtr. wide road from RD. 0/0 to 0/045). Under Deposit work.	Rs. 98,294/-	Rs. 2000/-	Three Months.	350/-	C & D
22	Construction of road from Banda Bahadur road to Lambardar Basti at Lohgarh km. 0/0 to 0/255. (SH:- Formation cutting 5/7 mtr. wide road from RD. 0/045 to 0/095). Under Deposit work.	Rs. 94,497/-	Rs. 2000/-	Three Months.	350/-	C & D
23	Repair and Maintenance of Ayurvedic Health Centre building at Bhanet. (SH:- Plaster boundary wall plinth protection skarting & white wash). Under Deposit work.	Rs. 73,466/-	Rs. 1500/-	Three Months.	350/-	C & D
24	Restoration of rain damages of HP.PWD. Store Majra Boundary wall. (SH:-Re-Construction of damage boundary wall around the Majra Store). Job. No.1	Rs. 94,330/-	Rs. 2000/-	Three Months.	350/-	C & D
25	Repair and Maintenance of Ayurvedic Health Centre building at Bhanet. (SH:- Dismantelling wooden work, New Pannel roof treatment floor tiles). Under Deposit work.	Rs. 79,912/-	Rs. 1600/-	Three Months.	350/-	C & D

CERTIFICATE:- Certified that the tenders mentioned above in this notice are exigencies/emergency of urgent nature (Upcoming Rainy Season) and in public interest.

Conditions:-

The tender document shall be issued to only those contractors / firms:-

1. Who possess valid Contractor Registration Number.
2. Who possess valid GST Registration Number, Permanent Account Number and EPF Number.
3. Ambiguous / telegraphic / conditional tenders or tenders by FAX / E-mail shall not be entertained / considered in any case.

4. If any date mentioned above happens to be local/gazetted holiday, the same shall be processed on next days.
5. The earnest money for above cited work should be submitted with the applications for purchase of tender form, no exemption for earnest money will be allowed.
6. The contractor / Firms are requested to insert the percentage rate in words as well as in figures/failing which XEN reserves the right to accept/ reject any or all tenders.
7. List of machinery tool plants as per schedule F Sr. No. 6.19 Ref. Clause No. 18 i.e. R.C. and purchase bills along with proof of ownership of JCB/Affidavit from owner of JCB and Tractor with Trolley on hire basis. Only Two tender forms issued against one R.C./Affidavit of JCB. i.e. adjoining Job/work of JCB.
8. GST Clearance Certificate from GST Department and up to date filling return as per instruction issued by the GST Department.

Sd/-
Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib.

No.PWP/CB-Tender Notice/2025-26- 2729-2778 Dated:- 02/07/2025

Copy forwarded to the following for information and necessary action please:-

1. The Engineer-in- Chief, HP. PWD Shimla-I
2. All the Superintending Engineer, in HP.PWD
3. The Sub Divisional Magistrate Paonta Sahib.
4. All the Executive Engineer in HP.PWD.
5. The Executive Engineer I&PH Division Paonta Sahib.
6. The Block Development Officer Block Paonta Sahib.
7. All the Assistant Engineer working under this Division.
8. The Executive Officer Municipal Committee Paonta Sahib.
9. All head of the Branches in this division.
10. Notice Board.

Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib

Draft Schedule of Quantity						Estimated cost:-99850/-only
Name of Work:-Restoration of rain damages to various roads under Kolar Section in HP.PWD (B&R)Sub Division Dhaulakuan.(SH:- Hiring of JCB and tractor with trolly for removal of slips and debris,dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).						Estimated Money:-2000/-only Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in Figures	Rate in Words	Amount
1	Hiring of hydraulic excavator cum loder of I cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of oprators, Pol charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the direction of Engineer-in-Charge.	70.00	Per hrs	1055.00	Rupees One thousand fifty five and paise nil only	73850
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. The break down or any kind of hindrence charges of Machinery or operating staff shall be met out of his own cost.Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of Engineer-in-Charge.	8.00	Per day	3250.00	Rupees Three thousand two hundred fifty and paise nil only	26000
					Total	99850

Note:- The cost of P.O.L.charge wear and tear of machinary salary and livery charges of operator and cleaner and repair of machinery etc.shall be borne by the contractor himself and nothing will be paid for the same.

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

(2)

98625/-only.

Draft Schedule of Quantity	Estimated cost:-~~99850/-~~only
Name of Work:-Restoration of rain damages to Link road Lohgarh Km 0/0 to 5/0, Jamnighat Jheelbankabara to Dhounwala Km 0/0 to 5/020, Haripur to Jamnighat road Km 0/0 to 2/600 & Lohgarh to Bandabhadur road Km 0/0 to 4/0.(SH:- Hiring of JCB and tractor with trolly for removal of slips and debris,dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).	**Estimated Money:-2000/-only** **Time:-Three Months**

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of hydraulic excavator cum loder of I cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of oprators, Pol charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the direction of Engineer-in-Charge.	75.00	Per hrs	1055.00	Rupees One thousand fifty five and paise nil only	79125
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. The break down or any kind of hindrence charges of Machinery or operating staff shall be met out of his own cost.Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of Engineer-in-Charge.	6.00	Per day	3250.00	Rupees Three thousand two hundred fifty and paise nil only	19500
					Total	98625

Note:- The cost of P.O.L.charge wear and tear of machinary salary and livery charges of operator and cleaner and repair of machinery etc.shall be borne by the contractor himself and nothing will be paid for the same.

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

(3)

Draft Schedule of Quantity						Estimated cost:-99850/-only
Name of Work:-Restoration of rain damages to Kolar Bilaspur road Km 0/0 to 12/0.(SH:- Hiring of JCB and tractor with trolly for removal of slips and debris,dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).						**Estimated Money:-2000/-only**
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of hydraulic excavator cum loder of I cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of oprators, Pol charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the direction of Engineer-in-Charge.	70.00	Per hrs	1055.00	Rupees One thousand fifty five and paise nil only	73850
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. The break down or any kind of hindrence charges of Machinery or operating staff shall be met out of his own cost.Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of Engineer-in-Charge.	8.00	Per day	3250.00	Rupees Three thousand two hundred fifty and paise nil only	26000
					Total	99850

Note:- The cost of P.O.L.charge wear and tear of machinary salary and livery charges of operator and cleaner and repair of machinery etc.shall be borne by the contractor himself and nothing will be paid for the same.

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

Draft Schedule of Quantity						Estimated cost:-99595/-only
Name of Work:-Restoration of rain damages to various roads under Dhaulakuan Section in HP.PWD (B&R)Sub Division Dhaulakuan.(SH:- Hiring of JCB and tractor with trolly for removal of slips and debris,dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).						Estimated Money:-2000/-only Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of hydraulic excavator cum loder of I cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of oprators, Pol charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the direction of Engineer-in-Charge.	79.00	Per hrs	1055.00	Rupees One thousand fifty five and paise nil only	83345
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. The break down or any kind of hindrence charges of Machinery or operating staff shall be met out of his own cost.Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of Engineer-in-Charge.	5.00	Per day	3250.00	Rupees Three thousand two hundred fifty and paise nil only	16250
					Total	99595

Note:- The cost of P.O.L.charge wear and tear of machinary salary and livery charges of operator and cleaner and repair of machinery etc.shall be borne by the contractor himself and nothing will be paid for the same.

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

(5)

Draft Schedule of Quantity							Estimated cost:-98540/-only
Name of Work:-Restoration of rain damages to Jamta Rajban road Km 23/0 to 43/0.(SH:- Hiring of JCB and tractor with trolly for removal of slips and debris,dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).							**Estimated Money:-2000/-only**
							Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount	
				Figures	Words		
1	Hiring of hydraulic excavator cum loder of I cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of oprators, Pol charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the direction of Engineer-in-Charge.	78.00	Per hrs	1055.00	Rupees One thousand fifty five and paise nil only	82290	
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. The break down or any kind of hindrence charges of Machinery or operating staff shall be met out of his own cost.Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of Engineer-in-Charge.	5.00	Per day	3250.00	Rupees Three thousand two hundred fifty and paise nil only	16250	
					Total		98540

Note:- The cost of P.O.L.charge wear and tear of machinary salary and livery charges of operator and cleaner and repair of machinery etc.shall be borne by the contractor himself and nothing will be paid for the same.

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

(6)

Draft Schedule of Quantity						Estimated cost:-98625/-only
Name of Work:-Restoration of rain damages to Dhaulakuan to Mehat Km 0/0 to 26/0.(SH:- Hiring of JCB and tractor with trolly for removal of slips and debris,dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).						**Estimated Money:-2000/-only**
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of hydraulic excavator cum loder of I cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of oprators, Pol charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the direction of Engineer-in-Charge.	75.00	Per hrs	1055.00	Rupees One thousand fifty five and paise nil only	79125
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. The break down or any kind of hindrence charges of Machinery or operating staff shall be met out of his own cost.Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of Engineer-in-Charge.	6.00	Per day	3250.00	Rupees Three thousand two hundred fifty and paise nil only	19500
					Total	98625

Note:- The cost of P.O.L.charge wear and tear of machinary salary and livery charges of operator and cleaner and repair of machinery etc.shall be borne by the contractor himself and nothing will be paid for the same.

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

Draft Schedule of Quantity						Estimated cost:-99680/-only
Name of Work:-Restoration of rain damages to various roads under Baila Section in HP.PWD (B&R)Sub Division Dhaulakuan.(SH:- Hiring of JCB and tractor with trolly for removal of slips and debris,dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).						**Estimated Money:-2000/-only**
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of hydraulic excavator cum loder of I cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of oprators, Pol charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the direction of Engineer-in-Charge.	76.00	Per hrs	1055.00	Rupees One thousand fifty five and paise nil only	80180
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. The break down or any kind of hindrence charges of Machinery or operating staff shall be met out of his own cost.Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of Engineer-in-Charge.	6.00	Per day	3250.00	Rupees Three thousand two hundred fifty and paise nil only	19500
					Total	99680

Note:- The cost of P.O.L.charge wear and tear of machinary salary and livery charges of operator and cleaner and repair of machinery etc.shall be borne by the contractor himself and nothing will be paid for the same.

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

Job No. (8)

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on link road Harizan Basti Kherni Palhodi upto Simbalwara km 0/00 to 5/00 (SH: Hiring of excavater cum loader for dressing of berms in km 0/0 to 5/00).

Estimated Cost:- Rs.96,940/-only
Earnest money:- Rs.2000/- only.
Time allowed:- Two months

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Hiring of hydraulic excavator cum loader 1 cum bucket capacity for excavation, removal of slips , removal of debris and dressing of berms including pay of operators , Pol chgarge , maintenance or any minor or major accidents and other damage to private and Govt . property is the whole responsibiliy of the contractor and shall be borne by the contractor at his own cost . The work shall be executed as per the MORT specification and as per the direction of the Engineer-in-Charge.	58.00	Per Hour	1055.00	Rupees one thousand fifty five and paise Nil only	61190.00
2	Hiring of tractor with trolley including operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. the break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	11.00	Per day	3250.00	Rupees three Thousand two hundred fifty and paise Nil only	35750.00
	Total :-					**96940.00**

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

1). The Rates should be quoted for all heights including all leads and lifts.

2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Job No. 9

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on link road from salwala to Puruwala 0/0to 2/0(SH: Hiring of JCB tractor with trolley hudraulic for removal of salips,removal of debries of Dopahria Khud from the road surface and dressing of berms in Km. 0/0 to 2/0).

Estimated Cost:- Rs.99,850/-only
Earnest money:- Rs.2000/- only.
Time allowed:- Two months

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Hiring of hydraulic excavator cum loader 1 cum bucket capacity for excavation, removal of slips , removal of debris and dressing of berms including pay of operators , Pol chgarge , maintenance or any minor or major accidents and other damage to private and Govt . property is the whole responsibiliy of the contractor and shall be borne by the contractor at his own cost . The work shall be executed as per the MORT specification and as per the direction of the Engineer-in-Charge.	70.00	Per Hour	1055.00	Rupees one thousand fifty five and paise Nil only	73850.00
2	Hiring of tractor with trolley including operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. the break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	8.00	Per day	3250.00	Rupees three Thousand two hundred fifty and paise Nil only	26000.00
	Total :-					**99850.00**

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

1). The Rates should be quoted for all heights including all leads and lifts.

2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Job No - 10

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on link road from NH 707 to village chhachheti 0/0 to 14/270 (SH: Hiring of JCB tractor with trolley for removal of salips,removal of debries of ~~Bepalmic~~ ~~filled from the~~ road surface and dressing of bermsetc. in Km. 0/0 to 2/0)~~dressing of berms~~).

Estimated Cost:- Rs.99,850/-only
Earnest money:- Rs.2000/- only.
Time allowed:- Two months

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Hiring of hydraulic excavator cum loader 1 cum bucket capacity for excavation, removal of slips , removal of debris and dressing of berms including pay of operators , Pol chgarge , maintenance or any minor or major accidents and other damage to private and Govt . property is the whole responsibiliy of the contractor and shall be borne by the contractor at his own cost . The work shall be executed as per the MORT specification and as per the direction of the Engineer-in-Charge.	70.00	Per Hour	1055.00	Rupees one thousand fifty five and paise Nil only	73850.00
2	Hiring of tractor with trolley including operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. the break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	8.00	Per day	3250.00	Rupees three Thousand two hundred fifty and paise Nil only	26000.00
	Total :-					**99850.00**

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Condition :-

1). The Rates should be quoted for all heights including all leads and lifts.

2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Job No- 11.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on link road to village Gutanpur km 0/0 to 2/500 & link road NH-907 to bangala Basti km 0/0 to 0/850 of Paonta local Section and main Kundio to Jhaba Basti km 0/0 to 1/600 & L/R Bata bridge Majra to Bias Mandir km 0/0 to 2/340 of Jamniwala section) (SH: Hiring of JCB tractor with trolley hudraulic for dressing of berms).

Estimated cost :- Rs :- 96,685/-
Earnist Money:- Rs:- 2,000/-
Time:- Two Months.

Sr. No	Description/ Item Rate	Quantity	unit	Rate		Amount
				Figure	Words	
1	Hiring of hydraulic excavator cum loader 1 cum bucket capacity for excavation, removal of slips , removal of debris and dressing of berms including pay of operators , Pol chgarge , maintenance or any minor or major accidents and other damage to private and Govt . property is the whole responsibiliy of the contractor and shall be borne by the contractor at his own cost . The work shall be executed as per the MORT specification and as per the direction of the Engineer-in-Charge.	67.00	Per Hour	1055.00	Rupees one thousand fifty five and paise Nil only	70685.00
2	Hiring of tractor with trolley including operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. the break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	8.00	Per day	3250.00	Rupees three Thousand two hundred fifty and paise Nil only	26000.00
	Total :-					96685.00

Quoted rate in Figure (+/-) (.....%)
Quoted rate in words (+/-) (.....%)

Executive Engineer,
Paonta HP.PWD., Division
Paonta Sahib

Condition :-

1). The Rates should be quoted for all heights including all leads and lifts.

2). The contractor shall procure all the materials confirming to the specifications of MORTH at his own risk and cost.

Signature of the contractor with full address:-

Draft Schedule of Quantity						Estimated cost:-98540/-only
Name of Work:-Restoration of rain damages to various roads under Majra Section in HP.PWD (B&R)Sub Division Dhaulakuan.(SH:- Hiring of JCB and tractor with trolly for removal of slips and debris,dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).						**Estimated Money:-2000/-only** **Time:-Three Months**
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in Figures	Rate in Words	Amount
1	Hiring of hydraulic excavator cum loder of I cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of oprators, Pol charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the direction of Engineer-in-Charge.	78.00	Per hrs	1055.00	Rupees One thousand fifty five and paise nil only	82290
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. The break down or any kind of hindrence charges of Machinery or operating staff shall be met out of his own cost.Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of Engineer-in-Charge.	5.00	Per day	3250.00	Rupees Three thousand two hundred fifty and paise nil only	16250
					Total	98540

Note:- The cost of P.O.L.charge wear and tear of machinary salary and livery charges of operator and cleaner and repair of machinery etc.shall be borne by the contractor himself and nothing will be paid for the same.

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

Draft Schedule of Quantity	Estimated cost:-97485/-only
Name of Work:-Restoration of rain damages to link road Badripur Jamniwala to Majra road km 0/0 to 4/100, link road Harizan basti Sainwala Km 0/0 to 3/200 & link road Jagatpur Parduni road Km 0/0 to 4/0 under Majra Section in HP.PWD (B&R)Sub Division Dhaulakuan.(SH:- Hiring of JCB and tractor with trolly for removal of slips and debris,dressing of berms and cleaning of side drains, restoration of rain cuts and filling of pot holes).	**Estimated Money:-2000/-only** **Time:-Three Months**

Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of hydraulic excavator cum loder of I cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of oprators, Pol charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the direction of Engineer-in-Charge.	77.00	Per hrs	1055.00	Rupees One thousand fifty five and paise nil only	81235
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor at his own cost. The break down or any kind of hindrence charges of Machinery or operating staff shall be met out of his own cost.Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of Engineer-in-Charge.	5.00	Per day	3250.00	Rupees Three thousand two hundred fifty and paise nil only	16250
					Total	97485

Note:- The cost of P.O.L.charge wear and tear of machinary salary and livery charges of operator and cleaner and repair of machinery etc.shall be borne by the contractor himself and nothing will be paid for the same.

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

(14)

Draft Schedule of Quantity						Estimated cost:-93544/-only
Name of Work:-Repair of Bridge on Kolar Bilaspur road Km 0/0 to 12/0. (SH:- Construction of Retaining wall in wire crate in Km 10/685 to 10/688.50).						Estimated Money:-2000/-only
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechnical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	10.06	Per cubic metre	190.00	Rupees One hundred ninty and paise nil only	1911
2	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg(Twenty five killogramme) each complete including carriage of materials within all leads,lifts & other incidential complete as per direction and entire satisfaction of the Engineer-in-Charge.	29.09	Per Cubic metre	3150.00	Rupees Three thousand One hundred fifty and paise nil only	91633
					Total	93544

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

Draft Schedule of Quantity						Estimated cost:-93383/-only
Name of Work:-Repair of Bridge on Kolar Bilaspur road Km 0/0 to 12/0. (SH:- Construction of Retaining wall in wire crate in Km 10/689.50 to 10/693).						**Estimated Money:-2000/-only**
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechnical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	10.87	Per cubic metre	190.00	Rupees One hundred ninty and paise nil only	2065
2	Providing and laying boulder apron laid in wire crate made with 4 mm (four millimetres) dia G.I. wires conforming to IS:280 & IS:4826 in 100mmx100 mm (One hundred millimetres into hundred millimetres) mesh (weaved diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulder weighing not less than 25 kg(Twenty five killogramme) each complete including carriage of materials within all leads,lifts & other incidential complete as per direction and entire satisfaction of the Engineer-in-Charge.	29.09	Per Cubic metre	3150.00	Rupees Three thousand One hundred fifty and paise nil only	91633
					Total	93698

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

(A6)

Draft Schedule of Quantity						Estimated cost:-96275/-only
Name of Work:-Construction of link road Rampur Bharapur Gunglow road Km 0/0 to 5/0. (SH:- Construction of Retaining wall in cement concrete at RD 0/930 to 0/935 & 0/940 to 0/941). under Deposit work.						**Estimated Money:-2000/-only**
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechnical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	8.10	Per cubic metre	190.00	Rupees One hundred ninty and paise nil only	1539
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth leve l :4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	18.60	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	92167
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	7.00	Per Nos	367.00	Rupees Three hundred sixty seven and paise nil only	2569
					Total	96275

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

(13)

Draft Schedule of Quantity						Estimated cost:-86488/-only
Name of Work:-Construction of link road Rampur Bharapur Gunglow road Km 0/0 to 5/0. (SH:- Construction of Retaining wall in cement concrete at RD 0/917 to 0/923). under Deposit work.						**Estimated Money:-1800/-only**
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechnical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	6.30	Per cubic metre	190.00	Rupees One hundred ninty and paise nil only	1197
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth leve l :4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	16.62	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	82355
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	8.00	Per Nos	367.00	Rupees Three hundred sixty seven and paise nil only	2936
					Total	86488

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

Draft Schedule of Quantity						Estimated cost:-86568/-only
Name of Work:-Construction of link road Rampur Bharapur Gunglow road Km 0/0 to 5/0. (SH:- Construction of Retaining wall in cement concrete at RD 0/910 to 0/916). under Deposit work.						**Estimated Money:-1800/-only**
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechnical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	6.72	Per cubic metre	190.00	Rupees One hundred ninty and paise nil only	1277
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth leve l :4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	16.62	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	82355
3	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	8.00	Per Nos	367.00	Rupees Three hundred sixty seven and paise nil only	2936
					Total	86568

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

Draft Schedule of Quantity						Estimated cost:-95158/-only
Name of Work:-Construction of link road Rampur Bharapur Gunglow road Km 0/0 to 5/0. (SH:- Construction of Retaining wall in cement concrete at RD 0/839 to 0/853).under Deposit work.						Estimated Money:-2000/-only
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth leve l :4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	6.30	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	31218
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in Charge 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern.	60.76	Per square metre	960.00	Rupees Nine hundred sixty and paise nil only	58330
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge. .	0.95	Per cubic metre	5905.85	Rupees Five thousand nine hundred five and paise eighty five only	5611
					Total	95158

Executive Engineer
Paonta(B&R)Division
HP.PWD.Paonta Sahib

Draft Schedule of Quantity						Estimated cost:-98272/-only
Name of Work:-Improvement of curve of link road to Jamnighat Km 0/0 to 2/400. (SH:- Improvement of curve at RD 1/340 to 1/400). under SCSP work.						**Estimated Money:-2000/-only**
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in Figures	Rate in Words	Amount
1	Excavation in hilly area in all kinds soils such as pick work,jumper work, soft and hard rock including chiseling , wedging out of rock (where blasting is prohibited) if required and saturated soil and their intermediate classification of soil seting out true to the required line, grades, width cutting and triming of side slopes and level as shown in the drawings and as directed by the Engineer-in-Charge.The recovery of the stones whether use full or not for 21.74 (Twenty one decimal seventy four) cubic metres in all cases at the rate of Rupees 300/- only (Three hundred only) per cubic metre shall be effected on pro-rata basis. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor , which shall have to be dully compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	434.83	Per cubic metre	226.00	Rupees Two hundred twenty six and paise nil only	98272
					Total	98272

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

Draft Schedule of Quantity						Estimated cost:-98294/-only
Name of Work:-Construction of road from Banda Bahadur road to lambardar basti at Lohgarh Km 0/0 to 0/255. (SH:- Formation cutting 5/7 mtr wide road from RD 0/0 to 0/045). under Deposit work.						Estimated Money:-2000/-only
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in hilly area in all kinds soils such as pick work,jumper work, soft and hard rock including chiseling , wedging out of rock (where blasting is prohibited) if required and saturated soil and their intermediate classification of soil seting out true to the required line, grades, width cutting and triming of side slopes and level as shown in the drawings and as directed by the Engineer-in-Charge.The recovery of the stones whether use full or not for 21.74 (Twenty one decimal seventy four) cubic metres in all cases at the rate of Rupees 300/- only (Three hundred only) per cubic metre shall be effected on pro-rata basis. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor , which shall have to be dully compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	434.93	Per cubic metre	226.00	Rupees Two hundred twenty six and paise nil only	98294
					Total	98294

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

Draft Schedule of Quantity						Estimated cost:-94497/-only
Name of Work:-Construction of road from Banda Bahadur road to lambardar basti at Lohgarh Km 0/0 to 0/255. (SH:-Formation cutting 5/7 mtr wide road from RD 0/045 to 0/095). under Deposit work.						**Estimated Money:-2000/-only**
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in Figures	Rate in Words	Amount
1	Excavation in hilly area in all kinds soils such as pick work,jumper work, soft and hard rock including chiseling , wedging out of rock (where blasting is prohibited) if required and saturated soil and their intermediate classification of soil seting out true to the required line, grades, width cutting and triming of side slopes and level as shown in the drawings and as directed by the Engineer-in-Charge.The recovery of the stones whether use full or not for 21.74 (Twenty one decimal seventy four) cubic metres in all cases at the rate of Rupees 300/- only (Three hundred only) per cubic metre shall be effected on pro-rata basis. Any loss to public or private property during the course of execution shall be the sole responsibility of the contractor , which shall have to be dully compensated by him at his own cost in all cases. The work shall be carried out as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	418.13	Per cubic metre	226.00	Rupees Two hundred twenty six and paise nil only	94497
					Total	94497

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

23
P-I

Draft Schedule of Quantity						Estimated cost:-73466/-only
Name of Work:- Repair and Maintenance of Ayurvedic Health centre building at Bhanet . (SH:- Plaster boundry wall plinth protection skarting & white wash). under Deposit work.						**Estimated Money:-1500/-only**
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Applying cement slurry on R.C.C. slab or cement concrete work using 2.75 kg. of cement per sq.metre of floor area before laying cement concrete flooring including roughening, cleaning of the concrete surfaces complete.	64.80	Per square metre	378.95	Rupees Three hundred seventy eight and paise ninty five only	24556
2	Providing under layer for plinth protection of 75mm (Seventy five milimetre) thick (Unconsolidated) bed of dry/stone aggregate 40mm(forty milimetre) nominal size with rammed and consolidated and grouted with fine sand including preparation of ground as per HP.PWD.,specification volume-I (one)including carriage of all labour equipment & materials to various location through all leads,lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	29.16	Per square metre	215.45	Rupees Two hundred fifteen and paise forty five only	6283
3	Providing plinth protection 50mm (fifty milimetre) thick in cement concrete 1 : 3 : 6 (One cement : three sand : six graded stone aggregate 20mm nominal size) as per HP.PWD., specification volume-I (one) including carriage of all labour equipment & materials to various location through all leads, lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	29.16	Per square metre	478.85	Rupees Four hundred seventy eight and paise eighty five only	13963
4	15mm (fifteen milimetre) cement plaster in single coat on rough side of brick/ concrete/stone walls of interior plastering upto floor two level including arrises,internal rounded angles, chamfers & rounded angles not exceeding 80mm in (eighty milimetre) grith finished even and smooth in cement mortar 1:6 (One cement : six approved sand) as per HP.PWD.,specification volume-I (one)including carriage of all labour equipment & materials to various location through all leads,lifts & other incidental charges complete as per entire satisfaction of the Engineer-in-Charge.	73.28	Per square metre	182.90	Rupees one hundred eighty two and paise ninty only	13403

5	Providing and laying spartic ceremic tiles 5.5mm (Five point five millimetres) thick in flooring,300 x300mm (Three hundred into three hundred millimetres size) treads of steps laid on a bed of 12 mm (Twelve millimetres) thick cement mortar 1:3(One cement: thjree sand) finished with flush pointing in white cement. including all leads ,lifts and carriage of material as per entire satisfaction of Engineer-in-charge.	16.52	Per square metre	859.70	Rupees Eight hundred fifty nine and paise seventy only	14202
6	White washing with lime to give an even shade :New work (two or more coats)all leads &lifts as per entire satisfaction & direction of Engineer-in -charge	73.28	Per square metre	14.45	Rupees Forteen and paise forty five only	1059
					Total	73466

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

(24)
P-1

Draft Schedule of Quantity						Estimated cost:-94330/-only
Name of Work:- Restoration of rain damage of HP.PWD Store Majra boundry wall. (SH:- Re-construction of damage boundary wall around the Majra store). Job No.I						**Estimated Money:-2000/-only**
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earth work in excavation by mechnical means (Hydraulic excavator)/ manual means over areas (30 cm in depth 1.5 mtr in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 mtr and lift upto 1.5 mtr, as directed by Engineer-in-charge.	12.60	Per cubic metre	190.00	Rupees One hundred ninty and paise nil only	2394
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth leve l :4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge	2.24	Per cubic metre	4955.20	Rupees Four thousand nine hundred fifty five and paise twenty only	11100
3	Random rubble masonry /polygonal rubble masonry, un coursed brought to courses with hard stone of approved quality in foundation and plinth in Cement mortor 1:6 (one cement: six sand) and cement concrete 1:6:12 (one cement six sand twelve aggregate graded stone 20mm nominal size)including haulage of materials with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.	5.60	Per cubic metre	5002.35	Rupees Five thousand two and paise thirty five only	28013
4	Providing and laying damp proof course 38mm thick with cement concrete 1:2:4 (1 cement:2 sand:4 stone aggregate 12.5mm nominal size) and curing complete. including all leads lifts and carriage of materials, as per entire satisfaction of Engineer-in-charge.	5.60	Per square metre	284.20	Rupees Two hundred eighty four and paise twenty only	1592
5	Brick work with common burnt clay F.P.S.non modular bricks in class desination 7.5 in foundation and plinth in cement mortar 1:4 (one cement : four sand) including all leads ,lifts and carriage of material as per entire satisfaction of Engineer-in-charge.	6.44	Per cubic metre	5528.25	Rupees Five thousand five hundred twenty eight and paise twenty five only	35602

6	15 mm cement plaster on the rough side of single or half brick wall of mix :1:4 (1 cement: 4 fine sand) including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge. .	56.00	Per square metre	200.45	Rupees Two hundred and paise forty five only	11225
7	White washing with lime to give an even shade :New work (two or more coats)all leads &lifts as per entire satisfaction & direction of Engineer-in -charge	56.00	Per square metre	17.45	Rupees seventeen and paise forty five only	977
8	Finishing walls with water proofing cement paint of required shade :New work (one or more coats applied @ 3.84 kg/10 sqm) as per entire satisfaction & direction of Engineer-in -charge	56.00	Per square metre	61.20	Rupees sixty one and paise twenty only	3427
					Total	94330

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.

Job No 25.
P-1.

Draft Schedule of Quantity						Estimated cost:-79912/-only
Name of Work:- Repair and Maintenanc of Ayurvedic Health centre building at Bhanet . (SH:- Dismantelling wooden work,new pannel roof treatment floor tiles).under Deposit work.						Estimated Money:-1600/-only
						Time:-Three Months
Ser No.	Sub heads and items of work.	Qty	Unit	Rate in Figures	Rate in Words	Amount
1	Dismantling doors, windows and clerestory windows, ventilators etc. (wood orclerestory windows,ventilators etc. (wood orsteel) shutters including chowkhats, architraves, hold fasts and other attachements etc. complete and stacking them within 20 metres leade exceeding 3 sqm in area.	2.00	Each	156.25	Rupees One hundred fifty six and paise twenty five only	313
2	Demolition above G.L. up to floor two level including disposal of unserveceable material with in 20 mtr lead and including cutting necessary reinforcement and RCC/RB work RCC work	6.59	Per cubic metre	845.00	Rupees Eight hundred forty five and paise nil only	5569
3	Providing and fixing panelled glazed or panelled and glazed shutters for doors windows and clerestory windows. Including black enamelled iron butt hinges with necessary screws. 40mm Forty millimetres) thick Second class deodar wood, including all leads, lifts and carriage of materials as per entire satisfaction of Engineer-in-charge.	1.30	Per square metre	2945.15	Rupees Two thousand nine hundred forty five and paise fifteen only	3829
4	Providing and fixing fly proof galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws,with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.	3.40	Per square metre	1354.00	Rupees one thousand three hundred fifty four and paise nil only	4604
5	Grading roof for water treatment with cement concrete 1:2:4 (1 cement:2sand:4 grade stone aggregate 20mm nominal size)including carriage of materials with in all leads,lifts and other incidentals complete as per entire satisfaction of the Engineer-in-charge.	4.63	Per cubic metre	5905.00	Rupees Five thousand nine hundred five and paise nil only	27340

6	Providing and laying Vitrified tiles in floor with different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to S:15622, of approved brand & manufacturer, in all colours and shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS : 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately Size of Tile 600x600 mm with in all leads, lifts and carriage of materials and as per the directions of the Engineer-in-Charge.	37.36	Per square metre	1024.00	Rupees One hundred twenty four and paise nil only	38257
					Total	79912

Executive Engineer,
B&R Division,
HP.PWD,Paonta Sahib.