

Himachal Pradesh
Public Works Department
NO.PW.TH.D/CB-TENDER/2025-26- 2624-35
To

Dated:- 9/7/2025

The Executive Engineer, (I.T. Cell),
O/O Engineer-in-Chief,
H.P.P.W.D., Nirman Bhawan,
Shimla-2

Subject:- Publication of Tender Notice
Sir,

I am enclosing herewith Notice Inviting Tenders for the various work typed in English for uploading the same on department website in view of Principal Secretary (PW) to the Government of Himachal Pradesh Notification No. PBW(B)A(3)1/2024 dated 03/01/2025.

As the works mentioned in the tender notice are urgent in nature and in public interest.

Encl:- As above

Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

Copy forwarded to the following a/w copy of tender notice for information:-

- 1 The Deputy Commissioner, Shimla Distt. Shimla, HP
- 2 The Superintending Engineer, 4th Circle, H.P.P.W.D., Shimla-3 .
- 3 The Sub-Divisional Officer(C) Theog
- 4 The Municipal Council Theog
- 5 Block Development Officer, Theog Block
- 6 All the Assistant Engineers working under this division
- 7 Superintendent Gr-II (Estt.) in this division
- 8 Drawing branch in this office.
- 9 Notice Board .

Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

Himachal Pradesh Public Works Department NOTICE INVITING TENDER

Scaled item rate tenders on PWD form 6 & 8 are hereby invited by the Executive Engineer, -/Theog Division, H.P.P.W.D., Theog on behalf of the Governor of HP, for the following works from the eligible contractors enlisted in H.P.P.W.D. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in this office on or before 19.07.2025 up to 11.00 A.M. and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on 18.07.2025 up to 4.00 P.M. and the application for issue of tender form shall be received on 17.07.2025 up to 4.00 P.M.

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/ Bank duly pledged in favour of XEN HPPWD. Theog must be accompanied with the application for tender documents. Please note no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 120 days. The Executive Engineer reserves the right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue.

Sr.No	Name of work	Name of Divn.	Estimated cost(Rs.)	Earnest money (Rs.)	Cost of form (Rs)	Time Allowed
1	C/O Devgarh Jarai to Manlog road Km 0/0 to 7/500 (SH:- P/L Kharanja stone soling at Km/Rd 2/225 to 2/375)	Theog	88,633/-	1,800/-	350	One Month
2	C/O Sarion Bhailech Jadeog road Km 0/00 to 3/300 (SH:- C/O unlined surface drain in Km 0/0 to 3/300)	Theog	95,700/-	1,900/-	1000/-	One Month
3	R/R damages on various roads under Theog Sub-Division (SH:- Hiring of JCB for removal of slips and dressing of berm)	Theog	98,700/-	2,000/-	350	One Month
4	R/R damages on various roads under Matiana Sub-Division (SH:- Hiring of JCB for removal of slips and dressing of roads and Hiring of Tipper in Mahori section.)	Theog	99,750/-	2,000/-	350	One Month
5	R/R Damages on Various road in Matiana Sub-Division (SH:- Hiring of JCB for removal of slips and dressing of roads and Hiring of Tipper in Mahori Section.)	Theog	99,750/-	2,000/-	350	One Month
6	R/R Damages on Various road under Theog Sub-Division (SH:- Hiring of JCB for removal of slips in various roads)	Theog	99,750/-	2,000/-	350	One Month
7	R/R Damages on Various road under Theog Sub-Division (SH:- Hiring of JCB for removal of slips in various roads)	Theog	99,750/-	2,000/-	350	One Month
8	Restoration of rain damages on Various road under Sub-Division Sainj (Deha Section) (SH:- Hiring of JCB for removal of slips and dressing of roads)	Theog	99,750/-	2,000/-	350	One Month

9	Restoration of rain damages on Various road under Sub-Division Sainj (Sainj Section) (SH:- Hiring of JCB for removal of slips and dressing of roads)	Theog	99,750/-	2,000/-	350	One Month
10	Restoration of rain damages on Various road under Sub-Division Sainj (Deha Section) (SH:- Hiring of JCB for removal of slips and dressing of roads)	Theog	99,750/-	2,000/-	350	One Month
11	Restoration of rain damages on Various road under Sub-Division Sainj (Deha Section) (SH:- Hiring of JCB for removal of slips and dressing of roads)	Theog	99,750/-	2,000/-	350	One Month
12	Restoration of rain damages on Various road under Sub-Division Sainj (Deha Section) (SH:- Hiring of JCB for removal of slips and dressing of roads)	Theog	99,750/-	2,000/-	350	One Month
13	R/R of rain damages on various roads under Sainj Sub-Division (SH:- Hiring of JCB for removal of slips.)	Theog	99,750/-	2,000/-	350	One Month
14	R/R damages on Treasury office Building at Theog (SH:- C/O R/wall behind the treasury office at Theog Distt. Shimla HP)	Theog	98,968/-	2,000/-	350	One Month
15	R/R of rain damages on Matiana Mahori Guthan road km 0/0 to 24/00 (under Matiana Sub-Division (SH:- Hiring of JCB for removal of slips at Rd 17/200. (Mahori Section)	Theog	99,750/-	2,000/-	350	One Month
16	Restoration of rain damages on Various road under Sainj Sub-Division (SH:- Hiring of JCB for removal of slips and dressing of roads)	Theog	99,500/-	2,000/-	350	One Month
17	Restoration of rain damages on Various road under Sainj Sub-Division (SH:- Hiring of JCB for removal of slips and dressing of roads)	Theog	45,150/-	1,000/-	350	One Month
18	R/R damages on various roads under Theog Sub-Division (SH:- Hiring of Tractor for carriage of debris/stone in Theog Section)	Theog	61,250/-	1,250/-	350/-	One Month
19	A/R & M/O of Degree College at Theog Distt. Shimla (HP) (SH:- P/F aluminium grill) balance work thereof)	Theog,	58,724/-	1,200/-	350/-	One Month
20	Restoration of rain damages on various roads under Matiana Sub-Division (SH:- Hiring of JCB for removal of slips) Mahori Section.	Theog,	99,750/-	2,000/-	350/-	One Month
21	Restoration of rain damages on various roads under Matiana Sub-Division (SH:- Hiring of JCB for removal of slips) Matiana Section.	Theog	99,750/-	2,000/-	350/-	One Month
22	Restoration of rain damages on various roads under Matiana Sub-Division (SH:- Hiring of JCB for removal of slips) Shilaroo Section.	Theog	99,750/-	2,000/-	350/-	One Month
23	Restoration of rain damages on various roads under Matiana Sub-Division (SH:- Hiring of JCB for removal of slips) Kiartoo Section.	Theog	99,750/-	2,000/-	350/-	One Month
24	Restoration of rain damages on various roads under Sainj Sub-Division (SH:- Hiring of JCB for removal of slips) Sainj Section.	Theog	99,750/-	2,000/-	350/-	One Month
25	Restoration of rain damages on various roads under Sainj Sub-Division (SH:- Hiring of JCB for removal of slips) Kuthar Section.	Theog	99,750/-	2,000/-	350/-	One Month

29	restoration of rain damages on various roads under Sainj Sub-Division (SH:- Hiring of JCB for removal of slips) Deha Section.	Theog	99,750/-	2,000/-	350/-	One Month
27	Restoration of rain damages on various roads under Theog Sub-Division (SH:- Hiring of JCB for removal of slips) Sandhu Section.	Theog	99,750/-	2,000/-	350/-	One Month
28	Restoration of rain damages on various roads under Theog Sub-Division (SH:- Hiring of JCB for removal of slips) Fagu Section.	Theog	99,750/-	2,000/-	350/-	One Month
29	Restoration of rain damages on various roads under Theog Sub-Division (SH:- Hiring of JCB for removal of slips) Theog Section.	Theog	99,750/-	2,000/-	350/-	One Month

Following documents should accompany the application for tenders:-

- (1) The contractors are required to be produce a copy of their PAN No. GST and should also produce a copy of enlistment/renewal letter.
- (2) The tender form will be issued to those contractors only who is having requisite machinery such as, J.C.B Tipper etc. or on production of legal documents in proof of tie-up with the owner of such machinery to be borrowed from another firm/contractor
- (3) Special care should be taken to write the rates both in figures and in words failing which tender is likely to be rejected
- (4) The contractor will have to submit the proof of registration Under Employees Provident Fund & Miscellaneous Provision Act, 1952 at the time of tender. Failure to observe this condition shall render the tender of contractor liable to summary rejection.

Executive Engineer,
Theog Division B&R,
H.P.W.D., Theog

It is certified that the tenders for various works as called for vide this office letter No. PW.TH/D/CB-tender/2025-26-2624-35 dated 9/7/25 are of emergent nature in exigency of public interest.

Dated: 9th July, 2025
Place: Theog


Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.88633

Earnest Money:1800/

Time: One months

1

ne of Work : C/O Devgarh Jarai Manlog road km 0/0 to 7/500(SH:- P/L Kharanja stone soling at RD 2/225 to 2/375.)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil. i/c all leads and lifts and as per direction of the Engineer-in-Charge.	552.75	1.00	One Rupee Only	Per square metre	
2	Consolidation of sub-grade with road roller including making good the undulation etc. with earth or quarry soil etc. and re-rolling the sub-grade. i/c all leads and lifts and as per direction of the Engineer-in- Charge.	552.75	2.10	Rupees Two and Paise Ten Only	Per square metre	
3	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour)	204.51	1727.00	Rupees One Thousand Seven Hundred Twenty Seven Only	Per cubic meter	
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

4

Earnest Money:-1950/

Time: One months

Line of Work : C/O Sarion Bhalech Jadeog road km 0/0 to 3/300 (SH:- C/O unlined surface drain in km 0/0 to 3/300.)


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

3

Estimated Cost Rs 98700/
Earnest Money: 2000 /
Time: one Month

Particulars of Work : - R/R damages on Various road under Theog Sub -Division . (SH:- Hiring of JCB for removal of slips and Dressing of berm)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB/ Excavator be deployed for removal of slips i/c cost of fuel oil lubricants and wages of operational staff any repair ,breakage during operation will be carried out by the owner at his risk and cost shifting of machineries from one place to other required location, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum removal of earth in one hours i/c loading in tippers/trucks and disposing excavated earth i/c all leads and lifts as per direction of the Engineer-in-Charge	94.00	1050.00	Rupees One Thousand Fifty Only	Per hours	98700
						98700
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

4

Sl. No.	Particulars	Amount
1	One of Work :- R/R damages on Various road under Matiana Sub -Division . (SH:- Hiring of JCB for removal of slips and Dressing of Roads and Hiring of Tipper in Mahori Section)	


Executive Engineer,
Theog Division,
HP.PWD. Theog

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

5

Estimated Cost Rs 99750/

Earnest Money: 2000 /

Time: one Month

Work : - R/R damages on Various road under Matiana Sub -Division . (SH:- Hiring of JCB for removal of slips and Dressing of Roads and
g. of Tipper in Mahori Section)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB/ Excavator be deployed for removal of slips i/c cost of fuel oil lubricants and wages of operational staff any repair ,breakage during operation will be carried out by the owner at his risk and cost shifting of machineries from one place to other required location, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum removal of earth in one hours i/c loading in tippers/trucks and disposing excavated earth i/c all leads and lifts as per direction of the Engineer-in-Charge	95.00	1050.00	Rupees One Thousand Fifty Only	Per hours	99750
						99750
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

6

Estimated Cost Rs 99750/

Earnest Money: 2000 /

Time: ~~15 days~~ *one month*

Item of Work : - R/R damages on Various roads in Theog Sub-Division (SH:- Hiring of JCB for removal of slips in Various road)

Sl. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB (excavator cum-loader) including P.O.I charges, shifting charges and other ancillary equipments as required at site of work for removal of slip in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work , pick work, Jumper work , soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary . The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damages tool place, the contractor is liable for it . All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30 cubic meter of earth work shall be done by machine in one hour , other wise number of hour shall be reduced accordingly as per instruction i/c all leads and lifts as per the direction of the Engineer-in-Charge.	95.00	1050.00	Rupees One Thousand Fifty Only	Per hours	99750
						99750
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

7

Estimated Cost Rs 99750/

Earnest Money:2000 /

Time: 15-days *one month*

e of Work : - R/R damages on Various roads in Theog Sub -Division (SH:- Hiring of JCB for removal of slips ain Various road)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
	Hiring of JCB (excavator cum-loader) including P.O.I charges, shifting charges and other ancillary equipments as required at site of work for removal of slip in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work , pick work, Jumper work , soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary . The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damages tool place, the contractor is liable for it . All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30 cubic meter of earth work shall be done by machine in one hour , other wise number of hour shall be reduced accordingly as per instruction i/c all leads and lifts as per the direction of the Engineer-in-Charge.	95.00	1050.00	Rupees One Thousand Fifty Only	Per hours	99750
						99750
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

9

Estimated Cost Rs 99750/
Earnest Money:2000 /
Time: one month

Work : - R/R damages on Various roads under Sainj Sub -Division (Deha section) . (SH:- Hiring of JCB for removal of slips and dressing roads)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB (excavator cum-loader) including P.O.I charges, shifting charges and other ancillary equipments as required at site of work for removal of slip in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work , pick work, Jumper work , soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary . The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damages tool place, the contractor is liable for it . All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30 cubic meter of earth work shall be done by machine in one hour , other wise number of hour shall be reduced accordingly as per instruction i/c all leads and lifts as per the direction of the Engineer-in-Charge.	95.00	1050.00	Rupees One Thousand Fifty Only	Per hours	99750
						99750
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

10

Estimated Cost Rs 99750/

Earnest Money:2000 /

Time: one Month

Work : - R/R damages on Various roads under Sainj Sub -Division (Sainj section) . (SH:- Hiring of JCB for removal of slips and dressing roads)

Sr. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB/ Excavator be deployed for removal of slips i/c cost of fuel oil lubricants and wages of operational staff any repair package during operation will be carried out at his risk and cost including carrying of machinery from one place to other required location, actual working hours will be accounted for the payment and proper disposal slip/by the contractor will be insured and i/c all leads and lifts as per direction of the Engineer-in-Charge	95.00	1050.00	Rupees One Thousand Fifty Only	Per hours	99750
						99750
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

13

Estimated Cost Rs 99750/
Earnest Money:2000 /

Time: 15 days

Work :- R/R damages on Various roads under Sainj Sub -Division (Deha section) . (SH:- Hiring of JCB for removal of slips and dressing roads)(Sainj section)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB (excavator cum-loader) including P.O.I charges, shifting charges and other ancillary equipments as required at site of work for removal of slip in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work , pick work, Jumper work , soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary . The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damages tool place, the contractor is liable for it . All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30 cubic meter of earth work shall be done by machine in one hour , other wise number of hour shall be reduced accordingly as per instruction i/c all leads and lifts as per the direction of the Engineer-in-Charge.	95.00	1050.00	Rupees One Thousand Fifty Only	Per hours	99750
						99750
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 99750/
Earnest Money:2000 /
Time: 15 days

Time of Work : - R/R damages on Various roads under Sainj Sub -Division (Deha section) . (SH:- Hiring of JCB for removal of slips and dressing roads)(Sainj section)	Time: 15 days
---	----------------------

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB (excavator cum-loader) including P.O.I charges, shifting charges and other ancillary equipments as required at site of work for removal of slip in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work , pick work, Jumper work , soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary . The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damages tool place, the contractor is liable for it . All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30 cubic meter of earth work shall be done by machine in one hour , other wise number of hour shall be reduced accordingly as per instruccction i/c all leads and lifts as per the direction of the Engineer-in-Charge.	95.00	1050.00	Rupees One Thousand Fifty Only	Per hours	99750
						99750
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

11

Estimated Cost Rs 99750/

Earnest Money:2000 /

Time: 15 days

Work : - R/R damages on Various roads under Sainj Sub -Division (Deha section) . (SH:- Hiring of JCB for removal of slips and dressing

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB (excavator cum-loader) including P.O.I charges, shifting charges and other ancillary equipments as required at site of work for removal of slip in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work , pick work, Jumper work , soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary . The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damages tool place, the contractor is liable for it . All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30 cubic meter of earth work shall be done by machine in one hour , other wise number of hour shall be reduced accordingly as per instruction i/c all leads and lifts as per the direction of the Engineer-in-Charge.	95.00	1050.00	Rupees One Thousand Fifty Only	Per hours	99750
						99750
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

12

Estimated Cost Rs 99750/

Earnest Money: 2000 /

Time: one Month

e of Work : - R/R damages on Various roads under Sainj Sub -Division (SH:- Hiring of JCB for removal of slips.)						
No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1.	Hiring of JCB/ Excavator be deployed for removal of slips i/c cost of fuel oil lubricants and wages of operational staff any repair package during operation will be carried out at his risk and cost including carrng of machinery from one place to other required location, actual working hours will be accounted for the payment and proper disposal slip/by the contractor will be insured and i/c all leads and lifts as per direction of the Engineer-in-Charge	95.00	1050.00	Rupees One Thousand Fifty Only	Per hours	99750
						99750
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs.98968

Earnest Money:2000/

Time: One months

name of work:- R/R Damages on Treasury office Building at Theog (SH:- C/O R/wall behind the Treasury office at Theog Distt. Shimla HP .)

Sl. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge In cement mortar	21.50	1011.75	Rupees One Thousand Eleven and Paise Seventy Five Only	Per cubic meter	21753
2	Random rubble masonry/polygonal rubble masonry (uncoursed/brought to courses) with hard stones of approved quality in foundation and plinth including leveling up with cement concrete 1:6:12 (1 cement :6 sand : 12 graded stone aggregate 20mm nominal size) at plinth level in cement mortar 1:6 (1 cement :6 sand) including all leads and lifts as per direction of the Engineer-in-Charge.	21.50	3260.00	Rupees Three Thousand Two Hundred Sixty Only	per cubic meter	70090
3	Providing and fixing weapholes in brick masonry/stone masonry plain RCC abument,B/wall R/wall with 110 mm dia (4 KgCm2 pressure)PVC pipe i/c all leads and lifts.as per direction of the Engineer -in -Charge.	6.00	242.50	Rupees Two Hundred Forty Two and Paise Fifty Only	each	1455
4	Back filling behind the retaining wall. all leads and lifts as per direction of the Engineer -in -Charge.	5.40	1050.00	Rupees One Thousand Fifty Only	Per cubic meter	5670
	Quoted Rate in +/- %					98968
	Quoted Rate in figer					

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

11

Estimated Cost Rs.99750
Earnest Money:2000/
Time: One months

Work : - R/R damages on Matiana Mohari Guthan road km 0/0 to 24/0 Matiana Sub -Division (SH:- Hiring of JCB for removal of slips at 17/200 Mohari Section .)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB/ Excavator be deployed for removal of slips i/c cost of fuel oil lubricants and wages of operational staff any repair ,breakage during operation will be carried out by the owner at his risk and cost shifting of machineries from one place to other required location, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum removal of earth in one hours i/c loading in tippers/trucks and disposing excavated earth i/c all leads and lifts as per direction of the Engineer-in-Charge	95.00	1050.00	Rupees One Thousand Fifty Only	Per hours	99750
						99750
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

8

Estimated Cost Rs.99500

Earnest Money: 1000/-

Time: One months

Line of Work :- R/R damages on Various roads under Sainj Sub -Division (SH:- Hiring of JCB for removal of slips and dressing of road)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB/ Excavator be deployed for removal of slips i/c cost of fuel oil lubricants and wages of operational staff any repair ,breakage during operation will be carried out by the owner at his risk and cost shifting of machineries from one place to other required location, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum removal of earth in one hours i/c loading in tippers/trucks and disposing excavated earth i/c all leads and lifts as per direction of the Engineer-in-Charge	95.00	1050.00	Rupees One Thousand Fifty Only	Per hours	99750
						99750
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

Earnest Money: 1000/

Time: One month

Sl. No.	Name of Work	- R/R damages on various roads under Sainj Sub -Division	(SH:- Hiring of JCB for removal of slips and dressing of roads)

Executive Engineer,
Theog Division,
HP.PWD. Theog

Executive Engineer,
Theog Division,
HP.PWD. Theog

Estimated Cost Rs.61250
Earnest Money:1250/

Time: One months

ne of Work : - R/R damages on various roads under Theog Sub -Division . (SH:- Hiring of tractor for carriage of debries/ stone in Theog - Division)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of tractor with Trolley for carriage of materials including P.O.L charges shifting charges and other ancilliary equipment as required at site of work . The work shall have to carried out as per Ministry of Transport specification of the the Engineer-in-Charge including all lead and lifts.	25.00	2450.00	Rupees Thousand Hundred Fifty Only Two Four	Per hours	61250
						61250
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

2

Estimated Cost Rs.58724

Earnest Money:1200/

Time: One months

ne of work:- A/R and M/O of Degree College at Theog Distt .Shimla H. P (SH):- P/F aluminium grill))balance work there of.)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Providing and fixing anodised aluminium grill (anodised transparent or dyed to required shade according to IS: 1868 with minimum anodic coating of grade AC 15) of approved design/pattern, with approved standard section and fixed to the existing window frame with C.P. brass/ stainless steel screws @ 200 mm centre to centre, including cutting the grill to proper opening size for fixing and operation of handles and fixing approved anodised aluminium standard section around the opening, all complete as per requirement and direction of Engineer-in-charge. (Only weight of grill to be measured for payment). including all leads and lifts as per direction of the Engineer-in-Charge.	71.83	599.90	Rupees Five Hundred Ninety Nine and Paise Ninety Only	Per kilo gram	43091
2	Prelaminated board /bwp phenol bonded exterior/interior grade both sides. including all leads and lifts as per direction of the Engineer-in-Charge. 12mm thick.	9.12	1407.90	Rupees One Thousand Four Hundred Seven and Paise Ninety Only	Per square meter	12840
3	Providing and fixing Brass 100mm mortice latch and lock with 6 levers without pair of handles (best make of approved quality) for aluminium doors including necessary cutting and making good etc. complete including all leads and lifts as per direction of the Engineer-in-Charge.	7	398.95	Rupees Three Hundred Ninety Eight and Paise Ninety Five Only	each	2793
						58724
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HPPWD Theog

Schedule OF Quantity

Estimated Cost: 99750-
Earnest Money: 2000/-
Time: one month

Name of Work:- Restoration of rain damages on Various road Under Matiana sub division (SH:-Hiring of JCB for removal of slips)Mohari Seaction

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total:-	99750.00
	Rate Quoted by the Contarctor	(Rs in Fig)		% above/Below	
		(Rs In words)		% above/Below	


Executive Engineer,
Theog Division,
HP.PWD. Theog

Schedule OF Quantity

Estimated Cost: 99750-
Earnest Money: 2000/-
Time: one month

Name of Work:- Restoration of rain damages on Various road Under Matiana sub division (SH:-Hiring of JCB for removal of slips)Matiana Seaction

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total:-	99750.00
	Rate Quoted by the Contarctor	(Rs in Fig)		% above/Below	
		(Rs In words)		% above/Below	


Executive Engineer,
Theog Division,
HP.PWD. Theog

Schedule OF Quantity

Estimated Cost: 99750-
Earnest Money: 2000/-
Time: one month

Name of Work:- Restoration of rain damages on Various road Under Matiana sub division (SH:-Hiring of JCB for removal of slips)Shilaroo Seaction

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total:-	99750.00
				% above/Below	
				% above/Below	

Executive Engineer,
Theog Division,
HP.PWD. Theog

Schedule OF Quantity

Estimated Cost: 99750-
Earnest Money: 2000/-
Time: one month

Name of Work:- Restoration of rain damages on Various road Under Matiana sub division (SH):-Hiring of JCB for removal of slips)Kiartoo Seaction

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total:-	99750.00
	Rate Quoted by the Contarctor	(Rs in Fig)		% above/Below	
		(Rs In words)		% above/Below	



Executive Engineer,
Theog Division,
HP.PWD. Theog

Schedule OF Quantity

Estimated Cost: 99750-
Earnest Money: 2000/-
Time: one month

Name of Work:- Restoration of rain damages on Various road Under Sainj sub division (SH:-Hiring of JCB for removal of slips)Sainj Seaction

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total:-	99750.00
				% above/Below	
				% above/Below	


Executive Engineer,
Theog Division,
HP.PWD. Theog

Schedule OF Quantity

Estimated Cost: 99750-
Earnest Money: 2000/-
Time: one month

Name of Work:- Restoration of rain damages on Various road Under Sainj sub division (SH:-Hiring of JCB for removal of slips)Kuthar Seaction

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total:-	99750.00
				% above/Below	
	Rate Quoted by the Contarctor	(Rs in Fig)		% above/Below	
		(Rs In words)			



Executive Engineer,
Theog Division,
HP.PWD. Theog

Schedule OF Quantity

Estimated Cost: 99750-
Earnest Money: 2000/-
Time: one month

Name of Work:- Restoration of rain damages on Various road Under Sainj sub division (SH:-Hiring of JCB for removal of slips)Deha Seaction

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total:-	99750.00
	Rate Quoted by the Contarctor	(Rs in Fig)		% above/Below	
		(Rs In words)		% above/Below	


Executive Engineer,
Theog Division,
HP.PWD. Theog

Schedule OF Quantity

Estimated Cost: 99750-
Earnest Money: 2000/-
Time: one month

Name of Work:- Restoration of rain damages on Various road Under Theog sub division (SH:-Hiring of JCB for removal of slips)Sandhu Seaction

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total:-	99750.00
				% above/Below	
				% above/Below	

Executive Engineer,
Theog Division,
HP.PWD. Theog

Schedule OF Quantity

Estimated Cost: 99750-
Earnest Money: 2000/-
Time: one month

Name of Work:- Restoration of rain damages on Various road Under Theog sub division (SH:-Hiring of JCB for removal of slips)Fagu Section

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total:-	99750.00
				% above/Below	
				% above/Below	
	Rate Quoted by the Contarctor	(Rs in Fig)			
		(Rs In words)			


Executive Engineer,
Theog Division,
HP.PWD. Theog

Schedule OF Quantity

Estimated Cost: 99750-
Earnest Money: 2000/-
Time: one month

Name of Work:- Restoration of rain damages on Various road Under Theog sub division (SH:-Hiring of JCB for removal of slips)Theog Seaction

Sr.No	Description of Item	Qty.	Rate	Unit	Amount
1	Hiring of JCB earth cutting / excavating machinaries to be deployed for earth cutting/excavation for filling including cost of fuel oil lubricants and wages of operational staff any repair brackage during operation will be carried out by the owner at his risk and cost including shifting of machinaries from one place to other at required locations, actual working hours will be accounted for the payment and six hours per day working will be required average minimum 20 cum excavation in all kinds of soil including loading in tipper /truks and disposing excavated earth in all leads and lifts will have to be ensured in one hour working (a. excavator -cum-loader)	95.00	1050.00	Hrs	99750.00
				Total:-	99750.00
				% above/Below	
				% above/Below	
	Rate Quoted by the Contarctor	(Rs in Fig)			
		(Rs In words)			


Executive Engineer,
Theog Division,
HP.PWD. Theog