



**Office of the Executive Engineer, Division Kalpa (B&R)
HP.PWD; Kalpa District Kinnaur Himachal Pradesh**

Phone No. 01786-226027 Web: www.hppwd.gov.in Email: hp-kin@nic.in Fax No. 01786-226027

No:- PW/KNR-E-Tender/2025/- 2391-2415

Dated:- 18-07-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar,
HP.PWD. Shimla-2.

Subject:-

Publication of Tender Notice (OFFLINE) on the Departmental website.

Dear Sir,

Enclosed please find herewith the Tender Notice for the work specified in the Notice Inviting Tender (NIT). You are therefore requested to upload the same on the official website of the department in accordance with Notification No. PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.


The works mentioned in the Notice Inviting Tender are urgent/emergent nature of works in public interest. Kindly ensure the prompt publication of the same on the website.

Encl:- NIT, Schedule of Quantity
& Certificate.


Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.


Copy forwarded for information to:-

1. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
2. All the Assistant Engineers working under this Division.
3. Drawing Branch of this office.
4. Notice Board.


Executive Engineer,
Kalpa Division (B&R),
HP. PWD; Kalpa.

CERTIFICATE

Certified that the Tender for works called vide this
office Letter No. PW/KNR/E-Tender/2025/- 2416-29.....dated 18/07/2025
from Sr. No. 1 to 7 are of urgent nature and public interest.


**Executive Engineer,
Kalpa Division (B&R),
HF-PWD; Kalpa**

HP.P.W.D. TENDER NOTICE (offline)


Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the **Executive Engineer, Kalpa Division, HP.PWD: Kalpa** for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **28-07-2025 up to 10.30 A.M.** and shall be opened on the same day at **11:00 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on any working day during the office hours upto **4:00 P.M.** on **26-07-2025** No application for issue of tender forms will be received on **26-07-2025** after **4:00 PM.** If the office happens to be closed on the above mentioned dates, the tenders will be sold/opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R,s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The officer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	Preparation of estimate for the construction of Multipurpose Hall at Ice Sketing Rink at Kalpa in Distt. Kinnaur (HP). (Revised)	125000/-	2500/-	One Month	350/-	"D" class
2	Preparation of estimate for the construction of Heliport at Sharbo in Distt. Kinnaur (HP)	449000/-	9000/-	One Month	350/-	"D" class
3	Preparation of estimate for the construction of Mini Statium at Rarang in Distt. Kinnaur (HP).	132000/-	3000/-	One Month	350/-	"D" class
4	Preparation of estimate for the special repair to Suspension Bridge over River Satluj to Gymthing valley road at 0/700.	175000/-	3500/-	One Month	350/-	"D" class
5	Construction of Ware House for storage of Electronic Voting Machine at Reckong Peo in Distt. Kinnaur (HP). (SH:- Providing and laying G.I. pipe line 32mm dia from main inlet tank to IPH storage tank)	219891/-	4500/-	One Month	350/-	"D" class
6	A/R & M/O link road to village Nako Km. 0/00 to 1/700. (SH:- C/O R/wall in RR Masonry at RD. 0/990 to 1/010).	451321/-	9500/-	One Month	350/-	"D" class
7	A/R & M/O Jeepable road from Aucktong to Dumdumka Km. 0/00 to 0/750. (SH:- C/O Edge wall in RR Masonry at RD. 0/090 to 0/135 and 0/560 to 0/600).	2,20,976/-	4500/-	One Month	350/-	"D" class

Terms and conditions:-

Following documents should accompany the application for tenders:-

1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts Number allotted by the Provident Fund Commissioner Shimla and copy of PAN Number.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not be entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in hand.



Executive Engineer,
Kalpa Division (B&R),
HP. PWD; Kalpa.

No.- PW/KNR-E-Tender/NIT/2025/- 2466-29

Dated:- 18-07-2025

Copy forwarded for information to:-

1. The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional Officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
5. The Block Development Officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.


Executive Engineer,
Kalpa Division (B&R),
HP. PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Preparation of estimate for the construction of Multipurpose Hall at Ice Skating Rink at Kalpa in Distt. Kinnaur (H.P.) (Revised)

Estimated Cost :: 1,25,000/-
Earnest Money :: 2,500/-
Time :: One month

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Job work for preparing of estimate of whole project as per architectural drawing for the construction of buildings in District Kinnaur (H.P.). Under the job work shall also include supplying detailed estimate duly supported with analysis of rates 2021 on prevailing market rates approved working estimate from the competent authority alongwith DNIT for material in the area and approved labour rate by Govt. of H.P. and submission of the same in this office in hard and soft copy as per direction of Engineer-in Charge, 11 th. Circle HP.PWD. Rampur (H.P.) /Executive Engineer Kalpa Division HPPWD. Kalpa.	1.00			Each	
				Total:-		

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Preparation of estimate for the construction of Heliport at Sharbo in Distt. Kinnaur (H.P.)

Estimated Cost :- 4,49,000/-
Earnest Money :- 9,000/-
Time :- One month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Job work for preparing of estimate of whole project as per architectural drawing for the construction of buildings in District Kinnaur (H.P.). Under the job work shall also include supplying detailed estimate duly supported with analysis of rates 2021 on prevailing market rates approved working estimate from the competent authority alongwith DNIT for material in the area and approved labour rate by Govt. of H.P. and submission of the same in this office in hard and soft copy as per direction of Engineer-in Charge, 11 th. Circle HP.PWD. Rampur (H.P.) /Executive Engineer Kalpa Division HPPWD. Kalpa.	1.00			Each	
				Total:-		

Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

73

SCHEDULE OF QUANTITY

Name of work:- Preparation of estimate for the construction of Mini Stadium at Rarang in Distt. Kinnaur (H.P.)

Estimated Cost :- 1,32,000/-
Earnest Money :- 3,000/-
Time :- One month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Job work for preparing of estimate of whole project as per architectural drawing for the construction of buildings in District Kinnaur (H.P.). Under the job work shall also include supplying detailed estimate duly supported with analysis of rates 2021 on prevailing market rates approved working estimate from the competent authority alongwith DNIT for material in the area and approved labour rate by Govt. of H.P. and submission of the same in this office in hard and soft copy as per direction of Engineer-in Charge, 11 th. Circle HP.PWD. Rampur (H.P.) /Executive Engineer Kalpa Division HPPWD. Kalpa.	1.00			Each	
				Total:-		


Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Prepration of estimate for the special repair to Suspension Bridge over River satluj to Gymthing valley road at 0/700

Estimated Cost :- 1,75,000/-
Earnest Money :- 3,500/-
Time :- One month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Job work for preparing of estimate of whole project as per site requirment for the repair of above said bridge in District Kinnaur (H.P.). Under the job work shall also include supplying detailed estimate duly supported with analysis of rates 2021 on prevailing market rates approved working estimate from the competent authority alongwith DNIT for material in the area and approved labour rate by Govt. of H.P. and submission of the same in this office in hard and soft copy as per direction of Engineer-in Charge, 11 th. Circle HP.PWD. Rampur (H.P.) /Executive Engineer Kalpa Division HPPWD. Kalpa.	1.00			Each	
				Total:-		



Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Construction of Ware House for storage of Electronic Voting Machine at Reckong Peo in Distt. Kinnaur (HP).
(SH:- Providing and laying G.I. pipe line 32mm dia from main inlet tank to IPH storage tank)

Estimated Cost :- 2,19,891/-
 Earnest Money :- 4,500/-
 Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Eartwork in excavation by mechanical means / manual means in foundation trenches, including dressings of sides and ramming of bottoms, including getting out of excavated soil as directed, All kinds of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	189.00			Per Cubic meter	
2	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 32 mm dia (Thirty two millimeter diameter) nominal bore, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	350.00			Per Running meter	
3	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete, 25 to 40 mm (Twenty five to forty millimeter) nominal bore, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1.00			Each	
				Total:-		


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- A/R & M/O link road to village Nako Km. 0/00 to 1/700

(SH:- C/O R/Wall in RR Masonry at RD 0/990 to 1/010).

Estimated Cost :- 4,51,321/-
Earnest Money :- 9,500/-
Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	22.40			Per Cubic meter	
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 & 1203 P.C.C. M-10(1) (Mechanical mix and vibrated graded crushed stone aggregate) 1:3:6 (One cement : three sand : six graded stone aggregate, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	70.320			Per Cubic meter	
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	12.00			Per Cubic meter	
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall,with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614.709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	46.00			Each	
Total:-						

Executive Engineer
Kalpa Division
H.P.P.W.D. Kalpa

7

SCHEDULE OF QUANTITY

Name of work:-

A/R & M/O Jeepable road from Aucktong to Dundunka Km. 0/00 to 0/750
(SH:- C/O Edge wall in RR Masonry at RD 0/090 to 0/135 and 0/560 to 0/600).

Estimated Cost :- 2,20,976/-

Earnest Money :- 4,500/-

Time :- One Month

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead dressing of sides and bottom and backfilling in trenches with excavated suitable material upto all depth,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	27.20			Per Cubic meter	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications clause 802,803 1202 and 1203. 1:6:12 (One cement : six sand : twelve graded stone aggregate 40mm (Forty millimeter) nominal size, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	9.61			Per Cubic meter	
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand,) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	30.63			Per Cubic meter	
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall,with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	75.00			Each	
Total:-						

Handwritten signature

Executive Engineer
Kalpa Division
H.P.P.W.D. Kalpa