

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-I-Tender-2025-26

3516-22

Dated:- 20/08/25


To

The Executive Engineer (IT Cell)  
H.P.P.W.D. Nigam Vihar Shimla-2.

**Subject:- Notice Inviting Tender for uploading the same on departmental website.**


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Pr. Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A(3)1/2024 dated shimla-2 the 03.01.2024 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

**Encl:-Copy of NIT**

  
Executive Engineer,  
Arki Division  
H.P.P.W.D. Arki.  
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.

  
Executive Engineer,  
Arki Division  
H.P.P.W.D. Arki.  
Ph. 01796-220714

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER**

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **29.08.2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **28.08.2025 up to 4:30 PM** and the application for issue of tender form shall be received on **28.08.2025 up to 5:00 PM.**


The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please note no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	Restoration of rain damages on various roads under Darla Sub-Division Mangal section(SH:-Hiring of JCB for removal of slips, dressing of roads, cleaning of drains etc.)Job No.II)	Rs. 99,000/-	Rs. 2000/-	One Month	Rs. 350/-
2	Restoration of rain damages on various roads under Darla Sub-Division Shalaghat section(SH:-Hiring of JCB for removal of slips, dressing of roads, cleaning of drains etc.)Job No.II)	Rs. 99,000/-	Rs. 2000/-	One Month	Rs. 350/-
3	Restoration of rain damages on various roads under Darla Sub-Division Navgaon section(SH:-Hiring of JCB for removal of slips, dressing of roads, cleaning of drains etc.)Job No.II)	Rs. 99,000/-	Rs. 2000/-	One Month	Rs. 350/-

4	Restoration of rain damages on various roads under Kunihar Sub-Division Mann section(SH:-Hiring of JCB for removal of slips, dressing of roads, cleaning of drains etc.)Job No.II)	Rs. 99,000/-	Rs. 2000/-	One Month	Rs. 350/-
5	Restoration of rain damages on various roads under Darla Sub-Division Shalaghat section(SH:-Hiring of Tipper for carriage of slips/debries)Job No.1)	Rs. 97,500/-	Rs. 2000/-	One Month	Rs. 350/-
6	Restoration of rain damages on various roads under Darla Sub-Division Navgaon section(SH:-Hiring of Tipper for carriage of slips/debries)Job No.1)	Rs. 97,500/-	Rs. 2000/-	One Month	Rs. 350/-
7	Restoration of rain damages on various roads under Darla Sub-Division Mangal section(SH:-Hiring of Tipper for carriage of slips/debries)Job No.1)	Rs. 97,500/-	Rs. 2000/-	One Month	Rs. 350/-
8	C/o link road from Main road Ukhoo Badal to Ghighat(SH:-C/o R/wall in km. 0/0 to 0/07	Rs.96,966/-	Rs. 2000/-	Two Month	Rs. 350/-
9	C/o link road from Main road Kunihar Brampukhar to Uperia Jabal(SH:-P/L Kharanja soling and cement concrete 1:3:6 in km. 0/0 to 0/050	Rs.96,926/-	Rs. 2000/-	Two Month	Rs. 350/-
10	A/R & M/o HP PWD Sub-Division office building Arki(SH:-C/o Pentary)	Rs.94,028/-	Rs. 2000/-	Two Month	Rs. 350/-
11	Special Repair of Health Sub-Centre building at Sai Tehsil Arki Dist. Solan(SH:-Providing and fixing prepainted sheet roofing)Balance work	Rs.99,997/-	2000/-	Two Month	Rs. 350/-
12	Restoration of rain damages on Darla Kanswala Parnoo Bugarh road in km. 0/0 to 12/500 C/o RCC hume pipe culvert 900mm dia at RD 0/090(SH:-P/L cement concrete 1:4:8	Rs. 83,495/-	Rs. 1700/-	One Month	Rs. 350/-
13	Construction of Gohry Karah Koyartu Bandi road km. 0/0 to 4/510 in District Solan(SH:-Preparation of technical sanction)	Rs.92,455/-	Rs. 1900/-	Two Month	Rs. 350/-

Followings documents should be attached with the application for tenders:-

- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


  
Executive Engineer  
Arki Division,  
H.P.P.W.D. Arki.

No: PW-AD-EA-I-Tender-2025-26- 3516-22

Dated:- 20/08/25


Copy forwarded for the following for information and necessary action to:-

1. The Superintending Engineer 3<sup>rd</sup> Circle HPPWD Solan.
2. The all Assistant Engineer working under this division for information and necessary action.
3. All the heads of the branches in this office.
4. Notice Board.

  
Executive Engineer  
Arki Division  
H.P.P.W.D.Arki.



**Certificate**

Certified that the tenders called vide this notice inviting tender for 1 (One) jobs are due to exigencies/emergency of works in the larger public interest.

  
Executive Engineer  
Arki Division  
H.P.P.W.D. Arki.

# SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Darla Sub Division Mangal Section SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- II)					Estimated Cost: -Rs 99,000/- only		
					Earnest Money : Rs 2000 /-Only		
					Time -One Months		
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimmimg of slops and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						Total:-	99000.00
	Quoted rate percentage in figures						
	Quoted rate percentage in words						

  
 Executive Engineer,  
 PWD (B&R)  



### SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Darla Sub Division Shallaghat Section SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- II)						Estimated Cost: -Rs 99,000/- only	
						Earnest Money : Rs 2000 /-Only	
						Time -One Months	
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						Total:-	99000.00
	Quoted rate percentage in figures						
	Quoted rate percentage in words						

  
 Executive Engineer,  
 H.P.W.D. (B&R)  
 Darla Sub Division

# SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Darla Sub Division Navgaon Section SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- II)						Estimated Cost: -Rs 99,000/- only	
						Earnest Money : Rs 2000 /-Only	
						Time -One Months	
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
				In figure	In words	6	7
1	2	3	4	5	6	7	8
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimmimg of slops and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						Total:-	99000.00
	Quoted rate percentage in figures						
	Quoted rate percentage in words						

  
 Executive Engineer,  
 H.P.W.D (B&R)  
 Jammu & Kashmir

# SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Kunihar Sub Division Mann Section (SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No-II)	Estimated Cost: -Rs 99,000/- only
	Earnest Money : Rs 2000 /-Only
	Time -One Months

S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	2	3				6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						Total:-	99000.00

Quoted rate percentage in figures

Quoted rate percentage in words

601  
Executive Engineer,  
H.O. PWD (B&R)  
Dindur Art

SCHEDULE OF QUANTITY						
Name of work:-Restoration of Rain Damages on various roads under Darla Sub Division Shallaghat Section (SH:- Hiring of Tipper for carriage of slips/ debries) ( Job No - I )					Estimated Cost: -Rs 97,500/- only	
					Earnest Money :- Rs 2000 /-Only	
					Time -One Month	
S.No	Sub head and items of work	Qty.		Rate		Unit
1	2	3		In figure	In words	6
1	Hiring of tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6 (six) hours per day. The contractor / owner of the tipper shall bear the expension of P.O.L. charges, repair of machineries. Any accident and other damages to be the private and govt property occur during the working hours is the responsibility of the contractor and debris disposed within all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees Six Hundred Fifty Only	Per hour.
						Total:- 97500

Quoted rate percentage in figures

Quoted rate percentage in words

16.01  
Executive Engineer,  
PWD (B&R)  
Darla

### SCHEDULE OF QUANTITY

Name of work:-Restoration of Rain Damages on various roads under Darla Sub Division Navgaon Section (SH:- Hiring of Tipper for carriage of slips/ debries) ( Job No - I )

Estimated Cost: -Rs 97,500/- only

Earnest Money :- Rs 2000 /-Only


Time -One Month

S.No	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6 (six) hours per day. The contractor / owner of the tipper shall bear the expension of P.O.L. charges, repair of machineries. Any accident and other damages to be the private and govt property occur during the working hours is the responsibility of the contractor and debris disposed within all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees Six Hundred Fifty Only	Per hour.	97500.00

Total:- 97500

Quoted rate percentage in figures


Quoted rate percentage in words

  
 Executive Engineer  
 PWD (B&R)  
 Division Add

SCHEDULE OF QUANTITY							
Name of work:-Restoration of Rain Damages on various roads under Darla Sub Division Mangal Section (SH:- Hiring of Tipper for carriage of slips/ debries) ( Job No - I )					Estimated Cost: -Rs 97,500/- only		
					Earnest Money :- Rs 2000 /-Only		
					Time -One Month		
S.No	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6 (six) hours per day. The contractor / owner of the tipper shall bear the expension of P.O.L. charges, repair of machineries. Any accident and other damages to be the private and govt property occur during the working hours is the responsibility of the contractor and debris disposed within all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees Six Hundred Fifty Only	Per hour.	97500.00
Total:-							97500

Quoted rate percentage in figures

Quoted rate percentage in words

  
 Executive Engineer,  
 H.P. PWD (B&R)  
 Division Arid

SCHEDULE OF QUANTITY							
Name of work:- C/o link road from main road Ukhoo Badal to Ghighat (SH:-C/o R/wall in km 0/000 to 0/07)					Estimated Cost: -Rs 96,966/- only		
					Earnest Money : Rs 2000 /-Only		
					Time -Two Months		
S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	5.46	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	936.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10( 40mm)	19.05	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	83641.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	9.24	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	11118.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	3.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1271.00
						Total	96966.00

Quoted rate percentage in figures

Quoted rate percentage in words

  
Executive Engineer  
H.P.W.D (B&R)  
Division Arki

SCHEDULE OF QUANTITY						
Name of work:- C/o link road from main road Kunihar Brampukhar to Uperla Jabal (SH:- P/L Kharanja soling and cement concrete 1:3:6 in km 0/000 to 0/050)				Estimated Cost: -Rs 96,926/- only		
				Earnest Money : Rs 2000 /-Only		
				Time -Two Months		
S.N	Sub head and items of work	Qty.		Rate		Amount
1	2	3		In figure	In words	7
1	Stone soling under floor properly hand packed filling interstics with Kharanja stone and consolidating with hand durmet to the requisite gradient and camber including spreading watering and rolling of binding materials complete as per HPPWD specification including carriage of materials within all leads and lifts and as per the direction of Engineer-in-Charge.	20.62	Cum	1300.10	Rupees One Thousand Three Hundred and Paise Ten Only	26808.00
2	Providing and laying concrete Mechanically mixed and vibrated P.C.C. M-10 nominal mix 1:3:6 (one cement isto three sand isto six graded crussed stone aggregate 40mm ( forty milimetre ) nominal size) for plain /reinforced concrete in open foundation and plinths or similar works complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 and curing complete including the cost of form work including carriage of material with in all leads and lifts and as per the direction of Engineer-in-Charge.	13.25	Cum	5291.95	Rupees Five Thousand Two Hundred Ninety One and Paise Ninety Five Only	70118.00
					Total	96926.00

Quoted rate percentage in figures

Quoted rate percentage in words

*wd*  
**Executive Engineer,**  
**M.P. PWD (D&R)**  
**Division Arki**

# SCHEDULE OF QUANTITY

Name of work:- A/R & M/O HP PWD Sub - Division Office Building Arki (SH:-C/O Pentary )

Estimated Cost:-Rs.94,028/-only

Earnest Money:-Rs.2000/-only

Time - Two Month


S.No	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 m. Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	1.20	Cum	290.15	Rupees two hundred fourty six and paise sixty five only	Per cubic metre.	348.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 & 1203 c.c. 1:4:8 ( 1cement :4 sand: 8graded stone aggregate) 40mm nominal size including carriage of materials upto all leads and lifts.	3.28	Cum	4955.20	Rupees four thousand one hundred fifty eight and paise seventy	Per cubic metre.	16253.00
3	Brick work using common burnt clay modular bricks of class designation 7.50 (seven point five zero) in foundation and plinth in cement modular 1:6 (one cement isto six sand) using second class building bricks including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	3.29	Cum	6230.90	Rupees six thousand two hundred thirty and paise ninty only	Per cubic metre.	20500.00
4	Cement concrete flooring 1:2:4 (1cement:2sand:4graded stone aggregate 20mm nominal size) laid in one layer finished with a floating coat of neat cement.including preparation of surface excluding grading complete as per the instruction of Engineer-in-Charge. including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge. (a). 40mm thick.	5.40	Sqm	378.95	Rupees three hundred seventy eight and paise ninty five only	Per square metre	2046.00
5	15 mm cement plaster in single coat on the rough side of brick/concrete/stone walls for interior plastering up to floor two level including arrises, internal rounded angles, chamfers and or rounded angles not exceeding 80 mm in girth and finished even and smooth(a) In C.ement mortar 1:6 (1Cement: 6 Sand) including carriage of material within all leads and lifts and as per the direction of Engineer-In- Charge.	31.68	Sqm	196.45	Rupees one hundred ninty six and paise fourty five only	Per square metre	6224.00
6	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm including carriage of material within all leads and lifts and as per the difection of Engineer-in- Charge.	31.68	Sqm	125.20	Rupees one hundred twenty five and paise twenty only	Per square metre	3966.00
7	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of material within all leads and lifts and as per the difection of Engineer-in- Charge.	4.48	Sqm	89.90	Rupees eighty nine and paise ninty only	Per square metre	403.00

8	Reinforced cement concrete work in beams , suspended floors , roofs having slope up to 15 landings, balconies, shelves, chajjas , lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level excluding the cost of centering, shuttering , finishing and reinforcement with 1:1.5:3 (1 cement : 21.5 coarse sand ) : 3 graded stone aggregate 20mm Nominal size Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	0.28	Cum	7835.75	Rupees seven thousand eight hundred thirty five and paise seventy five only	Per cubic metre.	2194.00
9	Steel reinforcement for R.C.C work including straighttending, bending , placing in position and binding all complete upto plinth level . Mild steel and Medium Tensile steel bars. Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	28.00	kg	93.80	Rupees seventy five and paise forty only	Per kilogram	2626.00
10	Steel work welded in built up sections / framed work. A priming coat of approval steel primer using structural steel etc. as required . In gratings, frames, guard bar, ladder railings, brackets, gates and similar works. Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	118.80	kg	107.45	Rupees one hundred seven and paise forty five only	Per kilogram	12765.00
11	Providing corrugated G.S. sheet roofing including vertical /Curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I limpet washers or with G.I. limpet washer filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete, excluding the cost of purlins, rafter and trusses and including cutting to size shape wherever required. 63 mm thick with zinc coating not less than 275 gm m2 Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	11.70	Sqm	837.30	Rupees eight hundred thirty seven and paise thirty only	Per square metre	9796.00
12	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, excluding panelling which will be paid for separately, all complete Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	2.24	Sqm	2700.90	Rupees two thousand seven hundred and paise ninty only	Per square metre	6048.00
13	Providing and fixing stainless steels A ISI 304 kitchen sink as per IS: 13983 with C.I brackets and stainless steel plug 40 mm , including painting of fittings and brackets, cutting and making good the walls wherever required: 510x 1040mm bowl depth 250 Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	1.00	No	4608.30	Rupees four thousand six hundred eight only	Each	4608.00
14	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C waste fittings complete. 32mm dia Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge..	1.00	No	87.70	Rupees eighty seven and paise seventy only	Each	88.00
15	Providing and fixing CP Brass 32mm size Bottle Trap of approved quality & make Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	1.00	No	883.05	Rupees eight hundred eighty three and paise five only	Each	883.00
16	Providing and fixing C.P. brass bib cock of approved quality conforming to IS: 8931. 15mm nominal bore. Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	1.00	No	418.95	Rupees four hundred eighteen and paise ninty five only	Each	419.00

17	Providing and fixing on wall face unplasticised- PVC moulded fittings/accessories for unplasticised rigid PVC rain water pipes conforming to IS: 13592 Type A, including jointing with seal ring conforming to IS: 5382, leaving 10mm gap for thermal expansion, (i) Single socketed pipes. 110mm diameter Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	10.00	Rmt	260.55	Rupees two hundred sixty and paise fifty five only	Per running meter	2606.00
18	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc. Internal work - 15 mm dia nominal bore Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	10.00	Rmt	225.00	Rupees two hundred twenty five only	Per running meter	2255.00
						Total:-	94028.00

Quoted rate percentage in figures

Quoted rate percentage in words

  
Executive Engineer,  
H.P. PWD (B&R)  
Division A-1

# SCHEDULE OF QUANTITY

Name of work: -Special Repair of Health Sub Center building at Sai Tehsil-Arki Distt- Solan (SH:- Providing and fixing pre painted sheet roofing) ( Balance work)

Estimated Cost: -Rs 99,997/- only

Earnest Money : Rs 2000 /-Only

Time -Two Months

S.No	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Dismantling G.S. sheetroofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	65.40	Sqm	69.80	Rupees Sixty Nine and Paise Eighty Only	Per square metre	4565.00
2	Providing and fixing 0.60mm thick prepainted steel sheet of TATA Durashine in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyster (RNP) organic coating of 20 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6 mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per HP. PWD. specifications of 1990 volume-I including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	65.40	Sqm.	1321.05	Rupees One Thousand Three Hundred Twenty One and Paise Five Only	Per square metre	86397.00
3	Providing and fixing ridges or hips 60 cm over all in plain GI steel sheets fixed with galvanised iron J or L hooks, bolts & nuts 8 mm dia G.I. limpet and bitumen washers complete with all accessories as required of TATA DURASHINE in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyster organic coating of 20 microns over 5 microns primer coating+ back coat of polyster of 5 microns over 5 microns primer coating including fixing as per the direction of Engineer-in-Charge.	16.40	Rmt	550.90	Rupees Five Hundred Fifty and Paise Ninety Only	Per running metre.	9035.00
						Total	99997.00

Quoted rates percentage in figures

Quoted rates percentage in words

*wd*  
Executive Engineer  
H.P. PWD (B&R)  
Division Arki

### SCHEDULE OF QUANTITY

**Name of work:** - Restoration of Rain damages on Darla Kanswala Parnoo Bugarh road in km 0/000 to 12/500 C/o  
RCC hume pipe culvert 900mm dia at RD 0/090 ( SH:- P/L Cement concrete 1:4:8)

Estimated Cost: -Rs 83,495/- only


Earnest Money : Rs 1700 /-Only

Time -One Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1	2	16.85	Cum	4955.20	Rupees Four Thousand Nine Hundred Fifty Five and Paise Twenty Only	Per cubic metre	83495.00
						Total	83495.00

Quoted rate percentage in figures

Quoted rate percentage in words

  
**Executive Engineer**  
Arkl Division, H.P. Road  
Arkl

# SCHEDULE OF QUANTITY

Name of work:- Construction of Gohry-Karah-Koyartu-Bandi road km 0/000 to 4/510 (Sub-Head:- Preparation of Technical Sanction, Working Estimate and DNIT )						Estimated Cost: -Rs 92,455/- only	
						Earnest Money : Rs 1900 /-Only	
						Time -One Months	
S.N	Sub head and items of work	Qty.		Rate		Unit	Amount
o.		3		In figure	In words	6	7
1	2						
1	Preparation of Technical Sanction. The Work will we carried in accordance with latest design specification, latest market rate and to satisfaction of Engineer-in-Charge. Printing Two set complete in all respect and submitting the same to Division office and there after approval from competent authority.	4.510	Km	7000.00	Rupees Seven Thousand Only	Per Kilometer	31570.00
2	Preparation of Working Estimate. The Work will we carried in accordance with latest design specification, latest market rate and to satisfaction of Engineer-in-Charge. Printing Two set complete in all respect and submitting the same to Division office and there after approval from competent authority.	4.510	Km	7000.00	Rupees Seven Thousand Only	Per Kilometer	31570.00
3	Preparation of DNIT. The Work will we carried in accordance with latest market rate and to satisfaction of Engineer-in-Charge. Printing Two set complete in all respect and submitting the same to Division office and there after approval from competent authority.	4.510	Km	6500.00	Rupees Six Thousand Five Hundred Only	Per Kilometer	29315.00
						Total	92455.00

Quoted rate percentage in figures

Quoted rate percentage in words

- Sd-  
Executive Engineer  
Arki Division  
MPPWD Arki