



Office of the  
Executive Engineer  
Una, Division, HP PWD Una  
Tel: +911975226036,  
E-mail: ee-una-hp@nic.in

No.PWU/CB//TA/Tender/2024-25/-

3927-34

Dated 18 <sup>08</sup>/<sub>25</sub>

To

The Executive Engineer (IT) Cell,  
NirmanBhawan, Nigam Vihar,  
Shimla-171002.

Subject: - Regarding publication of Tenders Notice.

Sir,


**“JAI HIND”**

Enclosed please find herewith Tenders Notice along with Schedule of Quantities for uploading the same on Departmental website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A(3)1/2024 dated Shimla-2 the 03.01.2025 as the work mentioned in the Tender Notice are urgent in nature and in Public interest. This is for your kind information and necessary action at your end please.

DA:-As above.

No.PWU/CB//TA/Tender/2024-25/-

To

  
Executive Engineer,  
Una, Division,  
HPPWD, Una.

Copy along with its enclosures is forwarded to the following for favour of information please:-

1. The Superintending Engineer, 15<sup>th</sup> Circle, HPPWD, Una.
2. All the Assistant Engineer, working under this Division.
3. All the Head of Branches in this office.

4. Notice Board.

Sir,

Executive Engineer,  
Una, Division  
HPPWD, Una

Enclosed please find herewith Tenders Notice along with Schedule of Quantities for uploading the same on Departmental website as per Notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B) A(3)1/2024 dated Shimla-2 the 03.01.2025 as the work mentioned in the Tender Notice are urgent in nature and in Public interest. This is for your kind information and necessary action at your end please.

DA:-As above.

No.PWU/CB//TA/Tender/2024-25/-

To

Executive Engineer,  
Una, Division,  
HPPWD, Una.

Copy along with its enclosures is forwarded to the following for favour of information please:-

1. The Superintending Engineer, 15<sup>th</sup> Circle, HPPWD, Una.
2. All the Assistant Engineer, working under this Division.
3. All the Head of Branches in this office.

4. Notice Board.

Executive Engineer,  
Una, Division  
HPPWD, Una

**HIMACHAL PRADESH**  
**PUBLIC WORKS DEPARTMENT**  
**"NOTICE INVITING TENDERS"**

Sealed item rate tender on PWD Form No. 6 & 8 are hereby invited by the Executive Engineer, Una Division HPPWD Una H.P. on behalf of Governor of H.P for the following works from the approved and eligible contractors/ firms enlisted in PWD Department so as to reach in this office or before **27.08.2025 upto 11.00 A.M.** and will be opened on the same day at **11.30 A.M.** in presence of the intending contractor s or their authorized representatives who may like to be present. If it happened be holiday on the day of opening of tender the same will be opened on next working day at the same time. The application for obtaining the tender forms will be received latest by **25.08.2025 at 10.00 AM upto 10.30 Noon** and the tender form can be had from this office upto **25.08.2025 at 03.00 AM to 5.00 PM** against cash payment (non-refundable).

The earnest money in the shape of F.D.Rs if any of the Nationalized Bank in H.P. duly pledged in the favour of the Executive Engineer, Una Division HPPWD Una , will be received alongwith the applications for obtaining tender forms. The applications received without earnest money shall summarily be rejected. The Executive Engineer reserves the right to reject any tender without assigning any reason. The conditional / telegraphic tenders shall also be rejected. The scope of the work can be increased/ decreased without any Notice. The offers of the tender (s) shall be kept open for 75-days from the date of opening the tender(s)

Sr. No.	Name of work	Estimate d cost	Earnest Money	Time Limit	Cost of tender	Eligible class of contract or
1	2	3	4	5	6	7
1	C/o Gramin Sampark Marge & Drainage from Shanti Wattan Chand H/O Near Bholenath Shop Upto Jatinder House Ward No. 05 at Barsara GP Jankour (Under VKVNY) (SH:-C/o V-shape drain (Phase-III (Deposit work)	68,806/-	15,00/-	One Month	350/-	Class-C & D
2	C/o Gramin Sampark Marg with R/wall near the h/o Sh. Bodh Raj Raman Kumar Ward no. 9 Sunehra at RD 0/0 to 0/11 (SH:- C/o R/wall at Rd 0/103.45 to 106.90) (Deposit work)	98,150/-	2000/-	One Month	350/-	Class-C & D
3	Construction of Path & Paver block near the house of Sh. Tara Singh GP Jalgran Tappa Tehsil & Distt. Una VKVNY Scheme. (Deposit work)	99,748/-	2000/-	One Month	350/-	Class-C & D
4	C/o retaining wall to protect the house of Sh. Munish Bhardwaj S/o Sh. Hardev Bhardwaj Ward No. 5 Gram Panchayat Charatgarh from Soil Erosion due to damage caused by torrential rain in July August -2023 (SH:- Supplying & filling earth work back side of retaining wall (Under VKVNY(MLALAD)	60163/-	1300/-	One Month	350/-	Class-C & D
5	Repair of damages Ajouli Santoshgarh road km 0/0 to 3/600 (SH:- P/L 60mm thick interlocking paver at RD 3/176 to 3/185 in shoulders (LHS) (Under OFC Deposit )	42,362/-	900/-	One Month	350/-	Class-C & D
6	Repair of damages on link road to village Bharolian Khurd km 0/0 to 2/0 (SH:- C/o U-Shape and V-Shape drain at Rd 0/670 to 0/740) (Under OFC Deposit	99,992/-	2000/-	One Month	350/-	Class-C & D
7	Repair of damages on link road to Village Bharolian Khurd Km 0/0 to 2/0 (SH:- C/o U-Shape and V-Shape drain at Rd 0/743 to 0/813 ) (Under OFC Deposit)	99,859/-	2,000/-	One Month	350/-	Class-C & D
8	Restoration of rain damage on link road from Village Lalsingi to Jhalera near brick kiln via Baba Beli Ram Km 0/0 to 1/200 (Old Leg) (SH:- Repair work in RD 0/550 to 1/0)	99,360/-	2,000/-	One Month	350/-	Class-C & D
9	Repair of damages on link road to Village Malahat Km 0/0 to 2/500 (SH:- C/o Paved shoulders at RD 0/780 to 1/189 along the drain (Under OFC Deposit)	99,878/-	2,000/-	One Month	350/-	Class-C & D
10	Repair of damages on link road to Village Malahat Km 0/0 to 2/500 (SH:- C/o Paved shoulders at Rd 0/300 to 0/709 along the drain (Under OFC Deposit)	99,878/-	2,000/-	One Month	350/-	Class-C & D
11	Repair of damages on Behdala to GMS Jakhera road km 0/0 to 4/600 (SH:- C/o U-Shape drain at RD 2/200 to 2/205.50) (Under OFC Deposit )	99,996/-	2,000/-	One Month	350/-	Class-C & D

12	Repair of damages on Behdala Chhattara Pirmigah road km 0/0 to 2/0 (SH:- C/o U-Shape drain at RD 1/914.50 to 1/957.25 (Under OFC Deposit )	99,427/-	2,000/-	One Month	350/-	Class-C & D
13	Restoration of rain damages on link road to village Malahat Km 0/0 to 3/0 (SH:- P/L CC interlocking paver block at RD 2/591 to 2/600) (Under OFC Deposit)	99,971/-	2000/-	One Month	350/-	Class-C & D
14	Restoration of rain damages on link road to village Malahat Km 0/0 to 3/0 (SH:- P/L CC interlocking paver block at RD 2/559 to 2/591) (Under OFC Deposit )	97,856/-	2000/-	One Month	350/-	Class-C & D
15	Repair & Maintenance of Non-residential building at Una Distt. Una (SH:- Providing services out sources basis of One No. Supervisor/work inspector for period of four month i.e. 1st September 2025 to 31 December 2025)	72,239/-	2,000/-	Four Month	350/-	Class-C & D
16	Restoration of rain damages on link road to Harijan Basti Dehlan km 0/0 to 0/800 (SH:- C/o U-Shape drain and P/L RCC NP2 pipe with CC Chambers in 0/700 to 0/727.50( GP, Dehlan lower) (Under Deposit work)	72,693/-	2000/-	One Month	350/-	Class-C & D
17	R/R Damage on link from Old UnaAmb road to Himotkarsh Girls College LalsingiUna (SH:- P/L Paver blocks at RD 0/036 to 0/056n and 0/267.60 to 0/272.60)	99,991/-	2000/-	One Month	350/-	Class-C & D
18	R/R Damage on link from Old Una Amb road to Himotkarsh Girls College Lalsingi Una (SH:- P/L Paver blocks at RD 0/0 to 0/036	99,983/-	2000/-	One Month	350/-	Class-C & D
19	Restoration of rain damage of 120 meter span bridge Rampur on Una Santoshgarh road at RD 1/760 (SH:- Hiring of Pock lane 1.50cum. bucket capacity for channelization of Khad on U/S side of Rampur bridge)(Under OFC Deposit) (Job No.1)	99,000/-	2000/-	One Month	350/-	Class-C & D
20	Restoration of rain damage of 120 meter span bridge Rampur on Una Santoshgarh road at RD 1/760 (SH:- Hiring of Pock lane 1.50cum. bucket capacity for channelization of Khad on U/S side of Rampur bridge)(Under OFC Deposit) (Job No.2)	99,000/-	2000/-	One Month	350/-	Class-C & D
21	Restoration of damages occurred due to laying of OFC in various roads under Basoli section sub division No.1 Una (SH:- Providing fixing and art painting of information sign boards etc. (Under OFC Deposit )	99,643/-	2000/-	One Month	350/-	Class-C & D
22	A/R & M/O PWD Rest House at Una (SH:- Providing services of out sources basis for One number Mali (Period of 153 days )	97,859/-	2000/-	One Month	350/-	Class-C & D
23	A/R & M/O PWD Rest House at Una (SH:- Providing services of out sources basis for One number sweeper (Period of 153 days )	97,859/-	2000/-	One Month	350/-	Class-C & D
24	Restoration of damages on link road from Dehlan to Basdehra upto Punjab Boundary km 0/0 to 2/400 (SH:- P/L NP-2 pipes 450mm dia at RD 2/371 to 2/385 RHS & P/F MS Grating over drain at RD 2/100 to 2/245 (RHS) (Under OFC Deposit)	99,432/-	2000/-	One Month	350/-	Class-C & D
25	Restoration of damages on link road from Dehlan to Basdehra upto Punjab Boundary km 0/0 to 2/400 (SH:- P/L NP-2 pipes 450mm dia at RD 2/385 to 2/388 RHS & P/F MS Grating over drain at RD 2/245 to 2/385 (RHS) & P/F MS Grating over drain at RD 2/300 to 2/385 (LHS) (Under OFC Deposit )	99,377/-	2000/-	One Month	350/-	Class-C & D
26	Repair and maintenance of residence of Civil Judge Court No.II Una at DC colony Una (HP) (SH:- P/L Painting and other repair etc.)	99,819/-	2000/-	One Month	350/-	Class-C & D

**TERM & CONDITIONS: -**

1. The contractor/ firms should be registered as or/ dealer under HP Sales Tax Act, 1968 and also produce Sale Tax clearance certificate from the Excise and Taxation Department, GST No. and Permanent account No. (PAN No.).
2. The intending contractors/ firms shall have to produce the copy of latest enlistment and renewal enlisted in HP: PWD.
3. The contractor/firms are required to quote their rates clearly both in words as well as in figures, failing which the Executive Engineer reserve the right to accept/ reject any or all tenders.
4. The conditional / ambiguous/ telegraphic tenders or tender by fax shall not entertain/ considered in any case

5. No payment will be made to the contractor/ firms for damage caused by flood, rain, local disturbance, war, epidemic or either natural calamities during execution of work and no such claim on this account will be entertained.
6. Security shall be released after 1 year from the date of completion of work provided no defect certificate is issued by the Engineer-in-charge.
7. The Executive Engineer has right to accept or reject any or all the tender without assigning any reason.
8. Any material left at site one month after completion of work shall become the property of the department and no payment shall be made to the contractor for the material.
9. A sign Board "Men at work / work in progress" shall be placed " by Contr. At least 200-150 meters ahead of places / roads where road are under repair / construction.
10. The tender shall be issued to those contractors/ firms who have not more than two works in hand.
11. Work should be completed by the contractor within stipulated period.
12. For Job No.22 experienced in Horticulture.


Executive Engineer  
Una Division, HP: PWD,  
Una.

No. PWU/CB/T-I/2024-25:-

Dated:-

Copy is forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP: PWD, Shimla-1.
2. The Chief Engineer, Hamirpur Zone, HP: PWD, Hamirpur.
3. All the Assistant Engineers under this Division.
4. The Deputy Commissioner, Una.
5. The Sub Divisional Officer I, Una.
6. The District Treasury Officer, Una.
7. The Block Development Officer, Una.
8. The Municipality, Una.
9. All the Head of the Branches in this office.
10. The Notice Board.

  
Executive Engineer,  
Una Division, HP: PWD,  
Una

Executive Engineer  
Una Division, HP: PWD,  
Una.

No. PWU/CB/T-I/2024-25:-

Dated:-


Copy is forwarded for information and necessary action to:-

1. The Engineer-in-Chief, HP: PWD, Shimla-1.
2. The Chief Engineer, Hamirpur Zone, HP: PWD, Hamirpur.
3. All the Assistant Engineers under this Division.
4. The Deputy Commissioner, Una.
5. The Sub Divisional Officer I, Una.
6. The District Treasury Officer, Una.
7. The Block Development Officer, Una.
8. The Municipality, Una.
9. All the Head of the Branches in this office.
10. The Notice Board.

Executive Engineer,  
Una Division, HP: PWD,  
Una.

**Certificate**

Certified that the tenders called vide this office letter  
No.PWU/CB/T-I/2024-25:- 3905-17 dated-18.08.2025 emergent nature and in  
Public interest.

  
Executive Engineer,  
Una Division, HP/PWD,  
Una

*Certificate*

*Certified that the tenders called vide this office letter  
No.PWU/CB/T-I/2024-25:- 3905-17 dated-18.08.2025 emergent nature and in  
Public interest.*

*Executive Engineer,  
Una Division, HP/PWD,  
Una*

198

1

SCHEDULE OF QUANTITY						
Name of work :C/O Gramin Sampark Marge & Drainage from Shanti Wattan Chand H/O Near Vholenath Shop upto Jatinder House ward No.05 at Barsara GP Jankour (Under VKVNY) (SH: C/O V-shape drain)(Phase-III) ( Deposit work)					Estimated Cost	68806/-
					Earnest Money	1500/-
					Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts..The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	1.50	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	14.25	Per cubic metre			
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	14.97	Per cubic metre			
4	Providing and fixing high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc.complete 200mm dia of Supreme / Kisan/finolex or its equivalent including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,GST,labour cess or other taxes imposed by the Government.	10.00	Per running metre			
					<b>G.Total</b>	
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018						
2) The rates shall be including of all types of taxes including GST etetra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						

*Kaurah*  
 Executive Engineer  
 Una Divn.HP.FWD.,  
 Una


17

200

2

SCHEDULE OF QUANTITY						
Name of work :C/O Gramin Sampark marg with R/wall near the h/o Sh. Bodh Raj Raman Kumar ward No.9 Sunehra at RD.0/0 to 0/111.(SH: C/O R/wall at RD.0/103.45 to 0/106.90)( Deposit work)					Estimated Cost	98150/- ✓
					Earnest Money	2000/- ✓
					Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.43	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	26.92	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	16.00	each			

4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specification MORD 2014 clause 1204.3.8 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.54	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)C(17)2/0212 dated 7.8.2018					G.Total
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

  
 Executive Engineer  
 Una Divn.HP.PWD,  
 Una




36

3

SCHEDULE OF QUANTITY						
					Estimated Cost	99748/-
	Name of work :Construction of Path & Paver block near the house of Sh. Tara singh GP Jalgran Tabba tehsil & Distt.Una under VKVNY scheme.(Deposit work)				Earnest Money	2000/-
					Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.40	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 40mm (forty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	26.04	Per cubic metre			
3	Providing weepholes in brick masonry/ stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100mm(hundred milimetre)dia PVC pipe not less than 4.50kg/pressure extending through the full width of the structures with slope of 1(v):20(H)(one vertical twenty horizontal) towards drawing face complete as per drawings and technical specification clause 614,709,1204.3.7 including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax ,octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	16.00	Each			
4	Providing and laying in position cement concrete1:2:4 (1 cement : 2 coarse sand) : 4 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering andshuttering - All work up to plinth level :including entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge .The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	0.18	Per cubic metre			

5	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	11.00	Per square metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				<b>G.Total</b>	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una


4

SCHEDULE OF QUANTITY				Estimated cost	60163/-
----------------------	--	--	--	----------------	---------

Earnest money 1300/-  
Time limit One month

Name of Work: C/O retaining wall to protect the house of Sh. Munish Bhardwaj S/O Sh. Hardev Bhardwaj ward No.5 Gram Panchayat Charatgarh from Soil Erosion due to damage caused by torrential rain in July August -2023(SH: Supplying & filling earth work back side of retaining wall (Under VKVNY(MLALAD)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto any leads and lifts. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	240.65	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


  
Executive Engineer,  
Una Divn. HPPWD.,  
Una

34

5

DRAFT SCHEDULE OF QUANTITY						
					Estimated Cost	42362/-
Name of work : Repair of damages Ajouli Santoshgarh road km.0/0 to 3/600 (SH: P/L 60mm thick interlocking paver at RD.3/176 to 3/185 in shoulders (LHS) (Under OFC Deposit)					Earnest Money	900/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentials .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.71	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2.65	Per cubic metre			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	35.37	Per square metre			

4	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge. The rates are inclusive octroi, royalty, malkana, toll tax, sale tax, GST, labour cess or other taxes imposed by the Government.	0.75	Per cubic metre			
					Total:	0
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018					
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

  
 Executive Engineer  
 Una Divn.HP.PWD.  
 Una

11

6

SCHEDULE OF QUANTITY						Estimated Cost	99992/-
Name of work :Repair of damages on link road to village Bharolian Khurd km.0/0 to 2/0(SH: C/O U-shape and V-shape drain at RD.0/670 to 0/740)(Under OFC Deposit)						Earnest Money	2000/-
						Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	49.95	Per cubic metre				
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	19.58	Per cubic metre				
3	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.01	Per cubic metre				
4	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	116.00	Per Kilogramme				
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018						G.Total	
2) The rates shall be including of all types of taxes including GST ectra)							
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021							

*K. S. Mehta*  
 Executive Engineer  
 Una Divn.HP.PWD, Una

7


DRAFT SCHEDULE OF QUANTITY						
Name of work :Repair of damages on link road to village Bharolian Khurd km.0/0 to 2/0(SH: C/O U-shape and V-shape drain at RD.0/743 to 0/813)(Under OFC Deposit)					Estimated Cost	99859/-
					Earnest Money	2000/-
					Time limit	one month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	46.58	Per cubic metre			
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	19.58	Per cubic metre			
3	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.01	Per cubic metre			
4	Steel reinforcement (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) make)for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	121.50	Per Kilogramme			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					G.Total	
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						

*Krupa*  
 Executive Engineer  
 Una Divn.HP.PWD.,Una

15

8

SCHEDULE OF QUANTITY						Estimated Cost	99360/-
Name of work : Restoration of rain damage on link road from village Lalsingi to Jhalera near brick kiln via Baba Beli Ram km.0/0 to 1/200(Old Leg) (SH: Repair work in RD.0/550 to 1/0)						Earnest Money	2000/-
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Construction of gravel/soil aggregate sub base/base by providing well graded material of nominal maximum size grading 80mm as per table 2.3 of IRC SP 77-2008 spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface mixing by mix in place method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN static roller capacity to achieve the desired density complete as per specifications MORD 2014 contained in para 2.2, 3.6 and 3.7 of IRC SP 77-2008 complete as per technical specification caluse 402 for grading -I material including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	86.40	Per Cubic metre				
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					Total:	
	2) The rates shall be including of all types of taxes including GST ectra)						

  
Executive Engineer  
Una Divn.HP.PWD.,  
Una



13

9

SCHEDULE OF QUANTITY						
Name of work : Repair of damages on link road to village Malahat km.0/0to 2/500(SH: C/O Paved shoulders at RD.0/780 to 1/189 along the drain(Under OFC Deposit)					Estimated Cost	99878/-
					Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	24.54	Per cubic metre			
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	24.54	Per cubic metre			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018					Total:	
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						

*Krupal*  
 Executive Engineer ,  
 Una Division, HPPWD,  
 Una


SCHEDULE OF QUANTITY						Estimated Cost	99878/-
						Earnest Money	2000/-
Name of work : Repair of damages on link road to village Malahat km.0/0 to 2/500(SH: C/O Paved shoulders at RD.0/300 to 0/709 along the drain(Under OFC Deposit)						Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	24.54	Per cubic metre				
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	24.54	Per cubic metre				
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018					Total:	
	2) The rates shall be including of all types of taxes including GST ectra)						
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						

*K. Singh*  
 Executive Engineer ,  
 Una Division, HPPWD,  
 Una

33

11

SCHEDULE OF QUANTITY						
					Estimated Cost	99996/-
Name of work : Repair of damages on Behdala to GMS Jakhera road km.0/0to 4/600(SH: C/O U-shape drain at RD.2/200 to 2/205.50) (Under OFC Deposit)					Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.92	Per cubic metre			
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	25.60	Per cubic metre			
NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					Total:	
2) The rates shall be including of all types of taxes including GST ectra)						
3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						


  
 Executive Engineer ,  
 Una Division, HPPWD.,  
 Una

32

12

SCHEDULE OF QUANTITY						Estimated Cost	99427/-
Name of work :Repair of damages Behdala Chattara Pirnigah road km.0/0 to 2/0 (SH: C/O U-shape drain at RD.1/914.50 to 1/957.25(Under OFC Deposit)						Earnest Money	2000/-
						Time limit	One month
						RATE In	
S. No.	Description of work	Quantity	Unit	Figures	Words		
				1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge	20.20	Per cubic metre
2	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade including the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	18.17	Per cubic metre				
3	Providing and laying 450mm dia reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 including carriage of materials within all leads and lifts .	5.00	Per running metre				
4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 ( One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.30	Per cubic metre				

5	Supplying fitting and placing HYSD bar reinforcement in substructure complete as per drawing and technical specification clauses 1002, 1005, 1010 and 1202 including cutting, bending binding and placing in position complete in all respect including cost of binding wire in all heights including carriage of material within all leads and lifts and other incidental. The rate includes sale tax octroi, royalty, malkhana, toll tax, GST, labour cess or other taxes imposed by the Government..	130.00	Per kilogramme			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy. to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy. PW to the Govt. of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					


  
 Executive Engineer  
 Una Divn. HP. PWD.,  
 Una

20

13

SCHEDULE OF QUANTITY						
					Estimated Cost	99971/-
	Name of work :Restoration of rain damages on link road to village Malahat km.0/0 to 3/0 (SH: P/L CC interlocking paver block at RD.2/591 to 2/600) (Under OFC Deposit)				Earnest Money	2000/-
					Time limit	One month
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	8.73	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	21.69	Per cubic metre			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	31.50	Per square metre			

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 ( One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.38	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					

  
**Executive Engineer,**  
**Una Division, HPRWD,**  
**Una.**

27

14

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY					Estimated Cost	97856/-
Name of work :Restoration of rain damages on link road to village Malahat km.0/0 to 3/0 (SH: P/L CC interlocking paver block at RD.2/559 to 2/591) (Under OFC Deposit)					Earnest Money	2000/-
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.44	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.44	Per cubic metre			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand 60 mm thick ISI mark C.C. paver block of M-30 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	107.13	Per square metre			



4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 ( One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	1.59	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					


  
 Executive Engineer ,  
 Una Division, HPRWD..  
 Una.

Schedule of Quantity						Estimated Cost	72239/-
Name of work: Repair & Maintenance of Non-residential building at Una Distt.Una (SH: Providing services out sources basis of One No.Supervisor/work inspector for Period of four month i.e. 1st September 2025 to 31 December 2025)						Earnest Money	2000/-
						Time limit	<del>One</del> month Four
						Sl. No.	
					Figures	Words	
1	Providing Services on temporary basis of Supervisor /work inspector to assist court cases during working hour 10AM to 5 PM or as when required by the officer-in-charge.		122 days	P/day			
						<b>Total:</b>	

  
 Executive Engineer  
 Una Divn.HP.PWD.  
 Una

SCHEDULE OF QUANTITY						Estimated Cost	72693/-						
Name of work :Restoration of rain damages on link road to Harijan Basti Dehlan km.0/0 to 0/800 (SH: C/O U-shape drain and P/L RCC NP2 pipe with CC chambers in 0/700 to 0/727.50(GP, Dehlan lower) ( Under <del>Deposit</del> WORK)						Earnest Money	2000/-						
												Time limit	One month
						Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words								
1	Demoiishing cement concrete manually / by mechanical means including disposal in cement concrete 1:3:6 material within any leads and lifts.including stacking of steel bars and disposal of unserviceable .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	0.75	Per cubic metre										
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	5.78	Per cubic metre										
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under wateror ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.38	Per cubic metre										
4	Providing and laying 450mm dia reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 including carriage of materials within all leads and lifts .	27.50	Per running metre										

5	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.19	Per cubic metre			
6	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	102.40	Per kilogramme metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@(17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					

  
 Executive Engineer,  
 Una Division, HPPWD,  
 Una.

219

17

SCHEDULE OF QUANTITY

Estimated cost 99991/-  
Earnest money 2000/-  
Time limit One month

Name of Work: R/R Damage on link road from Old Una Amb road to Himotkarsh Girls College Lalsingi Una (SH: P/L Paver blocks at RD.0/036 to 0/056n and 0/267.60 to 0/272.60)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	8.00	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water: ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.00	Per cubic metre			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter lockingpaver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and patternincluding entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	70.45	Per square metre			

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 ( One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts	0.86	Per cubic metre			
5	Half brick masonry with common burnt clay building bricks in cement mortar 1:4(One cement :four sand) in superstructure in all floor level/height curing complete and including entire carriage of material within all leads and lifts and other incidentals as per direction by the Engineer-in-charge .The rate includes octroi, royalty,malkhana ,toll tax,sale tax, GST,labour cess or other taxes imposed by the Government.	7.80	Per square metre			
6	Providing and fixing of road safety convex( size 80 cm) made of polycarbonate and ABS body suitable for indoor/ outdoor with hood complete with mounting hardware including post as per drawing and technical specifications including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	2	each			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					G.Total
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

  
**Executive Engineer ,**  
**Una Division, HPPWD.,**  
**Una**

22cc

18

SCHEDULE OF QUANTITY

Estimated cost 99983/-

Earnest money 2000/-

Time limit One month

Name of Work: R/R Damage on link road from Old Una Amb road to Himotkars Girls College Lalsingi Una (SH: P/L Paver blocks and drain at RD.0/0 to 0/036)

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed, within any all kind of soil including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	15.12	Per cubic metre			
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 ( One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water or ground complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in-charge ,including carriage of material within all leads and lifts and other incidental.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	7.56	Per cubic metre			
3	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns,drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand,compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand: 80 mm thick ISI mark C.C. paver block of M-40 grade with approved color design and pattern including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	72.85	Per square metre			

4	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of reinforced cement concrete grade M-20 (M-twenty) nominal mix 1:2:4 ( One cement :two sand: four graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802, 803,1202 and 1203 as per the direction of the Engineer-in- charge ,including carriage of material within all leads and lifts	1.50	Per cubic metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018				G.Total	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

  
 Executive Engineer ,  
 Una Division, HPPW  
 Una



31

19

SCHEDULE OF QUANTITY

				Estimated Cost	99000/-	
Name of work : Restoration of rain damage 120metre span bridge at Rampur on Una Santoshgarh road at RD.1/760 (SH: Hiring of Pocklane 1.50cum.bucket capacity for channalization of Khad on U/S side of Rampur bridge) (Under OFC Deposit) <i>Job No I</i>				Earnest Money	2000/-	
				Time limit	One month	
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Hiring of Pocklane 1.50cum. bucket capacity on through rate basis for making chanel and embankment as per the direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentials.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	33.00	Per Hour			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3).1/2020-1 dated 7.10.2021					
	4) The bidder should have his own machinery.					
	5) The bidder must have provide machinery immediately as an when required.					

*Krunal*  
 Executive Engineer  
 Una Divn.HP.PW  
 Una

SCHEDULE OF QUANTITY						Estimated Cost	99000/-
Name of work : Restoration of rain damage 120metre span bridge at Rampur on Una Santoshgarh road at RD.1/760 (SH: Hiring of Pocklane 1.50cum.bucket capacity for channalization of Khad on U/S side of Rampur bridge) (Under OFC Deposit) <i>Job No II</i>						Earnest Money	2000/-
						Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Hiring of Pocklane 1.50cum. bucket capacity on through rate basis for making chanel and embankment as per the direction of the Engineer-in-charge .The cost of Lubricant diesel etc. and wages of operational staff will be borne by the contractor including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	33.00	Per Hour				
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				Total:		
	2) The rates shall be including of all types of taxes including GST ectra)						
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						
	4) The bidder should have his own machinery.						
	5) The bidder must have provide machinery immediately as an when required.						

*Kishan*  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una

35

21

Estimated cost:- Rs. :-  
Earnest money:- Rs. :-  
Time limit :-

99643  
2000  
~~Two~~ Month  
one

**DRAFT SCHEDULE OF QUANTITY**


Name of work:- Restoration of damages occurred due to laying of OFC in various roads under basoli section sub division No 1 Una.  
(SH:- providing , fixing and art painting of information sign boards etc. (under ofc departt))

Sr. No.	Description of Item	Quantity	Unit	Rate	Rate in Words	Amount
1	Providing and erecting Direction and Place Identification signs bord with size 1200x900mm (twelve hundred into nine hundred milimetre) sign bord as per including priming coat IRC:67 (IRC - sixty seven) made of 1.5 mm (one point five millimetre) thick MS sheeting wide clouse 1701.23 with area not exceeding 0.9 sqm (zero point nine square metre) supported on mild steel 40 mm dia pipe 2 (two) Nos firmly fixed to the ground by means of properly designed foundation with M-15 (M-fifteen) grade cement concrete 450 x 450 x 600 mm (four hundred fifty into four hundred fifty into six hundred millimetres), 600 mm (six hundred millimetre) below ground level as per approved drawing and M.O.R.D. Tehnical Specification Clause 1701 including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes , duties /royalties, cess, Toll taxes of local bodies and authorities that the contractor will have to pay for the performanec of this contract.	4.00	Each			
2	Painting two coats (excluding priming cost on new steel and other metal surfaces eith enamel paint brush in to give an even shade including cleaning the surface of all dirt, dust and other foreign matters enamel paint other than white including the cost of material in all leads and lifts as per direction of Engineer-in-charge .	8.64	Sqm			
3	Writing letters or figures on any surface with black japan paint (Stops, comas, hyphens and the like not to be measured and paid separately) Indian (letters/figures) including the coat of material in all leads and lifts as per direction of Engineer-in-Charge.	37500.00	Per letter per cm height			
<b>Total</b>						


- NOTE: 1) All type of material shell be arranged by the contrector vide Notification by Additional Chief Secy. To the Govt. of HP. Vide letter No PBW(B)(17)2/2012 dated 7/8/2018
- 2) The rates shell be including of all types of taxes including GST etc
- 3) The bidder are requested to submit their bid as per notification issued by the Principal Sacy.PW to the Govt. of HP Vide Letter No PBW(B)A(3)1/2020 dated 22/7/2020 & Govt.of HP vide letter No PBW(B)A(3)1/2020-1 dated 7/10/2021

*K. S. Kumar*  
Executive Engineer  
Una Division  
H.P.P.W.D. Una

SCHEDULE OF QUANTITY						Estimated Cost	97859/-
Name of work :A/R & M/O PWD Rest House at Una (SH: Providing services out of sources basis for one number Mali (period of 153 days )						Earnest Money	2000/-
						Time limit	153 days
Sl. No.	Description of work	Qty	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing Services on temporary basis of one number Mali for maintenance , plantation & beautification of Rest House complex.	153.00	Per day				
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018					Total:	
	2) The rates shall be including of all types of taxes including GST ectra)						
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una

SCHEDULE OF QUANTITY						Estimated Cost	97850/-
Name of work :A/R & M/O PWD Rest House at Una (SH: Providing services of out sources basis for One number Sweeper (period of 153 days))						Earnest Money	2000/-
						Time limit	153 days
Sl. No.	Description of work	Quantity	Unit	RATE In		AMOUNT	
				Figures	Words		
1	Providing Services on temporary basis of one number Sweeper for sweeping the rest house.	153.00	Per day				
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018					Total:	
	2) The rates shall be including of all types of taxes including GST ectra)						
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021						

  
 Executive Engineer  
 Una Divn.HP.PWD  
 Una

45

24

SCHEDULE OF QUANTITY						
Name of work : Restoration of damages on link road from dehlan to Basdehra upto Punjab Boundary km.0/0 to 2/400 (SH: P/L NP-2 pipes 450mm dia at RD.2/371 to 2/385 RHS & P/F MS Grating over drain at RD.2/100 to 2/245(RHS) (Under OFC Deposit)					Estimated Cost	99432/-
					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:4:8 material within any leads and lifts..The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	5.13	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.26	Per cubic metre			
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	4.16	Per cubic metre			
4	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.69	Per cubic metre			
5	Providing and laying Non pressure NP-2 class(light duty) RCC pipes including collars/ spigot jointed with stiff mixture of cement mortar in the proportion of 1:2(1 cement: 2 fine sand) including testing of joints etc. complete 450mm dia RCC pipes including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	12.50	Per running metre			

6	Steel work work (Sai/RINL/Shyam steel Tisco, Jindal panther (JSPL) welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	456.00	Per Kilogramm e			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17)2/0212 dated 7.8.2018				Total:	
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

*K. Udela*

Executive Engineer

Una Divn.HP.PW

Una

46

25

SCHEDULE OF QUANTITY						
Name of work : Restoration of damages on link road from Dehlan to Basdehra upto Punjab Boundary km.0/0 to 2/400 (SH: P/L NP-2 pipes 450mm dia at RD.2/385 to 2/388 RHS & P/F MS Grating over drain at RD.2/245 to 2/385(RHS) & P/F MS Grating over drain at RD.2/300 to 2/385(LHS) (Under OFC Deposit)					Estimated Cost	99377/-
					Earnest Money	2000/-
					Time limit	One month
S. No.	Description of work	Quantity	Unit	RATE In		AMOUNT
				Figures	Words	
1	Demolishing cement concrete manually / by mechanical means including disposal in cement concrete 1:4:8 material within any leads and lifts..The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	0.81	Per cubic metre			
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto any height including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentials .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	0.27	Per cubic metre			
3	Providing and laying in position cement concrete 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level : as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentials .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	0.93	Per cubic metre			
4	Providing and laying in position specified grade of reinforced cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand): 3 graded stone aggregate 20 mm nominal size) excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level including entire carriage of material within all leads and lifts and other incidentials as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	1.50	Per cubic metre			
5	Providing and laying Non pressure NP-2 class(light duty) RCC pipes including collars/ spigot jointed with stiff mixture of cement mortar in the proportion of 1:2(1 cement: 2 fine sand) including testing of joints etc. complete 450mm dia RCC pipes including entire carriage of material within all leads and lifts and other incidentials and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	2.50	Per running metre			



6	Steel work work (Sail/RINL/Shyam steel Tisco, Jindal panther (JSPL) welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	866.40	Per Kilogramm e			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)©(17)2/0212 dated 7.8.2018					Total: 0
	2) The rates shall be including of all types of taxes including GST ectra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

  
 Executive Engineer  
 Una Divn.HP.PWD.  
 Una

30

26

SCHEDULE OF QUANTITY


Estimated cost 99819/-  
Earnest money 2000/-  
Time limit One month

Name of Work: Repair and maintenance of residence of Civil Judge Court No.II Una at DC colony Una (HP) (SH: P/L Painting and other repair etc.

S. No.	Description of work	Quantity	Unit	Rates (in. Rs.)		Amount (in. Rs.)
				Figures	Words	
1	Repair to plaster in patches of 2.50sqm and under 10 to 15mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a lead of 20mtr. with Cement mortar 1:5 (1cement:5sand)including carriage of material with in all leads and lifts and other incidentals .The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	18.00	Per square metre			
2	Applying birla white wall care putty over plaster surface after thoroughly brushing the surface free from mortar drops dust loose materials and other foreign matter sand paperd smooth to give final matt finish to the surface complete including carriage of material within all leads and lifts and other incidentals.The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	254.32	Per square metre			
3	Distempering (two coat) with oil bound washable distemper of approved brand and manufacture and of required shade on decorated wall surfaces to give an even shade after thoroughly brushing the surface clean of all grease dirt,loose,pieces of scales and also including preparing the surface even and sand papered smooth i including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	254.32	Per square metre			
4	Finishing walls with acrylic smooth exterior paint of required shade new work ( two or more coat applied @c1.67ltr/10sqm. over and including priming coat of exterior primer applied @2.20kg/10sqm.including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octori, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	383	Per square metre			

5	Painting one coats (excluding priming coat) on previously painted wood and wood based surface with enamel paint to give an even shade including cleaning of all dirt dust and other foreign matter sand papering and stopping with enamel paint other than white including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	62.21	Per square metre			
6	Providing and fixing glazing with glass panes of 4mm thickness ( weight not less than 10kg/sqm. including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	4.20	Per square metre			
7	Providing and fixing 25mm dia metre curtain rods with brackets, plugs etc. where ever required first class indian teak wood . including carriage of material within all leads and lifts and other incidentals. The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	22.30	Per running metre			
8	Providing and fixing M.S.BP sheet 1.66mm to 2mm(one point sixty six millimetre to two millimetre) thick in eaves board/facia/soffits/ceiling including cutting,fixing and welding to steel roof members and applying a coat of red lead primer complete as per instruction of Engineer-in-charge(Base members of steel work shall be measured & paid separately) including carriage of material within all leads and lifts and other incidentalsThe rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	5.33	Per square metre			
9	Providing and fixing Steel (Tata/Sail)work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar worksincluding entire carriage of material within all leads and lifts and other incidentals as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government. .	0.80	Per quantial			
10	Providing and fixing aluminium tower bolts (berrel type anodized transparent or dyed to required colour and shade with screws etcetra complete including carriage of material with in all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. (a) 200x10mm(two hundred into ten millimetre)	15.00	Each			
11	Providing and fixing aluminium handles anodized transparent or dyed to required colour and shade with necessary screws etc.including carriage of material with in all leads and lifts and other incidentals.The rate includes sale tax octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.. (a)125mm(one hundred twenty five millimetre)	15.00	Each			

12	Providing and fixing 19mm thick HDHMR board covered with lamination on both side including cutting of board as per required size and tapes, fevicol, nails and all other necessary arrangements to fix the boards on wall for panneling and for ward robe etcetra as per direction of Engineer-incharge including entire carriage of material within all leads and lifts and other incidentals and as per the direction by the Engineer-in-charge .The rates are inclusive octroi, royalty,malkana ,toll tax,sale tax,GST,labour cess or other taxes imposed by the Government.	6.08	Per square metre			
	NOTE: 1) All Type of material shall be arranged by the contractor vide Notification by Additional Secy.to the Govt. of HP vide letter No.PBW(B)@17/2/0212 dated 7.8.2018					G.Total
	2) The rates shall be including of all types of taxes including GST etetra)					
	3) The bidder are requested to submit their bid as per notification issued by the Principal Secy.PW to the Govt.of HP vide letter No.PBW(B) A(3)1/2020 dated 22.7.2020 & Govt. of HP vide letter No.PBW(B) A(3) 1/2020-1 dated 7.10.2021					

  
 Executive Engineer ,  
 Una Division, HPPWD.,  
 Una