



No. PW.CHD.CB.E-9/2025- 41340-42

Dated : 17/9/25


To

The Executive Engineer (IT Cell),
Nigam Vihar Shimla, H.P.

Subject :- Publication of Tender Notice.


Sir,

Enclosed please find herewith the tender notice of work(s) as given in the Notice Inviting Tender for uploading on departmental website as per notification vide Pr.Secy. (PW) to the Government of Himachal Pradesh letter No. PBW(B)1/2020 dated 27th May, 2021 and PBW(B)A(3)1/2020 dated 16th July, 2021 and even file dated 12.01.2023 as the work(s) mentioned in the tender notice is(are) urgent in nature and in public interest.


Executive Engineer,
Chopal Division,
HPPWD Chopal.

Copy forwarded for further necessary action to the :-

1. The Superintending Engineer, 04th Circle, HPPWD Shimla;
2. Computer Cell O/o the Executive Engineer, (IT Cell) Nigam Vihar Shimla-2.


Executive Engineer,
Chopal Division,
HPPWD Chopal.



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer Chopal Division, HPPWD, Chopal.

Web: www.hppwd.gov.in Email: ee-cho-hp@nic.in Phone/ Fax No.: - 01783-260033.

No. PW.CHD.CB.E-9/2025-

4040 - 4139

Dated: 17/9/25

NOTICE INVITING TENDERS

Sealed percentage rate tenders are hereby invited by the Executive Engineer, HPPWD Chopal District Shimla HP. in form No 6&8 on behalf of Governor of H.P. for the following works from the contractors of appropriate class enlisted with HPPWD. The tenders shall be opened in the presence of the contractors / firms or their representative who wish to be present.

TIME SCHEDULE OF TENDERS

1. Date and time of receipt of application for tender form : 26.09.2025 upto 04:00 PM
2. Date time of issue of tender form : 26.09.2025 04:00PM to 05:00PM
3. Date and time of receipt of tenders : 27.09.2025 11.00 AM
4. Date and time of opening of tenders : 27.09.2025 11.30 AM

The tender forms will be issued to only those contractors who qualify the criteria after the scrutiny of application forms:

Sl. No.	Name of work	Estimated cost (in Rupees)	EMD (in Rupees)	Cost of Tenders (in Rupees)	Time Limit	Eligible class of contractor.
1	Restoration of rain damages on various roads in Rewalpul Section under Shallu Sub-Division Nerwa (SH:- Hiring of Tipper for removal of Land Slide/ debris etc. at various RDs) DNIT No. 26 DL for the year 2025-26	92,800.00	2,000/-	350/-	One month	Class D& above
2	Restoration of rain damages on various roads under PIU Sub-Division Nerwa (SH:- Hiring of Excavator Cum- (PockLame/ L&T with breaker) for removal of boulders and slips & dressing of various roads (as and when required) DNIT No. 27 DL for the year 2025-26	497700.00	10,000/-	350/-	One month	Class D& above.
3	Restoration of rain damages on various roads under PIU Sub-Division Nerwa (SH:- Hiring of Excavator Cum- (PockLame/ L&T with breaker) for removal of boulders and slips & dressing of various roads (as and when required) DNIT No. 28 DL for the year 2025-26	497700.00	10,000/-	350/-	One month	Class D& above.



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer Chopal Division, HPPWD, Chopal.

Web: www.hppwd.gov.in Email: ee-cho-hp@nic.in Phone/ Fax No.:- 01783-260033.

4	Restoration of rain damages on various roads under PIU Sub-Division Nerwa (SH:- Hiring of Excavator Cum- (PockLame/ L&T with breaker) for removal of boulders and slips & dressing of various roads (as and when required) DNIT No. 29 DL for the year 2025-26	3,55,500.00	7,200/-	350/-	One month	Class D& above.
5	Restoration of rain damages on various roads in Kuthar Section under PIU Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 30 DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
6	Restoration of rain damages on various roads in Nerwa-I Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 31 DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
7	Restoration of rain damages on various roads in Nerwa-I Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 32DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
8	Restoration of rain damages on various roads in Nerwa-I Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 33DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
9	Restoration of rain damages on various roads in Nerwa-I Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 34DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
10	Restoration of rain damages on various roads in Jhiknipul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 35DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
11	Restoration of rain damages on various roads in Jhiknipul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 36DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer Chopal Division, HPPWD, Chopal.

Web: www.hppwd.gov.in Email: ee-cho-hp@nic.in Phone/ Fax No.: 01783-260033.

12	Restoration of rain damages on various roads in Jhiknipul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 37DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
13	Restoration of rain damages on various roads in Jhiknipul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 38DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
14	Restoration of rain damages on various roads in Jhiknipul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 39DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
15	Restoration of rain damages on various roads in Jhiknipul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 40DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
16	Restoration of rain damages on various roads in Rewalpul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 41DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
17	Restoration of rain damages on various roads in Rewalpul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 42DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
18	Restoration of rain damages on various roads in Rewalpul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 43DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
19	Restoration of rain damages on various roads in Rewalpul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 44DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
20	Restoration of rain damages on various roads in Rewalpul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 45DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer Chopal Division, HPPWD, Chopal.

Web: www.hppwd.gov.in Email: ee-cho-hp@nic.in Phone/ Fax No.:- 01783-260033.

21	Restoration of rain damages on various roads in Rewalpul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 46DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
22	Restoration of rain damages on various roads in Rewalpul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 47DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
23	Restoration of rain damages on various roads in Rewalpul Section under Shallu Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 48DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
24	Restoration of rain damages on various roads in Jhiknipul Section under Shallu Sub-Division Nerwa (SH:- Hiring of Tipper for removal of Land Slide/ debris etc. at various RDs) DNIT No. 49 DL for the year 2025-26	98,600.00	2,000/-	350/-	One month	Class D& above
25	Restoration of rain damages on various roads in Jhiknipul Section under Shallu Sub-Division Nerwa (SH:- Hiring of Tipper for removal of Land Slide/ debris etc. at various RDs) DNIT No. 50 DL for the year 2025-26	98,600.00	2,000/-	350/-	One month	Class D& above
26	Restoration of rain damages on various roads in Shamtha Section under PIU Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 51 DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
27	Restoration of rain damages on various roads in Kuthar Section under PIU Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 52 DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
28	Restoration of rain damages on various roads in Fediz Section under PIU Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 53 DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
29	Restoration of rain damages on various roads in Shamtha Section under PIU Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 54 DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer Chopal Division, HPPWD, Chopal.

Web: www.hppwd.gov.in Email: ee-cho-hp@nic.in Phone/ Fax No.: 01783-260033.

30	Restoration of rain damages on various roads in Shamtha Section under PIU Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 55 DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
31	Restoration of rain damages on various roads in Kuthar Section under PIU Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 56DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
32	Restoration of rain damages on various roads in Kuthar Section under PIU Sub-Division Nerwa (SH:- Hiring of JCB for removal of Land Slide/ debris etc. at various RDs) DNIT No. 57 DL for the year 2025-26	99,935.00	2,000/-	350/-	One month	Class D& above
33	Restoration of rain damages in Kuthar Section at various roads under PIU Sub-Division Nerwa (SH:- Hiring of Tipper for carriage of excavated materials) (DNIT No. 23DL for the year 2025-26)	98,600.00	2000/-	350/-	One month	Class D or above
34	Restoration of rain damages in Shamtha Section at various roads under PIU Sub-Division Nerwa (SH:- Hiring of Tipper for carriage of excavated materials) (DNIT No. 25 DL for the year 2025-26)	98,600.00	2000/-	350/-	One month	Class D or above
35	Restoration of rain damages on Fediz section at various roads under PIU Sub Division Nerwa (SH:- :- Removal of slips at various Roads as where required) (DNIT No. 46DL for the year 2024-25)	99,935.00	2000/-	350/-	One month	Class D or above
36	Restoration of rain damages on Fediz section at various roads under PIU Sub Division Nerwa (SH:- :- Hiring of Tipper for carriage of excavated materials) (DNIT No. 47DL for the year 2024-25)	98,600.00	2000/-	350/-	One month	Class D or above
37	Balance works in R/R damages on Tharoch to Madhana road km 0/0 to 9/0 (SH:- C/O Wire Crate R/Wall at RD. 4/0 to 4/020) under PDNA	97,733.00,	2000/-	350/-	One month	Class D or above
38	Restoration of rain damages various roads in Chambi Section under Chopal Sub Division (SH:- :- Hiring of JCB for removal of Land slide/debris etc. on various RDs) (DNIT No. 59DL for the year 2025-26)	99,935.00	2000/-	350/-	One month	Class D or above



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer Chopal Division, HPPWD, Chopal.

Web: www.hppwd.gov.in Email: ee-cho-hp@nic.in Phone/ Fax No.: 01783-260033.

39	Restoration of rain damages various roads in Chopal Section under Chopal Sub Division (SH:- :- Hiring of JCB for removal of Land slide/debris etc. on various RDs) (DNIT No. 60DL for the year 2025-26)	99,935.00	2000/-	350/-	One month	Class D or above
40	Restoration of rain damages various roads in Pulbahal Section under Chopal Sub Division (SH:- :- Hiring of JCB for removal of Land slide/debris etc. on various RDs) (DNIT No. 61DL for the year 2025-26)	99,935.00	2000/-	350/-	One month	Class D or above
41	Restoration of rain damages various roads in Sarain Section under Chopal Sub Division (SH:- :- Hiring of L&T for removal of Land slide/debris etc. on various RDs) (DNIT No. 62DL for the year 2025-26)	99,935.00	2000/-	350/-	One month	Class D or above
42	Restoration of rain damages various roads in Sarain Section under Chopal Sub Division (SH:- :- Hiring of L&T for removal of Land slide/debris etc. on various RDs) (DNIT No. 63DL for the year 2025-26)	99,935.00	2000/-	350/-	One month	Class D or above
43	Restoration of rain damages various roads in Dhabas Section under Chopal Sub Division (SH:- :- Hiring of JCB for removal of Land slide/debris etc. on various RDs) (DNIT No. 64DL for the year 2025-26)	99,935.00	2000/-	350/-	One month	Class D or above
44	Restoration of rain damages on Maneoty to Thangar road km 0/0 to 5/0(SH:- C/O B/Wall in RR Masnoyry in cement mortar 1:6 at RD 0/647 to 0/657)	99,695.00	2000/-	350/-	One month	Class D or above

TERMS AND CONDITIONS :-

1. The earnest money in the shape of National Saving Certificate, Time Deposit Account in any of the post office in HP/FDR of any Bank duly pledged in favour of Executive Engineer, Chopal Division HPPWD Chopal must be accompanied with the application for receipt of tender form along with cost of tender form in cash (Non refundable).
2. The conditional tender(s) and the application received without earnest money will summarily be rejected without assigning any reason(s).
3. The contractors/firms should possess the following documents (photo copy to be self attested with application for obtaining the tenders documents :-
 - a. Latest enlistment/renewal orders with application.
 - b. GST Number issued by the Sale Tax Department.
 - c. PAN (Permanent Account Number) issued by the Income Tax Department shall contain scanned copies of EPF issued from competent authority.
4. The Executive Engineer, Chopal Division HPPWD Chopal reserves the right to reject any tender without assigning any reason(s).
5. Only two number tender forms will be issued to the eligible contractor. If he bids for more than two works, only the first two works in sequence will be opened.
6. The work shall has to be started within fifteen days from the date of award. If the contractor fails to start the work within fifteen days, the work shall be cancelled and earnest money deposited will be forfeited.
7. The Cess Charges @ 1% will be deducted from the gross amount of work done of the contractor.
8. The work will be completed by the contractor within the stipulated period.
9. The contractor/firms are required to insert the rate of percentage in words as well as in figures, failing which Executive Engineer reserves the right to accept/reject any/overall tender.
10. The tender shall be issued to only those contractor/firms who are eligible suitable and competent.



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT


Office of the Executive Engineer Chopal Division, HPPWD, Chopal.

Web: www.hppwd.gov.in Email: ee-cho-hp@nic.in Phone/ Fax No.:- 01783-260033.

13. The contractor who has failed to start/complete the work already allotted in his favour within stipulated period shall not be issued tender forms.
14. A contractor enlisted in a particular class is eligible to tender for his own class and one step below.
15. If any kind of holiday to be happened, the tender documents shall be sold/opened on the next working day at the same time and venue.
16. GST will be deducted as per rates fixed by the Government.


CERTIFICATE

It is certified that tender for the above works are urgently required please.


Executive Engineer,
Chopal Division HPPWD Chopal
On behalf of Governor of H.P.

Copy forwarded for information to :-


1. The Chief Engineer (Shimla Zone) HPPWD Shimla.
2. The Superintending Engineer, 04th Circle, HPPWD Shimla.
3. The Deputy Commissioner, Shimla.
4. The SDO(C) Chopal Tehsil Chopal District Shimla H.P.
5. The BDO Chopal Tehsil Chopal District Shimla H.P.
6. All the Assistant Engineers working under this Division.
7. All the intending contractors in HPPWD.
8. Notice Board.


Executive Engineer,
Chopal Division HPPWD Chopal



CERTIFICATE

Certified that the tender(s) of work(s) as called vide this
office NIT No. PW.CHD.CB.C-9/2025- 4040-4139 dated
17/09/2025 are of urgent nature work(s).


Executive Engineer
Chopal Div. HPPWD Chopal
On behalf of Governor of H.P.

DRAFT / SCHEDULED OF QUANTITY

				Estimated Cost	Rs. 92800/-
				Earnest Money	Rs. 2000/-
				Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Rewalpul section under Shalhu Sub Division Nerwa.
(SH: Hiring of Tipper for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Hiring of Tipper 5.5 cum capacity daily basis for eight hour daily in good condition including the charges of P.O.L Repair and maintenance and wages of driver/operator for lifting of excavated earth/stone slips, Drain and disposal of the same in all leads and lifts including carriage of material and as per HP PWD specification of 1990 Vol. 1 and as per the direction o Engineer-in-charge at site.	16.00	5800.00	Fifty EightThousand only	Per day	92800.00
	Quoted rate in figure.					
	Quoted rate in words.					
	Total					92800.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machinerias shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

DNT / SCHEDULE OF QUANTITIES.

Job No.

ESTIMATED COST:- 497700/-

EARNEST MONEY:- RS. 10,000/-

TIME ALLOWED:- 1 Month

NAME OF WORK:- Restoration of rain damages on various roads in Kuthar section under PIU Sub-Division Nerwa. (SH:- Hiring of Excavator-Cum- (PockLane/L&T with breaker) for removal of Boulders and slips & Dressing of various roads (As & When Required)

Sr.No	Sub-Head and Item of works.	Quantity	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of Excavator -cum-loader (Pock Lane / L&T) with 90HP engine and lifting capacity of minimum 5000kgs including P.O.L. charges, shifting charges and other ancillary equipment as required of site of work for removal of boulders/slips in all kind of soil such as kanker, moorum shingle boulder decomposed or soft variety of soil such as spade work pick work jumper work soft & hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-servicable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stone from removal of slips shall have to be neatly stacked along side on road burns. The work shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instruction of the Engineer- in -charge.	126.00	3950.00	Rupees Three Thousand Nine Hundred & Fifty Only	Per Hour	497700.00
Total						497700.00

Note :

- 1 POL charges and all bear and tear shall be born by the contractor/owner of machine.
- 2 The repair of machinery shall be done by the contractor.
- 3 Any damages or loss of Govt./ Private property during the course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

DNT./SCHEDULE OF QUANTITIES.

Job No.

ESTIMATED COST:- 497700/-

EARNEST MONEY:- RS. 10,000/-

TIME ALLOWED:- 1 Month

NAME OF WORK:- Restoration of rain damages on various roads in Kuthar section under PIU Sub-Division Nerwa. (SH:- Hiring of Excavator-Cum- (PockLane/L&T with breaker) for removal of Boulders and slips & Dressing of various roads (As & When Required)

Sr.No	Sub-Head and Item of works.	Quantity	Rate in figures.	Rate in words.	Unit	Amount.
1	Hiring of Excavator -cum-loader(Pock Lane / L&T) with 90HP engine and lifting capacity of minimum 5000kgs including P.O.L. charges, shifting charges and other ancillary equipment as required of site of work for removal of boulders/slips in all kind of soil such as kanker, moorum shingle boulder decomposed or soft variety of soil such as spade work pick work jumper work soft & hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-servicable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stone from removal of slips shall have to be neatly staked along side on road burms. The work shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instruction of the Engineer- in -charge.	126.00	3950.00	Rupees Three Thousand Nine Hundred & Fifty Only	Per Hour	497700.00
	Total					497700.00

Note :

- 1 P.O.L. charges and all bear and tear shall be born by the contractor/owner of machine.
- 2 The repair of machinery shall be done by the contractor.
- 3 Any damages or loss of Govt./ Private property during the course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

DNT./SCHEDULE OF QUANTITIES.

Job No.

ESTIMATED COST:- 3,55,500/-
EARNEST MONEY:- RS. 7,200/-
TIME ALLOWED:- 1 Month

NAME OF WORK:- Restoration of rain damages on various roads in Kuthar section under PIU Sub-Division Nerwa. (SH:- Hiring of Excavator-Cum- (Pocklane/L&T with breaker) for removal of Boulders and slips & Dressing of various roads (As & When Required)

Sr.No	Sub-Head and Item of works.	Quantity	Rate in figures.	Rate in words.	Unit	Amount
1	Hiring of Excavator -cum-loader(Pock Lane / L&T) with 90HP engine and lifting capacity of minimum 5000kgs including P.O.L. charges, shifting charges and other ancillary equipment as required of site of work for removal of boulders/slips in all kind of soil such as kanker, moorum shingle boulder decomposed or soft variety of soil such as spade work pick work jumper work soft & hard rock including their intermediate classification of soil including mechanical transportation of necessary. The disposal of this un-servicable material has to be done in the acquired width of the road to avoid damage to the properties of the people or in case any damage took place, the contractor is liable for it. All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stone from removal of slips shall have to be neatly staked along side on road burms. The work shall be reduced accordingly. The work shall have to be carried out as per Ministry of Transport as per instruction of the Engineer- in -charge.	90.00	3950.00	Rupees Three Thousand Nine Hundred & Fifty Only	Per Hour	355500.00
	Total					355500.00

Note :

- 1 POL charges and all bear and tear shall be born by the contractor/owner of machine.
- 2 The repair of machinery shall be done by the contractor.
- 3 Any damages or loss of Govt./ Private property during the course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

			Estimated Cost	Rs. 99935/-
			Earnest Money	Rs. 2000/-
			Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Kutnar section under PIU Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops as per norms and IRC specification 48-1-998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935.00
	Quoted rate in figure.					
	Quoted rate in words.					
	Total					99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

DRAFT/ SCHEDULED OF QUANTITY

		Estimated Cost	Rs. 99935/-		
		Earnest Money	Rs. 2000/-		
		Time Allowed	One month		
NAME OF WORK :- R/R damages on various road in Nerva-I section under Shalu Sub Division Nerva.					
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDs)					
Sr. No	Description of item	Qty.	Rate	Unit	Amount
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops as per norms and IRC specification 48-1998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	In fig. 115.00 In words Rs one hundred fifteen only	P.C. cum	99935
	Quoted rate in figure.				
	Quoted rate in words.				
				Total	99935

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

			Estimated Cost	Rs. 99935/-
			Earnest Money	Rs. 2000/-
			Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Nerwa-I section under Shalinu Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	Pk cum	99935
	Quoted rate in figure:					
	Quoted rate in words:					
					Total	99935

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.

NA


Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

	Estimated Cost	Rs. 99935/-
	Earnest Money	Rs. 2000/-
	Time Allowed	One month

NAME OF WORK :- R/R damages on various road in Nerwa-I section under Shalla Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDs)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips as per norms and IRC specification 48-1998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935
	Quoted rate in figure:					
	Quoted rate in words:					
	Total					99935

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

DRAFT/ SCHEDULED OF QUANTITY

	Estimated Cost	Rs. 99935/-
	Earnest Money	Rs. 2000/-
	Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Nerwa-I section under Shalru Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935
	Quoted rate in figure.					
	Quoted rate in words.					
					Total	99935

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

				Estimated Cost	Rs. 99935/-
				Earnest Money	Rs. 2000/-
				Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Jhiknipul section under Shalinu Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 VOL I and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935
	Quoted rate in figure					
	Quoted rate in words.					
					Total	99935

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

DRAFT/ SCHEDULED OF QUANTITY

Estimated Cost	Rs. 99935/-
Earnest Money	Rs. 2000/-
Time Allowed	One month

NAME OF WORK :- R/R damages on various road in Jhiknupal section under Shalin Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1-98. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935
	Quoted rate in figure.					
	Quoted rate in words.					
	Total					99935

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the PDL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during construction shall be borne by the contractor.


 Executive Engineer
 P & R Division
 HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

Estimated Cost	Rs. 99935/-
Earnest Money	Rs. 2000/-
Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Jhikripul section under Shalla Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935
	Quoted rate in figure.					
	Quoted rate in words.					
	Total					99935

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during c


Executive Engineer
 B & R Division
 HPPWD, Chopal

DRAFT / SCHEDULED OF QUANTITY

	Estimated Cost	Rs. 99935/-
	Earnest Money	Rs. 2000/-
	Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Jhiknipur section under Shalla Sub Division Nerwa.
(SH: Hiring of L&T for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1998 vol I and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	807.00	113.00	Rs one hundred fifteen only	P/Cum	99935
	Total					99935
	Quoted rate in figure:					
	Quoted rate in words:					

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the PDL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT/ SCHEDULED OF QUANTITY

		Estimated Cost	Rs. 99935/-
		Earnest Money	Rs. 2000/-
		Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Jhiknupal section under Shalhu Sub Division Nerwa.
 (SH: Hiring of L&T for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1000 x 111 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	113.00	Rs one hundred fifteen only	P/Cum	99935
	Quoted rate in figure.					
	Quoted rate in words.					
	Total					99935

- Conditions:-**
- 1 The hour meter should be in working order.
 - 2 The Period will be as on depending upon the demand of department and weather condition.
 - 3 All the POL charges shall be borne by the contractor.
 - 4 All the repair of machineries shall be borne by the contractor.
 - 5 For any minor/major repair of any accident, contractor shall be responsible.
 - 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


B & R Engineer
 HPPWD Chopal

15

DRAFT / SCHEDULED OF QUANTITY

			Estimated Cost	Rs. 99935/-
			Earnest Money	Rs. 2000/-
			Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Jhiknupul section under Shalla Sub Division Nerwa.
(SH: Hiring of L&T for removal of Land slide/debris etc at various RDS)

Sr. No.	Description of item	Qty.	In fig.	Rate		Unit	Amount
				In words			
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol I and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	112.00	Rs. one hundred fifteen only	P/Cum	99935	
						Total	99935
	Quoted rate in figure:						
	Quoted rate in words:						

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
R/R Division
HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

Estimated Cost	Rs. 99935/-
Earnest Money	Rs. 2000/-
Time Allowed	One month

NAME OF WORK :- R/R damages on various road in Rewalpul section under Shalinu Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P.C cum	99935.00
	Quoted rate in figure.					
	Quoted rate in words.					
Total						99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.

[Signature]
Executive Engineer
B & R Division
HPPWD Chopal

DRAFT/ SCHEDULED OF QUANTITY

	Estimated Cost	Rs. 99935/-
	Earnest Money	Rs. 2000/-
	Time Allowed	One month

NAME OF WORK :- R/R damages on various road in Rewalput section under Shalru Sub Division Nerwa.
(SlH: Hiring of JCB for removal of Land slide/debris etc at various RDs)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935.00
	Quoted rate in figure.					
	Quoted rate in words					
Total						99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

			Estimated Cost	Rs. 99935/-
			Earnest Money	Rs. 2000/-
			Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Rewalpul section under Shalla Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops as per norms and IRC specification 48-1998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs. one hundred fifteen only	P/Cum	99935.00
	Quoted rate in figure.					
	Quoted rate in words.					
Total						99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopak

DRAFT / SCHEDULED OF QUANTITY


	Estimated Cost	Rs. 99935/-
	Earnest Money	Rs. 2000/-
	Time Allowed	One month

NAME OF WORK :- R/R damages on various road in Rewalpul section under Shalla Sub Division Nerya.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.I and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935.00
	Quoted rate in figure:					
	Quoted rate in words:					
Total						99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

Estimated Cost	Rs. 99935/-
Earnest Money	Rs. 2000/-
Time Allowed	One month

NAME OF WORK :- R/R damages on various road in Revalpul section under Shalhu Sub Division Nerwa.

(SH: Hiring of JCB for removal of Land slide/debris etc at various RDs)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compansated by him in all cases.	869.00	113.00	Rs one hundred fifteen only	P/Cum	99935.00
	Quoted rate in figure:					
	Quoted rate in words:					
Total						99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machinerics shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
 B & R Division
 HPPWD Chopra

DRAFT/ SCHEDULED OF QUANTITY

	Estimated Cost	Rs. 99935/-
	Earnest Money	Rs. 2000/-
	Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Rewalpul section under Shalhu Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	sq.m	99935.00
	Quoted rate in figure.					
	Quoted rate in words.					
	Total					99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

Estimated Cost	Rs. 99935/-
Earnest Money	Rs. 2000/-
Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Rewalpul section under Shalru Sub Division Nerwa.

(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops as per norms and IRC specification 48-1998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/C cum	99935.00
	Quoted rate in figure.					
	Quoted rate in words.					
Total						99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.



Executive Engineer
B & R Division
HPPWD Chopal

DRAFT/ SCHEDULED OF QUANTITY

Estimated Cost	Rs. 99935/-
Earnest Money	Rs. 2000/-
Time Allowed	One month

NAME OF WORK :- R/R damages on various road in Rewalpul section under Shalla Sub Division Nerwa.
 (SH: Hiring of JCB for removal of Land slide/debris etc at various RDs)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In Fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935.00
	Quoted rate in figure.					
	Quoted rate in words.					
Total						99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.

OP

Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

		Estimated Cost	Rs. 98600/-			
		Earnest Money	Rs. 2000/-			
		Time Allowed	One month			
NAME OF WORK :- R/R damages on various road in Jhiknipur section under Shailu Sub Division Nerwa.						
(SI: Hiring of Tipper for removal of Land slide/debris etc at various RDs)						
Sr. No	Description of item	Qty.	Rate	Unit	Amount	
1	Hiring of Tipper 5.5 cum capacity daily basis for eight hour daily in good condition including the charges of P.O.L Repair and maintenance and wages of driver/operator for lifting of excavated earth/stone slips, Drain and disposal of same in all leads and lifts including carriage of material and as per HP PWD specification of 1990 Vol. I and as per the direction o Engineer-in-charge at site.	17.00	5800.00	Fifty Eight Thousand only	Per day	98600.00
	Quoted rate in figure.					
	Quoted rate in words.					
Total					98600.00	

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

		Estimated Cost	Rs. 98600/-		
		Earnest Money	Rs. 2000/-		
		Time Allowed	One month		
NAME OF WORK :- R/R damages on various road in Jhiknripul section under Shalla Sub Division Nerwa.					
(SH: Hiring of Tipper for removal of Land slide/debris etc at various RDS)					
Sr. No	Description of item	Qty.	Rate	Unit	Amount
			In fig.		
1	Hiring of Tipper 5.5 cum capacity daily basis for eight hour daily in good condition including the charges of P.O.L Repair and maintenance and wages of driver/operator for lifting of excavated earth/stone slips, Drain and disposal of same in all leads and lifts including carriage of material and as per HP PWD specification of 1990 Vol. 1 and as per the direction o Engineer-in-charge at site.	17.00	5800.00 Fifty Eight Thousand only	Per day	98600.00
	Quoted rate in figure.				
	Quoted rate in words.				
Total					98600.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

	Estimated Cost	Rs. 99935/-
	Earnest Money	Rs. 2000/-
	Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Shamtha section under PIU Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips as per norms and IRC specification 48-1998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	11500	Rs one hundred fifteen only	P/Cum	99935.00
	Quoted rate in figure.					
	Quoted rate in words.					
	Total					99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Engineer
 & R Division
 HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

		Estimated Cost	Rs. 99935/-
		Earnest Money	Rs. 2000/-
		Time Allowed	One month
NAME OF WORK :- R/R damages on various road in Kuthar section under PIU Sub Division Nerwa.			
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)			
Sr. No	Description of item	Qty.	Rate
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	In fig. 115.00 In words Rs one hundred fifteen only
	Quoted rate in figure.		Unit P/C um
	Quoted rate in words.		Amount 99935.00
		Total	99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.

21

Executive Engineer
B & R Division
HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

		Estimated Cost	Rs. 99935/-
		Earnest Money	Rs. 2000/-
		Time Allowed	One month
NAME OF WORK : - R/R damages on various road in Fedij section under P111 Sub Division Nerva.			
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)			
Sr. No	Description of item	Qty.	Rate
		In fig.	In words
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	Rs one hundred fifteen only
			P/Cum
	Quoted rate in figure.		
	Quoted rate in words.		
		Total	99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


 Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

Estimated Cost	Rs. 99935/-
Earnest Money	Rs. 2000/-
Time Allowed	One month

NAME OF WORK :- R/R damages on various road in Shantha section under PIU Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935.00
	Quoted rate in figure.					
	Quoted rate in words.					
	Total					99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
 B & R Division
 HPPWD Chappal

DRAFT / SCHEDULED OF QUANTITY

Sr. No	Description of item	QTY.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935.00
	Quoted rate in figure:					
	Quoted rate in words:					
					Total	99935.00

NAME OF WORK : - R/R damages on various road in Shamtha section under PIU Sub Division Nerwa.

(Sl: Hiring of JCB for removal of Land slide/debris etc at various RDs)

Estimated Cost

Rs. 99935/-

Earnest Money

Rs. 2000/-

Time Allowed

One month

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

DRAFT / SCHEDULED OF QUANTITY

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips as per norms and IRC specification 48-1998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935.00
	Quoted rate in figure.					
	Quoted rate in words.					
Total						99935.00

NAME OF WORK : - R/R damages on various road in Kuthar section under PIU Sub Division Nerwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Estimated Cost	Rs. 99935/-
Earnest Money	Rs. 2000/-
Time Allowed	One month

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.



Executive Engineer
B & R Division
HPPWD Chapal

DRAFT / SCHEDULED OF QUANTITY

Estimated Cost	Rs. 99935/-
Earnest Money	Rs. 2000/-
Time Allowed	One month

NAME OF WORK : - R/R damages on various road in Kuthar section under PIU Sub Division Netwa.
(SH: Hiring of JCB for removal of Land slide/debris etc at various RDS)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips as per norms and IRC specification 48-1998. Including cartage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	P/Cum	99935.00
	Quoted rate in figure.					
	Quoted rate in words.					
Total						99935.00

Conditions:-

- 1 The hour meter should be in working order.
- 2 The Period will be as on depending upon the demand of department and weather condition.
- 3 All the PCL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be borne by the contractor.
- 5 For any minor/major repair of any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor



Executive Engineer
B & R Division
HPPWD Chopal

Job No (2)

33

DRAFT SCHEDULED OF QUANTITY.

Name of work :- Restoration of rain damage in Kuthar section at various road under PIU subdivision
nerwa (SH :- Hiring of tipper for carriage of excavated material)

Estimated Cost
Earnest Money

Rs. 98600/-
Rs. 2,000/-

Time

30 Days

Sr No	Description Of Items	Quantity	Rate	Rate (in words)	Unit	Amount
1	Hiring of tipper 5.5 cu.m capacity, self unloading system on daily basis (for eight hour daily in good condition including P.O.L, repair, operation charges and wages of driver/operation for lifting of excavated earth/stone slips, drain and disposal of the same in all leads and lifts and any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in charge and as per HPPWD specification of 1990 vol. 1	17.00	5800.00	Rupees Five Thousand and Eight Hundred Only	Per Day	98600
G. Total						98600

(Rupees Ninety eight Thousand Six Hundred Only

CONDITIONS :-

- 1 All the P.O.L charges shall be borne by the contractor.
- 2 All the repair of machineries shall be done by the contractor.
- 3 For any minor/ major repair or any accident, contractor shall be responsible.
- 4 Any damages or losses to Govt. / Private property during course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

Job No. (8)

34

DRAFT SCHEDULED OF QUANTITY.

Name of work :- Restoration of rain damage in Shamtha section at various road under PIU subdivision
nerwa (SH :- Hiring of tipper for carriage of excavated material)

Sr No	Description Of Items	Quantity	Rate	Rate (in words)	Unit	Amount	Estimated Cost	
							Earnest Money	Time
1	Hiring of tipper 5.5 cu.m capacity, self unloading system on daily basis (for eight hour daily in good condition including P.O.L, repair, operation charges and wages of driver/operation for lifting of excavated earth/stone slips, drain and disposal of the same in all leads and lifts and any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in charge and as per HPPWD specification of 1990 vol. 1	17.00	58000.00	Rupees Five Thousand and Eight Hundred Only	Per Day	98600	Rs. 98600/-	50 Days
G. Total							98600	

(Rupees Ninty eight Thousand Six Hundred Only

CONDITIONS :-

- 1 All the P.O.L charges shall be borne by the contractor.
- 2 All the repair of machineries shall be done by the contractor.
- 3 For any minor/ major repair or any accident, contractor shall be responsible.
- 4 Any damages or losses to Govt. / Private property during course of work shall have to be made by the contractor.



~~Executive Engineer~~
B & R Division
HPPWD Chopal

DRAFT/ SCHEDULED OF QUANTITY

NAME OF WORK :- Restoration of rain damages in Fediz section at various road under PIU Sub
Division Nerwa.(SH: Removal of slips at various Road as where requird)

Sr. No	Description of item	Qty.	Rate		Unit	Amount
			In fig.	In words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops as per norms and IRC specification 48-1998. Including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in charge at site in all leads and lifts. Any loss to the public and private property during the course of removal of slips shall be the absolute responsibility of during the course of removal of slips shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases.	869.00	115.00	Rs one hundred fifteen only	Cum	99935
Total						99935

Estimated Cost 99935/-
 Earnest Money Rs. 2000/-
 Time Allowed One month


 Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT SCHEDULED OF QUANTITY.

Name of work :- Restoration of rain damage in fediz section at various road under PIU subdivision nerna
(SH :- Hiring of tipper for carriage of excavated material)

Estimated Cost
Earnest Money
Time


Rs. 98600 /-
Rs. 2,000 /-
30 Days

Sr No	Description Of Items	Quantity	Rate	Rate (in words)	Unit	Amount
1	Hiring of tipper 5.5 cum capacity, self unloading system on daily basis (for eight hour daily in good condition including P. O.L, repair, operation charges and wages of driver/operation for lifting of excavated earth/stone slips, drain and disposal of the same in all leads and lifts and any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in charge and as per HPPWD specification of 1990 vol. 1.	17.00	5800.00	Rupees Five Thousand and Eight Hundred Only	Per Day	98600
G. Total						98600

(Rupees Ninty eight Thousand Six Hundred Only)

CONDITIONS :-

- 1 All the POL charges shall be borne by the contractor.
- 2 All the repair of machineries shall be done by the contractor.
- 3 For any minor/ major repair or any accident, contractor shall be responsible.
- 4 Any damages or losses to Govt. / Private property during course of work shall have to be made by the contractor.



Executive Engineer
B & R Division
HPPWD Chopal

SCHEDULED OF QUANTITY.

Name of work :- Balance work in R/R damage on Tharoch to Madhana road KM 0/00 to 9/00.
 (SH :- C/O wire crate R/wall at RD 4/00 to 4/020.)

Estimated cost :	Rs. 97733
Earnest money :	Rs. 2000
Time allowed :	One month

Sl. No	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.75	210.00	Rupees one hundred ninety five and paise zero only	Per cubic metre	788
2	Providing and laying of boulder apron laid in wire crate with 4mm dia G.I. wire conforming Is: 280 and Is:4826 in 100x100mm mesh including 10 per cent extra and joints laid with stone boulders weighing not less than 25kg each as per drawing and technical specification clause 1301 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	32.25	2900.00	Rupees two thousand six hundred fifty six and paise zero only	Per cubic metre	93525
3	Back filling behind abutment wing wall and returning wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	3.60	950.00	Rupees nine hundred fifty and paise zero only	Per cubic metre	3420
Total						97733-
Quoted rate in figure.						
Quoted rate in words.						


 P.S.M.D. Choudhary
 District Engineer
 District Division, Choudhary

DRAFT/SCHEDULED OF QUANTITY.

Estimated Cost	Rs 99935
Earnest Money	Rs 2000
Time Allowed	One Month

Sl. No.	Name of work (SH : Hiring of JCB for removal of Land slide/debris etc. on various Rds) Description of item	Qty.	Rate In figure	In words	Unit	A
1	Hiring of excavator -cum-loader for removal of slips, dressing of berms et minimum six hour per day including P.O.L and operation charges and all carriage of unserviceable material and stacked serviceable material in all leads and as per the direction of engineer in Charge at site, any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in Charge and as per HPPWD specification of 1990 vol. 1 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	869.00	115.00	Rupees one Hundred Ffifteen and paise zero only	Per Cum	
	Quoted rate in figure.				Total	
	Quoted rate in words.					

- Conditions -
- 1 The hour meter should be in working order.
 - 2 The period as will be as on depending upon the demand of department and weather condition.
 - 3 All the POL charges shall be borne by the contractor.
 - 4 All the repair of machineries shall be done by the contractor.
 - 5 For any minor/major repair or any accident, contractor shall be responsible.
 - 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

Estimated Cost	Rs. 99935
Earnest Money	Rs. 2000
Time Allowed	One Month

Sl. No.	Description of item	Qty.	Rate		Unit	Ar
			In figure	In words		
1	Hiring of excavator -cum-loader for removal of slips, dressing of berms etc minimum six hour per day including P.O.L and operation charges and all carriage of unserviceable material and stacked serviceable material in all leads and as per the direction of engineer in Charge at site, any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in Charge and as per HPPWD specification of 1990 vol 1 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	869.00	115.00	Rupees one Hundred Ffifteen and paise zero only	Per Cum.	9
	Quoted rate in figure					
	Quoted rate in words				Total	9

- Conditions :
- 1 The hour meter should be in working order.
 - 2 The period as will be as on depending upon the demand of department and weather condition.
 - 3 All the POL charges shall be borne by the contractor.
 - 4 All the repair of machineries shall be done by the contractor.
 - 5 For any minor/major repair or any accident, contractor shall be responsible.
 - 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

40

Estimated Cost	Rs. 99935
Earnest Money	Rs 2000
Time Allowed	One Month

Name of work : R/R damage on various roads in Pulbahal section under Chopal Sub-Division
 (SH : Hiring of JCB for removal of Land slide/debris etc. on various Rds)

Sl. No.	Description of item	Qty.	Rate		Unit	Am
			In figure	In words		
1	Hiring of excavator-cum-loader for removal of slips, dressing of berms etc minimum six hour per day including P O L and operation charges and all carriage of unserviceable material and stacked serviceable material in all leads and as per the direction of engineer in Charge at site, any loss or damage to private and Govt property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in Charge and as per HPPWD specification of 1990 vol 1 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	869.00	115.00	Rupees one Hundred Fiftien and paise zero only	Per Cum.	99
	Quoted rate in figure					
	Quoted rate in words					
					Total	99

Conditions:

- 1 The hour meter should be in working order.
- 2 The period as will be as on depending upon the demand of department and weather condition.
- 3 All the P.O.L charges shall be borne by the contractor.
- 4 All the repair of machineries shall be done by the contractor.
- 5 For any minor/major repair or any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

41

Estimated Cost	Rs. 99935
Earnest Money	Rs. 2000
Time Allowed	One Month

Name of work : R/R damage on various roads in Sarain section under Chopal Sub-Division
(SH : Hiring of L&T for removal of Land slide/debris etc. on various Rds)

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Hiring of L&T for removal of slips, dressing of berms etc minimum six hour per day including P.O.L and operation charges and all carriage of unserviceable material and stacked serviceable material in all leads and as per the direction of engineer in Charge at site, any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in Charge and as per HPPWD specification of 1990 vol. 1 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	869.00	115.00	Rupees one Hundred Fifteen and paise zero only	Per Cum	9993
	Quoted rate in figure				Total	9993
	Quoted rate in words					

Conditions :-

- 1 The hour meter should be in working order.
- 2 The period as will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be done by the contractor.
- 5 For any minor/major repair or any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

42

Estimated Cost	Rs. 99935
Earnest Money	Rs. 2000
Time Allowed	One Month

Name of work : R/R damage on various roads in Sarain section under Chopal Sub-Divison
(SH : Hiring of L&T for removal of Land slide/debris etc. on various Rds)

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Hiring of L&T for removal of slips, dressing of berms etc minimum six hour per day including P.O.L and operation charges and all carriage of unserviceable material and stacked serviceable material in all leads and as per the direction of engineer in Charge at site, any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in Charge and as per HPPWD specification of 1990 vol 1 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge- including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	869.00	115.00	Rupees one Hundred Filtien and paisa zero only	Per Cum	99935
	Quoted rate in figure				Total	99935
	Quoted rate in words					

Conditions :-

- 1 The hour meter should be in working order
- 2 The period as will be as on depending upon the demand of department and weather condition.
- 3 All the POL charges shall be borne by the contractor.
- 4 All the repair of machineries shall be done by the contractor.
- 5 For any minor/major repair or any accident contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
B & R Division
HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

43

Estimated Cost	Rs. 99935
Earnest Money	Rs. 2000
Time Allowed	One Month

Sl. No.	Name of work (SH : Hiring of JCB for removal of Land slide/debris etc. on various Rds) Description of item	Qty.	Rate In figure	In words	Unit	Amount
1	Hiring of excavator -cum-loader for removal of slips, dressing of berms etc minimum six hour per day including P.O.L and operation charges and all carriage of unserviceable material and stacked serviceable material in all leads and as per the direction of engineer in Charge at site. any loss or damage to private and Govt. property during working hour is the whole responsibility of contractor. The work shall be executed as per the direction of Engineer in Charge and as per HPPWD specification of 1990 vol. 1 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	869.00	115.00	Rupees one Hundred Fiftien and paise zero only	Per Cum.	99935
	Quoted rate in figure.				Total	99935
	Quoted rate in words.					

Conditions -

- 1 The hour meter should be in working order.
- 2 The period as will be as on depending upon the demand of department and weather condition
- 3 All the P.O.L charges shall be borne by the contractor.
- 4 All the repair of machineries shall be done by the contractor.
- 5 For any minor/major repair or any accident, contractor shall be responsible.
- 6 Any damages or losses to Govt/Private property during course of work shall have to be made by the contractor.


Executive Engineer
 B & R Division
 HPPWD Chopal

DRAFT/SCHEDULED OF QUANTITY.

44

RK dhangra

Name of work :- *K/O Maneoty to Thangad road km 0/6 to 5/6*

(SH :- C/O BWall in RR Masonry in cement mortar 1:6 at RD 0/647 to 0/657) Under MNP

Estimated cost :	Rs.99695
Earnest money :	Rs.2000
Time allowed :	One month

Sl. No.	Description of item	Qty.	Rate		Unit	Amount
			In figure	In words		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 mtr and a lead upto 20mtrs as per drawing and technical specifications clause 1603.2 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	20.15	195.00	Rupees one hundred ninety five and paisa zero only	Per cubic metre	3929
2	Earthwork in excavation for foundation of structure as per drawing and technical specification clause 305.1 including setting and c/o shoring and bracing removal of stumps and other deleterious material and disposal up to a lead of 50 mtr dressing of sides, and bottom backfilling in approved material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.03	210.00	Rupees two hundred ten and paisa zero only	Per cubic metre	2736
3	Providing and laying plain cement concrete 1:6:12 (1 cement : 6 sand : 12 graded stone aggregate 40 mm nominal size mixing by mechanical concrete mixture 0.40/0.28 & vibrated mechanically so as to give a compressive strength and curing complete including the cost of from work as per drawing and technical specification clause 802, 803, 1202, and 1203 including carriage of all labour material and equipments to various location through all modes of transportation as per HPPWD specification 1990 vol.1 and as per direction of Engineer in Charge at site in all leads and lifts.	1.74	4800.00	Rupees four thousand eight hundred and paisa zero only	Per cubic metre.	8331
4	Random rubble masonry / polygonal rubble masonry (uncoursed / brought to courses) with hard stones of approved quality in foundation and plinth in cement mortar 1:6 (one cement : 6 sand) at plinth level in. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	17.29	4900.00	Rupees four thousand two hundred and paisa zero only	Per cubic metre.	84698
Total						99695
Quoted rate in figure.						
Quoted rate in words.						


Executive Engineer
 B & R Division
 HPPWD Choppal