

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No.PWD/JMD/CB/Tender/2025-26:- 4053-67

Dated:- 11/09/25

To


The Executive Engineer (IT Cell)  
Nirman Bhawan , Nigam Vihar  
Shimla-2

**Subject:- Tender notice**

Sir,

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PWD) to the Govt. of HP vide NO PBW(B)A(3) 1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are ugent / emergent nature of works in public interest.

DA/As above

  
Executive Engineer,  
Jawaamukhi Division HPPWD.,  
Jawalamukhi.

Endst. No.PWD/JMD/CB/Tender/2025-26:-

Dated:-

Copy forwarded to the following:-

- 1 The FC-Cum Secy. (PW) to the Govt. of HP Shimla-2
- 2 The Engineer-in-Chief, HPPWD., Shimla.
- 3 The Chief Engineer(KZ) HP.PWD. Dharamshala.
- 4 The Superintending Engineer, Dehra Circle HP.PWD. Dehra
- 5 All the Executive Engineers under North Zone.
- 6 All the Assistant Engineers under Dehra Division.
- 7 The Deputy Commissioner Kangra at Dharamshala.
- 8 The SDM/Tehsildar/President NAC Jawalamukhi.
- 9 Notice Board.

Executive Engineer,  
Jawalamukhi Division HP.PWD.,  
Jawalamukhi

## H. P. P.W.D. TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Jawalamukhi Division HPPWD., Jawalamukhi on behalf of the Governor of HP for the following works from the approved and eligible contractors ( C&D Class) enlisted in HPPWD.

### TENDER SCHEULE

1. Date and time of receipt of application for tender form: 16.09.2025 upto 11.00 PM
2. Date and time of issue of tender form: 17.09.2025 upto 11.30 PM
3. Date and time of receipt of tenders: 18.09.2025 upto 11.00 AM
4. Date and time of opening of tenders: 18.09.2025 at 11.30 AM

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Jawalamukhi Division HPPWD Jawalamukhi must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit	Cost of form
1	Resoration of link road to village faked km 0/000 to 1/000 ( SH:- Providing and laying cement concrete at RD 0/251 to 0/275.40	Rs 99,469/-	Rs.2,000/-	One Months	350
2	Resoration of link road to village faked km 0/000 to 1/000 ( SH:- Providing and laying cement concrete at RD 0/226 to 0/250.50	Rs 99,045/-	Rs.2,000/-	One Months	350
3	Repair and maintenance of link road from Tihri to Daloh km 00/000 to 8/240 (SH:- Removal of slips Bush cutting and construction of various RDs 0/00 to 4/120 SDF/ 2024/ 728	Rs.99117/-	Rs.2,000/-	One Months	350
	Repair and maintenance of Chowki to Kasar km 00/000 to 5/000 (SH:- Removal of slips Bush cutting and construction of drain at various RDs 0/00 to 3/000 SDF/ 2024/ 726	Rs.99682/-	Rs.2,000/-	One Months	350
1.	The contractors/firms should possess the following documents(Photocopy to be attached): Copy of Registration/Latest renewal of enlistment. (i) PAN (Permanent Account No.) (ii) Registration under GST No. (iii) EPF(Employee Provident Fund Account No.) (iv)				
2	Ambiguous/telegraphic/conditional tenders or tender by Fax/E-mail shall not be entertained /considered in any case.				
3	The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).				
4	The offer of the tender shall remain valid upto 30 days after the opening.				

Executive Engineer  
HPPWD Division Jawalamukhi  
Distt Kangra H.P  
on behalf of Governor of Himachal Pradesh  
HIM LOK SAMPARK

**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs. 99,469.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Month.

Name of work:- Restoration of Link Road to Village faked Km 0/000 to 1/000 (SH:- Providing and laying Cement Concrete at RD 0/226 to 0/250.50

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourly millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete as per drawing and MORR technical specification 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, Sale tax, GST or any other taxes imposed by the Government.	5.60 Cubic meter	4050.00	Four Thousand and Fifty Rupees	Per Cubic meter	22,680.00
2	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORR technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government.	11.21 Cubic metre	6850.00	Six Thousand Eight Hundred Fifty Rupees	Per Cubic metre	76,789.00
<b>Total</b>						
			% Above/below			99,469.00
		Quoted Amount in Figures				
		Quoted Amount in Words				

Executive Engineer,  
Jawalamukhi Division,  
HPPWD Jawalamukhi.

JOB NO-02

**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs. 99,045.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Month.

Name of work:- Resoration of Link Road to Village faked Km 0/000 to 1/000 (SH:- Providing and laying Cement Concrete at RD 0/251 to 0/275.40

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying mechanically mixed and vibrated cement concrete 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 40mm (fourty millimeter) nominal size) for plain cement concrete, in or under water in open foundation for all types of structures, including pumping or bailing out water/ dewatering (surface/sub-soil water) and including removal of slush which may arise at the time of laying under water for all heights/depth and any quantum of water including cost of form work and curing complete	5.58 Cubic meter	4050.00	Four Thousand d Fifty Rupees	Per Cubic meter	22,599.00
2	Providing and laying mechanically mixed and vibrated concrete for Reinforced cement concrete Grade-M25 (M-Twenty five) Nominal mix 1:1.5:3(one cement : one decimal five sand : four graded crushed stone aggregate (20mm) twenty millimeters nominal size) in or under water in open foundation for all types of structure including cost of form work and curing complete as per drawing and MORd technical specification clause 802, 803, 1202 & 1203 and as per the direction and the entire satisfaction of Engineer-in-Charge, including	11.16 Cubic metre	6850.00	Six Thousand d Eight Hundred Fifty Rupees	Per Cubic metre	76,446.00
	<b>Total</b>					<b>99,045.00</b>
% Above/below						
Quoted Amount in Figures						
Quoted Amount in Words						

Executive Engineer,  
Jawalamukhi Division,  
JPPWD Jawalamukhi.

**PERCENTAGE BILL OF QUANTITY**

Name of work:- **Repair and maintenance of link road Tihri to Daloh Km. 0/00 to 8/240 (SH.-Removal of slips , Bush cutting & Construction of drain at various RD. 4/120 ) SDF/2024/728**

Estimate Cost :- Rs.99117.00  
 Earnest Money :-Rs. 2000.00  
 Time Limit :- One Month.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, GST tax or any other taxes imposed by the Government	146.88 Square metre	135.00	Rupees One Hundred Thirty Five Only	Per Square metre	19,829.00
2	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm (Thirty centimeter) measured at a height of 1mtr (One metre) above ground and removal of rubbish upto a distance of 20mtr (Twenty metres) outside the periphery of the area cleared and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the	4387.50 Square metre	15.00	Rupees Fifteen Only	Per Square metre	65,813.00

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	245.00 Running metre	55.00	Rupees Fifty Five Only	Per Running metre	13,475.00
	<b>Total</b>					99,117.00
			% Above/below			
			Quoted Amount in Figures			
			Quoted Amount in Words			

*Bill quantity checked and approved for Rs 99117.00 only*

Executive Engineer,  
Jawalamulhi Division,  
APRWD Jawalamulhi

**PERCENTAGE BILL OF QUANTITY**

Estimate Cost :- Rs.99682.00  
 Earnest Money :-Rs. 2000.00  
 Time Limit :- One Month.

Name of work:- Repair and maintenance of link road Chowki to Kasar Km. 0/00 to 5/500 (SH.-Removal of slips , Bush cutting & Construction of drain at various RD. 0/00 to 3/00 ) SDF/2024/726

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in lift upto 1.5m and lead upto 1000m as per technical specification 302.3.5 and 1611 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, Toll tax, GST tax or any other taxes imposed by the Government	174.31 Square metre	135.00	Rupees One Hundred Thirty Five Only	Per Square metre	23,532.00
2	Royalty, Malkhana, Octroi, Toll tax, GST tax or any other taxes imposed by the Government	4545.00 Square metre	15.00	Rupees Fifteen Only	Per Square metre	68,175.00
	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm (Thirty centimeter) measured at a height of 1mtr (One metre) above ground and removal of rubbish upto a distance of 20mtr (Twenty metres) outside the periphery of the area cleared and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the					

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. and as per the direction and the entire satisfaction of Engineer-in-Charge. including carriage of materials up to all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, GST, sale tax or any other taxes imposed by the Government.	145.00 Running metre	55.00	Rupees Fifty Five Only	Per Running metre	7,975.00
	<b>Total</b>					99,682.00
			% Above/below			
			Quoted Amount in Figures			
			Quoted Amount in Words			

*B<sup>2</sup> V<sup>2</sup> of quantity checked and approved for Rs 99682 only.*

Executive Engineer,  
Jawalandhi Division,  
HPPWD Jawalamulhi