

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-NHD-GA-TENDER/ 2025-26

4701-02

Dated:

17⁰⁹
2025

To

The Executive Engineer,
IT Cell Nirman Bhawan Nigam Vihar,
HP,PWD Shimla-02 (H.P)..


Subject:-

Regarding uploading of NIT on HP,PWD website .


Please find enclosed herewith the tender notice for the works as given in the Notice inviting tender for uploading on departmental website as per notification Pr. Sec. (PW) to the Govt. of (H.P.) letter No. PBW(B)A(3) 1/2024 dated 03 Jan 2024. The work mentioned in the tender notice are urgent in nature and public interest.

This is for your kind information and necessary action at your end please.

Encl:-NIT & copy of schedule of quantity.



Executive Engineer,
National Highway Division
HP,PWD Hamirpur.

Copy to the Superintendent Engineer, National Highway Circle HP.PWD Shahpur for information please.


Executive Engineer,
National Highway Division,
HP,PWD Hamirpur.

CERTIFICATE

Certified that the tenders of works, called vide this office letter No. PW-NHD-GA-TENDER/2025-26 4701-02 Dated:- 17/09/2025 are urgent nature.


Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)

HIMACHAL PRADESH
Public Works Department

NOTICE INVITING TENDER


Sealed Tenders on item rate basis are hereby invited on behalf of Governor of H.P. by Executive Engineer, NH Division, HPPWD, Hamirpur (H.P) from the experienced contractor/ firms enlisted in appropriate class with HPPWD for the following works. The tender shall be received in this office on **29.09.2025** up to 11.00 A.M. and the same shall be opened on the same day at 11:30 A.M. in the presence of Contractor/Firms or their authorized/representatives who wish to be present at the time of opening of tender. The application for issue of tender document shall be received on dated **26.09.2025** up to 11:30 P.M. on cash payment of Rs. 350/- (Non-Refundable) and tender document will be issued on **27.09.2025** up to 1:00 P.M. If the office happens to be closed on the scheduled date the tender form document will be sold/ opened on the next working day at the same time and venue.

Sr. No	Name of Work	Estimated cost	Earnest money	Time allowed	Class of Contractor
1	Restoration of road damaged caused due to laying of OFC on NH -20A (New NH-503) Km 39/0 to 91/0(SH: Providing and fixing dual side reflecting delinators at km 63/263 to 63/345). (Deposit work).	99960.00	2000.00	One Month	Class-D
2	Restoration of road damaged caused due to laying of OFC on NH -20A (New NH-503) Km 39/0 to 91/0(SH: Providing and fixing dual side reflecting delinators at km 63/346 to 63/428). (Deposit work).	99960.00	2000.00	One Month	Class-D
3	Restoration of road damaged caused due to laying of OFC on NH -20A (New NH-503) Km 39/0 to 91/0(SH: Providing and fixing dual side reflecting delinators at km 63/180 to 63/262). (Deposit work).	99960.00	2000.00	One Month	Class-D
4	Restoration of road damages caused due to laying of OFC on NH- 70(03). at Km 58/400 to 196/495 (SH:- Construction of drain & paved shoulder in Km. 138/590 to 138/660 Deposit work	97405.00	2000.00	One Month	Class-D
5	Restoration of road damage due to laying of water pipelines along the road on NH- 70(New NH- 03). at Km 58/400 to 140/200 (SH:- Repair of road between Km. 139/285 to 139/370 and 138/840 to 138/862 and dressing of berms (Deposit work)	96167.00	2000.00	One Month	Class-D
6	Restoration of road damage due to laying of water pipelines along the road on NH- 70(New NH- 03). at Km 58/400 to 140/200 (SH:- Concreting along the road between Km. 139/375 to 139/550 and 139/640 to 139/735 (Deposit work)	99225.00	2000.00	One Month	Class-D
7	Restoration of road damage due to laying of water pipelines along the road on NH- 70(New NH- 03). at Km 58/400 to 140/200 (SH:- Concreting along the road between Km. 139/740 to 140/00 (Deposit work)	99225.00	2000.00	One Month	Class-D

Draft notice inviting/ specification special conditions can be seen in this office on any working day, ambiguous/ conditional tenders shall not be entertained/ considered in any case. The contractors/ firms are requested to insert the rate of each item in words as well as in figure, failing which Executive Engineer, reserves the right to accept/ reject any or all tenders. The intending contractors/ firms are requested to see the site of work before submitting the tenders. The application without earnest money will not be entertained and out rightly rejected.

CONDITIONS: - The following document are required to be attached with the application: -

1. A copy of valid enlistment and renewal certificate. 2. A copy of GST. 3. Earnest Money duly pledged in favour of Executive Engineer. Any application not accompanied by above documents shall not be entertained. The tender shall be issued to those contractors/ firms who are found eligible, suitable and competent. The decision of the Executive Engineer, regarding suitability, eligibility and competence of the contractor/ firm applying for issue of tenders shall be final. In case, of any information supplied by the contractor/ firm, is found false at any stage, the tender is liable to be rejected and action taken against contractor/firm.


Executive Engineer,
NH Division, HPPWD
Hamirpur.

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of Road damages caused due to laying of OFC on NH -503 Km 39/00 to 91/00 (SH:- Providing and fixing dual side reflecting delinators at km 63/263 to 63/345).

Estimated Cost:- Rs. 99960.00
 Earnest Money:- Rs. 2000.00
 Time Limit: - One Month

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing dual directional delinators made of 18(Eighteen) galv. MS Rectangular pipe of 25/68mm (Twenty five into Sixty eight millimetre) and of length 600mm (Six Hundred millimetre) head made of ABS Plastic (Rectangular moded with flat face providing with high intensity prismatic reflectors of colour (yellow) of size 100X125 mm (One hundred into One hundred twenty five millimetre) with additional reflective strips of 25mm (Twenty five millimetre) wide including carriage of material within all leads and lifts as per direction of Engineer - In - Charge.	102.00	980.00	Rupees Nine Hundred Eighty and paise nil only	Each	99960.00
G.Total						99960.00

Draft Schedule of Quantity checked and Approved for Rs 99960.00 (Rupees Ninety nine Thousand Nine hundred and sixty) Only.


 Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur, (HP)

DRAFT SCHEDULE OF QUANTITY


Name of work :- Restoration of Road damages caused due to laying of OFC on NH -503 Km 39/00 to 91/00 (SH:- Providing and fixing dual side reflecting delimiters at km 63/346 to 63/428).

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing dual directional delimiters made of 18(Eighteen) galv. MS Rectangular pipe of 25/68mm (Twenty five into Sixty eight millimetre) and of length 600mm (Six Hundred millimetre) head made of ABS Plastic (Rectangular moded with flat face providing with high intensity prismatic reflectors of colour (yellow) of size 100X125 mm (One hundred into One hundred twenty five millimetre) with additional reflective strips of 25mm (Twenty five millimetre) wide including carriage of material within all leads and lifts as per direction of Engineer - In - Charge.	102.00	980.00	Rupees Nine Hundred Eighty and paise nil only	Each	99960.00
	G. Total					99960.00

Estimated Cost:- Rs.
Earnest Money:- Rs.
Time Limit:-

99960.00
2000.00
One Month

Draft schedule of Quantity checked and Approved for Rs 99960/- (Rupees Ninety Nine thousand Nine hundred sixty) only.


 Executive Engineer,
 National Highway Division,
 HP.PWD., Hamirpur (HP)

3

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of Road damages caused due to laying of OFC on NH -503 Km 39/00 to 91/00 (SH:- Providing and fixing dual side reflecting delinators at km 63/180 to 63/262).		Estimated Cost:- Rs.		99960.00		
		Earnest Money:- Rs.	2000.00			
		Time Limit:-		One Month		
Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Providing and fixing dual directional delinators made of 18(Eighteen) galv MS Rectangular pipe of 25/68mm (Twenty five into Sixty eight millimetre) and of length 600mm (Six Hundred millimetre) head made of ABS Plastic (Rectangular moded with flat face providing with high intensity prismatic reflectors of colour (yellow) of size 100X125 mm (One hundred into One hundred twenty five millimetre) with additional reflective strips of 25mm (Twenty five millimetre) wide including carriage of material within all leads and lifts as per direction of Engineer - In - Charge.	102.00	980.00	Rupees Nine Hundred Eighty and paise nil only	Each	99960.00
G.Total						99960.00

Draft schedule of Quantity checked and Approved for Rs 99960/- (Rupees ninety nine thousand nine hundred sixty only)

for
Executive Engineer,
National Highway Division,
HP.PWD., Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of road damages caused due to laying of OFC on NH- 70(03). at Km 58/400 to 196/495 (SH)- Construction of drain & paved shoulder in Km. 138/590 to 138/660 Deposit work

Estimated Cost:- Rs. 97405.00
Earnest Money:- Rs. 2000.00
Time Limit:- One Month

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and MORT&H specification clause 305.1 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and lift, including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and structring and pumping and bailing out water (surface and sub soil water upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government.	18.20	200.00	Rupees hundred and paise nil only	Per Cubic metre	3640.00
2	Providing and laying, mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation complete as per drawings and MORT&H specifications clause 802.803, 1202 and 1203, PCC Grade M10 (Nominal mix 1:3:6) (One cement : three sand : six graded/ crushed stone aggregate) 20mm (Twenty millimetre) nominal size including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government.	19.95	4700.00	Rupees Four thousand Seven hundred and paise nil only	Per Cubic metre	93765.00
G. Total						97405.00

Draft Schedule of quantity checked and approved for Rs. 97405/- (Rupees Ninety seven thousand four hundred five only)

Executive Engineer,
National Highway Division,
H.P. PWD., Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of road damage due to laying of water pipelines along the road on NH- 70(New NH- 03). at Km 58/400 to 140/200 (SH:- Repair of road between Km. 139/285 to 139/370 and 138/840 to 138/862 and dressing of berms (Deposit work)

Estimated Cost:- Rs. 96167.00
 Earnest Money:- Rs. 2000.00
 Time Limit: - One Month

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and MORT&H specification clause 305.1 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and lift, including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and structting and pumping and bailing out water (surface and sub soil water upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government.	11.03	200.00	Rupees Two hundred and paise nil only	Per Cubic metre	2206.00
2	Providing and laying, mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation complete as per drawings and MORT&H specifications clause 802,803,1202 & 1203. PCC Grade M10 (Nominal mix 1:3:6) (One cement : three sand : six graded/ crushed stone aggregate 20mm (Twenty millimetre) nominal size including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	11.03	4700.00	Rupees Four thousand Seven hundred and paise nil only	Per Cubic metre	51841.00
3	Making up loose of materail / irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification clause 1903 including entire carriage of material within all leads and lifts as per directions of Engineer-in-Charge and other incidental charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government.	1620.00	26.00	Rupees twenty six and paise nil only	Per square metre	42120.00
G.Total						96167.00

Drafts schedule of quantity checked and approved for Rs. 96167/09.

Jeeb
 Executive Engineer,
 National Highway Division,
 HP.PWD Hamirpur (HP)

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of road damage due to laying of water pipelines along the road on NH- 70(New NH- 03), at Km 58/400 to 140/200 (SH:- Concreting along the road between Km. 139/375 to 139/550 and 139/640 to 139/735 (Deposit work)

Estimated Cost:- Rs. 99225.00
 Earnest Money:- Rs. 2000.00
 Time Limit: - One Month

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and MORT&H specification clause 305.1 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and lift, including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and structting and pumping and bailing out water (surface and sub soil water upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	20.25	200.00	Rupees hundred and paise nil only	Per Cubic metre	4050.00
2	Providing and laying, mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation complete as per drawings and MORT&H specifications clause 802,803,1202 & 1203. PCC Grade M10 (Nominal mix 1:3:6) (One cement : three sand : six graded/ crushed stone aggregate 20mm (Twenty millimetre) nominal size including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	20.25	4700.00	Rupees Four thousand Seven hundred and paise nil only	Per Cubic metre	95175.00
G.Total						99225.00

Books Schedule of Quantity checked and approved for Rs. 99225/00.

Executive Engineer,
 National Highway Division,
 HP.PWD., Jammu (HP)

DRAFT SCHEDULE OF QUANTITY

Sr No.	Description of item.	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and MORT&H specification clause 305.1 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all lead and lift, including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and structting and pumping and bailing out water (surface and sub soil water upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals charges. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	20.25	200.00 Rupees hundred and paise nil only	Two hundred and paise nil only	Per Cubic metre	4050.00
2	Providing and laying, mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation complete as per drawings and MORT&H specifications clause 802,803,1202 & 1203. PCC Grade M10 (Nominal mix 1:3:6) (One cement : three sand : six graded/ crushed stone aggregate 20mm (Twenty millimetre) nominal size including entire carriage of materials within all leads and lifts and as per the direction of Engineer-in-charge. The rates are inclusive octroi , royalty , Malkana, toll tax, Sale tax, Good service tax, labour cess or other taxes imposed by the Government	20.25	4700.00	Rupees Four thousand Seven hundred and paise nil only	Per Cubic metre	95175.00
G.Total						99225.00

Drafts Schedule of Quantity checked and approved for Rs. 99225.00. Date: 13/08/2019.

Executive Engineer,
National Highway Division,
HP.PWD, Hamirpur (HP)

Estimated Cost:- Rs. 99225.00
Earnest Money:- Rs. 2000.00
Time Limit:- One Month

Name of work :- Restoration of road damage due to laying of water pipelines along the road on NH- 70(New NH- 03). at Km 58/400 to 140/200 (SH:- Concreting along the road between Km. 139/740 to 140/00 (Deposit work)