

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-I-Tender-2025-26

4483-91

Dated:- 15/09/2025


To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Pr. Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD. (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **22.09.2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **20.09.2025 up to 4:30 PM** and the application for issue of tender form shall be received on **20.09.2025 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	Restoration of rain damages on Bagga Hawanikol road km. 0/0 to 6/0(SH:-C/o R/wall in km. 3/210 to 3/216)Under PDNA)	93,696/-	1900/-	2 Months	Rs. 350/-
2.	Restoration of rain damages on Bagga Hawanikol road km. 0/0 to 6/0(SH:-C/o R/wall in km. 34/300 to 4/306)Under PDNA)	94,490/-	1900/-	2 Months	Rs. 350/-
3.	Restoration of rain damages on Kharsi Kandhar road km. 0/0 to 14/0(SH:-C/o R/wall in km. 9/410 to 9/416)Under PDNA)	95,275/-	2000/-	2 Months	Rs. 350/-
4.	Restoration of rain damages on Kharsi Kandhar road km. 0/0 to 14/0(SH:-C/o R/wall in km. 6/230 to 6/236)Under PDNA)	95,203/-	2000/-	2 Months	Rs. 350/-
5	Restoration of rain damages on Kharsi Kandhar road km. 0/0 to 14/0(SH:-C/o R/wall in km. 4/110 to 4/116)Under PDNA)	94,986/-	1900/-	2 Months	Rs. 350/
6	Restoration of rain damages on Kharsi Kandhar road km. 0/0 to 14/0(SH:-C/o R/wall in km. 6/110 to 6/116)Under PDNA)	95,926/-	2000/-	2 Months	Rs. 350/
7	Restoration of rain damages on Kharsi	60,122/-	1300/-	1 Months	Rs. 350/

	Kandhar road km. 0/0 to 14/0(SH:-C/o R/wall in km. 5/235 to 5/240)Under PDNA)				
8	Restoration of rain damages on Samog Charmog Dochi road km. 0/0 to 4/500(SH:-C/o R/wall in km. 0/375 to 0/385)Under PDNA)	63,392/-	1300/-	1 Months	Rs. 350/
9	Restoration of rain damages on Samog Charmog Dochi road km. 0/0 to 4/500(SH:-C/o R/wall in km. 0/255 to 0/265)Under PDNA)	62,586/-	1300/-	1 Months	Rs. 350/
10	Restoration of rain damages on Bathalang Jawara Palog roa km. 0/0 to 9/0(SH:-C/o R/wall in km. 0/650 to 0/665)Under PDNA)	97,027/-	2000/-	2 Months	Rs. 350/
11	Restoration of rain damages on Shalaghat Dadhogi road km. 0/0 to 5/0(SH:-C/o R/wall in km. 2/900 to 2/915)Under PDNA)	97,155/-	2000/-	2 Months	Rs. 350/
12	Restoration of rain damages on Shalaghat Dadhogi road km. 0/0 to 5/0(SH:-C/o R/wall in km. 3/060 to 3/075)Under PDNA)	96,201/-	2000/-	2 Months	Rs. 350/
13	Restoration of rain damages on Bathalang Jawara Palog road km. 0/0 to 9/0(SH:-C/o R/wall in km. 6/015 to 6/020)Under PDNA)	97,284/-	2000/-	2 Months	Rs. 350/
14	Restoration of rain damages on Bathalang Jawara Palog road km. 0/0 to 9/0(SH:-C/o Edge wall in km. 6/290 to 6/300 & 7/765 to 7/680)Under PDNA)	92,948/-	1900/-	2 Months	Rs. 350/
15	Restoration of rain damages on Kandhar Beral road km. 0/0 to 14/0(SH:-C/o R/wall in km. 11/315 to 11/321)Under PDNA)	94,986/-	2000/-	2 Months	Rs. 350/
16	Restoration of rain damages on SAKB road km. 0/0 to 17/500(SH:-C/o PCC R/wall at RD 10/190 to 10/200)Under PDNA)	93,797/-	1900/-	1 Months	Rs. 350/
17	Restoration of rain damages on SAKB road km. 0/0 to 17/500(SH:-C/o PCC R/wall at RD 13/960 to 13/970)Under PDNA)	93,797/-	1900/-	1 Months	Rs. 350/
18	Restoration of rain damages on KBSB road km. 0/0 to 17/500(SH:-C/o PCC R/wall at RD 34/630 to 34/640)Under PDNA)	93,797/-	1900/-	1 Months	Rs. 350/
19	Restoration of rain damages on ADB road km. 0/0 to 18/0(SH:-C/o PCC B/wall at RD 3/495 to 3/505)Under PDNA)	99,473/-	2000/-	1 Month	Rs. 350/
20	Restoration of rain damages on ADB road km. 0/0 to 18/0(SH:-C/o PCC B/wall at RD 3/506 to 3/515)Under PDNA)	88,359/-	1800/-	1 Month	Rs. 350/
21	Restoration of rain damages on Buila Koel Sanog road km. 0/0 to 28/500(SH:-C/o PCC R/wall at RD 21/930 to 21/945)Under PDNA)	99,376/-	2000/-	1 Month	Rs. 350/
22	Restoration of rain damages on Buila Koel Sanog road km. 0/0 to 28/500(SH:-C/o PCC R/wall at RD 1/015 to 1/030)Under PDNA)	99,376/-	2000/-	1 Month	Rs. 350/
23	Restoration of rain damages on Samog	63,303/-	1300/-	1 Month	Rs. 350/

	Chamrog Dochi road km. 0/0 to 4/500(SH:-C/o B/wall in km. 0/690 to 0/700)Under PDNA)				
24	Restoration of rain damages on KBSB road km. 0/0 to 17/500(SH:-C/o PCC R/wall at RD 22/190 to 22/199)Under PDNA)	84,147/-	1700/-	1 Month	Rs. 350/
25	Restoration of rain damages on Bambira Kaziyara road km. 0/0 to 2/220(SH:-C/o R/wall at RD 1/090 to 1/100)Under PDNA)	66,100/-	1400/-	1 Month	Rs. 350/
26	Restoration of rain damages on Shalaghat Dadhogi road km. 0/0 to 5/0(SH:-C/o R/wall at RD 4/030 to 4/042)Under PDNA)	77,933/-	1600/-	1 Month	Rs. 350/
27	Restoration of rain damages on Dohra Danga Kothi Jamogi road km. 0/0 to 5/0(SH:-C/o B/wall at RD 2/450 to 2/465)Under PDNA)	98,971/-	1600/-	1 Month	Rs. 350/
28	Restoration of rain damages on Bathalang Bara Tamred road km. 0/0 to 3/0(SH:-C/o R/wall at RD 0/210 to 0/217)Under PDNA)	97,297/-	2000/-	1 Month	Rs. 350/
29	Restoration of rain damages on Shalaghat Arki Kunihar Barotiwala road portion km. 17/500 to 26/0 Under PDNA 2023(SH:-C/o R/wall at RD 18/450 to 18/455)Under PDNA)	98,297/-	2000/-	1 Month	Rs. 350/
30	C/o link road from Chamla Javi Tawan Syar km. 0/0 to 3/270(SH:-C/o embankment at RD 0/570 to 0/675)DMFT Deposit)	99,840/-	2000/-	1 Month	Rs. 350/

Followings documents should be attached with the application for tenders:-

- (iii) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (iv) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

No: PW-AD-EA-I-Tender-2025-26-4483-91

Copy forwarded for the following for information and necessary action to:-

5. The Superintending Engineer, 3rd Circle HPPWD Solan.
6. The all Assistant Engineer working under this division for information and necessary action.
7. All the heads of the branches in this office.
8. Notice Board.

Executive Engineer
Arki Division,
H.P.P.W.D. Arki.

Dated:- 15/09/2025

Executive Engineer
Arki Division
H.P.P.W.D. Arki.

Certificate

Certified that the tenders called vide this notice inviting tender for 30 (Thirty) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer
Arki Division
H.P.P.W.D. Arki.

SCHEDULE OF QUANTITY


Name of work: - Restoration of Rain damages on Bagga Hawanikol road km 0/000 to 6/000 (SH:- C/o R/wall in km 3/210 to 3/216)

Estimated Cost: -Rs 93,696/- only
 Earnest Money : Rs 1900/-Only
 Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	11.76	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	2016.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	19.80	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	86934.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	3.24	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	3899.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	2.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	847.00
						Total	93696.00

Quoted rate percentage in figures

Quoted rate percentage in words


Executive Engineer,
H.P. PWD (B&R)
Division Arki

SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damages on Bagga Hawanikol road km 0/000 to 6/000 (SH:- C/o R/wall in km 4/300 to 4/306)

Estimated Cost: -Rs 94,490/- only

Earnest Money : Rs 1900/-Only

Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	2	3				6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	11.34	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1944.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	19.80	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	86934.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	3.96	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	4765.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	2.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	847.00
						Total	94490.00

Quoted rate percentage in figures

Quoted rate percentage in words


Executive Engineer,
H.P. PWD (B&R)
Division Arki

Name of work: - Restoration of Rain damages on Kharsi Kandar road km 0/000 to 14/000 (SH:- C/o R/wall in km 9/410 to 9/416)

SCHEDULE OF QUANTITY

Estimated Cost: -Rs 95,275/- only


Earnest Money : Rs 2000/-Only

Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	10.92	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1872.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	19.80	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	86934.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	4.32	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	5198.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	3.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1271.00
						Total	95275.00

Quoted rate percentage in figures

Quoted rate percentage in words


Executive Engineer,
H.P. PWD (B&R)
Division Arki

SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damages on Kharsi Kandar road km 0/000 to 14/000 (SH:- C/o R/wall in km 6/230 to 6/236)

Estimated Cost: -Rs 95,203/- only


Earnest Money : Rs 2000/-Only

Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	10.50	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1800.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	19.80	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	86934.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	4.32	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	5198.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	3.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1271.00
						Total	95203.00

Quoted rate percentage in figures

Quoted rate percentage in words


Executive Engineer.
H.P. PWD (B&R)
Division Arki

SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damages on Kharsi Kandar road km 0/000 to 14/000 (SH:- C/o R/wall in km 4/110 to 4/116)

Estimated Cost: -Rs 94,986/- only

Earnest Money : Rs 1900/-Only

Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	11.76	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	2016.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	19.80	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	86934.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	3.96	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	4765.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	3.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1271.00
						Total	94986.00

Quoted rate percentage in figures

Quoted rate percentage in words


Executive Engineer,
H.P. PWD (B&R)
Division Arki

Name of work: - Restoration of Rain damages on Kharsi Kandar road km 0/000 to 14/000 (SH:- C/o R/wall in km 6/110 to 6/116)

SCHEDULE OF QUANTITY

Estimated Cost: -Rs 95,926/- only


Earnest Money : Rs 2000/-Only

Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	2	3				6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	9.66	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1656.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	19.80	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	86934.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	5.04	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	6065.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	3.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1271.00
						Total	95926.00

Quoted rate percentage in figures

Quoted rate percentage in words


Executive Engineer.
H.P. PWD (B&R)
Division Arki

Name of work: - Restoration of Rain damages on Kharsi Kandar road km 0/000 to 14/000 (SH:- C/o R/wall in km 5/235 to 5/240)

SCHEDULE OF QUANTITY

Estimated Cost: -Rs 60,122/- only
 Earnest Money : Rs 1300/-Only
 Time -One Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	6.30	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1080.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	12.35	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	54224.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	3.30	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	3971.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	2.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	847.00
						Total	60122.00

Quoted rate percentage in figures

Quoted rate percentage in words


 Executive Engineer,
 H.P. PWD (B&R)
 Division Arvi

SCHEDULE OF QUANTITY


Name of work: - Restoration of Rain damages on Samog Charmog Dochi road km 0/000 to 4/500 (SH:- C/o R/wall in km 0/375 to 0/385)

Estimated Cost: -Rs 63,392/- only
 Earnest Money : Rs 1300/-Only
 Time -One Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	8.33	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1428.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	11.85	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	52029.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	7.20	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	8664.00
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	3.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1271.00
						Total	63392.00

Quoted rate percentage in figures

Quoted rate percentage in words


 Executive Engineer,
 P.W.D (B&R)
 Division Arid

SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damages on Samog Charmog Dochi road km 0/000 to 4/500 (SH:- C/o R/wall in km 0/255 to 0/265)

Estimated Cost: -Rs 62,586/- only
 Earnest Money : Rs 1300/-Only
 Time -One Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	2	3				6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	7.84	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1344.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	11.85	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	52029.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	6.60	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	7942.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	3.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1271.00
						Total	62586.00

Quoted rate percentage in figures

Quoted rate percentage in words


Executive Engineer.
H.P. PWD (B&R)
Division And

SCHEDULE OF QUANTITY


Name of work: - Restoration of Rain damages on Bathalang Jawra Palog road km 0/000 to 9/000 (SH:- C/o R/ wall in km 0/650 to 0/665)

Estimated Cost: -Rs 97,027/- only
 Earnest Money : Rs 2000/-Only
 Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	7.50	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1286.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	19.20	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	84300.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	8.10	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	9747.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	4.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1694.00
						Total	97027.00

Quoted rate percentage in figures

Quoted rate percentage in words


Executive Engineer,
H.P. PWD (B&R)
Division Arni

SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damages on Shallaghat Dadhogi road km 0/000 to 5/000 (SH:- C/o wall in km 2/900 to 2/915) R/ Estimated Cost: -Rs 97,155/- only
 Earnest Money : Rs 2000/-Only
 Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	8.25	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1414.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	19.20	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	84300.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	8.10	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	9747.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	4.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1694.00
						Total	97155.00

Quoted rate percentage in figures

Quoted rate percentage in words

Executive Engineer,
H.P. PWD (BAR)
Division Arki

Name of work: - Restoration of Rain damages on Shallaghat Dadhogi road km 0/000 to 5/000 (SH:- C/o wall in km 3/060 to 3/075)

SCHEDULE OF QUANTITY

R/ Estimated Cost: -Rs 96,201/- only
 Earnest Money : Rs 2000/-Only
 Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	9.00	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1543.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	19.20	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	84300.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	7.20	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	8664.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	4.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1694.00
						Total	96201.00

Quoted rate percentage in figures

Quoted rate percentage in words

wd
 Executive Engineer,
 N.P. PWD (B&R)
 Division Arts

SCHEDULE OF QUANTITY


Name of work: - Restoration of Rain damages on Bathalang Jawra Palog road km 0/000 to 9/000 (SH:- C/o R/ wall in km 6/015 to 6/030)

Estimated Cost: -Rs 97,284/- only
 Earnest Money : Rs 2000/-Only
 Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	9.00	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1543.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	19.20	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	84300.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	8.10	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	9747.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	4.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1694.00
						Total	97284.00

Quoted rate percentage in figures

Quoted rate percentage in words


Executive Engineer,
H.P. PWD (B&R)
Division Arki

SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damages on Bathalang Jawa Palog road km 0/000 to 9/000 (SH:- C/o Edge wall in km 6/290 to 6/300 & 7/765 to 7/680)

Estimated Cost: -Rs 92,948/- only


Earnest Money : Rs 1900/-Only

Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	9.55	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1637.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	17.78	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	78065.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	9.60	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	11532.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	4.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1694.00
						Total	92948.00

Quoted rate percentage in figures

Quoted rate percentage in words


Executive Engineer,
H.P. PWD (B&R)
Division Arki

Name of work: - Restoration of Rain damages on Kandar Beral road km 0/000 to 14/000 (SH:- C/o R/wall in km 11/315 to 11/321)

SCHEDULE OF QUANTITY

Estimated Cost: -Rs 94,986/- only


Earnest Money : Rs 2000/-Only

Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	2	3				6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	11.76	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	2016.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	19.80	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	86934.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	3.96	Cum	1203.30	Rupees One Thousand Two Hundred Three and Paise Thirty Only	Per cubic metre	4765.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	3.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1271.00
						Total	94986.00

Quoted rate percentage in figures

Quoted rate percentage in words


Executive Engineer
Arki Division, HPPWD
Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs93797/- only	
Name of Work:-R/R Damages on SAKB Road Km 0/00 to 17/500(SH:- C/o PCC R/wall at Rd 10/190 to 10/200) (Under PDNA)					Earnest Money :-Rs1900/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
1	2	3	Figure	Words	5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	6.44	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	1104
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	19.80	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	86934
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	21.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	5759
					Total	93797

Quoted Rate in Figure

Quoted Rate in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs93797/- only	
Name of Work:-R/R Damages on SAKB Road Km 0/00 to 17/500(SH:- C/o PCC R/wall at Rd 13/960 to 13/970) (Under PDNA)					Earnest Money :-Rs1900/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	6.44	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	1104
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	19.80	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	86934
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	21.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	5759
					Total	93797

Quoted Rate in Figure

Quoted Rate in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs93797/- only	
Name of Work:-R/R Damages on KBSB Road Km 11/00 to 39/00 (SH:- C/o PCC R/wall at Rd 34/630 to 34/640) (Under PDNA)						Earnest Money :-Rs1900/-only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount	
1	2		Figure	Words	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	6.44	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	1104	
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	19.80	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	86934	
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	21.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	5759	
					Total	93797	

Quoted Rate in Figure

Quoted Rate in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY				Estimated Cost: -Rs99473/- only		
Name of Work:-R/R Damages on ADB Road Km 0/00 to 18/00(SH:- C/o PCC B/wall at Rd 3/495 to 3/505) (Under PDNA)				Earnest Money :-Rs2000/-Only		
				Time :-One Month		
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	19.89	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	3409
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	20.88	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	91676
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	16.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	4388
					Total	99473

Quoted Rate in Figure

Quoted Rate in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs88359/- only	
Name of Work:-R/R Damages on ADB Road Km 0/00 to 18/00(SH:- C/o PCC B/wall at Rd 3/506 to 3/515) (Under PDNA)					Earnest Money :-Rs1800/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	17.68	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	3030
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	18.56	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	81490
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	14.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	3840
					Total	88359

Quoted Rate in Figure

Quoted Rate in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY				Estimated Cost. -Rs99376/- only		
Name of Work:-R/R-Damages on Buila Koel Sanog Road Km 0/00 to 28/500 (SH:- C/o PCC R/wall at Rd 21/930 to 21/945) (Under PDNA)				Earnest Money :-Rs2000/-Only		
				Time :-One Month		
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	6.90	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	1183
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	21.24	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	93256
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	18.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	4937
					Total	99376

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words



Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs99376/- only
Name of Work:-R/R Damages on Buila Koel Sanog Road Km 0/00 to 28/500 (SH:- C/o PCC R/wall at Rd 1/015 to 1/030) (Under PDNA)						Earnest Money :-Rs2000/-Only
						Time :-One Month
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	6.90	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	1183
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	21.24	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	93256
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	18.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	4937
					Total	99376

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damages on Samog Charmog Dochi road km 0/000 to 4/500 (SH:- C/o B/wall in km 0/690 to 0/700)

Estimated Cost: -Rs 63,303/- only


Earnest Money : Rs 1300/-Only

Time -One Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	2	3				6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	9.18	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1573.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	13.77	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	60459.00
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	3.00	Nos	423.60	Rupees Four Hundred Twenty Three and Paise Sixty Only	Each	1271.00
						Total	63303.00

Quoted rate percentage in figures

Quoted rate percentage in words


 Executive Engineer,
 H.P. PWD (B&R)
 Division Arvi

SCHEDULE OF QUANTITY					Estimated Cost: -Rs84147/- only	
Name of Work:-R/R Damages on KBSB Road Km 11/00 to 39/00 (SH:- C/o PCC R/wall at Rd 22/190 to 22/199) (Under PDNA)					Earnest Money :-Rs1700/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	5.85	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	1003
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	18.00	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	79031
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	15.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	4114
					Total	84147

Quoted Rate in Figure

Quoted Rate in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of work:-R/R damage on Bambira kaziara road km 0/00 to 2/230(SH:-C/O R/wall at RD 1/090 to 1/100)					Estimated Cost:-Rs.66100/-only		
					Earnest Money:-Rs.1400/-only		
					Time - one Month		
S.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	8.50	Cum			Per cubic metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 & 1203 including carriage of materials upto all leads and lifts.(i) 1:5:10 (40mm).	12.80	Cum			Per cubic metre	
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204 3 8 including carriage of materials in all leads and lifts	4.20	Cum			Per cubic metre	
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	8.00	Nos			Per Each	
						Total	66100.00

Quoted rate percentage in figures

Quoted rate percentage in words


Executive Engineer
H.P. PWD (B&R)
Division And

SCHEDULE OF QUANTITY

Name of work:-R/R damage on Shalaghat- Dadhogi road km 0/00 to 5/00)(SH:-C/O R/wall at RD 4/030 to 4/042)						Estimated Cost:-Rs.77933/-only	
						Earnest Money:-Rs.1600/-only	
						Time - one Month	
S.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	10.00	Cum			Per cubic metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 & 1203 including carriage of materials upto all leads and lifts.(i) 1:5:10 (40mm).	14.22	Cum			Per cubic metre	
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	8.64	Cum			Per cubic metre	
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	8.00	Nos			Per Each	
						Total	77933.00

Quoted rate percentage in figures

Quoted rate percentage in words



Executive Engineer
H.P. PWD (R&R)
Division A-1

SCHEDULE OF QUANTITY

Name of work:-R/R damage on Dohra-Danga-kothi-Jamogi Chaiyan road km 0/00 to 5/00)(SH:-C/O B/wall at RD 2/450 to 2/465)						Estimated Cost:-Rs.98971/-only	
						Earnest Money:- Rs.2000/-only	
						Time - one Month	
S.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	13.00	Cum			Per cubic metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 & 1203 including carriage of materials upto all leads and lifts.(i) 1:5:10 (40mm).	20.78	Cum			Per cubic metre	
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	8.00	Nos			Per Each	
						Total	98971.00

Quoted rate percentage in figures

Quoted rate percentage in words


 Executive Engineer
 H.P. PWD (B&R)
 District Office

SCHEDULE OF QUANTITY

Name of work:- R/R damage on Bathalang- Bara-Tamred road km 0/00 to 3/00)(SH:-C/O R/wall at RD 0/210 to 0/217)

Estimated Cost:-Rs.97297/-only

Earnest Money:-Rs.2000/-only

Time - one Month

S. No	Sub head and items of work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	2	3				6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	5.67	Cum			Per cubic metre	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803, 1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	20.48	Cum			Per cubic metre	
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204 3.8 including carriage of materials in all leads and lifts.	4.62	Cum			Per cubic metre	
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	2.00	Nos			Per Each	
						Total	97297.00
	Quoted rate percentage in figures						
	Quoted rate percentage in words						


Executive Engineer,
H.P. PWD (B&R)
Division Ardi

DRAFT SCHEDULE OF QUANTITY

Name of work :-R/R damages on Shalaghat Arki Kunihar Barotiwala Road portion Km 17/500 to 26/000 UNDER PDNA (SH:-C/O R/wall at RD18/450 to 18/455)

Estimated Cost :- Rs 98,297.00

Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	2	3		4	5	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	13.55	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	2322.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	19.94	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	87549.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	8.26	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	2265.00
4.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	5.12	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	6161.00
						Total	98297.00

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words



 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of work: -Construction of link road from Chamla javi Tawan Syar km 0/00 to 3/270)(SH:-C/O embankment at RD 0/570 to 0/675)(DMFT Deposit)		Estimated Cost:-Rs.99840/-only					
		Earnest Money:- Rs2000/-only					
		Time - one Month					
S. No.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Construction of embankment with approved material obtained from borrow pites with a lift upto 1.5m, transporting to site, spreading,grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000m as per Technical Specification Clause 301.5	512.00	Cum			Per Cubic metre	
						Total	99840.00

Quoted rate percentage in figures

Quoted rate percentage in words


Assistant Engineer
Art & Design, KPPWB
Art