

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
No.PW-AD-EA-I-Tender-2025-26 4425-32

Dated:- 11/09/2025


To

The Executive Engineer (IT Cell)  
H.P.P.W.D. Nigam Vihar Shimla-2.

**Subject:- Notice Inviting Tender for uploading the same on departmental website.**


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Pr. Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A(3)1/2024 dated shimla-2 the 03.01.2024 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT

  
Executive Engineer,  
Arki Division  
H.P.P.W.D. Arki.  
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.

  
Executive Engineer,  
Arki Division  
H.P.P.W.D. Arki.  
Ph. 01796-220714

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER**

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.P.W.D. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **18.09.2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **17.09.2025 up to 4:30 PM** and the application for issue of tender form shall be received on **17.09.2025 up to 5:00 PM.**


The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please note no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	Restoration of Rain damages on various roads under Arki Sub-Division Arki Section (SH:- Hiring of JCB for Removal of slips, dressing of roads, cleaning of drains etc.) (Job No.II)	Rs. 99,000/-	Rs. 2,000/-	One Month	Rs. 350/-
2	Restoration of Rain damages on various roads under Arki Sub-Division Piplughat Section (SH:- Hiring of JCB for Removal of slips, dressing of roads, cleaning of drains etc.) (Job No.III)	Rs. 99,000/-	Rs. 2,000/-	One Month	Rs. 350/-
3	Restoration of Rain damages on various roads under Kunihar Sub-Division Mann Section (SH:- Hiring of JCB for Removal of slips, dressing of roads, cleaning of	Rs. 99,000/-	Rs. 2,000/-	One Month	Rs. 350/-

13	Restoration of rain damages on Darla Kanswala Parnoo Bugarh road in km. 0/0 to 12/500 C/o RCC hume pipe culvert 900mm dia at RD 0/090)SH:-C/o both side wing wall)	Rs. 89,487/-	Rs. 1800/-	One Month	Rs. 350/-
----	--	--------------	------------	-----------	-----------

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


  
Executive Engineer  
Arki Division,  
H.P.P.W.D. Arki.

**Dated:-**

**No: PW-AD-EA-I-Tender-2025-26-**


Copy forwarded for the following for information and necessary action to:-

1. The Superintending Engineer 3<sup>rd</sup> Circle HPPWD Solan.
2. The all Assistant Engineer working under this division for information and necessary action.
3. All the heads of the branches in this office.
4. Notice Board.

  
Executive Engineer  
Arki Division  
H.P.P.W.D.Arki.

**Certificate**

Certified that the tenders called vide this notice inviting tender for 13 ( Thirteen) jobs are due to exigencies/emergency of works in the larger public interest.

  
Executive Engineer  
Arki Division  
H.P.P.W.D. Arki.

**SCHEDULE OF QUANTITY**

Name of Work - Restoration of rain damages on various roads under Arki Sub Division Arki Section (SH:- Hiring of JCB for removal of slips, dressing of roads, cleaning of drains etc.) ( Job No- II)						Estimated Cost: -Rs 99,000/- only	
						Earnest Money : Rs 2000 /-Only	
						Time -One Months	
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						<b>Total:-</b>	<b>99000.00</b>

Quoted rate percentage in figures

Quoted rate percentage in words

  
**Executive Engineer**  
**H.P. PWD (Roads)**  
**Arki Division Arki**

### SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Arki Sub Division Piplughat Section (SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- III)					Estimated Cost: -Rs 99,000/- only		
					Earnest Money : Rs 2000 /-Only		
					Time -One Months		
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
				In figure	In words		
1	2	3					
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						<b>Total:-</b>	<b>99000.00</b>

Quoted rate percentage in figures

Quoted rate percentage in words

  
 Executive Engineer,  
 H.P. PWD (S&R),  
 Division Arki

**SCHEDULE OF QUANTITY**

Name of Work:- Restoration of rain damages on various roads under Kunihar Sub Division Mann Section SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- III)						Estimated Cost: -Rs 99,000/- only	
						Earnest Money : Rs 2000 /-only	
						Time -One Months	
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						<b>Total:-</b>	<b>99000.00</b>

Quoted rate percentage in figures  
 Quoted rate percentage in words

  
 Executive Engineer  
 H.O. PWD (B&R)  
 Division Arki

**SCHEDULE OF QUANTITY**

Name of Work:- Restoration of rain damages on various roads under Darla Sub Division Nalgaoon Section SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- III)					Estimated Cost: -Rs 99,000/- only		
					Earnest Money : Rs 2000 /-Only		
					Time -One Months		
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						<b>Total:-</b>	<b>99000.00</b>

Quoted rate percentage in figures

Quoted rate percentage in words

  
 Executive Engineer,  
 H.P. PWD (B&R) -  
 Division Arki

**SCHEDULE OF QUANTITY**

Name of Work:- Restoration of rain damages on various roads under Darla Sub Division Shallaghat Section						Estimated Cost: -Rs 99,000/- only	
SH:- Hiring of JCB for removal of slips, dressing of roads, cleaning of drains etc.) ( Job No- III)						Earnest Money : Rs 2000 /-Only	
						Time -One Months	
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						<b>Total:-</b>	<b>99000.00</b>

Quoted rate percentage in figures

Quoted rate percentage in words

  
 Executive Engineer,  
 H.P. PWD (B&R)  
 Jaisan Ardi

**SCHEDULE OF QUANTITY**

Name of Work:- Restoration of rain damages on various roads under Darla Sub Division Mangal Section SH:- Hiring of JCB for removal of slips , dressing of roads, cleaning of drains etc.) ( Job No- III)					Estimated Cost: -Rs 99,000/- only		
					Earnest Money : Rs 2000 /-Only		
					Time -One Months		
S.No.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Hiring of JCB removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in all lead and lifts as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	99.00	Hours	1000.00	Rupees One Thousand Only	Per hour	99000.00
						<b>Total:-</b>	<b>99000.00</b>

Quoted rate percentage in figures  
Quoted rate percentage in words

  
 Executive Engineer  
 H.P. PWD (S&R)  
 Malan Arki

**DRAFT SCHEDULE OF QUANTITY**

**Name of work:** -Special Repair of Govt. High School building Sehrol Tehsil-Arki Distt- Solan (SH:- Demolision of RCC work, C/o stair case and P/L tiles)

Estimated Cost: -Rs 97,523/- only

Earnest Money : Rs 2000 /-Only

Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	0.80	Cum	1465.35	Rupees One Thousand Four Hundred Sixty Five and Paise Thirty Five Only	Per cubic metre	1172.00
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed by the Engineer-In- Charge at site, according to the H.P.P.W.D. specification including all incidental charges. i/c all leads , lifts & carriage of material.	2.05	Cum.	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	351.00
3	Providing Centering and Shuttering including strutting ,propping etc. and removal of form for floor to ceiling up to all heights and removal of the same:complete as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge. In foundation, footings, bases of columns etc. and mass concrete.						
3.10	In stair,(excluding landings) except spiral staircase.	7.32	Sqm	444.40	Rupees Four Hundred Forty Four and Paise Forty Only	Per squarw metre.	3253.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803, 1202 & 1203 c.c. 1:4:8 ( 1cement :4 sand: 8graded stone aggregate) 40mm nominal size including carriage of materials upto all leads and lifts.	0.73	Cum	4955.20	Rupees Four Thousand Nine Hundred Fifty Five and Paise Twenty Only	Per cubic metre	3617.00
5	Reinforced cement concrete work in beams , suspended floors , roofs having slope up to 15 landdings, balconies, shelves,chajjas , lintels,bands, plain wi ndow sillls, staircases and spiral stair cases above plinth level up to floor five level excluding the cost of centering, shuttering , finishing and reinforcement with 1:1:5:3 (1 cement : 21.5 coarse sand ) :3 grtaded stone aggregate 20mm Nominal size Including carriage of material within all leads and lifts and as per direction of Engineer-in- Charge.	2.65	Cum	7835.75	Rupees seven thousand eight hundred thirty five and paise seventy five only	Per cubic metre.	20765.00

6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Mild steel including carriage of material with in all leads and lifts and as per the direction of Engineer-in-Charge	357.75	Kg	93.80	Rupees Ninety Three and Paise Eighty Only	Per kilogramme	33557.00
7	Providing and laying vetrified floor tiles of size 60x60 CM (Sixty into sixty centimeter) (thickness to be specified by the manufacturer) with water absorption less than 0.08% and confirming to IS : 15622, of approved make, in all colours and shades, laid on 20 mm thick (twenty milimeter) cement mortar 1:4 (one cement is to four sand) jointed with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc. complete and as per HP. PWD. specifications of 1990 volume-I including carriage of matenals, labour, tool and plant through all modes of transportion within all leads and lifts and as per direction of Engineer-in-Charge.	25.31	Sqm	1375.25	Rupees One Thousand Three Hundred Seventy Five and Paise Twenty Five Only	Per Square metre	34808.00
						<b>Total</b>	<b>97523.00</b>

Quoted rate percentage in figures

Quoted rate percentage in words

-Sd-

Executive Engineer  
Arki Division,  
HPPWD, Arki

**SCHEDULE OF QUANTITY**

Name of work:-Restoration of Rain Damages on various roads under Daria Sub Division Mangal Section (SH- Hiring of Tipper for carriage of slips/ debris) ( Job No - II )

Estimated Cost -Rs 97,500/- only


Earnest Money - Rs 2000 /-Only

Time -One Month

S.No	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Hiring of tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6 (six) hours per day. The contractor / owner of the tipper shall bear the expension of P.O.L. charges, repair of machineries. Any accident and other damages to be the private and govt property occur during the working hours is the responsibility of the contractor and debris disposed within all leads and lifts as per the direction of Engineer-In- Charge	150.00	Hour	650.00	Rupees Six Hundred Fifty Only	Per hour	97500.00
						<b>Total:-</b>	<b>97500</b>

Quoted rate percentage in figures

Quoted rate percentage in words

  
 Executive Engineer  
 PWD (B&R)  
 Division Addl

**SCHEDULE OF QUANTITY**

Name of work:-Restoration of Rain Damages on various roads under Darla Sub Division Navgaon Section (SH:- Hiring of Tipper for carriage of slips/ debris) ( Job No - II )					Estimated Cost: -Rs 97,500/- only		
					Earnest Money :- Rs 2000 /-Only		
					Time -One Month		
S.No	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Hiring of tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6 (six) hours per day. The contractor / owner of the tipper shall bear the expension of P.O.L. charges, repair of machineries. Any accident and other damages to be the private and govt property occur during the working hours is the responsibility of the contractor and debris disposed within all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees Six Hundred Fifty Only	Per hour.	97500.00
						<b>Total:-</b>	<b>97500</b>

Quoted rate percentage in figures

Quoted rate percentage in words

  
 Executive Engineer  
 N.P. PWD (BAR)  
 Division Arki

**SCHEDULE OF QUANTITY**

Name of work:-Restoration of Rain Damages on various roads under Darla Sub Division Shallaghat Section (SH:-  
Hiring of Tipper for carriage of slips/ debris) ( Job No - II )

Estimated Cost: -Rs 97,500/- only  
Earnest Money :- Rs 2000 /-Only  
Time -One Month

S.No	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Hiring of tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6 (six) hours per day. The contractor / owner of the tipper shall bear the expension of P.O.L. charges, repair of machineries. Any accident and other damages to be the private and govt property occur during the working hours is the responsibility of the contractor and debris disposed within all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees Six Hundred Fifty Only	Per hour.	97500.00
						<b>Total:-</b>	<b>97500</b>

Quoted rate percentage in figures

Quoted rate percentage in words

  
**Executive Engineer**  
 P.W.D (S&S)  
 Division Arunachal Pradesh

**SCHEDULE OF QUANTITY**

Name of work:-Restoration of Rain Damages on various roads under Arki Sub Division Piplughat Section (SH:- Hiring of Tipper for carriage of slips/ debris) ( Job No - II )

Estimated Cost: -Rs 97,500/- only

Earnest Money :- Rs 2000 /-Only

Time -One Month

S.No	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		In figure	In words		
1	Hiring of tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6 (six) hours per day. The contractor / owner of the tipper shall bear the expension of P.O.L. charges, repair of machineries. Any accident and other damages to be the private and govt property occur during the working hours is the responsibility of the contractor and debris disposed within all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees Six Hundred Fifty Only	Per hour.	97500.00
						<b>Total:-</b>	<b>97500</b>

Quoted rate percentage in figures

Quoted rate percentage in words

  
 Executive Engineer  
 H.P. PWD (B&R)  
 Division Arki

**SCHEDULE OF QUANTITY**

Name of work:-Restoration of Rain Damages on various roads under arki Sub Division Bhumti Section (SH:- Hiring of Tipper for carriage of slips/ debris) ( Job No - 1 )

Estimated Cost: -Rs 97,500/- only

Earnest Money :- Rs 2000 /-Only

Time -One Month

S.No	Sub head and items of work	Qty.		Rate		Unit	Amount
		3		in figure	In words	6	7
1	Hiring of tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6 (six) hours per day. The contractor / owner of the tipper shall bear the expension of P.O.L. charges, repair of machineries. Any accident and other damages to be the private and govt property occur during the working hours is the responsibility of the contractor and debris disposed within all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees Six Hundred Fifty Only	Per hour.	97500.00
						<b>Total:-</b>	<b>97500</b>

Quoted rate percentage in figures

Quoted rate percentage in words

  
 Executive Engineer,  
 P.W.D (R.R.)  
 Division Adm.

SCHEDULE OF QUANTITY						
Name of work: - Restoration of Rain damages on Darla Kanswala Parnoo Bugarh road in km 0/000 to 12/500 C/o RCC hume pipe culvert 900mm dia at RD 0/090( SH:- C/o both side wing wall)					Estimated Cost: -Rs 89,487/- only	
					Earnest Money: Rs 1800 /-Only	
					Time -One Months	
S.N	Sub head and items of work	Qty.	Rate		Unit	Amount
o.			In figure	In words		
1	2	3			6	7
	Excavating and construction of shoring and bracing, removal of materials and disposal upto all leads and lifts dressing of top and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge				Per cubic metre	1739.00
	Complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10( 40mm)	18.42	Cum	4390.60	Per cubic metre	80875.00
3	Backfilling behind abutment wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads and lifts.	3.60	Cum	1203.30	Per cubic metre	4332.00
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads and lifts.	6.00	Nos	423.60	Each	2542.00
					<b>Total</b>	<b>89487.00</b>

Quoted rate percentage in figures  
 Quoted rate percentage in words

*Wol*  
 Executive Engineer  
 Arts Division, M.P.W.D.,  
 1998