



Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in

NO: PWD/BN/TA/NIT/2025-26/-
To

9255-60 Dated:-25.09.2025

✓
The Executive Engineer, (IT Cell),
Nirman Bhawan Nigam Vihar,
Shimla-2.

Subject:- Publication of Tender Notice on the Departmental website.

Dear Sir,

Enclosed herewith is the Tender Notice for the work specified in the Notice Inviting tender (NIT). You are kindly requested to upload the same on the official website of the department in accordance with Notification No.PBW(B)A(3)1/2024 dated 03.01.2024, issued by the Secretary (PW) to the Government of Himachal Pradesh.

The works mentioned in the Notice Inviting Tender are urgent/emergent nature of works as per guidelines for implementation decentralized planning programmes (SDP, VMJS, VKVNY and MMGSY) issued vide Engineer-in-Chief HP.PWD, Shimla letter No.PW/CTR/32-20/Gen.Inst/2025-8165-8260 dated 27.08.2025 and as well in public interest. Kindly ensure the prompt publication of the same on the website.

Encl: Notice Inviting Tender
& Schedule of Quantity.

Yours faithfully,

Executive Engineer
Baijnath Division
H.P.P.W.D. Baijnath

Copy forwarded for information to:-

1. The Superintending Engineer, JNR. Circle HPPWD, Joginder Nagar.
2. All the Assistant Engineers working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer
Baijnath Division
H.P.P.W.D. Baijnath



**Office of
Executive Engineer Baijnath Division HP.PWD, Baijnath
Himachal Pradesh Public works Department Baijnath-176125
Phone No. 01894-263035 Fax 262704 e-mail:-ee-baij-hp@nic.in**

“NOTICE INVITING TENDER”

Sealed percentage rate on tender form No. 6 & 8 are hereby invited by the Executive Engineer, Baijnath Division H.P.PWD., Baijnath on behalf of the Governor of HP for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rule and also registered under the HP General Sales Tax act 1968 so as to reach in this office on or before **09.10.2025** up to **11.30 A.M** and will be opened on the same day at **12.00 Noon** in the presence of intending contractors or their authorized representatives. The tender forms can be had from his office against cash payment (Non refundable) on **08.10.2025 between 2.00 PM up to 4.30 P.M** and the application for issue of tender forms shall be received on **06.10.2025 up to 12.00 Noon**.

The earnest money in the shape of National Saving Certificate/Time Deposit accounts/Saving Accounts in any Post Office/Bank in H.P. duly pledged in favour of the XEN H.P.PWD., Baijnath must be accompanied with the each tender. Conditional/incomplete tenders and the tenders received without earnest money as mentioned above will be similarly rejected, the offer of the tender shall be kept open for 75 days. The XEN reserves the right to accept or reject any or all tenders or to drop the proposal of the tender without assigning any reasons.

Sr. No.	Name of Works	Amount put to tender/Estimated cost.	Earnest Money	Cost of tender form	Time limit
1	C/O OBC Bhawan at Ghirtholi (2nd Part) Balance work (SH: Civil Work) (Deposit Work) VKV/2024/1189	2,31,048/-	4700/-	Rs.350/-	Two Months
2	C/O Mahila Mandal Bhawan at Gawal (First Floor) (SH: C/O Civil work) (Deposit work VKV/2024/1188)	2,91,075/-	5900/-	Rs.350/-	Two Months
3	C/O Mahila Mandal Bhawan Janehad (SH: P/F Door Shutter, Grill work, Plastering and Flooring work etc.) (Deposit work SDP/2021/1145, VKV/2024/49)	1,21,827/-	2500/-	Rs.350/-	Two Months
4	C/O Road from Chaniyara to House of Hoshiar Singh Mehta at Chobin (SH: P/L interlocking paver block 60 mm concrete block in RD 0/136.30 to 0/183.56) (Deposit work VKV/2024/1175)	1,93,167/-	3900/-	Rs.350/-	Two Months
5	C/O Building work 2 rooms in GSSS Jandpur (SH: Civil work) (Deposit work SDP/2023/1141)	1,96,701/-	4000/-	Rs.350/-	Two Months
6	C/O Bridge at village Hartada (SH: Super structure) (Deposit work SDP/2023/379, SDP/2021/1137)	1,95,220/-	4000/-	Rs.350/-	One Month
7	C/O Gaziabad to Kholi km 0/00 to 0/520 (SH: C/O R/wall at RD 0/195 to 0/201.50 & P/L C.C. pavement at RD 0/055 to 0/096.50) Deposit work VKV/2025/372	1,95,583/-	4000/-	Rs.350/-	One Month
8	C/O Jeepable Road From Sen. Sec. School Averi to Gangoh-Ward No.3 P.O. Jandpur) (SH: Construction of 1.00 Mtr. Span culvert at RD 0/017 & P/L C.C. Pavement at RD 0/00 to 0/015 (Deposit work SDP/2024/833	1,96,818/-	4000/-	Rs.350/-	Two Months
9	C/O Pucca Path from Joginder Kumar House to Darku Nallan Nohra road (SH: P/L G-II and C.C. Pavement at Km 0/060 to 0/170 & C/O Edge wall at Km 0/060 to 0/116) Deposit work (VKVNY/2023/1185)	1,48,087/-	3000/-	Rs.350/-	Two Months

- The contractor should be registered as dealer under H.P. GST Tax Act. 2018 and also produce the Tin number, H.P. sales Tax clearance certificate from the Excise and Taxation Department.
- The contractor will have to produce the attested copy of his/their enlistment/renewal at the time of submitting application for issue of tender form failing which their application will not be entertained.
- In case of holiday on the day of opening of tenders, the same will be opened on the next working day on the same time and venue.
- Only two tenders form will be issued to the contractor/firm which may be noted.
- Tender not received on prescribed form and manner shall not be considered and will be liable for rejection straightway.
- The contractor shall be responsible for rectifying defects noticed within One year from the date of completion of the work and the portion of security deposit relating to as phallic Work shall be refunded after the expiry of this period.
- The contractor shall have all required machinery such as Truck/Tipper, Mixture, water tanker Vibrator etc or should submit the undertaking/affidavit regarding providing to him such machinery of owner's having such machinery.
- The Contractor shall not have more than Two works in hand and in this regard along with application shall submit an under taking viz he will get complete the works in hand before award of work with in schedule time.
- All kind of material shall be arranged by the contractor by itself from the authorized firms/dealers as per clause No-10A.
- The Cement shall be procured by the contractor at his own from the nearby godowns of Civil Supply against the approved/ permit.

**Executive Engineer
Baijnath Division
HP.PWD, Baijnath.
For & On behalf of the Govt. of H.P.**

SCHEDULE OF QUANTITY

Name of work :- C/O OBC Bawran at Ghirtholi (2nd Part) Balance work
 (SH:- Civil work) (Deposit work) VKV/2024/1189

Estimate Cost: 2,31,048.00
 Earnest Money: 4,700.00
 Time Limit: Two Months

Sr.n	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing for steel reinforcement for reinforced cement concrete work including bending, binding and placing in position complete in all respects as per drawing and design in all floor levels including the cost of binding wire as per PWD specification and approved design. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	773.25	Per kilo gram	96.00	Rupess Ninety Six Only	74232.00
2	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	2.43	Per cubic metre	7,500.00	Rupess Seven Thousand Five Hundred Only	18,225.00
3	Providing and laying of Kota stone slab flooring 20mm (average) thick base of cement mortar 1:4 laid over slury mixed with pigment match the shade of slab 20 mm. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	95.58	Per square metre	1450.00	Rupess One Thousand Four Hundred & Fifty Only	1,38,591.00
Quated rates Percentage in figures						2,31,048.00
Quated rates Percentage in words						

Executive Engineer
 Baijnath Division
 HPP WD Baijnath

SCHEDULE OF QUANTITY

Name of work :- C/O Mahila Mandal Bhawan at Gawal (First floor)
(sh:- C/O Civil work) (Deposit work VKV/2024/1188)

Estimate Cost: 2,91,075.00
Earnest Money: 5,900.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing form work with steel plates 3.15mm thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centring, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: Sides and soffits of beams, beam haunchings, cantilevers, bressumers and lintels not exceeding 1 Mtr. in depth in all heights from floor. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	16.44	Per Square metre	375.00	Ruppes Three Hundred & Seventy Five Only	6,165.00
2	Providing form work with steel plates 3.15mm (three point fifteen) thick welded with angle iron in frame 30x30x5mm (thirty inii thirty into five) . so as to give a fair finish including centring, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 (four) Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in Square, rectangular or polygonal in plan column pillar posts and sturts. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	31.32	Sqm	475.00	Ruppes Four Hundred & Seventy Five Only	14,877.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering in column pillar posts and sturts level :1:2:4 (One Cement : Two coarse sand) : Four graded stone aggregate 20 mm (twenty millimeter) nominal size. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	2.11	Per cubic metre	6,950.00	Ruppes Six Thousand Nine Hundred & Fifty Only	14,665.00
4	Providing and laying mechanically mixed and vibrated reinforced cement concrete work, grade M-20 design mix to obtain the minimum compressive strength of M-20 N/mm2 with cement contents not less than of 320kg/m3 (three hundred twenty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in floor all level and curing complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	0.38	Per cubic metre	7000.00	Ruppes Seven Thousand Only	2,660.00
5	Providing and laying mechanically mixed and vibrated reinforced cement concrete work, grade M-20 design mix to obtain the minimum compressive strength of M-20 N/mm2 with cement contents not less than of 320kg/m3 (three hundred twenty kilogramme per cubic metre) excluding cost of form work and reinforcement for reinforced concrete work in stair cases (except spiral stair cases) excluding landing but including preparing of top surface and finishing of nosing upto all floor level and curing complete including carriage of material within all leads, lifts and other incidental charges complete in all respect as per direction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.32	Per cubic metre	7100.00	Ruppes Seven Thousand One Hundred Only	9,372.00

② (a)

26

6	Providing mild steel/Tor steel reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor two level Tor Steel The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	544.80	KG	95.00	Rupees Ninety Five Only	51,756.00
7	Providing and fixing 0.60mm (zero point sixty millimeter) thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating i/c fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (six millimeter) dia metre with pre-painted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	20.65	Sqm	1600.00	Rupees One Thousand Six Hundred Only	33,040.00
8	Providing and fixing pre-painted sheet ridge or hips 60cm (sixty centimetre) over all of Kotar metal skin trapezoidal profiled sheeting 0.60mm (zero point sixty centimetre) cover with over all width 1126mm (one thousand one hundred twenty six) 28mm (twenty eight) crest depth at 353mm, (three hundred fifty three) 2mm (two millimetre) C/C crest distance. There will be two ribs at the centre for stiffening heaving crest depth of 2.50mm (two point five millimetre) the main crest with at top zinc waiting top coat with regular modified polyester coating of approved shade and balancing reverse coat 5.5mm (five decimal five millimetre) dia and 55mm (fifty five millimetre) length with EPDM seal complete in all respect as per approved drawing design and in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	24.50	Per running metre	900.00	Rupees Nine Hundred Only	22,050.00
9	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1252.20	Per Kilogram	109.00	Rupees One Hundred & Nine Only	1,36,490.00
Quated rates Percentage in figures						
Quated rates Percentage in words						2,91,075.00

Executive Engineer
Bainnath Division
HPPW/D Bainnath

SCHEDULE OF QUANTITY

Name of work :- C/O Mathia Mandal Bhawan Janchad.
 (Sh:- P/E Door Shutter, Grill work, Plastering and Flooring work etc) (Deposit work SDP/2021/1145, VKV/2024/49)

Sr.n	Description of work	No. or Qty.	Unit	Estimate Cost: 1,21,827.00		AMOUNT Rs. P
				Figures	Rate	
1	Providing and fixing 12mm (Twelve millimeter) Thick Premeinated board in matt finished ISI marked NO 12823 as per approved shade of vitronica / ket ply / nona pan / green ply both side BWP phenol bonded exterior / interior grade panelled shutter with frame of first class Dender wood including bright finished black enamaled butt hinges with necessary screws 40 mm (Forty millimeter) thick shutter as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-in-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	2.76	Per square metre	2,657.80	Rupess Two/Thousand Six Hundred & Fifty Seven - Paise Eighty Only	7,336.00
2	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings / wooden frames with rawl plugs screws etc. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	89.04	Kg	120.10	Rupess One Hundred & Twenty - Paise Ten Only	10,694.00
3	15 mm (fifteen) cement plaster in single coat on rough side of brick/stone masonry for interior plastering upto floor two level with Cm 1:6 as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	56.27	Sqm	375.00	Rupess Three Hundred & Seventy Five Only	21,101.00
4	15 mm (fifteen) cement plaster in single coat on fair side of brick/ stone masonry for outer plastering upto floor two level with Cm 1:6 as per entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	74.09	Sqm	320.00	Rupess Three Hundred & Twenty Only	23,709.00
5	6mm (six millimeter) cement plaster 1:3 (One : Three) in ceiling as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	49.17	Sqm	275.00	Rupess Two Hundred & Seventy Five Only	13,522.00
6	Providing and fixing 10mm(ten millimeter) thick anti skid water proof paint and impact resistant heavy duty varnished tiles Nisco or equivalent 60x60mmx10mm (Six hundred into six hundred into ten millimeter) manufactured of approved shade and colour in flooring, reads of steps and landings laid over 12mm thick cement mortar 1:3 (one cement into three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	34.99	Per square metre	1268.10	Rupess One Thousand Two Hundred & Sixty Eight - Paise Ten Only	44371.00
7	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete 250x16 mm (two fifty into sixteen millimetre) "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.00	Each	214.20	Rupess Two Hundred & Fourteen - Paise Twenty Only	214.00
8	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete 250x10 mm (two hundred fifty into ten millimetre) "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	4.00	Each	125.00	Rupess One Hundred & Twenty Five Only	500.00
9	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete 150 mm (One twenty five millimetre) "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	4.00	Each	95.00	Rupess Ninety Five Only	380.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						1,21,827.00


 Executive Engineer
 Bajinath Division
 HPPWD Bajinath

SCHEDULE OF QUANTITY

Name of work: C/O Road from Chanayara to House of Hoshnar Singh Mehta at chobin
 (SH:- P/L interlocking paver block 60 mm concrete block in RD 0/136.30 to 0/183.56)
 (Deposit Work VKV/2024/1175)

Estimate Cost: 1,93,167.00/-
 Earnest Money: 3,900.00/-
 Time Limit : Two months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803,1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals . "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	0.66	Per Cubic metre	6,950.00	Rupees Six Thousand Nine Hundred & Fifty Only	4,587.00
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawing and Technical Specification Clause 1504 entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. The rate shall include all lead, lift and proper stacking complete in all respect as per the direction of the Engineer-in-charge. 60 mm "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	134.70	Per Square metre	1400.00	Rupees One Thousand Four Hundred Only	188580.00
Quoted rates Percentage in figures						1,93,167.00
Quoted rates Percentage in words						


 Executive Engineer
 Bajinath Division
 HPPWD Bajinath

④

SCHEDULE OF QUANTITY

Name of work :- C/O Building work 2 rooms in GSSS Jandpur
(Sh-- Civil Work) (Deposit work SDP/2023/1141)

Estimate Cost: 1,96,701.00
Earnest Money: 4,000.00
Time Limit : Two Months

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing form work with steel plates 3.15mm thick welded with angle iron in frame 30x30x5mm. so as to give a fair finish including centring, shuttering, strutting and propping etc. with wooden battens and ballies, height of propping and centring below supporting floor to ceiling not exceeding 4 Mtrs. and removal of the same for insitu-reinforced concrete & plain concrete work in: Sides and soffits of beams, beam haunchings, cantilevers, breasters and lintels not exceeding 1 Mtr. in depth in all heights from floor. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	34.60	SQM	295.00	Rupees Two Hundred & Ninety Five Only	10,207.00
2	Providing and fixing angle iron door, window, clerestory window frame manufactured from M.S. Angle iron section of 50*50*6mm, thickness including hinges jamb, look jamb, beed and if required angle threshold old mild steel angle 50*25 mm welded or rigidly fixed by mechanical means and applying a coat of approved steel primer after pretreatment of the surface as directed by Engineer-in-charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	63.80	RMT	400.00	Rupees Four Hundred Only	25,520.00
3	Second class brick work using common burnt clay building bricks in cement mortar 1:6 (one cement isto six sand) in super structure as per PWD specification including curring and carriage of material within all leads and lifts complete in all respect as per direction of Engineer in Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	8.35	CUM	7400.00	Rupees Seven Thousand Four Hundred Only	61,790.00
4	Square rubble masonry coursed with hard stone of approved quality in foundation and plinth including racking out joints in cement mortar 1:6 (one cement : six sand) and curing complete including carriage of materials within all leads and lifts complete in all respect as per the direction of Engineer-in-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	3.47	CUM	5400.00	Rupees Five Thousand Four Hundred Only	18,738.00
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand) : 4 graded stone aggregate 40 mm nominal size) The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	5.19	CUM	6850.00	Rupees Six Thousand Nine Hundred & Fifty Only	36,071.00
6	Providing for steel reinforcement for RCC work including bending, binding and placing in position complete upto floor two level. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	467.10	KG	95.00	Rupees Ninety Five Only	44,375.00
Quoted rates Percentage in Figures						
Quoted rates Percentage in words						1,96,701.00

5

Executive Engineer
Bainnath Division
HPPWD Bainnath


6

SCHEDULE OF QUANTITY

Name of Work : C/O Bridge at Village Hartada
(Sh:- Super structure) (Deposit work SDP/2023/379 , SDP/2021/1137)

Estimate Cost: 1,95,220.00
Earnest Money: 4,000.00
Time Limit : One Month

Sr.n	Description of work	No.or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Providing for steel reinforcement for RCC work including bending binding and placing in position complete: as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	2270.00	Kg	86.00	Rupees Eighty Six Only	1,95,220.00
	Quated rates Percentage in figures					1,95,220.00
	Quated rates Percentage in words					


Executive Engineer
Bajinath Division
HPPWD Bajinath

SCHEDULE OF QUANTITY

Name of work :- C/O Gaziabad to kholf km 0/00 to 0/520
(SH:-C/O R/wall at RD 0/195 to 0/201.50 & P/L C C Pavement at RD 0/055 to 0/096.50) Deposit work VKV/2025/372

Estimate Cost: 1,95,583.00/-
Earnest Money: 4,000.00/-
Time Limit : One Month

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer- In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	2.08	Per Cum	290.00	Rupees Two Hundred & Ninety Only	603.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:5:10 (one cement : five sand : ten graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	8.10	Per Cum	4950.00	Rupees Four Thousand Nine Hundred & Fifty Only	40,095.00
3	Providing back filling with granular material behind abutment wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material including entire carriage of materials within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	2.73	Per Cum	990.00	Rupees Nine Hundred & Ninety Only	2,703.00
4	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7. including entire carriage of materials within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	5.00	Each	290.00	Rupees Two Hundred & Ninety Only	1,450.00

4 (A)

7/6

<p>5 Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."</p>	9.03	Per Cubic Metre	2,800.00	Rupees Two Thousand Eight Hundred Only	25,284.00
<p>6 Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."</p>	18.05	Per Cubic metre	6,950.00	Rupees Six Thousand Nine Hundred & Fifty Only	1,25,448.00
<p>Quated rates Percentage in figures</p>					1,95,583.00
<p>Quated rates Percentage in words</p>					1,95,583.00
			Total		


 Executive Engineer
 Bajinath Division
 HPPWD Bajinath

SCHEDULE OF QUANTITY

(8) (a)

Name of Work: C/O Jeevable Road From Sen. Sec School Averi to Gangoh ward No. 3 P.O Jandpur (Deposit work) Estimated Cost: Rs 1,96,818.00/-
 (SH:- Construction of 1.00 Mtr span culvert at RD 0/017 & P/L C C pavement at RD 0/00 to 0/015). S D P / 2023/833 Earnest Money: 4,000.00/-
 Time Limit : Two Months

S No.	Description of work	No. or Qty.	Unit	Estimated Rate		AMOUNT Rs. P
				Figure	Words	
1	Earth work in excavation for structures in all depths as per drawing and M.O.R.D technical specification section 300 & 1600 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal in all lead and lift including dressing of sides and bottom and back filling in trenches with excavated Suitable materials. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etc. and to protect stability of hill side rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super elevation and level as shown on the drawings or as directed by the Engineer-in-Charge, hauling and stacking of materials useful for construction at suitable sites and safe disposal of unsuitable cut materials in specified manner, filling of unevenness and finishing the road to specified dimension or as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage, rain and other causes it shall be removed by suitable diversion, bailing out or pumping as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of excavation shall be the whole responsibility of the contractor which shall have to be duly compensated by him at his own cost. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	19.67	Cum	290.00	Rupees Two Hundred & Ninety Only	5,704.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) per cubic metre nominal mix 1:3:6 (one cement is to three sand is to six crushed stone agg. 40mm(forty millimetre) nominal size) in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work and open in foundation as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and to the entire satisfaction and direction of Engineer - in- Charge including hauling /cartage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	2.37	Cum	5600.00	Rupees Five Thousand Six Hundred Only	13,272.00

3	<p>Providing and laying mechanically mixed and vibrated plain/ cement concrete in sub structure for all type of structure complete using plain cement concrete grade M-15 (M fifteen) design mix with cement contents not less than 275 kg (two hundred seventy five kilogram) per cubic metre in or under water including curing complete including pumping or hauling out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in abutments as per drawings and M.O.R.D. technical specification section 800,900 & 1200 and curing complete including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."</p>	12.54	Cum	6100.00	Rupees Six Thousand One Hundred Only	76,494.00
4	<p>Providing and laying mechanically mixed vibrated reinforced concrete in substructure using concrete grade M-20 (M twenty) design Mix with cement contents not less than 330 Kg (three hundred and thirty kilogram) per cubic meter as per drawing and M.O.R.D. technical specification section 800, 900,1200. Including the cost of form work in bed block and dirt wall etc. excluding the cost of reinforcement for reinforced concrete work but including curing complete as per direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."</p>	7.36	Cum	6950.00	Rupees Six Thousand Nine Hundred & Fifty Only	51,152.00
5	<p>Providing and laying mechanically mixed and vibrated reinforced cement concrete in super structure as per drawing and M.O.R.D. technical specification section 800, 900 and 1400 using R.C.C. grade M-25 (twenty five) design mix with cement contents not less than 400 kgs (four hundred kilogram) per cubic meter with 20 mm (twenty millimeter) nominal size gradd crushed stone aggregate and curing complete including cost of form work but excluding the cost of reinforcement for reinforced concrete work in deck slab and to the entire satisfaction and direction of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."</p>	1.92	Cum	7900.00	Rupees Seven Thousand Nine Hundred Only	15,168.00
6	<p>Supplying fitting and placing HYSD bar for reinforcement (Fe-415) in super structure complete as per drawing and M.O.R.D. technical specifications section 1000 including cutting, bending, binding and placing in position complete in all respect including cost of binding wire including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-In-Charge. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."</p>	230.00	Kg	98.00	Rupees Ninety Eight Only	22,540.00

82

7	Providing and laying hard stone Soling properly hand packed interspers with kharanja stone and consolidating with power / hand- roller to requested gradient and camber including spreading watering and rolling of binding mortar or earth etc complete as per HPPWD specification 100 mm spread thickness finished work including materials and labour as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	6.75	Per Cubic metre	1850.00	Ruppes One Thousand Eight Hundred & Fifty Only	12488.00
	Quated rates Percentage in figures					1,96,818.00
	Quated rates Percentage in words					

Executive Engineer
Bajnath Division
HPPWD Bajnath

SCHEDULE OF QUANTITY

Name of work : C/O Pucea Path from Joginder Kumar House to Darku Nallah Nohra road
 (SH: P/L G-II and C C pavement at km 0/060 TO 0/170 & C/O Edge wall at km 0/060 to 0/116) (VKVNY/2023/1185) Deposit work.

Estimate Cost: 1,48,087.00/-
 Earnest Money: 3,000.00/-
 Time Limit : Two Months

Sr. No.	Description of work	No. or Qty.	Unit	Rate		AMOUNT Rs. P
				Figures	Words	
1	Earth work in excavation for all type of road structure and in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) for retaining walls, breast walls, culverts, bridges, drains and parapets etcetera as per drawings and M.O.R.D. technical specification clause 305.1 and as per direction of the Engineer-In - Charge, including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	6.72	Per Cum	290.00	Rupees Two Hundred & Ninety Only	1,949.00
2	Providing laying spreading and compacting stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.20 cubic metre (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 cubic metre (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause No. 405 and to the entire satisfaction and direction of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	1.86	Per Cubic Metre	2,800.00	Rupees Two Thousand Eight Hundred Only	5,208.00
3	Providing and laying mechanically mixed and vibrated reinforced cement concrete in open foundation of plain cement concrete of Grade M-20 (M-Twenty) designed mix with minimum cement contents of 350 Kgs (Three hundred fifty kilograms) per cubic meter with 20 mm (Twenty Millimeters) nominal size graded crushed/ broken stone aggregate and curing complete including the cost of form work complete as per drawings and MORD technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	7.92	Per Cubic metre	6,950.00	Rupees Six Thousand Nine Hundred & Fifty Only	55,044.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation and plinth, as per drawing and Morth technical specification section 800, 900 & 1200 for nominal mix 1:4:8 (one cement : four sand : Eight graded stone agg. 40mm (forty millimeter) nominal size) and curing complete as per direction of Engineer-in-Charge and as per the drawing and hauling carriage of labour, equipments and materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	15.68	Per Cum	5200.00	Rupees Five Thousand Two Hundred Only	81,536.00

⑨ 61

96

5	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7, including entire carriage of materials within all leads and lifts and other incidentals. "The rate quoted shall be deemed to include all taxes, duties, levies, and charges including GST, octroi, royalty, toll tax, sales tax, or any other tax as applicable and imposed by the Government from time to time."	15.00	Each	290.00	Rupees Two Hundred & Ninety Only	4,350.00
Total						1,48,087.00
Quoted rates Percentage in figures						
Quoted rates Percentage in words						


 Executive Engineer
 Bajinath Division
 HPPWD Bajinath