

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DPD/CB/EA-I/Tender/2025- 2956-57
To


Dated:- 10-09-2025

The Executive Engineer (IT Cell)
Nirman Bhawan, Nigam Vihar,
Shimla-2


Subject: - Publishing of tender Notice.
Sir,

Enclosed please find herewith tender notice of work as given in the Notice inviting Tender along with Schedule of Quantities for uploading the same on department website as per Notification No. Pr. Secy. (PW) to the Govt. of HP letter No. PBW (B) A(3) 1/2024 dated Shimla-2, the 03.01.2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ As above.


Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

Copy along with tender notice is forwarded to the Superintending Engineer, 15th Circle, HPPWD Una for information please.
DA/ As above.


Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur chowk.

HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed **Percentage rates** tenders on form 6 & 7 are hereby invited by the Executive Engineer Daulatpur Chowk Division, HPPWD, Daulatpur Chowk on behalf of Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office and opened as per time schedule given below. The offer of the tender will be kept open for 75 days from the date of opening of the tenders.


Date and time of receipt of applications for the tender form : 17.09.2025 **up to 04.30 PM**
Date and time of issue/Sale of tender forms against cash Payment : 18.09.2025 **(03.00 PM to 5.00 PM)**
Date and time of receipt of tenders : 19.09.2025 **up to 11.00 AM**
Date and time of opening of tenders : 19.09.2025 **at 11.30 AM**

The tender forms will be issued against cash payment (non-refundable). The earnest money in the shape of NSC/Time Deposit/FDR of nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

Sr. No.	Name of Work	Estimated Cost	Earnest money	Time Limit	Cost of Form	Eligible Class of Contractor
1	Repair & Restoration of Rain Damages on various roads in Gagret Sub Division, Section Mubarikpur. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)	99571.00	2000.00	One Month	350-	C & D
2	Repair & Restoration of Rain Damages on various roads in Daulatpur Chowk Sub Division, Section Daulatpur-I. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)	98531.00	2000.00	One Month	350-	C & D
3	Repair & Restoration of Rain Damages on various roads in Gagret Sub Division, Section Gagret-II. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)	99371.00	2000.00	One Month	350-	C & D
4	Repair & Restoration of Rain Damages on link road NH-70 to Pambra Thaplan Km 0/0 to 8/330. (SH: C/o Embankment for roadway from borrow pits from Km 7/800 to 7/860)	97200.00	2000.00	Two Month	350-	C & D
5	Repair & Restoration of Rain Damages on various roads in Daulatpur Chowk Sub Division, Section Daulatpur-II. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)	98771.00	2000.00	One Month	350-	C & D

TE35RMS AND CONDITIONS: -

1. The contractor should produce a copy of enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his registration and GST No. and copy of the same be attached with the application.
3. The earnest money for the above works should be submitted duly pledged in favour of Executive Engineer, Daulatpur Chowk Division, HPPWD Daulatpur chowk with the application for the purchase of tender forms. The application received without earnest money shall be summarily rejected.
4. The contractor/firms are required to insert the rate in words as well as in figures failing which Executive Engineer reserves the right to accept/rejects any or all tenders.
5. If any of the date mentioned above happens to be Local/Gazetted Holidays the same shall be process on next date.
6. The tender form will be issued to those contractors who have relevant machinery and equipment, list of which may be attached with their application along with proof of ownership of machinery/legal tie up.
7. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.



Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.

No. PWD/DPD/CB-Tender/2025- 2949-55

Dated: - 10-09-2025


Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-Chief, HPPWD Nirman Bhawan Shimla.
2. The Chief Engineer (HZ) HPPWD Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD Una.
4. All the Assistant Engineers working under this division.
5. Drawing Branch in this office.
6. Notice Board.


Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.

CERTIFICATE

Certified that tenders called vide this office letter No. PWD/DPD/CB-Tender/2025- 2949-55 dated 10-09-2025 are required to be carried out immediately being emergent nature of work in the public interest.



Executive Engineer,
Daulatpur chowk Division,
HPPWD Daulatpur Chowk.

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99571/-
Earnest Money: Rs.2000/-
Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages on various roads in Gagret Sub Division, Section Mubarikpur. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	418.50 Cubic metre	80.00	Rupees Eighty Only	Per Cubic metre	33480.00
Total Amount in Rs.						99571.00
Quoted Rate in Figure						% above/below
Quoted Rate in Words						



Executive Engineer,
HPPWD Division,
Daulatpur Chokk

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 98531/-
 Earnest Money: Rs.2000/-
 Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages on various roads in Daulatpur Chowk Sub Division, Section Daulatpur-I. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	405.50 Cubic metre	80.00	Rupees Eighty Only	Per Cubic metre	32440.00
Total Amount in Rs.						98531.00
Quoted Rate in Figure						% above/below
Quoted Rate in Words						



Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 99371/-
 Earnest Money: Rs.2000/-
 Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages on various roads in Gagret Sub Division, Section Gagret-II. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	416.00 Cubic metre	80.00	Rupees Eighty Only	Per Cubic metre	33280.00
Total Amount in Rs.						99371.00
Quoted Rate in Figure						% above/below
Quoted Rate in Words						



Executive Engineer,
HPPWD Division,
Daulatpur Chowk

DRAFT BILL OF QUANTITY

Estimate Cost :- Rs. 97200/-
Earnest Money :-Rs. 2000/-
Time Limit :- Two Month.

Name of Work:- Repair & Restoration of Rain Damages on link road NH-70 to Pabra Thaplan Km 0/0 to 8/330. (SH: C/o Embankment for roadway from borrow pits from Km 7/800 to 7/860)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Construction of embankment with approved materials deposited at site obtained from roadway cutting and excavation from drains and foundation of all other structures or other sources, or obtained from borrow pits within all leads and lifts, graded and compacted to meet requirement, including setting out, true to the lines, grades, width and side slopes in accordance with drawings, including spreading the embankment material with motor-Grader in successive layers of 200mm (two hundred millimeter) uniform thickness, and compacting with vibratory roller 8-10 (eight to ten) Tonne static weight to meet the requirements of table 300.1 & 300.2 of MORD technical specification section 300 and 1600 and as per the entire satisfactions and directions of Engineer-in-Charge, including carriage of material within all leads, lifts and other incidentals. The rate is including Octroi, Royalty, Malkana, toll tax, goods service tax, labour cess or any other taxes imposed by the Government.	405.00 Cubic metre.	240.00	Rupees Two Hundred Forty Only	Per cubic metre	97200.00
	TOTAL					97200.00
					% above/below	
			Quoted Rate in Figure			
			Quoted Rate in Words			


Executive Engineer,
HPPWD Division,
Daulatpur Chowk.

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 98771/-
 Earnest Money: Rs.2000/-
 Time Limit : One Month.

Name of Work:- Repair & Restoration of Rain Damages on various roads in Daulatpur Chowk Sub Division, Section Daulatpur-II. (SH: Maintenance of Earthen shoulder Dressing of berms, Making loss of material, unlined surface drains and Removal of land slide)

Sr. No.	Sub-Head and Items of work	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903, complete as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	972.00 Square metre	16.10	Rupees Sixteen And Paise Ten Only	Per Square metre	15649.00
2	Maintenance of Earthen shoulders (filling with fresh selected soil) making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any all lead as per technical specification Clause 1903 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	880.00 Square metre	38.50	Rupees Thirty Eight And Paise Fifty Only	Per Square metre	33,880.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm (zero decimal four zero) in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	543.00 Running metre	30.50	Rupees Thirty And Paise Fifty Only	Per running metre	16,562.00
4	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts, stacking the serviceable material and disposal of unserviceable material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax, GST or any other taxes imposed by the Government.	408.50 Cubic metre	80.00	Rupees Eighty Only	Per Cubic metre	32680.00
Total Amount in Rs.						98771.00
Quoted Rate in Figure						% above/below
Quoted Rate in Words						

[Handwritten Signature]

[Handwritten Signature]
Executive Engineer,
HPPWD Division,
Daulatpur Chowk