

Himachal Pradesh
Public Works Department

NO.PW.TH.D./CB-tender/2025-26

4518-32

Dated:-

11/09/2025

To


✓ The Executive Engineer. (IT Cell)
O/O Engineer-in- Chief,
H.P.P.W.D., NirmnBhawan, Shimla-2

Subject:- Publication of Tender notice.

Sir,

I am enclosing herewith Notice Inviting Tender for the various work typed in English for uploading the same on department website in view of Principal Secretary (PW) to the Government of Himachal Pradesh Notification No. PBW (B) A (3) 1/2020 dated 16th July 2021.

As the work mentioned in the tender notice are urgent in nature and in public interest.


Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

Copy forwarded to the following a/w copy of tender notice for information:-

- The Deputy Commissioner, Shimla Distt. Shimla H.P
- The Superintending Engineer, 4th circle H.P.P.W.,D , Shimla-3.
- The Sub-divisional officer© Theog.
- The municipal Council Theog.
- Block development officer, Theog block.
- All the Assistant Engineer working under this division
- Superintendent Gr-II (Estt.) in this division.
- Drawing branch in this office.
- Notice Board

Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

Himachal Pradesh
Public Works Department
NOTICE INVITING TENDER

Sealed percentage rate tenders on PWD form 6 & 8 are hereby invited by the Executive Engineer, /-Theog Division, H.P.P.W.D., Theog on behalf of the Governor of HP. for the following works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the H.P. General Sales Tax Act, 1968 so as to reach in this office on or before **22.09.2025 up to 11.00 A.M.** and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender documents can be had from this office against cash payment (Non-refundable) on **20.09.2025 up to 4.00 P.M.** and the application for issue of tender form shall be received on **19.09.2025 up to 4.00 P.M.**


The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/ Bank duly pledged in favour of XEN HPPWD, Theog must be accompanied with the application for tender documents. Please note no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 120 days. The Executive Engineer reserves the right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue.

Sr.No	Name of work	Name of Divn.	Estimated cost(Rs.)	Earnest money (Rs.)	Cost of form (Rs)	Time Allowed
1	2	3	4	5	6	7
1	R/R damages on Various road under Matiana Sub- Division Matiana Section . (SH:- Hiring of JCB for removal of Land slide /Debries etc.on various RDs in Various road)	Theog	99750	2000	350	One Month
2	R/R damages on Various road under Theog Sub- Division Fagu Section (SH:- Hiring of JCB for removal slips)	Theog	98700	2000	350/-	One Month
3	R/R damages on Various road under Fagu Section Theog Sub- Division (SH:- C/O unlined surface drain)	Theog	97150	2000	350	One Month
4	R/R damages on Various road under Fagu Section Theog Sub- Division (SH:- C/O unlined surface drain)	Theog	97150	2000	350	One Month
5	Restoration of rain damages on Various road under Matiana Sub- Division . (SH:- Hiring of tipper of carriage of debries stone in Matiana Section)	Theog	99000	2000	350	One Month
6	R/R damages on Various road under Fagu Section Theog Sub- Division (SH:- Hiring of JCB for removal slips)	Theog	98700	2000	350	One Month
7	R/R damages on Various road under Sainj Sub- Division Sainj Section . (SH:- Hiring of breaker for hard rock in various RDs)	Theog	96250	1925	350	One Month

8	C/O New block and over hauling of Existing block of civil Hospital at Theog Distt shimla HP (SH:-Repair to plaster in patches,Providing and applying white cement based putty)	Theog	88232	1770	350	One Month
9	C/O New block and over hauling of Existing block of civil Hospital at Theog Distt shimla HP (SH:- Finishing with Epoxy paint etc)	Theog	43589	1000	350	One Month
10	Supplying and stacking at site crusher sand Various road under Sainj Sub- Division in Deha Section . (SH:- supplying and stacking at site crusher sand	Theog	81400	1650	350	One Month
11	R/R damages on Various road under Matiana Sub- Division . (SH:- Hiring of JCB for removal of slips and dressing of roads in Mahori Section.)	Theog	98700	2000	350	One Month
12	R/R damages on Various road under Matiana Sub- Division (SH:- Hiring of JCB for removal of slips and dressing of roads in Mahori Section.)	Theog	98700	2000	350	One Month
13	R/R damages on Various road under Sainj Sub- Division (SH:-Hiring of Tipper for carriage of debries /stone in Ghoond Section)	Theog	99000	2000	350	One Month
14	R/R damages on Various road under Sainj Sub- Division (SH:- Hiring of Tipper for carriage of debries /stone in Ghoond Section)	Theog	99000	2000	350	One Month
15	R/R damages on Various road under Sainj Sub- Division . (SH:- Hiring of JCB for removal of slips and surface dressing of roads in Sainj Section)	Theog	99750	2000	350	One Month
16	R/R damages on Various road under Sainj Sub- Division . (SH:- Hiring of JCB for removal of slips and surface dressing of roads in Surface Sainj Section)	Theog	99750	2000	350	One Month
17	R/R damages on Various road under Theog Sub- Division . (SH:- Hiring of JCB for removal of slips in various of roads)	Theog	99750	2000	350	One Month


Following documents should accompany the application for tenders:-

- The contractors are required to be produce a copy of their PAN No. GST and should also produce a copy of enlistment /renewal letter.
- The tender form will be issued to those contractors only who is having requisite machinery such as, J.C.B Tipper etc.
- Special care should be taken to write the rates both in figures and in words failing which tender is likely to be rejected
- The contractor will have to submit the proof of registration Under Employees Provident Fund & Miscellaneous Provision Act,1952 at the time of tender. Failure to observe this condition shall render the tender of contractor liable to summary rejection.

91

 Executive Engineer
 HPPWD. (B&R) Division

"Exigency Certificate"

It is certified that the tenders for various works as called for vide this office letter No. PW/THD/CB/Tender/2025-26 4518-32 dt 11-09-2025 are of emergent nature in exigency of public interest.


Executive Engineer,
Theog Division, B&R,
H.P.P.W.D., Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 99750/
 Earnest Money:2000 /
 Time: one Month

Name of Work : - R/R damages on Various road under Matiana Sub-Division .(SH:- Hiring of JCB for removal of slips Matiana Section)

Sl. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
	Hiring of JCB (excavator cum-loader) including P.O.I charges, shifting charges and other ancillary equipments as required at site of work for removal of slip in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work , pick work, Jumper work , soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary . The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damages tool place, the contractor is liable for it . All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 20 cubic meter of earth work shall be done by machine in one hour , other wise number of hour shall be reduced accordingly as per instruction i/c all leads and lifts as per the direction of the Engineer-in-Charge.	95.00	1050.00	Rupees One Thousand Fifty Only	Per hours	99750
			Quoted rate in figer +/- (%.....)			99750
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HPPWD Theog

SCHEDULE OF QUANTITY

ESTIMATED COST :- 98700

EARNEST MONEY :-2000

NAME OF WORK :- R/R DAMAGES ON VARIOUS ROAD UNDER AGU SECTION THEOG SUBDIVISION (SH:- HIRING OF JCB FOR REMOVAL OF SLIPS)

SR.NO.	DESCRIPTION OF ITEM	QTY	RATE	UNIT	AMOUNT
			Rate in figure	Rate in words	
1	Hiring of JCB /Excavated be deployed for removal of slips i/c cost of fuel oil lubricants and wages of operational staff any repair , breakage during operation will be carried out by the owner at his risk and cost shifting of machineries from one place to other required location , actual working hours will be accounted for the payement and six hours per day working will be required average minimum 20cum removal of earth in one hours i/c loading in tippers/ trucks and disposing excavated earth i/c all leads and lifts as per direction of Engineer - in - Charge	94	1050	Rs one thousand fifty only.	98700
			Quoted rate in figure +/-(%.....)		
			Quoted rate in words		


Executive Engineer
Theog Division
HPPWD Theog

SCHEDULE OF QUANTITY

ESTIMATED COST :-97150

EARNEST MONEY :-2000

NAME OF WORK :- R/R DAMAGES ON VARIOUS ROAD UNDER FAGU SECTION THEOG SUBDIVISION (SH:- C/O UNLINED SURFACE DRAIN)

R.N O.	DESCRIPTION OF ITEM	QTY	RATE	Rate in words	UNIT	AMOUNT
1	Construction of unlined surface drains of average cross sectional area 0.40 sqm in soil to specified lines , grades levels and dimensions . Excavated material to be used in embankment with a lift upto 3 m and lead of 510 m (average lead 25m) as per Technical Specification Clause 307 including in all leads and lifts as per direction of Engineer - in - Charge .	3350	29.	Rs twenty nine only	Per running mtr	97150
						97150
				Quoted rate in Figure /		
				Quoted rate in words.		



Executive Engineer
Theog Division
HPPWD Theog

SCHEDULE OF QUANTITY

ESTIMATED COST :-97150

EARNEST MONEY :-2000

NAME OF WORK :- R/R DAMAGES ON VARIOUS ROAD UNDER FAGU SECTION THEOG SUBDIVISION (SH:- C/O UNLINED SURFACE DRAIN)

S.N	DESCRIPTION OF ITEM	QTY	RATE	Rate in words	UNIT	AMOUNT
1	Construction of unlined surface drains of average cross sectional area 0.40 sqm in soil to specified lines , grades levels and dimensions . Excavated material to be used in embankment with a lift upto 3 m and lead of 510 m (average lead 25m) as per Technical Specification Clause 307 including in all leads and lifts as per direction of Engineer - in - Charge .	3350	29	Rs Twenty nine only .	Per running mtr	97150
						97150
				quoted rate in figure - (-) %		
				quoted rate in words		



Executive Engineer
Theog Division
HPPWD Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 99000/
Earnest Money:2000 /
Time: one Month

Name of Work : - R/R damages on Various road under Matiana Sub- Division . (SH:- Hiring of tipper for carriage of debries /stone in Matiana Section)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of Tipper carrying of material including P.O.L charges and other shifting Charges and other ancilliary equipment as required at site of work . The work shall have to carried out as per Ministry of transport specifications of i/c all leads and lifts as per direction of the Engineer-in-Charge	22.00	4500.00	Rupees Four Thousand Five Hundred Only	per day	99000
			Quoted rate in figer +/- (%.....)			99000
			Quoted rate in words			99000


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

ESTIMATED COST :- 98700

EARNEST MONEY :-2000

NAME OF WORK :- R/R DAMAGES ON VARIOUS ROAD UNDER AGU SECTION THEOG SUBDIVISION (SH:- HIRING OF JCB FOR REMOVAL OF SLIPS)

SR.NO.	DESCRIPTION OF ITEM	QTY	RATE	Rate in words	UNIT	AMOUNT
1	Hiring of JCB /Excavated be deployed for removal of slips i/c cost of fuel oil lubricants and wages of operational staff any repair , breakage during operation will be carried out by the owner at his risk and cost shifting of machineries from one place to other required location , actual working hours will be accounted for the payement and six hours per day working will be required average minimum 20cum removal of earth in one hours i/c loading in tippers/ trucks and disposing excavated earth i/c all leads and lifts as per direction of Engineer - in - Charge	94	1050	Rs one thousand and fifty only	Per hours	98700
				Quoted rate in figure +/-(%.....)		
				Quoted rate in words		



 Executive Engineer
 Theog Division
 HPPWD Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 96250/
 Earnest Money: 1925 /
 Time: one Month

Name of Work : - R/R damages on Various road under Sainj Sub -Division . (SH:- Hiring of Breaker for hard rock in various

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB/ Excavator be deployed for removal of slips i/c cost of fuel oil lubricants and wages of operational staff any repair package during operation will be carried out at his risk and cost including carrying of machinery from one place to other required location, actual working hours will be accounted for the payment and proper disposal slip/by the contractor will be insured and i/c all leads and lifts as per direction of the Engineer-in-Charge	55.00	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Per hours	96250
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			
						96250


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs. 88232

Earnest Money:-1770/

Time: One months

Work : C/O New block and over hauling of Existing block of civil Hospital at Theog Distt shimla HP (SH:-Repair to plaster in patches,Providing and applying cement based putty)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
	Repair to plaster in patches of area 2.5 sqm and under, 15 mm thick including cutting the patch in proper shape, plastering the wall surface of wall including disposal of rubbish to the dumping rosd with in a lead of 20 mtrswith Cement Motar 1:4 (1cement 4 sand)all completeincluding in all leads and lifts as per direction of Engineer-in-Charge.	263.38	240.00	Rupees Two Hundred Forty Only	Per square meter	63211
	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including in all leads and lifts as per direction of Engineer-in-Charge.	263.38	95.00	Rupees Ninety Five Only	Per square meter	25021
						88232
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			

Executive Engineer,
Theog Division,
HPPWD Theog

B-

SCHEDULE OF QUANTITY

Estimated Cost Rs. 43589

Earnest Money:-1000/

Time: One months

of Work : C/O New block and over hauling of Existing block of civil Hospital at Theog Distt shimla HP (SH:- Finishing with Epoxy paint etc)

Sl. No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete including in all leads and lifts as per direction of Engineer-in-Charge.	263.38	165.50	Rupees One Hundred Sixty Five and Paise Fifty Only	Per square meter	43589
				Quoted rate in figer +/- (%.....)		
				Quoted rate in words		43589

Executive Engineer,
Theog Division,
HPPWD Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 81400/

Earnest Money: 1650/

Time: one Month

Name of Work : - - Supplying and stacking at site crusher sand various road under Sainj Sub- Division in Deha Section) (SH:- Supplying and stacking

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Supply and stacking at Site of work crusher sand clean and free from adherent coating and organic matter and shall not contain any appreciable amount of nay clay bails pills etc. i/c all leads and lifts as per direction of the Engineer-in-Charge	74.00	1100.00	Rupees One Thousand One Hundred Only	Per hours	81400
			Quoted rate in figer +/- (%.....)			81400
			Quoted rate in words			

Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 98700/
 Earnest Money:2000 /
 Time: one Month

of Work : - R/R damages on Various roads under Matiana Sub -Division .(SH:- Hiring of JCB for removal of slips and dressing of roads in Matiana Sub-Div)

S.No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
	Hiring of JCB/ Excavator be deployed for removal of slips i/c cost of fuel oil lubricants and wages of operational staff any repair package during operation will be carried out at his risk and cost including carrying of machinery from one place to other required location, actual working hours will be accounted for the payment and proper disposal slip/by the contractor will be insured and i/c all leads and lifts as per direction of the Engineer-in-Charge	94.00	1050.00	Rupees One Thousand Fifty Only	Per hours	98700
						98700
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 98700/
 Earnest Money:2000 /
 Time: one Month

Name of Work : - R/R damages on Various roads under Matiana Sub -Division . (SH:- Hiring of JCB for removal of slips and dressing of roads in

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB/ Excavator be deployed for removal of slips i/c cost of fuel oil lubricants and wages of operational staff any repair package during operation will be carried out at his risk and cost including carrying of machinery from one place to other required location, actual working hours will be accounted for the payment and proper disposal slip/by the contractor will be insured and i/c all leads and lifts as per direction of the Engineer-in-Charge	94.00	1050.00	Rupees One Thousand Fifty Only	Per hours	98700
						98700
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 99000/
Earnest Money:2000 /

Time: one Month

Work : - R/R damages on Various roads under Sainj Sub -Division . (SH:- Hiring of tipper for carriage of debris /stone in Ghoond
Division .)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of full size Tipper 5.5 cum /10 tones capacity to be deployed for disposing /carring of material like earth, Kankar moorum , shingle and boulders etc.including cost of fuel,oil lubricants and wages of operational staff , any repair breaaage during operation will be carried out by the owner at his own risk and cost including shifting of vehicle from one place to other at required location , actual working hours will be accounted for the payment and six hours per day wrking will be required having of front and loading capacity 1.00 cum i/c all leads and lifts as per direction of the Engineer-in-Charge	22.00	4500.00	Rupees Thousand Hundred Only Four Five	Per hours	99000
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			
						99000



Executive Engineer,
Theog Division,
HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 99000/
 Earnest Money:2000 /
 Time: one Month

14
 Name of Work : - R/R damages on Various roads under Sainj Sub -Division . (SH:- Hiring of tipper for carriage of debries /stone in Ghoond
 tion .)

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of full size Tipper 5.5 cum /10 tones capacity to be deployed for disposing /carring of material like earth, Kankar moorum , shingle and boulders etc.including cost of fuel,oil lubricants and wages of operational staff , any repair breaaage during operation will be carried out by the owner at his own risk and cost including shifting of vehicle from one place to other at required location , actual working hours will be accounted for the payment and six hours per day wrking will be required having of front and loading capacity 1.00 cum i/c all leads and lifts as per direction of the Engineer-in-Charge	22.00	4500.00	Rupees Thousand Hundred Only Four Five	Per hours	99000
			Quoted rate in figer +/- (%.....)			99000
			Quoted rate in words			


 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 99750/
 Earnest Money:2000 /
 Time: 15 days

Work : - R/R damages on Various roads under Sainj Sub-Division-~~(Beha section)~~ (SH:- Hiring of JCB for removal of slips & surface
 sing) ~~Sainj Section~~ Sainj section

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
	Hiring of JCB (excavator cum-loader) including P.O.I charges, shifting charges and other ancillary equipments as required at site of work for removal of slip in all heights in all kinds of soil such as kanakar, moorum shingle boulders decomposed or soft variety of soil such as spade work , pick work, Jumper work , soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary . The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damages tool place, the contractor is liable for it . All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30 cubic meter of earth work shall be done by machine in one hour , other wise number of hour shall be reduced accordingly as per instruction i/c all leads and lifts as per the direction of the Engineer-in-Charge.	95.00	1050.00	Rupees Thousand Fifty Only One	Per hours	99750
			Quoted rate in figer +/- (%.....)			99750
			Quoted rate in words			



 Executive Engineer,
 Theog Division,
 HP.PWD. Theog

SCHEDULE OF QUANTITY

Estimated Cost Rs 99750/
Earnest Money:2000 /
Time: 15 days

Work : - R/R damages on Various roads under Sainj Sub -Division (~~Police Section~~) (SH:- Hiring of JCB for removal of slips and dressing roads)(~~Sainj-section~~) Sainj section

No.	Description of Item	QTY	Rate		Unit	Amount
			Rate in fig.	Rate in words		
1	Hiring of JCB (excavator cum-loader) including P.O.I charges, shifting charges and other ancillary equipments as required at site of work for removal of slip in all heights in all kinds of soil such as kankar, moorum shingle boulders decomposed or soft variety of soil such as spade work , pick work, Jumper work , soft rock hard rock including their intermediate classification of soil including mechanical transportation of necessary . The disposal of this un-serviceable material has to be done in the acquired width of the road to avoid damages to the properties of the people or in case any damages tool place, the contractor is liable for it . All salvaged material such as quarried stone shall belong to the department and maximum useful quantity of stones from removal of slips shall have to be neatly stacked along road side on road burms. Minimum 30 cubic meter of earth work shall be done by machine in one hour , other wise number of hour shall be reduced accordingly as per instruccion i/c all leads and lifts as per the direction of the Engineer-in-Charge.	95.00	1050.00	Rupees Thousand Fifty Only	Per hours	99750
			Quoted rate in figer +/- (%.....)			
			Quoted rate in words			99750


Executive Engineer,
Theog Division,
HP.PWD. Theog

