

REGISTERED

Office of the Executive Engineer, B&R Division, HP PWD Kalpa District Kinnaur (HP)

Web:- www.hppwd.gov.in E mail:- hp-kin@nic.in

Phone No:- 01786-226027 Fax:- 01786-226027.

No:- PW/KNR-E-Tender/2025-

3886-88

Dated:- 5/7/25

To


The Executive Engineer (IT Cell),
HP.PWD. Shimla-2.

Subject:-

Publication of Tender Notice (OFFLINE)


Enclosed please find herewith the Tender of works costing below 1.00 Lac as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) 1/2020 dated 16-07-2021 and even file No. 1/2024 dated 03-01-2024, 03-01-2025 and 1/2024-241828 dated 17-07-2025. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity
& Certificate.


Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.

Copy forwarded for information to:-

1. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.


Executive Engineer,
Kalpa Division,
HP. PWD, Kalpa

HP.P.W.D. TENDER NOTICE (offline)

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the **Executive Engineer, Kalpa Division, HP,PWD; Kalpa** for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **12-09-2025 up to 10.30 A.M.** and shall be opened on the same day at **11:00 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on **11-09-2025** upto 4.00 P.M. No application for issue of tender forms will be received on **11-09-2025 after 4.00 PM.** If the office happens to be closed on the above mentioned dates, the tenders will be sold/opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R,s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The officer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	Balance work for the Construction of Modern Mess at Police Thana Pooh (SH:-Distempering and minor work etc.)	3,61,457/-	7,500/-	One Month	350/-	D Class
2	R/R damages on Bailey bridge over Pazer Khad at at Lippa in District Kinnaur (HP) (SH:- Hiring of Hydraulic Excavator (L & T) for removal of debris up stream side)	4,95,300/-	10,000/-	One Month	350/-	D Class
3	R/R damages on Link road from Leo Bridge to Hango Km. 0/00 to 16/00 (SH:- Removal of slips/landslides from Km. 13/00 to 16/00)	4,99,235/-	10,000/-	One Month	350/-	D Class
4	C/O Jeepable road from Change to Japroden Panva Milisti Village Khawangi) (Portion Khawangi to Milisti 0/00 to 0/365) and Japroden to Tale Km. 0/00 to 2/00 (SH:- Providing steel grating over U-shape drain at RD. 0/040 to 0/070)	4,91,285/-	10,000/-	One Month	350/-	D Class
5	C/O Jeepable road from Change to Japroden Panva Milisti Village Khawangi) (Portion Khawangi to Milisti 0/00 to 0/365) and Japroden to Tale Km. 0/00 to 2/00 (SH:- Providing steel grating over U-shape drain at RD. to 0/070 to 0/100)	4,91,285/-	10,000/-	One Month	350/-	D Class
6	Improvement of black spot on link road from Kalpa to Roghi Km. 0/00 to 6/365 (SH:- P/F W-Metal crash barrier in essential reaches from Km. 5/00 to 5/100) (Under Road safety funds)	1,54,753/-	3500/-	One Month	350/-	D Class

7	Improvement of Black spot on Link road from Leo Bridge to Hango Km. 0/00 to 16/00 (SH:- P/F W-Metal Crash barrier in essential reaches from Km 7/00 to 7/100) (Under road safety funds)	75,763/-	2000/-	One Month	350/-	D Class
8	R/R damages on link road from Giabong Bus Stand to Parla Giabong Km. 0/00 to 0/910 (SH:- C/O B/wall in PCC at RD. 0/520 to 0/565)	4,68,635/-	9,500/-	One Month	350/-	D Class

Terms and conditions:-


Following documents should accompany the application for tenders:-

1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts Number allotted by the Provident Fund Commissioner Shimla and copy of PAN Number.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not be entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in Hand.

No.:- PW/KNR-E-Tender/NIT/2025- **3904-15**
Copy forwarded for information to:-


1. The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional Officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, *11th Circle, HP.PWD. Rampur Bushahr.
5. The Block Development Officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.


Executive Engineer,
Kalpa Division,
HP. PWD; Kalpa.
Dated:- **15/9/25**


Executive Engineer,
Kalpa Division,
HP. PWD; Kalpa.

CERTIFICATE

Certified that the Tender for work called vide this office Letter No. PW/KNR/E-Tender/2025- 3904-15 dated 05-9-2025 and Sr. No. 1 to 8 work is of urgent nature and public interest.


Executive Engineer,
Kalpa Division,
HP.PWD, Kalpa.


 

SCHEDULE OF QUANTITY

Sr. No.		Description of items	Qty.	Rate		Unit	Amount
				In Fig.	In Words		
Name of work:- Balance work for the C/O Modern Mess at Police Thana Pooch (SH:- Distemping and minor work etc).							
Estimated Cost :-							3,61,457/-
Earnest Money :-							7,500/-
Time :-							One Month
1	Painting with Premium acrylic emulsion paint of approved brand and manufacture to give an even shade :Two or more coats on new work, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	47.00	105.25	Rupees One Hundred Five Paise TwentyFive Only	Per Square meter	₹ 4,947.00	
2	Providing and fixing chromium plated brass curtain rod having wall thickness of 1.25mm with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etc., wherever necessary complete 20 mm dia, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	5.00	410.20	Rupees Four Hundred Ten Paise Twenty Only	Per Running meter	₹ 2,051.00	
3	Finishing with Deluxe Multi surface paint system forinteriors and exteriors using Primer as permanufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacturer, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	25.00	89.90	Rupees EightyNine Paise Ninety Only	Per Square meter	₹ 2,248.00	
4	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately)2nd class deodar wood, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	0.12	128532.20	Rupees One Lakh TwentyEight Thousand Five Hundred ThirtyTwo Paise Twenty Only	Per Cubic meter	₹ 15,424.00	

5	Providing and fixing 6 mm (Six millimeter) thick ply wood lining with butt jointing and nails. (framework and cover fillet to be measured and paid for separately.), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	13.50	680.20	Rupees Six Hundred Eighty Paise Twenty Only	Per Square meter	₹ 9,183.00
6	Providing and fixing Rai wood panelling with plank size 75x25mm & 75mmx12.5mm in combination over frame of wood work (to be paid separately) with top moulding complete in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	13.50	2787.75	Rupees Two Thousand Seven Hundred Paise SeventyFive Only	Per Square meter	₹ 37,635.00
7	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete :50x12mm, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	9.00	175.00	Rupees One Hundred SeventyFive Only	Per Running meter	₹ 1,575.00
8	Polishing two coats with malamine polish of required shade on new wood and wood based surfaces to give an even surface including cleaning the surface of all dirt, dust and sand papered smooth and including a coat of wood filler, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	13.50	240.20	Rupees Two Hundred Fourty Paise Twenty Only	Per Square meter	₹ 3,243.00
9	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1150.00	125.00	Rupees One Hundred TwentyFive Only	Per Kilogram	₹ 143,750.00
10	Providing and placing on terrace (at all floor level) Polyethelene water storage tan, IS 12701 marked, with cover and suitable locking arrangement and marking necessary holes for inlet outlet and overflow pipe but without fittings, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	1000.00	10.00	Rupees Ten Only	Per Liter	₹ 10,000.00


11	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	5.74	1275.25	Rupees One Thousand Two Hundred SeventyFive TwentyFive Only	Per Square meter	₹ 7,320.00
12	Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). Size of Tile 600x600 mm, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	12.00	1683.80	Rupees One Thousand Six EightyThree Eighty Only	Per Square meter	₹ 20,206.00
13	Supplying of Dining table of superior quality, 8 Seater with cushion chairs, including carriage of material and all taxes, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	2.00	51000.00	Rupees FiftyOne Thousand Only	Each	₹ 102,000.00
14	Providing and fixing superior quality cloth curtain including sewing (double lining) complete, (Size not less than 1.20m x 2.05m), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	3.00	625.00	Rupees Six Hundred TwentyFive Only	Each	₹ 1,875.00
Total in figures:-						
Total in Words:-						
Quoted Percentage rate upto three Digits :-						
		Rupees Three Lakh SixtyOne Thousand Four Hundred FiftySeven Only				₹ 361,457.00
		(+)/(-)				



 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD: Kalpa.

SCHEDULE OF QUANTITY


Description of items	Qty.	Rate		Unit	Amount
		In Fig.	In Words		
Hiring of One No. Hydraulic excavator (L&T 200 in good condition Hyundai, L & T Make, (excavator bucket with 360 degree rotation) on hire charges basis at the site of work for removal of slips in all classification of soil dressing of berms, filling of depression and filling behind retaining wall etc. including P.O.L. and establishment charges or running staff wages for minimum six hours per day.	127.00	₹ 3,900.00	Rupees Thousand Hundred Only	Per Hours	₹ 495,300.00
Total in figures:-					₹ 495,300.00
Total in Words:-			Rupees Four Lakh NinetyFive Thousand Three Hundred Only		
Quoted Percentage rate upto three Digits :-	(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

name of work:- Restoration of rain damages on Link road from Leo Bridge to Hango Km. 0/00 to 16/00
(SH):- Removal of slips/landslides from Km. 13/00 to 16/00).

Sr. No.	Description of items	Qty.	Rate		Unit	Estimated Cost :-
			In Fig.	In Words		
1	Removal of land slide in hilly area in all kinds of soil, ordinary rock / big boulders requiring breaking by mechanical means , i.e. breaker etc. including cutting and trimming of slops and disposal of cut material with in all leads and lifts of material as per technical specification 302.3.5 and 1611, including carriage of materials through all modes of transportation with in all leads and lifts, as per direction of the Engineer-in-charge.	3130.00	₹ 159.50	Rupees One Hundred FiftyNine Paise Fifty Only	Per Cubic meter	4,99,235/-
Total in figures:-						₹ 499,235.00
Total in Words:-						₹ 499,235.00
Quoted Percentage rate upto three Digits :-						₹ 499,235.00
Total						₹ 499,235.00


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

4


SCHEDULE OF QUANTITY

Description of items	Qty.	Rate		Unit	Estimated Cost
		In Fig.	In Words		
Steel work welded in built up sections/ framed work of TATA, SAIL or RASHTRIYA ISPAT or its equivalent, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	3924.00	₹ 125.20	Rupees One Hundred TwentyFive Twenty Only	Per Kilogram	₹ 491,285.00
Total in figures:-					₹ 491,285.00
Total in Words:-					₹ 491,285.00
Quoted Percentage rate upto three Digits :-					

Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

SCHEDULE OF QUANTITY


name of work:- C/O Jeepable road from Change to Japrodan-Panva-Millisti village Khawangi (Portion Khawangi to Millisti 0/00 to 0/365 and Japrodan to Tale Km 0/00 to 2/00 (SH:- Providing Steel grating over U-Shape drain at RD 0/070 to 0/100).		Estimated Cost :- 4,91,285/-				
		Earnest Money :- 10,000/-				
		Time :- One Month				
S.No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Steel work welded in built up sections/ framed work of TATA, SAIL or RASHTRIYA ISPAT or its equivalent, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	3924.00	₹ 125.20	Rupees One Hundred TwentyFive Twenty Only	Per Kilogram	₹ 491,285.00
Total in figures:-						₹ 491,285.00
Total in Words:-		Rupees Four Lakh NinetyOne Thousand Two Hundred EightyFive Only				
Quoted Percentage rate upto three Digits :-		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Improvement fo Black spot on link road from Kalpa to Roghi Km. 0/00 to 6/365
(SH:- Providing and fixing W-Metal beam crash barrier in essential reaches from Km. 5/00 to 5/100). (Under Road Safety funds)

Sr. No.	Description of items	Qty.	Rate		Unit	Estimated Cost :-
			In Fig.	In Words		
			Amount			
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	4.86	261.72	Rupees Two Hundred SixtyOne SeventyTwo Only	Per Cubic meter	₹ 1,272.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M-15 (Fifteen) Nominal mix 1:2.5:5 (One cement : two point five sand : five aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	4.86	7015.00	Rupees Thousand Fifteen Only	Per Cubic meter	₹ 34,093.00
3	Providing erecting type "A" W metal Crash barrier comprising of 3mm corrugated sheet metal beam rail 70cm above road/ ground level , fixed an ISMC series channel Vertical post 150x75x5 mm spaced 2 mtr c/c 1.80mtr high 1.1 mtr below ground level all steel parts and fitment to be galvanised by hot dip process, all fittings to conform to IS 1364 metal beam rail to be fixed on the vertical post with a space of channel section 150x75x5 mm 330 mm long complete as per clause 810, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	37.00	3226.70	Rupees Thousand Hundred Paise Seventy Only	Per Running meter	₹ 119,388.00
Total in figures:-						₹ 154,753.00
Total in Words:-						
Quoted Percentage rate upto three Digits :-						
Rupees One Lakh FiftyFour Thousand Seven Hundred FiftyThree Only						
(+)/(-)						


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY


Name of work:- Improvement of Black spot on link road from Leo Bridge to Hango Km. 0/00 to 16/00 (SH:- Providing and fixing W-Metal beam crash barrier in essential reaches from Km. 7/00 to 7/100). (Under Road Safety funds)		Estimated Cost	75,763/-			
		Earnest Money	2,000/-			
		Time	One Month			
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.43	261.72	Rupees Two Hundred SixtyOne SeventyTwo Only	Per Cubic meter	₹ 636.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C grade M-15 (Fifteen) Nominal mix 1:2.5:5 (One cement : two point five sand : five aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	2.43	7015.00	Rupees Thousand Fifteen Only	Per Cubic meter	₹ 17,046.00
3	Providing erecting type "A" W metal Crash barrier comprising of 3mm corrugated sheet metal beam rail 70cm above road/ ground level, fixed an ISMC series channel Vertical post 150x75x5 mm spaced 2 mtr c/c 1.80mtr high 1.1 mtr below ground level all steel parts and fitment to be galvanized by hot dip process, all fittings to conform to IS 1364 metal beam rail to be fixed on the vertical post with a space of channel section 150x75x5 mm 330 mm long complete as per clause 810, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	18.00	3226.70	Rupees Thousand Hundred TwentySix Paise Seventy Only	Per Running meter	₹ 58,081.00
Total in figures:-						₹ 75,763.00
Total in Words:-				Rupees SeventyFive Thousand Seven Hundred SixtyThree Only		
Quoted Percentage rate upto three Digits :-		(+)/(-)				


Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road from Giabong Bus Stand to Parla Giabong Km. 0/00 to 0/910.
(SH:- C/O B/Wall in PCC at RD 0/520 to 0/565)

Sr. No.	Description of items	Qty.	Rate		Unit	Estimated Cost
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (within all lead and lift including dressing of sides and ramming of bottoms, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m (Fifty Meter) All Kind of Soil . including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge. including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	45.55	261.05	Rupees Two Hundred SixtyOne Paise Five Only	Per Cubic meter	₹ 11,891.00
2	Providing concrete for plain /reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202,&1203.P.C.C. grade M ten . (i) nominal mix 1:3:6 (One Cement :Three Sand: Six Aggregate). including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	72.00	6057.00	Rupees Six Thousand FiftySeven Only	Per Cubic meter	₹ 436,104.00
3	Providing weepholes in brick masonry / stone masonry /plain reinforced concrete aboutment , wing wall, return wall with 100 mm dia (One hundred millimeter diameter) pvc pipe extending through the full with of the structures with stop of 1 (v) : 20 (H) towards drawings face complete as per drawing and technical specification clauses 614,709,1204.3.7. including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge, including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	75.00	275.20	Rupees Two Hundred SeventyFive Paise Twenty Only	Each	₹ 20,640.00
Total in figures:-						₹ 468,635.00
Total in Words:-						Rupees Four Lakh SixtyEight Thousand Six Hundred ThirtyFive Only
Quoted Percentage rate upto three Digits :-						(+)/(-)


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.