

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No:-PW-NCD-E-Tender- Publication/2025-26- 4592-99

Dated:- 17-9-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan, Nigam Vihar, Shimla-2

Subject: - Publishing of tender Notice.

Dear Sir,

Enclosed please find herewith the tender Notice of works as given in the Notice Inviting Tender for uploading on Department website as per Notification No. Pncipal Secretary (PW), to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03-01- 2024 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA: - Notice Inviting Tender.
(28 Nos. Works)


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

Copy forwarded to for information:-


Copy forwarded to the Superintending Engineer, 1st Circle, HP.PWD.,
Mandi for information please.

Copy to all the Assistant Engineers, working under this Division.

Copy to Account Branch in this office.

Copy to Drawing Branch in this office.

Notice Board.


Executive Engineer
Nerchowk Division
HPPWD Nerchowk.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER"

Sealed **Percentage rate** tenders on form **"6&8"** are invited by the Executive Engineer, Nerchowk, HPPWD Nerchowk for the following works from the approved and eligible contractors enlisted in H.P.PWD. so as to reach in this office on or before **26.09.2025 upto 01.30 PM** and will be opened on the same day at **3.00 PM** in the presence of interesting contractors or their authorized representatives who may like to be present. If it happen to be holiday on the tender will be open on next working day. The application for obtaining the tender form will be received up to **11:30 AM on 25.09.2025** and tender form will be issued on dated **25.09.2025 upto 11:30 AM**. The EMD should be attached during the submission of application for obtaining the tender form. The application will not be accepted without Earnest Money & Cost of tender form.

The earnest money in the shape of FDR National Saving Certificate/Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany with each tender. The conditional tenders and the tenders received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for **75 days**. The Executive Engineer reserves the right to reject the tender's without assigning any reason:-


Sr. No	Name of work	Estimated Cost (Rs.)	Earnest Money (Rs.)	Cost of Tender From (Rs.)	Time limit	Appropriate Class of Contractor
1	Restoration of rain damages on Galma Majhyali road km 0/0 to 9/0. (SH:- Construction of Breast wall at RD 2/817.50 to 2/825).	89056	2000	350	Two Months	"D"
2	Construction of toilet at GSSS Rajgarh Tehsil Balh. (SH:- Providing and fixing WC and sanitary items) Deposit work.	99071	2000	350	Two Months	"D"
3	Restoration of rain damages on various roads under Chakkar Sub Division HPPWD Nerchowk. (Gagal Section). (SH:- Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc).	93500	1900	350	One Month	"D"
4	Restoration of rain damages on Ratti to Randhara road km 0/0 to 9/0. (SH:- Construction of Breast wall at RD 5/020 to 5/026.50).	98942	2000	350	One Month	"D"
5	Restoration of road damages on Chandigarh Mandi Manali (Old NH-21) road km 184/600 to 198/050. (SH:- Construction of PCC Retaining wall at RD 184/612 to 184/614).	82776	1700	350	Two Months	"D"
6	Providing and laying Paver Block at Statue of Martyr Sh. Tek Singh Mastana Village Sayanh, PO Lohara Tehsil Balh Distt. Mandi (HP)	83704	1800	350	Two Months	"D"
7	Restoration of rain damages on various roads under Chakkar Sub Division HPPWD Nerchowk. (Nerchowk Section). (SH:- Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc).	96800	2000	350	One Month	"D"
8	Restoration of rain damages on Amblagaloo Ghadyater Sunder Nagar road km 0/0 to 13/600. (SH:- Construction of wire crate R/wall at RD 5/885 to 5/891).	76054	1600	350	Two Months	"D"
9	A/R & M/O of various roads under Rewalsar Sub Division HPPWD Rewalsar. (SH:- Preparation of Forest Diversion Case with including online Submission). 1. Hawani Galoo to Reur via Jalpa Mata Mandir road km 0/0 to 2/500).	95000	2000	350	Six Months	"D"
10	Restoration of rain damages on various roads under Chakkar Sub Division HPPWD Nerchowk. (Ratti Section). (SH:- Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc).	94600	2000	350	One Month	"D"

11	Balance work of SLBS Govt. Medical College & Hospital at Nerchowk Distt. Mandi (HP). (SH:- Construction of Roof/ Paragola at main entry of Teritary Care Center (T.C.C.).	99831	2000	350	Two Months	"D"
12	Restoration of rain damages on various roads under Rewalsar Sub Division HPPWD Rewalsar. (Sardhwar Section). (SH:- Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc).	99000	2000	350	One Month	"D"
13	Annual repair and maintenance of various Non-Residential buildings of SLBSGMC&H at Nerchowk, Distt. Mandi HP. (SH:- Providing and fixing of toughened glass Door with its accessories at various locations of Hospital and Medical College).	96206	2000	350	Two Months	"D"
14	A/R & M/O Chandigarh Mandi Manali road km 184/600 to 198/050. (SH:- Costruction of unlined surface drain in km 191/0 to 193/0).	99630	2000	350	One Month	"D"
15	Restoration of damages due to laying of O.F.C. on Kalkhar Leda Sundernagar road (SH. Providing and fixing blinds and curtains for Divisional office building HPPWD Nerchowk).	98758	2000	350	One Month	"D"
16	Construction of Chandyal to Chhatru via Sihal Trambi road km 0/00 to 6/00. (SH:- Providing and filling selected soil in road stretch from RD 0/0 to 0/023) Under SCDP.	98618	2000	350	One Month	"D"
17	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Supplying and stacking at site stone aggregate Grade-III 53mm to 22.4mm for repair of pot holes). Ratti Section.	96525	2000	350	15 Days	"D"
18	Restoration of rain damages on Galma Majhyali road km 0/0 to 9/0. (SH:- Construction of Breast wall at RD 2/810 to 2/817.50).	89275	2000	350	Two Months	"D"
19	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Hiring of tractor with trolley for carriage of muck/ debris and shifting of materials etc).	99000	2000	350	Three Months	"D"
20	Addition & alteration work in Atal Medical & Research University HP in the compus of SLBS Govt. Medical College & Hospital at Nerchowk. (SH:- Balance work of providing and fixing aluminium partion walls in lobby).	82096	1700	350	One Month	"D"
21	RRD on various roads under Rewalsar Sub Division HPPWD Rewalsar. (SH:- Hiring of JCB for clearing of debris drains and dressing of berms etc). (Rewalsar Section).	99750	2000	350	One Month	"D"
22	RRD on various roads under Rewalsar Sub Division HPPWD Rewalsar. (SH:- Hiring of JCB for clearing of debris drains and dressing of berms etc). (Leda Section).	97650	2000	350	One Month	"D"
23	Annual repair and maintenance of Non-Residential buildings of SLBSGMC & H at Nerchowk, Distt. Mandi (HP). (SH:- Supply and stacking Accessories items for repair and maintenance work).	99272	2000	350	Two Months	"D"
24	A/R & M/O Chandigarh Mandi Manali road km 184/650 to 190/00 & 191/190 to 198/050. (SH:- Costruction of U-Shape drain at RD 188/310 to 188/334).	98544	2000	350	Two Months	"D"
25	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH:- Supplying and stacking at site stone aggregate Grade-III 53mm to 22.4mm for repair of pot holes). Galag Section.	98280	2000	350	15 Days	"D"

26	A/R & M/O on various roads under Chakkar Sub Division HPPWD Nerchowk (Gagal Section) (SH: Hiring of JCB clearing of debris drains and dressing of berms etc.).	99750	2000	350	One Month	"D"
27	A/R & M/O Chandigarh Mandi Manali road (Old NH-21) km 184/600 to 198/050. (SH: Repair of culvert at RD 188/510).	90492	1900	350	One Month	"D"
28	A/R & M/O various roads under Chakkar Sub Division HPPWD Nerchowk. (SH: Hiring of tractor with trolley for carriage of muck/ debris and shifting of materials etc).	99000	2000	350	Two Months	"D"

Note:- The Constructors/Firms should possess the following documents (Photo copy to be attached).

1. The Contractor/Firm should be enlisted with the HP.PWD. & Registration/Renewal copy attached.
2. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
3. The list of similar type of work executed and work done performance certificate issued by the concerned Executive Engineer required to be produced by the contractor along with application.
4. **Only two tenders shall be issued to each contractor.**
5. The contractor will not have more than two works in hand at the time of tender and only up to completion of work satisfactory including adherence to quality parameters further work will be awarded to him. All under taking/affidavit alongwith application that he is not having more than two works in hand in HP.PWD for execution failing which the application for issuing the tender forms shall not be accepted.
6. The contractor/firm shall be issued tenders on the production of valid GST/income tax clearance certificate.
7. As per Govt. Notification No.PBW (B)A(3)1/2020-I dated 07.10.2021, in case the tendered amount of the lowest bidder comes more than 5% in 1st call the negotiation can be conducted with him but the negotiated amount should remain within 5% of the amount put to tender (on market rate) and vide Govt notification No.PBW (B)A(3)1/2020-I dated 10.05.2023 tendered amount below 30% of the estimated cost will be accepted.


**Executive Engineer
Nerchowk Division
HPPWD Nerchowk**

DMIT No 48 for the year 2015-26

Job No. 2

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Galma Manjhail road km. 0/0 to 9/00. (SH:- Construction of Breast wall at RD. 2/817.50 to 2/825)

Estimated Cost:- 89056.00
Earnest Money :- 2000.00
Time :- Two Months

S.N	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.	In word		
0			In figure			
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth up to any lead and lift as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	9.45	172.00	Rupees One hundred seventy two and paise zero only.	Per Cubic Metre	1625.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	10.28	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	2950.00
3	Stone masonry in cement mortar in substructure complete as per drawing & technical specification clause 702.704, 1202 and 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	16.69	3650.00	Rupees Three thousand six hundred fifty and paise zero only.	Per Cubic Metre	60919.00
4	Construction of dry rubble stone masonry for retaining and Breast walls as per drawing & technical specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	11.22	2100.00	Rupees Two thousand one hundred and paise zero only.	Per Cubic Metre	23562.00
			Total			89056.00

Draft schedule of quantity approved for Rs 89056/-
(Rupees Eighty Nine Thousand and Fifty six only)

Executive Engineer,
HPPWVD Division,
HPPWVD, Nerchowki

DRAFT Sr.No 71 For Ho Year 2015-26

Job No. 2

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of toilet at G.S.S.S. Rajgarh Tehsil Ballh. (SH:- Providing and fixing WC and sanitary items) Deposit work

Estimated Cost:- 99071.00
Earnest Money :- 2000.00
Time :- Two Months

S No	Description of item	Quantity	Rate with all taxes including GST in Rs		Unit	Amount
			In figure	In word		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means in all kinds of soil over areas (exceeding 30 cm (thirty centimetre) in depth, 1.5 m (one point five metre) in width as well as 10 sqm (ten squaremetre) on plan) including getting out and disposal of excavated earth all complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.84	290.00	Rupees two hundred ninety and paise zero only.	Per Cubic Metre	1114.00
2	Providing form work with steel plates 3.15mm (Three point one five millimetre) thick welded with angle iron in frame 30x30x5mm (Thirty into thirty into five millimetre) so as to give a fair finish including centering, shuttering, strutting and propping etcetera with wooden battens and ballies for all heights of propping and centering below supporting floor to ceiling upto all height and removal of the same for in-situ reinforced concrete and plain concrete work in :					
2.01	Flat surface such as soffits of suspended floors, roofs, landings and the like upto any thickness including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	6.58	468.30	Rupees four hundred sixty eight and paise thirty only	Per square metre	3081.00
2.02	Edges of slabs and breaks in floors and walls in any width within all leads, lifts and carriage of materials and other incidentals or as per direction and satisfaction of Engineer-in-Charge.	10.28	131.50	Rupees one hundred thirty one and paise fifty only	Per Rmt.	1352.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation/ Plinth complete as per drawing and technical specification in cement concrete 1:3:6 (one cement, three sand : six graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	0.77	4400.00	Rupees four thousand four hundred and paise zero only.	Per cubic Metre	3388.00
4	Providing and laying in position specific grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level 1:1.5:3 (one cement : one and half coarse sand) : three graded stone aggregate 20 mm (Twenty millimetre) nominal size) Foundation and footing and base of column and mass concrete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.					
4.01	Suspended floors, roofs, landings and shelves and their support balconies beams, girders, bressumers and cantilevers upto all floor level including mixing concrete within all leads, lifts and carriage of materials and other incidentals or as per direction and satisfaction of Engineer-in-Charge.	0.79	7835.20	Rupees seven thousand eight hundred thirty five and paise twenty only.	Per cubic Metre	6190.00
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete including cost of binding wire upto all floor level. Thermio-Mechanically Treated bars of grade Fe-500D or more including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	55.29	100.00	Rupees one hundred and paise zero only.	Per Kilogram	5529.00

6	Providing and laying Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 12.5 (twelve point five) conforming to IS:2222 in superstructure above plinth level up to floor five level in all shapes and sizes in : Cement mortar 1:6 (one cement : six coarse sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.27	6382.90	Rupees six thousand three hundred eighty two and paise ninety only.	Per Cubic Metre	8106.00
7	Providing and laying Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 (seven point five) in superstructure above plinth level up to floor five level in cement mortar 1:4 (one cement : four coarse sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	16.24	747.65	Rupees seven hundred forty seven and paise sixty five only.	Per Square Metre	12142.00
8	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in-charge. (Note - Butt hinges and necessary screws shall be paidseparately) Second class Deodar wood 40mm thick shutters including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.405	4260.00	Rupees four thousand two hundred sixty and paise zero only.	Per Square Metre	1725.00
9	Providing and fixing 30mm (Thirty millimetre) thick ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters with Stainless Steel butt hinges with necessary screws including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.80	1628.60	Rupees one thousand six hundred twenty eight and paise sixty only.	Per square metre	4560.00
10	Providing second class deodar wood work in frames of doors, windows, clerestory, windows and other frames wrought, framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast or dash fastener shall be paid for separately) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.0378	95500.00	Rupees ninety five thousand five hundred and paise zero only.	Per cubic metre	3610.00
11	Boulder filling dry hand packed tightly under flooring complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.99	1100.10	Rupees one thousand one hundred and paise ten only.	Per cubic metre	1089.00
12	15mm (Fifteen millimetre) thick cement plaster in single coat on rough side of brick/concrete/stone walls for internal plastering upto all heights including arrises, internal rounded angles, chamfers and / or rounded angles not exceeding 80mm in girth and finished even and smooth, cement mortar 1:4 (one cement : four sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	16.24	220.00	Rupees two hundred twenty and paise zero only.	Per cubic metre	3573.00
13	6mm (Six millimetre) thick cement plaster in single coat in cement mortar 1:3 (one cement : three fine sand) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.00	190.10	Rupees one hundred ninety and paise ten only.	Per cubic metre	380.00
14	Finishing wall with Textured Exterior Paint of required shade in new work (Two or more coats applied @ 3.38 Ltr/Sqm (three point thirty eight litre/ Square metre) over and including priming coat applied @ 2.20 kg/10 Sqm (two point twenty kilogram/ten square metre) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	16.24	196.05	Rupees one hundred ninety six and paise zero five only.	Per square metre	3184.00

15	Distempering with dry distemper of approved brand and manufacture (two coats) and of required shade on new work, over and including water thinnable primer coat to give an even shade after thoroughly brushing the surface free from mortar droppings and other foreign matter including preparing the surface even and sand papered smooth including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.00	72.45	Rupees seventy two and paise forty five only.	Per square metre	145.00
16	Applying priming coat With ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.81	35.00	Rupees thirty five and paise zero only	Per square metre	28.00
17	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.81	94.30	Rupees ninety four and paise thirty only.	Per Square Metre	76.00
18	Providing and fixing expansion hold fasteners on C.C./R.C.C./ Brick masonry surface backing including drilling necessary and bolt etc. completed. Fastener with threaded dia 6mm (six millimetre) including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	8.00	27.45	Rupees twenty seven and paise forty five only.	Each	220.00
19	Providing and fixing aluminium handles. ISI marked, anodised (anodic coating not less than grade AC 10 (ten) as per IS : 1868 (one thousand eight hundred sixty eight)) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.					
19.01	100mm (one hundred millimetre)	4.00	50.75	Rupees fifty and paise seventy five only.	Each	203.00
19.02	125mm (one hundred twenty five millimetre)	2.00	57.55	Rupees fifty seven and paise fifty five only.	Each	115.00
20	Providing and fixing 300X16mm (three hundred into sixteen millimetre) oxidised M.S. sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 (ten) as per IS : 1868 (one thousand eight hundred sixty eight), transparent or dyed to required colour or shade, with nuts and screws etc. complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.00	250.10	Rupees two hundred fifty and paise ten only.	Each	500.00
21	Providing and fixing aluminium tower bolts (barrel type), ISI marked, anodised (anodic coating not less than grade AC 10 (ten) as per IS : 1868 (one thousand eight hundred sixty eight)) transparent or dyed to required colour or shade, with necessary screws etc. complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.					
21.01	100mm (one hundred millimetre)	2.00	77.20	Rupees seventy two and paise twenty only.	Each	154.00
21.02	125mm (one hundred twenty five millimetre)	4.00	99.20	Rupees ninety nine and paise twenty only.	Each	397.00

22	Steel work welded in built up section/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc as required. In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	10.80	89.65	Rupees eighty nine and paise sixty five only	Kilogram	958.00
23	Providing and laying 600x600 mm (six hundred millimetre) size Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % (zero point zero eight percent) and conforming to I.S. 15622, of approved brand & manufacturer, in all colours & shade, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477 average 6mm (six millimetre) thickness, including grouting the joint (Payment for grouting of joints to be made separately)etc, including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	4.62	1412.96	Rupees eighty nine and paise sixty five only.	Per Square Metre	6528.00
24	Providing and laying 600x600 mm (six hundred millimetre) size Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % (zero point zero eight percent) and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm (twelve millimetre) thick bed of cement mortar 1:3 (one cement: three coarse sand), jointing with grey cement slurry @ 3:3 (three point three) kg/ sqm including grouting the joint with white cement & matching pigments etc, complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	6.095	1375.25	Rupees one thousand three hundred seventy five and paise twenty five only.	Per Square Metre	8382.00
25	Providing and fixing wash basin with C.I. brackets, . 32 mm (thirty two millimetre) C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous Chinawash basin size 630x450mm (six hundred thirty into four hundred fifty millimetre) of Cera or its equivalent including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	2643.75	Rupees two thousand six hundred forty three and paise seventy five only.	Each	2644.00
26	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 (ten) litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS: 7231, with all fittings and fixtures complete including cutting and making good the W.C pan with ISI marked white solid plastic seat and lid including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	4990.00	Rupees four thousand nine hundred ninety and paise zero only.	Each	4990.00
27	Providing and fixing Polyethelene-Aluminium -Polyethelene PE-AL-PE composite tank, IS : 12701(twelve thousand seven hundred one) marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	500.00	8.80	Rupees eight and paise eighty only.	Litres	4400.00

28	Providing and fixing rectangular shape 453x357mm (four hundred fifty three into three hundred size with plastic moulded frame of approved quality) and of required shape and AC sheet or ply wood sheet and fixed to wooden plugs with CP brass screws and washers complete in all respect as directed by Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	1.00	880.00	Rupees eight hundred eighty and paise zero only.	Each	880.00
29	Providing and fixing G.I pipes complete with G.I fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.					
29.01	(a) 15 mm (fifteen millimetre) nominal bore	1.00	225.50	Rupees two hundred twenty five and paise fifty only.	Per Running Metre	225.00
29.02	(b) 20 mm (twenty millimetre) nominal bore	1.00	278.20	Rupees two hundred seventy eight and paise twenty only.	Per Running Metre	278.00
30	Providing and fixing 110mm (one hundred ten millimetre) diameter PVC collars ISI marked including fixing with approved adhesive etcetera including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	97.75	Rupees ninety seven and paise seventy five only.	Each	98.00
31	Providing and fixing 110mm (one hundred ten millimetre) diameter PVC plain bend ISI marked including fixing with approved adhesive etcetera complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.00	235.25	Rupees two hundred thirty five and paise twenty five only.	Each	471.00
32	Providing and fixing 15 mm (fifteen millimetre) nominal bore C.P. brass bib cock of approved quality conforming to IS:831 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	97.00	Rupees ninety seven and paise zero only.	Each	97.00
33	Providing and fixing 110 mm (one hundred ten millimetre) high pressure PVC spigot and socket waste and ventilating pipes ISI marked including fixing with approved adhesive etc. complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	4.00	266.15	Rupees two hundred sixty six and paise fifteen only.	Per Running Metre	1065.00
34	Providing and fixing 110mm (one hundred ten millimetre) diameter PVC cowl ISI marked including fixing with approved adhesive etcetera including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	87.00	Rupees eighty seven and paise zero only.	Each	87.00
35	Providing and fixing 110mm (one hundred ten millimetre) dia drainage pipe soil, waste, and vent pipes 17.35.1 including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	298.00	Rupees two hundred ninety eight and paise zero only.	Per Running Metre	298.00

36	Constructing masonry Chamber 60x60x75cm (sixty into sixty into seventy five centimetre) inside in brick work in cement mortar 1:4 (one cement : four coarse sand) for fire hydrants, with C1 surface box 350x350mm (three hundred fifty into three hundred fifty millimetre) top diameter, 165mm (one hundred sixty five millimetre) deep (inside) with chamed lid and RCC top slab 1:2:4 mix (one cement : two coarse sand : four graded stone aggregate 20mm (twenty millimetre) nominal size), if necessary excavation, foundation concrete 1:5:10 (one cement : five fine sand : ten graded stone aggregate 40 mm (fourty millimetre) nominal size) and inside plastering with cement mortar 1:3 (one cement : three coarse sand) 12mm (twelve millimetre) thick, finished with a floating coat of neat cement complete as per standard design with 150mm (one hundred fifty millimetre) thick walls of reinforced cast in situ PCC 1:2:4 mix (one cement : two coarse sand : four graded stone aggregate nominal) size including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	3500.00	Rupees three thousand five hundred and paise zero only.	Each	3500.00
37	Providing and fixing 8 mm (eight millimetre) dia C.P. / S.S. Jet with flexible tube upto 1 (one) metre long with S.S. triangular plate to European type W.C. of quality and make including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge	1.00	297.55	Rupees two hundred ninety seven and paise fifty five only.	Each	297.55
38	Providing and fixing Sanitary Pans Dispenser including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	3000	Rupees three thousand and paise zero only.	Each	3000.00
		Total				99071.00

*Draft Schedule of Quantity checked & approved for Rs 99071/-
Rupees Ninety Nine Thousand Seventy one Only.*

[Signature]
Executive Engineer,
H.P.P.V.D. Division,
H.P.P.V.D. Nashik


DNT No. 3
 DNT No. 3
 Part to Year 2025-26

DRAFTSCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Chakkara Sub Division, HPPWD Nerchowk (Gagal Section). (SH:- Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc.).

Sr. No.	Description of item	Quantity	Unit	Estimated Cost:-		Amount
				Earnest Money:- Time:- One Month	Rate with all taxes including GST in Rs. P.	
1	Hiring of JCB one Cum bucket capacity for debris/ cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB contractor. The repair and spare including watch and ward of JCB also born by the contractor. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	85.00	Per Hour	1100.00	Rupees One Thousand One Hundred Only	93500.00
TOTAL:-						93500.00

Draft Schedule of Quantity approved for Rs 93500/-
 Rupees Ninety Three Thousand Five Hundred only


 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DMIT Ser. No 90 For the Year 2025-26.

Tab No. 4

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Ratti to Randhara road km. 0/10 to 9/00. (SH:- Construction of Breast wall at RD. 5/020 to 5/026.50)

Estimated Cost:- 98942.00
Earnest Money :- 2000.00
Time :- One Month

S.N	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.	In word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth up to any lead and lift as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	13.20	172.00	Rupees One hundred seventy two and paise zero only.	Per Cubic Metre	2270.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	10.34	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	2968.00
3	Stone masonry in cement mortar in substructure complete as per drawing & technical specification clause 702.704, 1202 and 1203. Random rubble masonry in cement mortar 1:6 (one cement : six sand) with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	16.72	3650.00	Rupees Three thousand six hundred fifty and paise zero only.	Per Cubic Metre	61028.00
4	Construction of dry rubble stone masonry for retaining and Breast walls as per drawing & technical specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	15.56	2100.00	Rupees Two thousand one hundred and paise zero only.	Per Cubic Metre	32676.00
					Total	98942.00

Draft Schedule of Quantity Approved Jorbs 98942/-
Rupees Ninety Eight Thousand Nine Hundred Forty Two Only.

Executive Engineer,
HPPWD Division,
HPPWD Nerchowki

DNIT NO. (241) FOR THE YEAR 2024-25

Vol No 5

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of road damages on Chandigarh Mandi Manali (Old NH-21) road km. 184/600 to 198/050.
 (SH:- Construction of P.C.C. Retaining wall at RD. 184/612 to 184/614)

Estimated Cost:- 82776.00
 Earnest Money :- 1700.00
 Time :- Two Months

S.N	Description of Item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.38	287.00		Per Cubic Metre	2118.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802, 803, 1202 and 1203 in cement concrete 1:3:6 (one cement: three sand : six graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	15.96	4770.00		Per Cubic Metre	76129.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204, 3, 8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	2.40	1050.00		Per Cubic Metre	2520.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3, 7 including carriage of material and other incidentals as per the direction of the Engineer-in Charge.	7.00	287.00		Each	2009.00
Total						82776.00

(Draft schedule of quantity approved for Rs. 82776/- Rupees Eighty two thousand seven hundred seventy SRX) only.

Executive Engineer,
 HPPWD Division,
 HPPWD, Nerchowk

DNIT No 45 for the Year 2025-26

Job No. 6

DRAFT SCHEDULE OF QUANTITY

Name of work:- Providing and laying Paver Block at statue of Martyr Sh. Tek Singh Mastana Village-Sayanh,
P.O. Lohara, Tehsil Balh, Distt. Mandi (HP)

Estimated Cost:- 83704.00
Earnest Money :- 1800.00
Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST		Unit	Amount
			In figure in Rs.	In word		
1	Earth work in excavation for structure as per dry and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	13.56	205.20	Rupees Two hundred Five and paise twenty only.	Per Cubic Metre	2783.00
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (One hundred millimetre) spread thickness (finished work including materials and labour) including carriage of material with in all leads, lifts and other incidentals and as per the direction of the Engineer-in-Charge.	8.14	1480.00	Rupees One thousand eight hundred eighty and paise zero only.	Per Cubic Metre	12047.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203, 1:4:8 (one cement: four sand: eight graded stone aggregate 40mm (forty millimetre) nominal size) including carriage of materials with in all leads, lifts and other incidentals and as per the entire satisfaction and direction of Engineer-in-Charge	3.08	5090.15	Rupees Five thousand ninety and paise fifteen only.	Per cubic Metre	15678.00
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm (Sixty millimetre) as per drawings and Technical Specification Clause 1504 including carriage of material with in all leads, lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	44.33	1200.00	Rupees One thousand two hundred and paise zero only.	Per Square Metre	53196.00
Total						83704.00

Draft Schedule of Quantity approved for Rs 83,704/-
Rupees Eight Three Laks Seven Hundred Four Only.


Executive Engineer,
HPPWD Division,
HPPWD Nerchowki

Vol No. 7

DIT No. 144 for 2015-16

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Chakkar Sub Division, HPPWD Nerchowk (Nerchowk Section). (SH:- Hiring of JCB for removal of silps, clearance of drains and dressing of berms etc.).

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Hiring of JCB one Cum bucket capacity for debris/ cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB contractor. The repair and spare including watch and ward of JCB also born by the contractor. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	88.00	Per Hour	1100.00	Rupees One Thousand One Hundred Only	96800.00
TOTAL:-						96800.00

Draft Schedule of Quantity approved for Rs 96800/-
Rupees Ninety Six Thousand and Eight Hundred Only.


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DWT No 20. for the Year 2025-26

Vol No. 8

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Ambalagaloo Ghadyater Sunder Nagar road km. 0/0 to 13/600.
(SH:- Construction of wire crate R/wall at RD. 5/885 to 5/891)

Estimated Cost:- 76054.00
Earnest Money :- 1600.00
Time :- Two Months

S.No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.	In word		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	15.12	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	4339.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighing not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.19	2880.00	Rupees Two thousand eight hundred eighty and paise zero only.	Per Cubic Metre	69667.00
3	Back filling behind abutment wing wall and retaining wall complete as per drawing & technical specification clause 1204.3.8 and including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	1.95	1050.00	Rupees One thousand fifty and paise zero only.	Per Cubic Metre	2048.00
Total						76054.00

Draft Schedule of Quantity checked & approved for Rs 76054/-
(Rupees Seventy Six Thousand Fifty Four only)


Executive Engineer,
HPPWD Division,
HPPWD, Merchow

DNT SR.No. 28 for the year 2025-26 No. 9

DRAFT SCHEDULE OF QUANTITY

Estimated Cost: Rs. 95000.00
 Earnes Money: Rs. 2000.00
 Time: Six months

Name of work:- A/R & M/O of various roads under Rewalsar Sub-Division, HP, PWD Rewalsar. (SH. Preparation of Forest Diversion case with including Online Submission)

(1) Hawanigaloo to Reur via Jalpa Mata Mandir road km. 0/0 to 2/500.

S.No.	Description	Qty.	Rate including GST		Unit	Amount
			Figure	Words		
1	Preparation of Forest Deversion case under Forest Conservation Act-1980 including collection of field data, preparation of Digital map, KML files, CA map, preparation of relevent documents/ Formation mandatory required to be attached with the case as per latest requirement of Ministry of Environment and forest conservation Govt. of India after getting the joint inspection/ site including computer typing in 6 copies, binding complete and getting it checked through HPPWD Division Nerchowk, Office of DFO's Mandi & Suket and Conservator of Forest Department Mandi including attending all the observations, if raised at any time by any office and to prepare the same by neatly and accurately filling in all the formats/Documents with scanning of all papers in PDF files as per requirement and as per direction of Engineer-in-charge.	1.00	95000.00	Rupees Two Lakh Ten Thousand only	Per Job	95000.00
			Total			95000.00

Quoted Rate in Figures :
 Quoted Rate in words :

Draft schedule of quantity checked and approved for Rs. 95,000/- only
 (Rs. Ninety Five Thousand only)


 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DNIT No. ~~718~~ For the Year 2025-26

Lab No. 10

DRAFTSCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Chakkur Sub Division, HPPWD Nerchowk (Ratti Section). (SH:- Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc.)

Sr. No.	Description of item	Quantity	Unit	Estimated Cost:-		Amount
				In figure	In words	
1	Hiring of JCB one Cum bucket capacity for debris/ cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB contractor. The repair and spare including watch and ward of JCB also born by the contractor. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	86.00	Per Hour	1100.00	Rupees One Thousand One Hundred Only	94600.00
TOTAL:-						94600.00

Draft Schedule of Quantity approved for Rs 94600/-
 Ruben Ninety Four Thousand Six Hundred only


 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DNI T NO 8 For the Year 2025-26

Job No. 11

DRAFT SCHEDULE OF QUANTITY

Name of work:- Balance work of SLBS Govt. Medical College & Hospital at Nerchowk Distt. Mandi (HP), (Sub Head:- Construction of Roof/ Paragola at main entry of Tertiary Care Center (T.C.C).)

Estimated Cost:- 99831.00
 Earnest Money :- 2000.00
 Time :- Two Months

S.N	Description of item	Quantity	Rate with all taxes including GST		Unit	Amount
			Rs. In figure	In word		
1	Providing and fixing 0.62mm (zero point sixty two millimetre) thick troughed prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (five) microns primer coating to back coat of polyester 5 (five) microns over 5 (five) microns primer coating including fixing with screws prepainted iron J or L hooks, bolts and nuts 6mm (six millimetre) diameter with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-Charge complete as per specification including carriage of material within all leads, lifts and other incidental charges.	48.30	1498.40	Rupees One thousand four hundred ninety eight and paise fifty five only	Per Square Metre	72373.00
2	Providing and fixing flushing 38cm (Thirty eight centimetre) overall with 0.62mm (Zero point sixty two millimeter) thick prepainted steel sheet in roofing with dipped metallic zinc coated sheet with top coat of regular modified polyester organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating Plus back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with screws prepainted iron J or L hooks, bolts and nuts 6mm (Six millimetre) diameter with prepainted GI limpet and bitumen washers complete with all accessories as required including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	29.40	933.95	Rs. Nine hundred eighty nine and paise ten only	Per Running metre	27458.00
Total						99831.00

*Draft Schedule of Quantity approved for Rs 99,831.00
 C Rupees Ninety Nine Thousand Eight Hundred Thirty one Only.*

Executive Engineer,
 HPPWD Division,
 Nerchowk

Part No. 12

DNT 58/NO/43 For the Year 2025-26

DRAFTSCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on various roads under Rewalsar Sub Division, HPPWD Rewalsar (Sardhwar Section). (SH:- Hiring of JCB for removal of slips, clearance of drains and dressing of berms etc.).

Sr. No.	Description of item	Quantity	Unit	Rate with all taxes including GST in Rs. P.		Amount
				In figure	In words	
1	Hiring of JCB one Cum bucket capacity for debris/ cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB contractor. The repair and spare including watch and ward of JCB also born by the contractor. The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	1100.00	Rupees One Thousand One Hundred Only	99000.00
TOTAL:-						99000.00

Draft schedule of Quantity checked & approved for Rs. 99000/-
C Rubens Ninety Nine Thousand Only


Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DNIT No 10 For the Year 2025-26

Vol No. 13

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Annual repair and maintenance of various non-residential buildings of SLBSGM&H at Nerchowk, Distt. Mandi (HP) (SH):- Providing and fixing of Toughened Glass Door with its accessories at various locations of Hospital and Medical College).		Estimated Cost:-		2000.00		
		Earnest Money :-		Time :- Two Months		
S.No.	Description of item	Quantity	Rate with all taxes including GST		Unit	Amount
			In figure	In word		
1	Providing and fixing Toughened glass panes of 12mm thickness weight not less than 30kg for doors including carriage of materials within all leads and lifts and other incidentals and as per the direction and satisfaction of Engineer-in-Charge.	14.21	4018.70	Rupees Four Thousand Eighteen and paise Seventy only	Per Square Metre	57106.00
2	Providing and fixing S.S. Door Handels, (600 mm) ISI marked, with necessary screws etc. complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.00	900.00	Rupees Nine Hundred and paise Nil only	Set	4500.00
3	Providing and fixing Connector for Toughened glass fittings with necessary screws etc. complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	10.00	60.00	Rupees Sixty and paise Nil only	Each	600.00
4	Providing and fixing center lock for Toughened glass fittings with necessary screws etc. complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.00	800.00	Rupees Eight Hundred and paise Nil only	Each	4000.00
5	Providing and fixing Floor Spring Machine for Toughened glass fittings with necessary screws etc. complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	5.00	6000.00	Rupees Six Thousand and paise Nil only	Set	30000.00
Total						96206.00

*Draft Schedule of Quantity approved for Rs 96206/-
(Rupees Ninety Six Thousand Two Hundred Six Six only)*

[Signature]
Executive Engineer
Nerchowk Division
HPPWD Nerchowk

DNT No 60 For the Year 2025-26

2nd Mar. 24

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Chandigarh-Mandi- Manali road km. 184/600 to 198/050. (SH:- Construction of unlined surface drain in km. 191/0 to 193/0)

Estimated Cost:- 99630.00
 Earnest Money :- 2000.00
 Time :- One Month

S N	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P	In word		
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment as per Technical Specification Clause 307 complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1230.00	81.00	Rupees Eighty one paise zero only	Per Running Metre	99630.00
Total						99630.00

*Drafts Schedule of Quantity checked & approved by Rs 99630/-
 Rupees Ninety Nine Thousand Six Hundred Thirty only*

[Signature]
 Executive Engineer,
 HPPWD Division,
 HPPWD Nerchowk

DNT No 61 for the Year 2015-26

Lab No. 15

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages due to laying optical fiber cable on Kalkhar Leda Sundernagar road (SH:- Providing and fixing blinds and curtains for Divisional office building HPPWD Nerchowk).

Estimated Cost:-	98758.00
Earrest Money Cost:-	2000.00
Time:- One Months	

Sl. No.	Item Description	Quantity	Units	Rate including GST Rs. P.	Total amount with all taxes including GST in Rs. P.	Total amount with all taxes including GST in words
1	Providing and fixing Provide and install chromium plated brass curtain rod of 1.25mm wall thickness along with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etc. wherever required complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in-charge.	3	Per running meter	653.24	1959.72	Rupees Nine Thousand Six Hundred Three Only
2	Providing and fixing zebra blinds with all fittings and complete accessories complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in-charge.	12.00	Per square meter	4331.50	51978.00	Rupees FiftyOne Thousand Nine Hundred SeventyEight
3	Providing and fixing curtains of 4'X9' size. complete with in all leads, lifts and carriage of material and other incidental as per direction, entire satisfaction of Engineer-in-charge.	19.00	Each	1956.70	37177.00	Rupees ThirtySeven Thousand One Hundred SeventySeven Only
Total :-					98758.00	Rupees NinetyEight Thousand Seven Hundred FiftyEight Only

Draft schedule of quantity approved for Rs 98758/-
 Rubes Ninety Eight Thousand Seven Hundred Fifty Eight Only.

[Signature]
 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DMIT No 62 For the Year 2025-26

Job No. 16

DRAFT SCHEDULE OF QUANTITY

Name of work:- Construction of Chandyal to Chatru via Sihal Trambi road 0/00 to 6/00 (S.H. :- Providing and filling selected soil in road stretch from RD 0/0 to 0/023 (under SCDP)

Estimated Cost:- 98618.00
 Earnest Money :- 2000.00
 Time :- One Month

S No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs.	P.		
1	Excavating, supplying and filling of local earth by mechanical transport upto a lead of 5 km (five kilometre) also including ramming and watering of the earth in layers not exceeding 20cm (Twenty centimetre) in trenches, plinth, sides of foundation etc. complete including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	268.07	367.88	Rupees Three hundred sixty seven and paise eighty eight only.	Per cubic Metre	98618.00
Total						98618.00

Draft Schedule of Quantity approved for Rs. 98618/-
 Rupees Ninety Eight Thousand Six Hundred Eighteen Only.

[Signature]
 Executive Engineer,
 HPPWD Division,
 HPPWD-Nerchowki

DNT No 46 For the year 2025-26

Sub No. 18

DRAFT SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Galma Manjyali road km. 0/0 to 9/00. (SH:- Construction of Breast wall at RD. 2/810 to 2/817.50)

Estimated Cost:- 89275.00
 Earnest Money :- 2000.00
 Time :- Two Months

S.N	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P. In figure	In word		
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth up to any lead and lift as per technical specification clause 1603.1 and 1603.2 and as per the entire satisfaction and direction of Engineer-in-Charge.	10.72	172.00	Rupees One hundred seventy two and paise zero only.	Per Cubic Metre	1844.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	10.28	287.00	Rupees Two hundred eighty seven and paise zero only.	Per Cubic Metre	2950.00
3	Stone masonry in cement mortar in substructure complete as per drawing & technical specification clause 702.704.1202 and 1203. Random rubble masonry in cement mortar 1.6 (one cement : six sand) with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	16.69	3650.00	Rupees Three thousand six hundred fifty and paise zero only.	Per Cubic Metre	60919.00
4	Construction of dry rubble stone masonry for retaining and Breast wall as per drawing & technical specification Clause 704.6 and 1302.5 including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	11.22	2100.00	Rupees Two thousand one hundred and paise zero only.	Per Cubic Metre	23562.00
					Total	89275.00

*Draft Schedule of Quantity approved for Rs 89275/-
 (Rupees Eighty Nine Thousand Two Hundred Seventy Five only)*

[Signature]
 Executive Engineer,
 HPPWD Division,
 HPPWD Nerchovk

DNT No (3) for the Year

Vol No. 19

DRAFT SCHEDULE OF QUANTITY

Name of work: - A/R & M/O various roads under Chakkar Sub Division, H.P.PWD, Nerchowk (Gagal Section)

(SH:- Hiring of Tractor with trolley for carriage of muck/debris and shifting of material etc.

Estimated Cost Rs.99000/-
Earnest Money Rs.2000/-
Time: -Two Month

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of tractor with trolley with hydraulic lift system for carriage of material to different sites of work with in all leads & lifts and to the entire satisfaction of the Engineer-in-Charge. The tractor should work minimum 8 hours from 9 AM to 5 PM daily, any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the tractor owner which shall have to be fully compensated by him in all cases. The expenditure for fuel, lubricants, driver and repair work shall have to be borne by the tractor owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in Charge.	60 days	1650.00	Rupees one thousand Six Hundred Fifty only	Per Days	99000.00
Total:-						99000.00

Draft Schedule of Quantity checked & approved for RD-99, only

SK

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk

DNT NO. (22) FOR THE YEAR 2024-25

5) Lab No. 20

Draft Schedule of Quantity

Estimated Cost:-Rs. 82096.00
 Earnest Money:- Rs. 1700.00
 Time:- One Month

Name of work:- Addition & alteration work in Alai Medical & Research University H.P. in the campus of SLBS Govt. Medical College & Hospital at Nerchowk
 (SH:- Balance work of providing and fixing aluminium partition walls in lobby)

Sr. No.	Description of Item	Qty	Rate with all taxes including GST in Rs. P.		Unit	Amount	
			In Figure	In words			
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, milled and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) .For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	90.58	544.23	Rupees Five Hundred Forty Four and paise twenty three only	Per Kg	49236.00	
2	Providing and fixing wash basin ETIOS CAT NO-10122 With half pedestal In White Shade of Penware Jaquar/ Hindware/ Cera or equivalent including cutting holes & making good the same and carriage of materials within all leads and lifts :- Of Superior quality as per direction of Engineer-in-Charge.	3.00	Each	4078.75	Rupees Four Thousand Seventy Eight and paise Seventy Five only	Each	12236.00
3	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Semi rigid pipe 32 mm (Thirty two millimetre) dia including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	3.00	Each	76.90	Rupees Seventy Six and paise Ninety only	Each	231.00
4	Providing and fixing 20 mm (Twenty millimetre) thick gang saw cut, Roughly Finished machine cut for flooring approved shade, colour and texture laid over 20 mm (Twenty millimetre) thick base cement mortar 1:4 (1 cement: 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade With antiskid taping including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	1.80	Sqm	5446.40	Rupees Five Thousand Four Hundred Forty Six and paise Forty only	Per Sqm	9804.00
5	Providing and fixing 12 mm thick prelaminated particle board with decorative lamination on one side and balancing lamination on other side, flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge	9.60	Sqm	1096.75	Rupees One Thousand Ninety Six and paise Seventy Five only	Per Sqm	10529.00
TOTAL						82096.00	

Draft schedule of quantity approved for Rs. 82,096/- only

E. K. S. Engineer
 NRP GWD Division
 APPROVED Nerchowk

DNT No 23 for the Year 2025-26

Sub No. 21

DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on various roads under Rewalsar Sub Division HPPWD Rewalsar. (SH:- Hiring of JCB for clearing of debris drains and dressing of berms etc.) (Rewalsar Section)

Estimated Cost:- 99750.00
 Earnest Money:- 2000.00
 Time:- One month

S. No.	Description of item	Qty.	Rate with all taxes including GST in		Unit	Amount
			Rs. P. Figure	Words		
1	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	95.00	1050.00	Rupees One thousand fifty only.	Per hour	99750.00
Total						99750.00

Agel

Draft Schedule of Quantity checked & approved for Rs 99750/- only.

[Signature]
 Executive Engineer
 HPPWD Division
 Nerchowka

DMT No 28 for the year 2015-16

date No. 22

DRAFT SCHEDULE OF QUANTITY

Name of work:- RRD on various roads under Rewalsar Sub Division HPPWD Rewalsar. (SH:- Hiring of JCB for clearing of debris drains and dressing of berms etc.) (Leda Section)

Estimated Cost:-	97650.00
Earnest Money:-	2000.00
Time:-	One month

S. No.	Description of item	Qty.	Rate with all taxes including GST in		Unit	Amount
			Rs. P.	Words		
1	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	93.00	1050.00	Rupees One thousand fifty only.	Per hour	97650.00
Total						97650.00

Draft Schedule of Quantity checked & approved for Rs 97650/- only.

[Signature]
 Executive Engineer
 HPPWD Division
 Nerchowak

DNIIT No 11 For the Year 2025-26

Job No. 23

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Annual repair and maintenance of non-residential buildings of SIBSGM&H at Nerchowk, Distt. Mandi (HP)
 (SH:- Supply and Stacking Accessories Items for repair and maintenance work)

Estimated Cost:- 99272.00
 Earnest Money :- 2000.00
 Time :- Two Months

S.No.	Description of item	Quantity	Rate with all taxes including GST		Unit	Amount
			In Rs. In figure	In word		
1	Supply and stacking of Vitrified Floor Tiles 600X600mm, approved brand (SOMANY/KAJARIA etc.) and quality at site of work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	74.88	650.00	Rupees Six Hundred Fifty and paise Nil only	Per Square Metre	48672.00
2	Supply and stacking Below Counter Wash-Basin (Oval) 555X450X205 mm at site of work including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge (Cascade NXT-C0407 White)-Parryware.	12.00	3000.00	Rupees Three Thousand and paise Nil only	Nos	36000.00
3	Supply and stacking at site graded crushed stone aggregate 20 mm nominal size free from dirt, dust disintegrated pieces, deleterious and organic matter in proper stacks at site including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	4.00	1850.00	Rupees One Thousand Eight Hundred Fifty and paise Nil only	Cubic Meter	7400.00
4	Supply and stacking at site clean coarse sharp sand free from dirt, dust disintegrated pieces, deleterious and organic matter in proper stacks at site including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	4.00	1800.00	Rupees One Thousand Eight Hundred and paise Nil only	Cubic Meter	7200.00
Total						99272.00

*Draft Schedule of Quantity approved for Rs 99272/-
 C Rubens Ninety-Nine Thousand Two Hundred Seventy Two Only*

[Signature]
 Executive Engineer
 Nerchowk Division
 HPPWD Nerchowk

DNI T No 50 FOR THE YEAR 2025-26

Sub No. 24

DRAFT SCHEDULE OF QUANTITY

Name of work:- AR & M/O Chandigarh Mandi Manali road (Old NH-21) Km. 184/650 to 190/00 & 191/190 to 198/050. (SH:- Construction of U-Shape drain at RD. 188/310 to 188/334)

Estimated Cost:- 98544.00
 Earnest Money :- 2000.00
 Time :- Two Month

SN	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.	In word		
1	Earth work in excavation of foundation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	45.33	200.00	Rupees Two hundred and paise zero only.	Per Cubic Metre	9066.00
2	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification Clause 802.803, 1202 and 1203 in cement concrete 1:5:10 (one cement: five sand : Ten graded stone aggregate 40mm nominal size) including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	3.24	4240.00	Rupees Four thousand two hundred forty and paise zero only.	Per Cubic Metre	13738.00
3	Providing and laying plain/reinforced concrete in substructure as per drawing and technical specification clause 802.803, 1202 and 1203 P.C.C nominal mix 1:3:6 (One cement: three sand:six graded stone aggregate) including carriage of material with in all leads and lifts and as per the entire satisfaction and direction of Engineer-in-Charge.	13.62	4790.00	Rupees Four thousand seven hundred ninety and paise zero only.	Per Cubic Metre	65240.00
4	Providing and laying 600 mm (Six hundred millimetre) diameter reinforced cement concrete pipe NP2 (buried conduits) on first class bedding of granular material including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets.	7.50	1400.00	Rupees One thousand four hundred and paise zero only.	Per Running metre	10500.00
Total						98544.00

*Draft Schedule of Quantity approved for Rs 98544/-
 Rupees Ninety Eight Thousand Five Hundred Forty Four only*

Executive Engineer,
 HPPWD Division,
 HPPWD Nerchowk

DWT No I For the Year 2025-26

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O on various roads under Chakkar Sub Division HPPWD Nerchowk (Gagal section)

(SH: - Hiring of JCB clearing of debris drains and dressing of berms etc.)

Estimated Cost Rs. 99750/-
Earnest Money Rs. 2000/-
Time: - One Month.

208 No 26

Sr. No.	Description of Items	Qty.	Rate In		Unit	Amount
			Figure	Words		
1.	Hiring of J.C.B. one Cum bucket capacity for debris/cleaning of drain from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the J.C.B. owner which shall have to be fully compensated by him in all cases. The fuel and J.C.B. operator and stays for J.C.B. operator will be provided by the J.C.B. owner. The repair and spare including watch and ward of J.C.B. also born by the contractor/owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge.	95 hours	1050.00	Rupees one Thousand fifty only	Per hours	99750.00
Total:-						99750.00

*Draft Schedule of Quantity approved for Rs 99750/-
Rupees Ninety Nine Thousand Seven Hundred Fifty Only.*

Kelsof
SC

Assistant Engineer,
Chakkar Sub Division,
HPPWD Nerchowk.

Executive Engineer,
Nerchowk Division,
HPPWD Nerchowk.

22

D.N.I.T No. 217 for the year 2024-25

Job No. 27

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O Chandigarh Mandi Manali road (Old NH-21) km. 184/600 to 198/050. (SH:- Repair of Culvert at RD. :38/510)

Estimated Cost:- Rs. 90492.00
 Earnest Money :- Rs. 1900.00
 Time :- One Month

S No	Description of item	Quantity	Rate with all taxes including GST in		Unit	Amount
			Rs. P.	In figure		
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in-Charge.	3	4	5	6	7
2	Providing and laying concrete mechanically mixed and vibrated mix 1:3:6 (one cement: three sand: six graded, crushed stone aggregate 40mm (forty millimetre) nominal size for plain /reinforced concrete in abutments, open foundations and plinths or similar works complete as per drawings and technical specification clause 802, 803, 1202 and 1203 and curing complete including the cost of form work and carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	18.64	4770.00	Rupees Four thousand seven hundred seventy and paise zero only.	Per Cubic Metre	88913.00
Total						90492.00

Draft schedule of quantity approved for RS = 90492/- only

(Rupees Ninety thousand four hundred Ninety two) only

[Signature]
 Executive Engineer,
 HPRWD Division,
 Nerchowk

DMIT No. 58 for the Year 2025-26

Not No. 28

DRAFT SCHEDULE OF QUANTITY

Name of work:- A/R & M/O various roads under Chakkar Sub Division, HPPWD Nerchowk. (SH:- Hiring of Tractor with trolley for carriage of muck/ debris and shifting of materials etc.) (Gagal Section)

Estimated Cost:-	99000.00
Earnest Money:-	2500.00
Time:-	Three Months

S. No.	Description of item	Qty.	Rate with all taxes including GST in		Unit	Amount
			Rs. Figure	Words		
1	Hiring of tractor with trolley with hydraulic lift system for carriage of material to different sites of work with in all leads & lifts and to the entire satisfaction of the Engineer-in-Charge. The tractor should work minimum 8 hours from 9 AM to 5 PM daily. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the tractor owner which shall have to be fully compensated by him in all cases. The expenditure for fuel, lubricants, driver and repair work shall have to be borne by the tractor owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in Charge.	60.00	1650.00	Rupees One thousand six hundred fifty only.	Per day	99000.00
Total:-						99000.00

*Draft Schedule of quantity approved for ₹ 99,000 only.
(Rupees Ninety nine thousand only).*

Assistant Engineer,
Chakkar Sub-Division
Nerchowk

Executive Engineer
HPPWD Division
Nerchowk