

NOTICE INVITING TENDER


Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Division, HP: PWD, Kangra on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors/firms enlisted in HPPWD in the appropriate class for the work mentioned below on **29.09.2025 up to 11-00 A.M.** and will be opened on the same day at **11-30 A.M.** in the presence of intending contractors or their authorized representatives who may wish to be present. The tender forms can be obtained from this office on cash payment (non refundable) on **27.09.2025 up to 4.00 P.M.** The tender applications for issue of tender forms will be received in this office on **26.09.2025 up to 05.00 P.M.** The earnest money in shape FDR National Saving certificate/Saving Account/Time Deposit Account in any of the Post Office/National Bank in H.P. duly pledged in favour of Executive Engineer, HPPWD., Division, Kangra. The conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days.

Sr. No.	Name of work	Estimated cost	Earnest Money	Cost of tender form	Time Limit
1.	Balance work for C/O Pucca Path alongwith R/Wall near House of Sh. Rajan Parrihar at Shamirpur(Deposit work)(SH-P/L Cement Concrete Pavement at RD 0/030 to 0/055)	30342/-	600/-	350/-	Two Month
2.	C/O ambulance road to Bandh (Bhaniyari Basti)(Ward No.5 G.P. Bhangwar Tehsil & Distt. Kangra (HP)(SH:- C/O 3.00 mtr. Span R.C.C. slab culvert at RD 0/012(Sub Work:- Excavation work, Bed Block & Dirt wall etc.)	75369/-	1550/-	350/-	Two Month
3.	Repair and additional work of Atal Bihari Vajpayee Govt. Degree College at Takipur Tehsil & Distt. Kangra(HP)(SH:- P/F A.C. Sheet ceiling)(Deposit work)	93606/-	1900/-	350/-	Two Month
4.	Repair and additional work of Atal Bihari Vajpayee Govt. Degree College at Takipur Tehsil & Distt. Kangra (HP)(SH:- P/F WS & Sl Pre-painted sheet roofing etc.)(Deposit work)	90989/-	1900/-	350/-	Two Month
5.	C/O Rait Salol road km. 7/445 to 11/600(SH- P/L Cement Concrete Pavement at RD 8/015 to 8/030)(Action Plan of HPPWD under Items and Norms for Assistance under Recovery and Re construction (R&R) window of PDNA 2023)	98065/-	2000/-	350/-	Two Month
6.	Repair and additional work of Atal Bihari Vajpayee Govt. Degree College at Takipur Tehsil & Distt. Kangra(HP)(SH:- Providing and laying 60mm thick NTC interlocking tile)(Deposit work)	88500/-	1800/-	350/-	Two Month
7.	Repair and additional work of Atal Bihari Vajpayee Govt. Degree College at Takipur Tehsil & Distt. Kangra(HP)(SH:- Dismantling of steel work, precast stone slab & providing and laying O-II 63mm to 45mm)(Deposit work)	99791/-	2000/-	350/-	Two Month
8.	Repair and additional work of Atal Bihari Vajpayee Govt. Degree College at Takipur Tehsil & Distt. Kangra (HP)(SH:- P/L C.C. 1:2:4 Cement Plaster Steel work & Paint etc.)(Deposit work)	96148/-	2000/-	350/-	Two Month

Certified that tender of above works are being called of urgent nature in public interest.

TERMS & CONDITIONS:-

1. The contractors/firms should produce the attested copy of latest enlistment and renewal enlisted in HPPWD, GST No. and EPF No. with the application failing which their application will not be entertained.
2. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
3. The Earnest Money for the above works should be required at the time of sale of tender forms.
4. The contractor/firms should be quoted percentage rate in the tender both in figures and in words failing which tender is likely to be rejected.
5. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason


Executive Engineer,
HPPWD, Division, Kangra.
Distt. Kangra (H.P.)


(On behalf of Governor of Himachal Pradesh)

Endst:- No.PW/KD/CB/Tenders/2025-26-
Copy is forwarded to:-

3786-3800 Dated:-

22/9/25

1. The Computer Cell Office of the Engineer-in-Chief, HPPWD., Shimla for uploading the NIT on the Department website.
2. The Chief Engineer (KZ) HPPWD., Dharamshala for information please.
3. The Superintending Engineer, 5th Circle, HPPWD., Palampur for information please.
4. All the Assistant Engineer's working under Kangra Division.
5. NIT Register.
6. All Head of Branches.
7. Notice Board.


Executive Engineer,
HPPWD, Division, Kangra.
Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY


NAME OF WORK :- BALANCE WORK FOR CONSTRUCTION OF PUCCA PATH ALONG WITH R/WALL NEAR HOUSE OF SH RAJAN PARRIHAR AT SHAMIRPUR (DEPOSIT WORK)(SUB HEAD:- PROVIDING AND LAYING CEMENT CONCRETE PAVEMENT AT RD 0/30 TO 0/055.

Estimated Cost:- 30342.00
Earnest Money:- 600/-
Time Limit:- TWO MONTH

Sr. No.	DESCRIPTION OF ITEM	QTY.	UNIT	RATES		AMOUNT
				In Figures	In Words	
1	Providing and laying mechanically mixed and vibrated, concrete for plain cement concrete in open foundation of all type of structure complete, grade-M-20 (M twenty) nominal mix 1:2:4 (One cement isto Two sand isto Four graded crushed stone aggregate 20mm (Twenty milimetre) nominal size with cement contents not les than of 330 (Three hundred thirty) Kilogramme Per Cubic metre with 20mm (Twenty milimetre) nominal size graded crushed stone aggregate and curing complete, for all heights/ depths including the cost of form work as per drawings and MORD technical section 800, 900 and 1200 and as per the direction of Engineer-in-Charge. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	4.80	Per Cubic metres	6321.20	Rupees Six Thousand Three Hundred & Twenty One Paise Twenty Only	30342.00
TOTAL						30342.00

EXCESS = _____ %


LESS = _____ %


 Executive Engineer
 HPPWD Kangra
 Division Kangra

SCHEDULE OF QUANTITY

NAME OF WORK :- CONSTRUCTION OF AMBULANCE ROAD TO BANDH (BHANIYARI BASTI) WARD NO 5
GRAM PANCHAYAT BHANGWAR TEHSIL AND DISTT. KANGRA (HP)(SH:- CONSTRUCTION OF 3.00 MTR SPAN
R.C.C. SLAB CULVERT AT RD 0/012(SUB WORK:- EXCAVATION WORK, BED BLOCK,& DIRT WALL ETC.

Sr. No.	DESCRIPTION OF ITEM	QTY.	UNIT	In Figures	RATES		Estimated Cost:- Earnest Money:- Time Limit:- TWO MONTH AMOUNT
					In Words	AMOUNT	
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan),including dressing of sides and ramming of bottoms,lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 50 metres hard rock(blasting prohibited)Excavation in foundation, excavated earth as per specification, approved drawing design as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within leads, lifts and other incidentals. Ther ate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	103.57	Per Cubic metres	535.45	Rupees Five Hundred & Thirty Five - Paise Fourty Five Only	55457.00	
2	Providing and laying mechanically mixed and vibrated, concrete for plain cement concrete in open foundation of all type of structure complete, grade- M-20 (M twenty) nominal mix 1:2:4 (One cement isto Two sand isto Four graded crushed stone aggregate 20mm (Twenty millimetre) nominal size with cement contents not les than of 330 (Three hundred thirty) Kilogramme Per Cubic metre with 20mm (Twenty millimetre) nominal size graded crushed stone aggregate and curing complete, for all heights/ depths including the cost of form work as per drawings and MORD technical section 800, 900 and 1200 and as per the direction of Engineer-in-Charge. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the	3.15	Per Cubic metres	6321.20	Rupees Six Thousand Three Hundred & Twenty One - Paise Twenty Only	19912.00	
TOTAL							75369.00


 Qualified Engineer
 H.P.W.D. Kangra
 District Kangra


1%
 3%
 1%

SCHEDULE OF QUANTITY

NAME OF WORK :- REPAIR AND ADDITIONAL WORK OF ATAL BIHARI VAJPAYEE GOVERNMENT DEGREE COLLEGE AT TAKIPUR TEHSIL AND DISTRICT KANGRA (H.P.)SH:-PROVIDING AND FIXING A.C. SHEET CEILING (DEPOSIT WORK)							Estimated Cost:- Earnest Money:- Time Limit:-	93606.00 1900.00 TwoMonth
Sr. No	Description of work	Qty	Unit	Rates		AMOUNT		
				In Figures	In Words			
1	Providing and fixing A.c. sheet ceiling with approved brand as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	225.15	Per. Square metre	415.75	Rupees Four Hundred & Fifteen - Paise Seventy Five Only	93606.00		
Total:							93606.00	

EXCESS = %

LESS = %



Executive Engineer,
HPPWD Kangra
Division Kangra.

SCHEDULE OF QUANTITY

Sr. No		Description of work	Qty	Unit	Rates		Estimated Cost:- Earnest Money:- Time Limit:-	TwoMonth AMOUNT
					In Figures	In Words		
NAME OF WORK :- REPAIR AND ADDITIONAL WORK OF ATAL BIHARI VAJPAYEE GOVERNMENT DEGREE COLLEGE AT TAKIPUR TEHSIL AND DISTRICT KANGRA (H.P.) (SHI-PROVIDING AND FIXING WATER SUPPLY & SANITARY INSTALLATION, PRE-PAINTED SHEET ROOFING ETC.) (DEPOSIT WORK)								
1		Providing and fixing 15mm dia(Fifteen Milimetre) wall ceiling and floor galvanised mild steel tubes (Medium grade) i/c all tube fitting such as nipple, elbows, unions, tees and clamps etc; and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, GST and any other taxes imposed by the Government.	150.28	Per. Running metre	225.50	Rupees Two Hundred & Twenty Five - Paise Fifty Only	33888.00	
2		Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	2.00	Each	3737.75	Rupees Three Thousand Seven Hundred & Thirty Seven - Paise Seventy Five Only	7476.00	
3		Providing and fixing 32mm dia (Thirty two milimetres) diametres P.V.C. (Poly Vynyl Chloride) waste pipe Supreme of Finolex/ Reliance and Vectas for wash basin or sink including brass check nut complete including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	2.00	Each	219.20	Rupees Two Hundred & Nineteen - Paise Twenty Only	438.00	
4		Providing and fixing G.I. /M.I Unions complete with G.I. fittings including trenching and refilling etc 20 mm (Twenty milimetre) nominal bore as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty--malkhana, toll tax, GST or any other taxes imposed by the Government.	2.00	Each	124.35	Rupees One Hundred & Twenty Four - Paise Thirty Five Only	249.00	
5		Providing and fixing 100mm(Hundred milimetre)sand cast iron grating for gully trap as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	2.00	Each	75.30	Rupees Seventy Five - Paise Thirty Only	151.00	
6		Providing and fixing 600x450 mm (Six-hundred into four hundred fifty milimetre) beveled edge mirror of superior glass (of approved quality) complete with 6 mm (Six milimetre) thick hard board ground fixed to wooden cleats with C.P- brass- screws and washers complete. including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	2.00	Each	1659.70	Rupees One Thousand Six Hundred & Fifty Nine - Paise Seventy Only	3319.00	

7	Providing and fixing flat back 600x20mm (Six hundred into twenty millimetres) Towel rail of complete fitting Prayag/ Hindware/Cera I.S. marked complete with C.P. (Chromium plated) brass brackets fixed to wooden plugs with Chromium Plated brass screws, as per specification, approved drawing, design including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	2.00	Each	435.50	Rupees Four Hundred & Thirty Five - Paise Fifty Only	871.00
8	Providing and fixing Brass bib tap of 15 mm dia. Long body as per specification, approved drawing, design, including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	2.00	Each	650.00	Rupees Six Hundred & Fifty Only	1300.00
9	Steel work of TATA/SAIL/TISCO welded in built up sections in trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint in trusses and trussed purlins in building complete, as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	177.80	Per Kilogram	124.00	Rupees One Hundred & Twenty Four Only	22047.00
10	Providing and fixing 0.60mm thick prepainted steel sheet in(TATA) roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax, GST or any other taxes imposed by the Government.	17.00	Per. Square metre	1250.00	Rupees One Thousand Two Hundred & Fifty Only	21250.00
Total:						90989.00

DNIT checked and approved for Rs 90989 -/-

gln

Executive Engineer,
HPPWD Kangra
Division Kangra.

EXCESS = %


LESS = %

SCHEDULE OF QUANTITY

NAME OF WORK:- CONSTRUCTION OF RAIT SALOL ROAD KM. 7/445 TO 11/600(SH:- PROVIDING AND LAYING CEMENT CONCRETE PAVEMENT AT RD 8/015 TO 8/030)ACTION PLAN OF HPPWD UNDER ITEMS AND NORMS FOR ASSISTANCE UNDER RECOVERY AND RECONSTRUCTION (R&R) WINDOW OF PDNA 2023		Estimated Cost:- 98065.00				
		Earnest Money:- 2000/-				
		Time Limit:- Two Month				
Sr. No.	Description of work	Qty	Unit	Rates		AMOUNT
				In Figures	In Words	
1	Providing and laying spreading and compacting stone aggregate of specified size to water bound macadam specifications in including spreading in uniform thickness, hand packing, rolling with 3 wheeled road/ vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening/ binding material to fill up interstices of coarse aggregate, watering and compacting to the required density. Grading 2 as per technical specifications clause 405. By Mechanically Means. as per the direction of the Engineer-in-Charge including carriage of material with in all leads, lifts and other incidental. The rate including of octroi, royalty, Malkhana, toll tax, GST or other taxes imposed by the government.	4.90	Per Cubic metres	2526.50	Rupees Two Thousand Five Hundred & Twenty Six - Paise Fifty Only	12380.00
2	Providing and laying design mix cement concrete of M-30 Grade in roads/taxi trucks /runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm. nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeves/tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction /expansion, construction & longitudinal joints (10 mm wide x50mm deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineer-in Charge (item of joint fillers, sealants, dowel bars, with sleeve/tie bars to be paid separately)	11.50	Per Cubic metres	7450.85	Rupees Seven Thousand Four Hundred & Fifty - Paise Eighty Five Only	85685.00
				Total:		98065.00

EXCESS = _____ %


LESS = _____ %


 Executive Engineer,
 HPPWD Kangra
 Division, Kangra

SCHEDULE OF QUANTITY

NAME OF WORK :- REPAIR AND ADDITIONAL WORK OF ATAL BIHARI VAJPAYEE GOVERNMENT DEGREE COLLEGE AT TAKIPUR TEHSIL AND DISTRICT KANGRA (H.P.) SHE-PROVIDING AND LAYING 60MM THICK NTC INTERLOCKING TILE) (DEPOSIT WORK)						Estimated Cost:- Earnest Money:-	88500.00 1800.00
Description of work						Time Limit:-	Two Month
Sr. No	Qty	Unit	In Figures	In Words	Rates	AMOUNT	
1	70.80	Per. Square metre	1250.00	Rupees One Thousand Two Hundred & Fifty Only	88500.00	88500.00	
						Total:	88500.00

ONLY CHECKED and approved for Rs 88500/-


 Executive Engineer,
 HPPWD Kangra
 Division Kangra.

EXCESS = _____ %

LESS = _____ %

SCHEDULE OF QUANTITY

Sr. No		Description of work	Qty	Unit	Rates		Estimated Cost:- Earnest Money:- Time Limit:-	AMOUNT
					In Figures	In Words		
NAME OF WORK :- REPAIR AND ADDITIONAL WORK OF ATAL BIHARI VAJPAVEE GOVERNMENT DEGREE COLLEGE AT TAKIPUR TEHSIL AND DISTRICT KANGRA (H.P.) (SH:-DISMANTLING OF STEEL WORK, PRECAST STONE SLAB, & PROVIDING AND LAYING G-II 63MM TO 45 MM) (DEPOSIT WORK)								
1		Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc, including dismembering and stacking within 50 metres (Fifty meters) lead as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	634.44	Per Kilogram	2.35	Rupees Two - Paise Thirty Five Only	1491.00	99791.00 2000.00 Two Month
2		Dismantling precast concrete or stone slabs in walls, partition walls including stacking of serviceable materials and disposal of unserviceable materials within 50 metres (Fifty metres) lead as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	103.50	Per Square metre	181.05	Rupees One Hundred & Eighty One - Paise Five Only	18739.00	
3		Excavation in foundation, trenches etcetra in earth work in all kind of classification of soil such as pick work, jumper work, pick jumper work, blasting work, soft and hard blasting and doing work in saturated soil, including chiselling or wedging out rocks where blasting work is prohibited or any other mixed variety of soil including shoring, strutting, de-watering and pumping or bailing out water (surface and sub soil water) upto any depths any quantum of water including slush which may arise during de-watering or removal of slush, lift upto any height stacking the excavated soil not more than 3 metres (Three metres) clear from the edge of excavation and then returning the stacked soil in 15cm (Fifteen centimetre) layers, when required into plinths, sides of foundation etcetra consolidating each deposited layer by ramming, watering and then disposing of all surplus excavated earth as per specification, approved drawing design as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	21.92	Per Cubic metre	489.20	Rupees Four Hundred & Eighty Nine - Paise Twenty Only	10723.00	

4	Filling with available fly ash and earth (excluding rock) in trenches or embankment in layers (each layer should not exceed 15cm), with intermediate layer of compacted earth (Soil density of 98%) after every four layers of compacted depth of fly ash, sides & top layer of filling shall be done with earth having total minimum compacted thickness 30 cm (Thirty Centimetre) or as decided by Engineer-in-charge including compacting each layer by rolling /ramming and watering, all complete as per drawing and direction of Engineer in charge. including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government	70.84	Per. Cubic metre	124.50	Rupees One Hundred & Twenty Four - Paise Fifty Only	8820.00
5	Providing, and laying spreading and compacting stone aggregate of specified size to water bound macadam specifications in including spreading in uniform thickness, hand packing, rolling with 3 wheeled road/ vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening/ binding material to fill up interstices of coarse aggregate, watering and compacting to the required density, 63mm to 45 mm size stone aggregate, Grading-II as per technical specifications clause 405. By Mechanically Means. as per the direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate including of octroi, royalty, malikhana, toll tax, GST or other taxes imposed by the government.	5.92	Per. Cubic metre	2526.50	Rupees Two Thousand Five Hundred & Twenty Six - Paise Fifty Only	14957.00
6	Brick masonry in common burnt clay building bricks in super structure above plinth level to floor any level in cement mortar 1:6 (One Cement is to Six Sand), as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	3.88	Per. Cubic metre	6700.00	Rupees Six Thousand Seven Hundred Only	25996.00
7	Half brick masonry using common burnt clay building bricks in super-structure above plinth level to floor all level in cement mortar 1:4 (One cement is to four sand) and curing complete, as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.	25.50	Per. Square metre	747.65	Rupees Seven Hundred & Forty Seven - Paise Sixty Five Only	19065.00
					Total:	99791.00

DNIT Checked and approved for Rs 99791-00/-

[Signature]
Executive Engineer,
HPPWD Kangra
Division Kangra.

EXCESS = _____ %

LESS = _____ %

SCHEDULE OF QUANTITY

NAME OF WORK :- REPAIR AND ADDITIONAL WORK OF ATAL BIHARI VAJPAYEE GOVERNMENT DEGREE COLLEGE AT TAKIPUR TEHSIL AND DISTRICT KANGRA (H.P.)-(SH)-PROVIDING AND LAYING C.C.1:2:4, CEMENT PLASTER, STEEL WORK & PAINT.ETC.X DEPOSIT WORK		Estimated Cost:-		96148.00		
		Earmest Money:-		2000.00		
Time Limit:-		Rates		TwoMonth		
Sl. No	Description of work	Qty	Unit	In Figures	In Words	AMOUNT
1	Providing and laying mechanically mixed and vibrated, concrete for plain cement concrete in open foundation of all type of structure complete, grade- M-20 (M twenty) nominal mix 1:2:4 (One cement isto Two sand isto Four graded crushed stone aggregate 20mm (Twenty milimetre) nominal size with cement contents not les than of 330 (Three hundred thirty) Kilogramme Per Cubic metre with 20mm (Twenty milimetre) nominal size graded crushed stone aggregate and curing complete, for all heights/ depths including the cost of form work as per drawings and MORD technical section 800, 900 and 1200 and as per the direction of Engineer-in-Charge. The rate is inclusive for carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	1.62	Per. Cubic metre	6321.20	Rupees Six Thousand Three Hundred & Twenty One - Paise Twenty Only	10240.00
2	15 mm (Fifteen milimetre) thick cement plaster in single coat on rough side of brick/concrete/stone walls for interior plastering up to all floor level including arises, internal angles, chamfers and rounded angles any girth and finished even and smooth with cement mortar 1:6 (One cement isto Six sand) as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	91.99	Per. Square metre	169.50	Rupees One Hundred & Sixty Nine - Paise Fifty Only	15592.00
3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate \ 20 mm nominal size). per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, GST or any other taxes imposed by the Government.	0.68	Per. Cubic metre	7958.80	Rupees Seven Thousand Nine Hundred & Fifty Eight - Paise Eighty Only	5412.00

4	Providing and laying Tor steel of TATA/ SAIL/TISCO reinforcement for Reinforced cement concrete work including cutting, straighting, bending, binding and placing in position, including cost of binding wire complete for all floor level, as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana, toll tax, GST or any other taxes imposed by the Government.	290.90	Per Kilogram	99.85	Rupees Ninety Nine - Paise Eighty Five Only	29046.00
5	Applying Birla J.k. white wall care putty (two or more coats) over plaster surface after thoroughly brushing the surface free from mortar drops, dirt, dust, loose materials and other foreign matter sand papered smooth to give final matter finish to the surface complete upto all floor levels, as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana and toll tax, sale tax, GST or any other taxes imposed by the Government.	84.69	Per. Square metre	85.00	Rupees Eighty Five Only	7199.00
6	Finishing wall with water proofing cement paint of approved brand and manufacture and of required shade on undecorated wall surface (two coats) to give an even shade after thoroughly brushing the surface to remove all dirt and remains of powered. Material as per specifications, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkhana and toll tax, sale tax, GST or any other taxes imposed by the Government.	84.69	Per. Square metre	95.00	Rupees Ninety Five Only	8046.00
7	Providing weapholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia (Hundred milimetre) PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drainage face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction and entire satisfaction of Engineer-in-charge and as per the drawing and carriage of labour, equipments and materials to various location through transportation in all leads, and other incidental complete in all respect. The rate including octroi, royalty, toll tax, sale tax or other taxes imposed by the Government.	20.00	Each	422.50	Rupees Four Hundred & Twenty Two - Paise Fifty Only	8450.00
8	Painting steel work with deluxe Multi surface paint to give an even shade. Two or more coat applied at the rate of 0.90ltr/ 10 square metre over an under coat of primer applied at the rate of 0.80 ltr/10 sqm of approved brand and manufacture nerolac/ Asian, Burger paint as per direction and entire satisfaction of Engineer-in-charge and as per the drawing and carriage of labour, equipments and materials to various location through transportation in all leads, and other incidental complete in all respect. The rate including octroi, royalty, toll tax, sale tax or other taxes imposed by the Government.	82.40	Per. Square metre	89.30	Rupees Eighty Nine - Paise Thirty Only	7358.00

<p>9) Providing form work with steel plates 3.15mm.(Three decimal one five millimetre) thick welded with angle iron frame of 30x30x5mm.,(Thirty into thirty into five millimetre)so as to give a fair finish including centring,shuttering, strutting and propping etcetra with wooden battens and ballies complete upto all heights/ depth of propping and centering below supporting floor to ceiling for all height and removal of the same for insitu-reinforced concrete and plain concrete work in Flat surfaces such as soffits of suspended floors, roofs, landings and the like, as per specification, approved drawing, design, as per entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, GST or any other taxes imposed by the Government.</p>	10.26	Per. Square metre	468.30	Rupees Four Hundred & Sixty Eight - Paise Thirty Only	4805.00
Total:				96148.00	

ONIT checked and approved @ 96148.00/-

[Signature]

Executive Engineer,
HPPWD Kangra
Division Kangra.

EXCESS = %

LESS = %