

Dated:- 19-09-2025

To

The Executive Engineer (IT Cell),  
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- **Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PW(B) A (3)1/2024 dated Shimla-2 the 03-01-2024 as the works mentioned in the tender Notice are urgent in nature and in public interest.

**Encl:-Copy of NIT**

Executive Engineer,  
Shimla Rural Division  
H.P.P.W.D. Dhani  
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer,  
Shimla Rural Division  
H.P.P.W.D. Dhani  
Ph. 0177-2790534

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
NOTICE INVITING TENDER

Sealed percentage tenders on F.W.D Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P. J. D. Dhani on behalf of Government of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R, whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **29.09.2025 up to 11:30 AM** and the same shall be opened on the same day at **12:00 P.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **27.09.2025 up to 4.30 PM** and the application for issue of tender form shall be received on **26.09.2025 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposits at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division H.P.PWD Dhani must be accompanied with the application for tender documents. Please note any exemption order of earnest money will be entertained. Conditional tenders and the tender received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD	Time	Cost of Form
1	R/R damages on Kadharghat to Domehar road Km.0/00 to 5/00 (SH: Hiring of JCB & Tipper for removal of slips at Km. 0/00 to 2/500).	99080/-	2000/-	One Month	Rs. 50/-
2	R/R damages on Kadharghat to Domehar road Km.0/00 to 5/00 (SH: Hiring of JCB & Tipper for removal of slips at Km. 2/500 to 5/00).	99080/-	2000/-	One Month	Rs. 50/-
3	A/R & M/O on Tara Mata temple road Km. 0/00 to 2/200 (SH: Construction of unlined surface drain in Km. 0/00 to 2/00)	99750/-	2000/-	One Month	Rs. 50/-
4	A/R & M/O on Tara Mata temple road Km. 0/00 to 2/200 (SH: Maintenance of drain, trimming of grass and painting on steel railing).	99390/-	2000/-	One Month	Rs. 50/-
5	Annual repair to Director residence at Judicial Academy Ghandal (SH: Providing & Fixing Jaffari on back side, Aluminium work. Interlocking tiles and painting etc) Job No 6	97200/-	2000/-	One Month	Rs. 50/-
6	Annual repair to Director residence at Judicial Academy Ghandal (SH: Providing & Fixing Jaffari on back side, Aluminium work. Interlocking tiles and painting etc) Job No 5	90181/-	2000/-	One Month	Rs. 50/-
7	A/R & M/O to Judicial Academy at Ghandal, Distt. Shimla (HP) (SH: Painting, Polishing in set No. 5 & 6).	99954/-	2000/-	One Month	Rs. 50/-

8	C/O link road from Jalog Gadheri to village Kandharti Ojdu Shaw Seri Km. 0/00 to 1/330 (SH: C/O R/Wall at Rd. 0/244.90 to 0/249.80) Under BASP Head.	99588/-	2000/-	One Month	Rs. 250 -
9	C/O link road from Jalog Himri to village Jhurnu Km. 0/00 to 1/150 (SH: C/O R/Wall at Rd. 0/499.30 to 0/503.60) Under BASP Head.	98705/-	2000/-	One Month	Rs. 250 -
10	A/R & M/O on Pakki Bawari Shakrah Sedan road Km. 0/00 to 5/700 (SH: Maintenance of earthen shoulder, Trimming of grass, Maintenance of drain and Maintenance of hurne pipe culvert in Km. 2/800 to 5/700).	98090/-	2000/-	One Month	Rs. 350 -
11	R/R damages on Palkari Makri road Km. 0/00 to 1/600 (SH: Removal of slip at various Rds. in Km. 0/00 to 1/600).	92214/-	2000/-	One Month	Rs. 250 -
12	R/R damages on Galog Nehra Okhroo road Km. 0/00 to 11/135 (SH: Removal of slip at various Rds. in Km. 0/00 to 6/00).	99479/-	2000/-	One Month	Rs. 350 -
13	R/R damages on Galog Nehra Okhroo road Km. 0/00 to 11/135 (SH: Removal of slip at various Rds. in Km. 6/000 to 12/000).	97622/-	2000/-	One Month	Rs. 350 -
14	R/R damages on Dargi Macharyana Judioo road Km. 0/00 to 11/900 (SH: Removal of slips in between Km. 2/960 to 2/980, 3/750 to 3/780, 5/810 to 5/840 & 7/100 to 7/130).	98945/-	2000/-	One Month	Rs. 350 -
15	R/R damages on Bagipul Thachi Sarog road Km. 0/00 to 6/00 (SH: Removal of slips in between Km. 0/550 to 0/700, 1/550 to 1/580 & 1/930 to 1/970).	99306/-	2000/-	One Month	Rs. 350 -
16	R/R damages on link road from Basantpur to Naltu Km. 0/00 to 7/00 (SH: Hiring of Tipper for removal of slips on various Rds.).	98600/-	2000/-	One Month	Rs. 350 -
17	R/R damages on link road from Basantpur to Naltu Km. 0/00 to 7/00 (SH: Hiring of JCB/Rock Breaker for breaking/removal of Rock/boulder of slips at various Rds.).	99000/-	2000/-	One Month	Rs. 350 -
18	R/R damages on (1) Slapper Tattapani Sunni Luhri portion road Km. 86/00 to 104/00 & (2) Jalog to Kothi road Km. 0/00 to 5/180 (SH: Hiring of JCB for removal of slips and debris, cleaning of drain, dressing of berms at various Rds. in various roads).	99645/-	2000/-	One Month	Rs. 350 -
19	A/R & M/O Totu Taradevi bypass road Km. 0/00 to 4/105 (SH: C/O extension wing wall at Rd. 0/455 to 0/457) LHS (Balance Work).	99214/-	2000/-	One Month	Rs. 250 -
20	R/R damages on (1) Banuna to Himri road Km. 0/00 to 3/825 (2) Jalog to Gadheri road Km. 0/00 to 10/500 (SH: Removal of slips, carriage of debris, cleaning of drain, dressing of berms at various Rds. in various roads).	99645/-	2000/-	One Month	Rs. 350 -
21	R/R damages on (1) Karyali to Shara Nallah road Km. 0/00 to 104/00 & (2) Shara to village Nadoth road Km. 0/00 to 1/750 (3) Karyali to Mateog road Km. 0/00 to 1/750 (SH: Removal of slips, Carriage of debris, cleaning of drain, dressing of berms at various Rds. in various roads).	99645/-	2000/-	One Month	Rs. 350 -
22	R/R damages on Khel Ka Chaura Baggi road Km. 10/00 to 11/500 (SH: Removal of slips at various Rds.).	97868/-	2000/-	One Month	Rs. 350 -
23	A/R & M/O on link road to Mandyalu road Km. 0/00 to 2/820 (SH: Trimming of grass, maintenance of earthen shoulder, maintenance of drain in Km. 0/00 to 2/820).	99979/-	2000/-	One Month	Rs. 350 -
24	A/R & M/O on link road to village Nadukhar Km. 0/00 to 2/00 (SH: Trimming of grass, maintenance of earthen shoulder, maintenance of drain, in various road in various Rd.)	99318/-	2000/-	One Month	Rs. 350 -

25	R/R damages on Bangora Kalihatti Bastigunana road Km. 0/00 to 11/675 (SH: Removal of slips at various Rds.).	98069 /-	2000/-	One Month	Rs.350/-
26	R/R damages on Shimla Mandi road Km. 39/200 to 52/300 (SH: Hiring of Tipper for removal of slips at various Rds.).	98600 /-	2000/-	One Month	Rs.350/-
27	R/R damages on various roads under Sunni Sub Division (SH: Hiring of JCB/Rock Breaker for breaking/removal of rock/boulder of slips at various roads in various Rds.).	99000 /-	2000/-	One Month	Rs.350/-
28	R/R damages on various roads under Dargi section of sub division Dharni (SH: Removal of slips at various Rds.).	98069 /-	2000/-	One Month	Rs.350/-
29	R/R damages on thachi Seri Shalli road Km 0/00 to 3/00 (SH: Removal of slips at various Rds.).	98069 /-	2000/-	One Month	Rs.350/-
30	R/R damages on various roads under Badmain section (SH: Hiring of Tipper for removal of slips at various roads).	98600 /-	2000/-	One Month	Rs.350/-
31	R/R damages on various roads under Badmain section (SH: Hiring of JCB for removal of slips and debris, cleaning of drain, dressing of berms at various Rdss in various road).	99645 /-	2000/-	One Month	Rs.350/-
32	R/R damages on various roads under sunni section-II (SH: Hiring of Tipper for removal of slips at various roads).	98600 /-	2000/-	One Month	Rs.350/-
33	R/R damages on various roads under Sunni section-I (SH: Hiring of JCB for removal of slips and debris, cleaning of drain, dressing of berms at various Rdss in various road).	99645 /-	2000/-	One Month	Rs.350/-
34	R/R damages on various roads under Thaila section (SH: Hiring of JCB for removal of slips and debris, cleaning of drain, dressing of berms at various Rdss in various road).	99645 /-	2000/-	One Month	Rs.350/-
35	R/R damages on various roads under Thaila section (SH: Hiring of Tipper for removal of slips at various roads).	98600 /-	2000/-	One Month	Rs.350/-
36	R/R damages on Kanda Ladvi Kunihar road Km. 0/00 to 9/150 (SH: Hiring of JCB for removal of slips, cleaning of drain, dressing of shoulder & catch pit/ pot holes etc. in Km. 0/00 to 6/00).	98550 /-	2000/-	One Month	Rs.350/-
37	R/R damages on Didoghatti Karechi road Km. 0/00 to 12/015 (SH: Hiring of JCB for removal of slips, cleaning of drain, dressing of shoulder & catch pit/ pot holes etc. in Km. 6/00 to 12/015).	98550 /-	2000/-	One Month	Rs.350/-
38	R/R damages on Badhari section under Jutogh Sub Division (SH: Hiring of JCB for removal of snow/slips).	98550 /-	2000/-	One Month	Rs.350/-
39	R/R damages on Badhari section under Jutogh Sub Division (SH: Hiring of JCB for removal of snow/slips).	98550 /-	2000/-	One Month	Rs.350/-
40	R/R damages on Bangora Kalihatti Bastigunana road Km. 0/00 to 11/675 (SH: Removal of slips at various Rds.) Job No.II	99374 /-	2000/-	One Month	Rs.350/-
41	R/R damages on various roads under sub division Dharni (SH: Removal of slips at various Rds.) Job No.I.	97709 /-	2000/-	One Month	Rs.350/-
42	R/R damages on various road under sub division Dharni (SH: Removal of slips at various Rds.) Job No.II.	98020 /-	2000/-	One Month	Rs.350/-
43	R/R damages on various road under sub division Dharni (SH: Removal of slips at various Rds.) Job No.III.	98633 /-	2000/-	One Month	Rs.350/-
44	R/R damages on Nehra Shaltu Dargot road Km.0/00 to 5/530 (SH: Removal of slips at various Rds.).	98167 /-	2000/-	One Month	Rs.350/-
45	R/R damages on Baggipul Thachi Sarog road Km. 0/00 to 6/00 (SH: Removal of slips at various Rds.) Job No.I.	98848 /-	2000/-	One Month	Rs.350/-
46	R/R damages on Baggipul Thachi Sarog road Km. 0/00 to 6/00 (SH: Hiring of JCB/Rock breaker for breaking/removal of rock/boulder of slips at various Rds.).	99000 /-	2000/-	One Month	Rs.350/-

47	R/R damages on (i) Thachi Rehana road Km. 0/00 to 2/645 (ii) Link road to village Bashol Km. 0/00 to 1/700 (SH: Removal of slips at various Rds.).	98269/-	2000/-	One Month	Rs. 50/-
48	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 1/556 to 1/560).	98542/-	2000/-	One Month	Rs. 50/-
49	C/O Okhroo Nehra via Keru road Km. 0/00 to 3/00 (SH: C/O R/Wall at Rd. 1/524 to 1/528).	99324/-	2000/-	One Month	Rs. 50/-
50	R/R damages on Shoghi Salana road Km.0/00 to 8/00 (SH: Hiring of JCB for removal of slips at various Rds.).	99645/-	2000/-	One Month	Rs. 50/-
51	R/R damages on Shoghi Salana road Km.0/00 to 8/00 (SH: Hiring of Tipper for removal of slips at various Rds.).	98600/-	2000/-	One Month	Rs. 50/-
52	R/R damages on Shoghi Mehli road Km.0/00 to 12/375 (SH: Hiring of JCB for removal of slips at various Rds.).	98550/-	2000/-	One Month	Rs. 50/-
53	R/R damages on Shoghi Mehli road Km.0/00 to 12/375 (SH: Hiring of Tipper for removal of slips at various Rds.).	98600/-	2000/-	One Month	Rs. 50/-
54	R/R damages on Chauri Ki Ghatti to Yaan via Bhad road Km.0/00 to 8/850 (SH: Hiring of Tipper for removal of slips at various Rds.).	98600/-	2000/-	One Month	Rs. 50/-
55	R/R damages on Chauri Ki Ghatti to Yaan via Bhad road Km.0/00 to 8/850 (SH: Hiring of JCB for removal of slips at various Rds.).	98550/-	2000/-	One Month	Rs. 50/-
56	C/O Bag to Kayalu road Km. 0/00 to 10/500 & C/O link road Bathora to Panevat Km. 0/000 to 3/500 (SH: Providing & fixing of village board and reflectorized cautionary, mandatory and informatory sign board and RCC Km. stone/local stone).	92000/-	2000/-	One Month	Rs. 50/-
57	C/O Lambidhar to Sariaya road Km. 0/00 to 1/180 (SH: Providing & fixing of village board and reflectorized cautionary, mandatory and informatory sign board).	78000/-	2000/-	One Month	Rs. 50/-
58	A/R & M/O HPPWD Rest House building at Jalog (SH: Providing painting work and misc. work etc.).	99927/-	2000/-	One Month	Rs. 350/-
59	R/R damages on (1) Bathora to Panewat road Km. 0/00 to 3/500 & (2) Bag to Kayalu road Km. 0/00 to 10/500 (3) DGBR to Barota road Km. 0/00 to 1/550 (SH: Hiring of JCB for removal of slips and debris, cleaning of drain, dressing of berms at various Rds. in various roads).	99645/-	2000/-	One Month	Rs. 50/-

Following documents should be attached with the application for tenders:-

- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.

Executive Engineer  
Shimla Rural Division  
H.P.P.W.D. Dhamsi

Certificate

Certified that the tenders called vide this notice inviting tender for 59 (fifty nine) jobs are due to exigencies/emergency of works in the larger public interest.

Executive Engineer  
Shimla Rural Division  
H.P.P.W.D. Dhamsi

**Schedule Of Quantity**

**Name of Work :- R/R Damages on Kadharghat to Domehar Road km. 0/00 to 5/00 (SH:- Hiring of JCB & Tipper for removal of slips at Rd 0/00 to 2/500)**

Estimated Cost:- 99,080.00

Earnest Money:- 2,000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.			Rate		Unit	Amount
					In figures	In words		
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost. Including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	3	4	5	6	7	8	
2	Hiring of Tipper for removal of Land slides/slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	10.00	Day	2900.00	Rupees Two Thousand Nine Hundred Only	Per Days	29000	
<b>Total Rs</b>							<b>99080</b>	
<b>Amount Quoted by the Contractor in Percentage</b>								
<b>Note :- All the material will procured by the contractor him self</b>								

**Executive Engineer,**  
 Shimla Rural Division,  
 HP, PWD, Dhani, *[Signature]*

### Schedule Of Quantity


**Name of Work :- R/R Damages on Kadharghat to Domehar Road km. 0/00 to 5/00 (SH:- Hiring of JCB & Tipper for removal of slips at Rd 2/500 to 5/00)**

Estimated Cost:- 99,080.00

Earnest Money:- 2,000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount	
				In figures	In words			
1	2	3	4	5	6	7	8	
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	64.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per hours	70080	
2	Hiring of Tipper for removal of Land slides/slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	10.00	Day	2900.00	Rupees Two Thousand Nine Hundred Only	Per Days	29000	
<b>Total Rs</b>								
<b>Amount Quoted by the Contractor in Percentage</b>								<b>99080</b>
<b>Note :- All the material will procured by the contractor him self</b>								


  
 Executive Engineer,  
 Shimla Rural Division,  
 HP, PWD, Dhamsi.

### Schedule Of Quantity

**Name Of Work :- Annual Repair & Maintenance on Tara Mata Temple road km. 0/00 to 2/200 (SH:- Construction of Unlined surface drain in km. 0/00 to 2/000)**

Estimated Cost:- 99750.00  
 Earnest Money:- 2,000.00  
 Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge.	1995.00	Per Rmt.	50.00	Rupees Fifty Only	Per running metre	99750
<b>Total Rs.</b>							<b>99750</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

  
 Executive Engineer,  
 Shimla Rural Division,  
 HP,PWD, Dhamsi. 23/7

Schedule Of Quantity						Estimated Cost:- 99,390.00		
Name of Work :- Annual Repair & Maintenance on Tara Mata Temple road km. 0/00 to 2/200 (SH:- Maintenance of drain, Trimming of grass & painting on steel Railing)						Earnest Money:- 2000.00		
						Time:- One Months.		
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount	
				In figures	In words			
1	2	3	4	5	6	7	8	
1	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907, including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	200	Rmt	4.50	Rupees Four and Paise Fifty Only	Per running metre	900	
2	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	5940	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	26730	
3	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture. including carriage of materials with in all leads, lifts and other incidentals.	1104	Sqm	65.00	Rupees Sixty Five Only	Per Square metre	71760	
<b>Total Rs</b>								<b>99390</b>
<b>Amount Quoted by the Contractor in Percentage</b>								
<b>Note :- All the material will procured by the contractor him self</b>								

Executive Engineer,  
Shimla Rural Division,  
HP,PWD, Dhama. 6/7/22

**SCHEDULE OF QUANTITY**

**Name of Work:- Annual Repair to Director Residence at Judicial Academy Ghandal (Sh: Providing & fixing Jaffari on back Side, Aluminium Work, Interlocking tiles and painting etc. ) Job No. 6**

Estimated Cost - Rs 97200 /- only  
 Earnest Money - Rs 2000 /- only  
 Time - One Month

S. No.	Sub head and items of work	Qty.		Rate	Unit	Amount
		3	4	figures		
1	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern with the 12 mm thick (1:4) cement mortar etc. all complete including carriage of material upto all leads and lifts as per the directions of Engineer in Charge (NTC Make or its equivalent)	72.00	Sqm	1350.00	Per Square Metre	97200.00
0					<b>Total:</b>	<b>97200.00</b>

**Amount Quoted by the Contractor in Percentage**

Rs.

**Note : (i) All the material will procured by the contractor him self.**

Executive Engineer,  
 Shimla Rural Division,  
 HPPWD, Dhamsi

**SCHEDULE OF QUANTITY**

Name of Work: Amul Refer to Director Residence at Judicial Academy Ghandal (Sh: Providing & fixing Jaffari on back Side, Aluminium Work, Interlocking tiles and painting etc. ) Job No. 5

Estimated Cost - Rs 90181 /- only  
 Earnest Money - Rs 2000 /- only  
 Time - One Month

S. No.	Sub head and items of work	Qty		Rate	Unit	Amount
		3	4	5	6	7
1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS 733 and IS 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle. Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-incharge. (Glazing, paneling and dash fasteners to be paid for separately) For fixed portion: Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15) including camage of matenal upto all leads and lifts as per the direction of Engineer in Charge.	122.25	Kg	388.10	Per Kilogramme	47445.00
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle. Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-incharge. (Glazing, paneling and dash fasteners to be paid for separately) For fixed portion: Anodised aluminium (anodised transparent or dyed to required shade according to IS:1868, Minimum anodic coating of grade AC15)	69.36	Kg	449.45	Per Kilogramme	31174.00
3	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : including carriage of material in all leads and lifts as per direction of the Engineer in Charge. 300x16 mm	5.00	No.	239.60	Each	1198.00
4	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete : including carriage of material in all leads and lifts as per direction of the Engineer in Charge. 200x10 mm	10.00	No.	85.60	Each	856.00
5	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : including carriage of material in all leads and lifts as per direction of the Engineer in Charge. 100 mm	10.00	No.	50.75	Each	508.00
6	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm), with double speed adjustment with necessary accessories and screws etc. complete.	5.00	No.	1800.00	Each	9000.00
0						<b>Total: 90181.00</b>

**Amount Quoted by the Contractor in Percentage** Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,  
 Shimla Rural Division,  
 HPPWD, Dhamsi

### Schedule Of Quantity

Name of Work :- A/R & M/O to Judicial Academy at Ghandal, Distt. Shimla (HP) (SH:- Painting, Polishing in set No. 5 & 6)

Estimated Cost:- 99,954.00

Earnest Money:- 2,000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Removing dry or oil bound distemper by washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete including carriage of materials with in all leads and lifts and as per the direction of Engineer in Charge.	533.76	Sqm.	11.15	Rupees Eleven and Paise Fifteen Only	Per Square metre	5951
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. including carriage of materials with in all leads and lifts and as per the direction of Engineer in Charge.	533.76	Sqm.	85.10	Rupees Eighty Five and Paise Ten Only	Per Square metre	45423
3	Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty a required for metling the surface including carriage of materials with in all leads and lifts and as per the direction of Engineer in Charge.	533.76	Sqm.	58.75	Rupees Fifty Eight and Paise Seventy Five Only	Per Square metre	31358
4	Painting one coat (excluding priming coat) on previously painted concrete/masonry/plastered surface with readymixed paint/brushing for use on floors to give an even shade including cleaning the surface of all dirt,dust and other foreign matter and sand papering as required with including carriage of materials with in all leads and lifts and as per the direction of Engineer in Charge.	113.88	Sqm.	62.85	Rupees Sixty Two and Paise Eighty Five Only	Per Square metre	7157

5	Polishing one or more coats with french polish on Old wood and wood based surfaces to give an even surface including cleaning the surface of all dirt, dust, and sand paped smooth and including a coat of wood filler including carriage of materials with in all leads and lifts and as per the direction of Engineer in Charge.	10.49	Sqm	119.49	Rupees One Hundred Nineteen and Paise Forty Nine Only	Per Square metre	1253	
6	Repairs to plaster in patches of 2.50 Sq.M. and under and 12 to 20mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a Lead of 20 metres with:- including carriage of materials with in all leads and lifts and as per the direction of Engineer in Charge. (1:4)	33.33	Sqm.	264.35	Rupees Two Hundred Sixty Four and Paise Thirty Five Only	Per Square metre	8811	
<b>Total Rs</b>								<b>99954</b>
<b>Amount Quoted by the Contractor in Percentage</b>								
<b>Note :- All the material will procured by the contractor him self</b>								

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhama

### Schedule Of Quantity


**Name of Work :- C/O road from Jalog Gadheri to village Kandharti Ojdu shaw seri km. 0/00 to 1/330 (SH:- Construction of Retaining wall at Rd. 0/244.90 to 0/249.80 ) Under BASP Head**

**Estimated Cost:- 99,588.00**

**Earnest Money:- 2000.00**

**Time:- One Months.**

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount	
		3	4	In figures	In words			
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chisealing and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried, out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings including carriage of material within all leads and lifts.	8.92	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	1775	
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	1.13	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	403	
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.77	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	93850	
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	11.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	2090	
5	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP PWD . specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	1.47	Per cum	1000.00	Rupees One Thousand Only	Per cubic metre	1470	
<b>Total Rs.</b>								<b>99588</b>
<b>Amount Quoted by the Contractor in Percentage</b>								
<b>Note :- All the material will procured by the contractor him self</b>								

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhamsi. 

## Schedule Of Quantity

Estimated Cost:- 98,705.00

Earnest Money:- 2000.00

Time:- One Months

**Name of Work :- C/O road from Jalog Himri to village Jhutnu km. 0/00 to 1/150 (SH:- Construction of Retaining wall at Rd. 0/499.30 to 0/503.60 ) Under BASP Head**

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount	
				In figures	In words			
1	2	3	4	5		6	7	
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings including carriage of material within all leads and lifts.	6.19	Cum	199.00	Rupees One Hundred Ninety Nine Only	Per cubic metre	1232	
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth.	0.99	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	353	
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 40mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.45	Cum	5000.00	Rupees Five Thousand Only	Per cubic metre	92250	
4	Providing and laying 100mm dia metre PVC pipe for weep holes complete of approved quality Including carriage of material within all leads and lifts.	10.00	Rmt	190.00	Rupees One Hundred Ninety Only	Per running metre	1900	
5	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP PWD, specifications of 1990 volume-I. Including carriage of material within all leads and lifts.	2.97	Per cum	1000.00	Rupees One Thousand Only	Per cubic metre	2970	
<b>Total Rs.</b>								<b>98705</b>
<b>Amount Quoted by the Contractor in Percentage</b>								
<b>Note :- All the material will procured by the contractor him self</b>								

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhamsi. *S.M.*

### Schedule Of Quantity

Name of Work :- A/R & M/O Pakki Bawari Shakrah Sedan Road km. 0/00 to 5/700 (SH:- Maintenance of earth shoulder, Trimming of grass, Maintenance of earth shoulder, Maintenance Of Drain, and Maintenance of Hume pipe Culvert in km. 2/800 to 5/700)

Estimated Cost:- 98,090.00  
 Earnest Money:- 2000.00  
 Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materils within all leads and lifts and as per the direction of Engineer-In-Charge .	2860.00	Sqm	4 50	Rupees Four and Paise Fifty Only	Per Square metre	12870 00
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2860.00	Sqm	24.50	Rupees Twenty Four and Paise Fifty Only	Per Square metre	70070 00
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	2200.00	Rmt.	4.50	Rupees Four and Paise Fifty Only	Per Running Metre	9900 00
4	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908 including carriage of materils within all leads and lifts and as per the direction of Engineer-In- Charge .	3.00	No.	1750.00	Rupees One Thousand Seven Hundred Fifty Only	Each	5250 00
<b>Total Rs.</b>							<b>98090</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
 Shimla Rural Division,  
 HP, PWD, Dhamsi.

SCHEDULE OF QUANTITY


Name of work :- Restoration of rain damages on Palkari Makri Road Km. 0/00 to 1/600 (Sh: Removal of slip at various Rds. in Km. 0/00 to 1/600 )

Estimated Cost: - Rs 91214 /- only  
 Earnest Money : - Rs. 2000 /- only  
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount	
			4	5			
1	Removal of land slide slip clearance, Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	960.15	Cum	95.00	Rupees Ninety Five Only	Per cubic metre	91214.00
0							
<b>Total:</b>							<b>91214.00</b>

**Amount Quoted by the Contractor in Percentage**

Rs.

  
 Executive Engineer,  
 Shimla Rural Division,  
 HPPWD, Dhampur


SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Galog Nehra Okhroo Road Km. 0/00 to 11/135 (Sh: Removal of slip at various Rds. in Km. 0/00 to 6/00 )

Estimated Cost : - Rs 99479 /- only  
 Earnest Money : - Rs. 2000 /-only  
 Time : - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount	
			4	5			
1	2	3	figures		6	7	
1	Removal of land slide slip clearance, Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	1047 15	Cum	95.00	Rupees Ninety Five Only	Per cubic metre	99479.00
0						<b>Total:</b>	<b>99479.00</b>

<b>Amount Quoted by the Contractor in Percentage</b>	<b>Rs.</b>
--	------------

  
 Executive Engineer,  
 Shimla Rural Division,  
 HPPWD, Dharam

**SCHEDULE OF QUANTITY**

Name of work :- Restoration of rain damages on Galog Nehra Okhroo Road Km. 0/00 to 11/135 (Sh: Removal of slip at various Rds. in Km. 6/000 to 12/000 )

Estimated Cost: - Rs 97622 /- only  
 Earnest Money : - Rs. 2000 /-only  
 Time: - One Month

S. No.	Sub head and items of work	Qty.		Rate figures		Unit	Amount
		3	4	5	6	7	
1	Removal of land slide slip clearance, Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	1027.60	Cum	95.00	Rupees Ninety Five Only	Per cubic metre	97622.00
0						<b>Total:</b>	<b>97622.00</b>

**Amount Quoted by the Contractor in Percentage**

**Rs.**

Executive Engineer,  
 Shimla Rural Division,  
 HPPWD, Dhampur

Schedule Of Quantity						Estimated Cost:- 98,945.00	
Name Of Work :- R/R damages on Dargi Macharyana Judloo road Km. 0/00 to 11/900 (SH:- Removal of Slips in between km. 2/690 , 3/750 to 3/780, 5/810 to 5/840 & 7/100 to 7/130)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of land slides / slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3.5 and 1611 as per the directions of Engineer-in-Charge.	1041.53	Cum	95.00	Rupees Ninety Five Only	Per Cubic Metre	98945
<b>Total Rs.</b>							<b>98945</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will pro cured by the contractor him self</b>							

Executive Engineer,  
Shimla Rural Division,  
HP,PWD, Dhara

### Schedule Of Quantity

**Name Of Work :- R/R damages on Baggipul Thachi Sarog road Km. 0/00 to 6/00 (SH:- Removal of Slips in between km. 0/550 to 0/700, 1/550 to 1/580 & 1/930 to 1/970)**

**Estimated Cost:- 99,306.00**  
**Earnest Money:- 2000.00**  
**Time:- One Months.**

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of land slides / slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3.5 and 1611 as per the directions of Enigneer-in-Charge.	1045.33	Cum	95.00	Rupees Ninety Five Only	Per Cubic Metre	99306
<b>Total Rs.</b>							<b>99306</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
 Shimla Rural Division,  
 HP, PWD, Dharti

Schedule Of Quantity						Estimated Cost:- 98,600.00	
Name Of Work :- Restoration of rain Damages on Link road from Basantpur to Naltu km. 0/00 to 7/00 (SH:- Hiring of Tipper for removal of slips on Various Rds)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Hiring of Tipper for removal of Land slides/slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	34.00	Hour	2900.00	Rupees Two Thousand Nine Hundred Only	Per Hour	98600
<b>Total Rs.</b>							<b>98600</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
Note :- All the material will procured by the contractor him self							

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dham

### Schedule Of Quantity

**Name Of Work :- Restoration of rain Damages on Link road from Basantpur to Naltu km. 0/00 to 7/00 (SH:- Hiring of JCB/ Rock Breaker for breaking/ removal of Rock/ boulder of Slips at various Rds.)**

Estimated Cost:- 99,000.00

Earnest Money:- 2000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount	
		3	4	In figures	In words			
1	2	3	4	5	6	7	8	
1	Hiring of JCB/ Rock Breaker for breaking/ removal of rock /boulders including cost of fuel oil, lubricants wages of operational staff, any repair during operation will be carried out at his risk & cost, including carriage of machinery from one place to another at required location. Actual working will be accounted for payment & proper disposal of snow. slips will be insured by the contractor & including all leads & lifts & work will be executed as per direction of Engineer- in - Charge.	55.00	Hour	1800 00	Rupees One Thousand Eight Hundred Only	Per Hour	99000	
<b>Total Rs.</b>								<b>99000</b>
<b>Amount Quoted by the Contractor in Percentage</b>								
<b>Note : All the material will procured by the contractor or him self</b>								

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhansi

Schedule Of Quantity						Estimated Cost:- 99,645.00			
Name Of Work :- Restoration of Rain damage on (1) Slapper Tattapani Sunni Luhri Portion road km. 86/00 to 104/00 & (2) Jalog to Kothi road km 0/00 to 5/180 (SH:- Hiring of JCB for removal of slips and debris ,cleaning of drain , dressing of berms at various Rd,s in various roads.)						Earnest Money:- 2000.00			
						Time:- One Months.			
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount		
				In figures	In words				
1	2	3	4	5	6	7	8		
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow,slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge	91.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	99645		
Total Rs.							99645		
Amount Quoted by the Contractor in Percentage									
Note :- All the material will procured by the contractor him self							-		

Executive Engineer,  
Shimla Rural Division,  
HP,PWD, Dharti

## Schedule Of Quantity

**Name Of Work :- A/R & M/O Totu Tara Devi Bypass Road Km. 0/00 to 4/105 (SH:-  
Costruction of Extension Wing wall at Rd. 0/455 to 0/457 ) Left Hand Side( Balance Work)**

Estimated Cost:- 99,214.00

Earnest Money:- 2,000.00

Time:- One Month.

S.No	Description of Work	No of Qty.		Rate		Unit	Amount	
				In figures	In words			
1	2	3	4	5	6	7	8	
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited) all earth work in cutting/excavation including rock excavation shall be carried out true to lines grades, side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	3.78	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	882	
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth Including carriage of material within all leads and lifts.	7.35	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2620	
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 20 mm nominal size) for plain/ reinforced concrete in open foundation and plinth or similar works complete as per drawing and technical specification MORD clause 802, 803, 1202, 1203 & 1204 and curing complete including the cost of form work and carriage of material within all leads and lifts as per the direction of Engineer-in-Charge	19.64	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	90344	
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7	18.60	Rmt.	180.00	Rupees One Hundred Eighty Only	Per running Metre	3348	
5	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP PWD specifications of 1990 volume-I. Including carriage of material within all leads and lifts	2.40	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2020	
<b>Total Rs.</b>								<b>99214</b>
<b>Amount Quoted by the Contractor in Percentage</b>								
<b>Note :- All the material will procured by the contractor him self</b>								

Executive Engineer,  
Shimla Rural Division,  
HPPWD, Dham

### Schedule Of Quantity

**Name Of Work :- Restoration of Rain damage on (1)Banuna to Himri road km 0/00 to 3/825  
(2) Jalog to Gadheri road km 0/00 to 10/500 (SH:- Removal of slips , carriage of debris,cleaining of drain , dressing of berms at various Rd,s in various roads.)**

Estimated Cost:- 99,645.00

Earnest Money:- 2000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow, slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge	91.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	99645
<b>Total Rs.</b>							<b>99645</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhami

### Schedule Of Quantity

<b>Name Of Work :- Restoration of Rain damage on (1) Karyali to Shara Nallah road km 0/00 to 6/00 (2) Shara to village Nadoth road km 0/00 to 2/300 (3) Karyali to Mateog road km 0/00 to 1/750(SH:- Removal of slips , carriage of debris, cleaning of drain , dressing of berms at various Rd,s in various roads.)</b>						Estimated Cost:- 99,645.00	
						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5		6	7
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost .including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow,slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge	91.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	99645
<b>Total Rs.</b>							<b>99645</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

~~Executive Engineer,~~  
 Shimla Rural Division,  
 HP,PWD, Dhampur

**SCHEDULE OF QUANTITY**

Name of Work:- Restoration of rain damages on Khel Ka Chaura Baggi Road Km. 10/00 to 11/500 ( Sh: Removal of slips at various RDs)

Estimated Cost: - Rs 97868 /- only  
 Earnest Money : - Rs. 2000 /-only  
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Unit	Rate figures	Unit	Amount
1	2	3	4	5	6	7
1	Hiring of Excavator-cum-Loader for removal of slips including cost of fuel oil lubricants wages of operational staff any repair during operation will be carried out at his risk and cost including carriage of machinery from one place to another at required location. Actual working hours will be accounted for payment and proper disposal of slips will be insured by the contractor & including all leads and lifts & work shall be executed as per the direction of Engineer -in-Charge.	1030.19	Cum	95.00	Rupees Ninety Five Only	Per Cubic Meter 97868.00
<b>Total:</b>						<b>97868.00</b>

Amount Quoted by the Contractor in Percentage


Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer,  
 Shimla Rural Division,  
 HPPWD, Dhami

### Schedule Of Quantity

Name of Work :- A/R & M/O on Link road to Mandyalu road km. 0/00 to 2/820 (SH:-Trimming of Grass, Maintenance of earthen Shoulder, Maintenance of drain, in km, 0/00 to 2/820)						Estimated Cost:- 99,979.00	
						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	3525.00	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	15863
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2820.00	Sqm	24.40	Rupees Twenty Four and Paise Forty Only	Per Square metre	68808
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	1410.00	Rmt.	4.50	Rupees Four and Paise Fifty Only	Per Running Metre	6345
4	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	277.50	Sqm	32.30	Rupees Thirty Two and Paise Thirty Only	Per Square metre	8963
<b>Total Rs.</b>							<b>99979</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

  
 Executive Engineer,  
 Shimla Rural Division,  
 HP, PWD, Dhami.

### Schedule Of Quantity

Name of Work :- A/R & M/O on Link road to Village Nadukhar km. 0/00 to 2/00 & Link Road to village Kamladunghri in km. 0/00 to 1/390 (SH:-Trimming of Grass, Maintenance of earthen Shoulder, Maintenance of drain, in Various road in Various Rds.)

Estimated Cost:- 99,318.00

Earnest Money:- 2000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5		6 7	8
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	3390.00	Sqm	4.50	Rupees Four and Paise Fifty Only	Per Square metre	15255
2	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	2792.00	Sqm	24.40	Rupees Twenty Four and Paise Forty Only	Per Square metre	68125
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907. including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	1550.00	Rmt.	4.50	Rupees Four and Paise Fifty Only	Per Running Metre	6975
4	White washing two coats on parapet walls and tree trunks including preparation of surface by cleaning scraping etc. as per technical specifications Clause 1915 including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge.	277.50	Sqm	32.30	Rupees Thirty Two and Paise Thirty Only	Per Square metre	8963
<b>Total Rs.</b>							<b>99318</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhami

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Bangora Kalihatti Bastigunana Road Km. 0/00 to 11/675 (Sh: Removal of slips in various Rds)

Estimated Cost: - Rs 98069 /- only  
 Earnest Money : - Rs. 2000 /-only  
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
1	2	3	4	5	6	7
1	Removal of land slide slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	1032.31 Cum	95.00	Rupees Ninety Five Only	Per cubic metre	98069.00
0						
					<b>Total:</b>	<b>98069.00</b>

**Amount Quoted by the Contractor in Percentage**


Rs.

Executive Engineer  
 Shimla Rural Division  
 HPPWD, Dhani

Schedule Of Quantity						Estimated Cost:- 98,600.00	
Name of Work :- Restoration of rain Damages on Shimla Mandi Road km. 39/200 to 52/300 (SH:- Hiring of Tipper for removal of slips on Various Rds)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Hiring of Tipper for removal of Land slides/slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	34.00	Day	2900.00	Rupees Two Thousand Nine Hundred Only	Per day	98600
<b>Total Rs</b>							<b>98600</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhamsi.

Schedule Of Quantity						Estimated Cost:- 99000.00	
Name of Work :- Restoration of rain Damages on Various road under sub Division Sunni (SH:- Hiring of JCB/ Rock Breaker for breaking/ remvoal of Rock/ boulder of Slips at Various road in various Rds.)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Hiring of Excavator- cum- Loader for removal of rock /boulders including cost of fuel oil, lubricants,wages of operational staff, any repair during operation will be carried out at his risk & cost, including carriage of machinery from one place to another at required location. Actual working will be accounted for payment & proper diposal of snow, slips will be insured by the contractor & including all leads & lifts & work will be executed as per directon of Engineer- in - Charge.	55.00	Hour	1800.00	Rupees One Thousand Eight Hundred Only	Per Hour	99000
<b>Total Rs</b>							<b>99000</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
Shimla Rural Division,  
HP,PWD, Dhama. 

work :- Restoration of rain damages on various Roads under Dargi Section of Sub Division Dhama (Sh: Removal of slips in various Rds)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 98069 /- only  
Earnest Money : - Rs. 2000 /-only

Time: - One Month  
Rate Unit Amount  
figures

1	2	3	4	5	6	7
Sub head and items of work	Qty.		Rate		Unit	Amount
1 Removal of land slide slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	1032.31	Cum	95.00	Rupees Ninety Five Only	Per cubic metre	98069.00
<b>Total:</b>						<b>98069.00</b>

Amount Quoted by the Contractor in Percentage

Rs.

Executive Engineer  
Shimla Rural Division  
HPPWD, Dhama

**SCHEDULE OF QUANTITY**


**Chief work :- Restoration of rain damages on Thachi Seri Shalli Road Km. 0/00 to 3/00 (Sh: Removal of slips in various Rds)**

**Estimated Cost: - Rs 98069 /- only  
Earnest Money : - Rs. 2000 /-only  
Time: - One Month**

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
1	2	3	4	5	6	7
1	Removal of land slide slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	1032.31 Cum	95.00	Rupees Ninety Five Only	Per cubic metre	98069.00
0						
<b>Total:</b>						<b>98069.00</b>

**Amount Quoted by the Contractor in Percentage**

**Rs.**

  
**Executive Engineer**  
**Shimla Rural Division**  
**HPPWD, Dhamsi**

### Schedule of Quantity

**Name of Work:- Restoration of Rain damage on various Road under Badmain (Sh:- Hiring of Tipper for removal of slips in various road)**

**Estimated Cost: - Rs 98600 /- only**  
**Earnest Money :-2000/- Only**  
**Time:- One Month**

Sr. No.	Description of Work	No.of Qty.		Rate		Unit	Amount	
				In figures	In words			
1	Hiring of Tipper for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/, slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	34	Day	2900	Rupees Two Thousand Nine Hundred Only	Per Per Day	98600.00	
	Total							
<b>Amount Quoted by the Contractor in Percentage</b>								<b>98600.00</b>
<b>Note :- All the material will procured by the contractor him self</b>								

Executive Engineer,  
 Shimla Rural Division,  
 HP,PWD, Dhara

### Schedule of Quantity


**Name of Work:- Restoration of Rain damage on various Road under Badmain Section  
g(Sh:- Hiring of JCB for removal of slips and debris , cleaning of Drain , dressing of  
berms at various Rd,s in various road)**

**Estimated Cost: - Rs 99645 /- only**

**Earnest Money :-2000/- Only**

**Time:- One Month**

Sr. No.	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/, slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	91	Per Hours	1095	Rupees One Thousand Ninety Five Only	Per Hours	99645
Total							99645
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

  
 Executive Engineer,  
 Shimla Rural Division,  
 HP,PWD, Dhansi.

### Schedule of Quantity


**Name of Work:- Restoration of Rain damage on various Road under Suni Section-II (Sh. Hiring of Tipper for removal of slips in various road)**

Estimated Cost: - Rs 98600 /- only

Earnest Money :-2000/- Only


Time:- One Month

Sr. No.	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	Hiring of Tipper for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/. slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	34	Day	2900	Rupees Two Thousand Nine Hundred Only	Per Per Day	98600.00
	Total						98600.00
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

  
 Executive Engineer,  
 Shimla Rural Division,  
 HP,PWD, Dhara

### Schedule of Quantity

Schedule of Quantity							
Name of Work:- Restoration of Rain damage on various Road under Suni Section-II (Sh: Hiring of JCB for removal of slips and debris , cleaning of Drain , dressing of berms at various Rd,s in various road)						Estimated Cost: - Rs 99645 /- only	
						Earnest Money :-2000/- Only	
						Time:- One Month	
Sr. No.	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/, slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	91	Per Hours	1095	Rupees One Thousand Ninety Five Only	Per Hours	99645.00
Total							99645.00
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							


  
 Executive Engineer,  
 Shimla Rural Division,  
 HP,PWD, Dham

### Schedule of Quantity

**Name of Work:- Restoration of Rain damage on various Road under Thaila Section (Sh:- Hiring of JCB for removal of slips and debris , cleaning of Drain , dressing of berms at various Rd.s in various road)**

**Estimated Cost: - Rs. 99645 /- only**  
**Earnest Money :-2000/- Only**  
**Time:- One Month**

Sr. No.	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil. lubricants. wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/, slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	91	Per Hours	1095	Rupees One Thousand Ninety Five Only	Per Hours	99645.00
Total							99645
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							


  
 Executive Engineer,  
 Shimla Rural Division,  
 HP,PWD, Dhampur

### Schedule of Quantity

**Name of Work:- Restoration of Rain damage on various Road under Thaila Section (Sh:- Hiring of Tipper for removal of slips in various road)**

**Estimated Cost: - Rs 98600 /- only**  
**Earnest Money :-2000/- Only**  
**Time:- One Month**

Sr. No.	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	Hiring of Tipper for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow , slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	34	Day	2900	Rupees Two Thousand Nine Hundred Only	Per Day	98600.00
	Total						
	<b>Amount Quoted by the Contractor in Percentage</b>						98600.00
	<b>Note :- All the material will procured by the contractor him self</b>						

  
 Executive Engineer,  
 Shimla Rural Division,  
 HP,PWD, Dhanni.

SCHEDULE OF QUANTITY

**Name of work :-** Restoration of rain damages on Kanda Ladvi Kunihar Road Km. 0/00 to 9/150 ( Sh: Hiring of JCB for removal of slips, clearing of drain, dressing of shoulder & catch pit / pot holes etc. in Km.0/00 to 6/000 )

Estimated Cost : - Rs 98550 /- only  
 Earnest Money : - Rs. 2000 /-only

Time : - One Month  
 Rate figures

S. No.	Sub head and items of work	Qty.	Rate	Unit	Amount	
1	2	3	4	5	6	
1	Hiring of excavater Cum loader for removal of slips including cost of fuel oil lubricants, wages of operational staff any repair during operation will be carried out at his own risk, cost including carriage of machinery from one place to another at required location. Actual working hours will be accounted for payment and proper disposal of slips will be insured by the contractor and including all leads and lifts & work shall be executed as per the direction of Engineer-in-Charge.	90.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	98550.00
<b>Total:</b>					<b>98550.00</b>	

**Amount Quoted by the Contractor in Percentage**

Rs.

**Note : (i) All the material will procured by the contractor him self.**

Executive Engineer  
 Shimla Rural Division  
 HPPWD, Dhama

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Didughatti Karechi Road in Km. 0/00 to 12/015 ( Sh: Hiring of JCB for removal of slips, clearing of drain, dressing of shoulder & catch pit / pot holes etc. in Km. 6/00 to 12/015)

Estimated Cost: - Rs 98550 /- only  
 Earnest Money : - Rs. 2000 /-only  
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			3	4		
1	Hiring of excavater Cum loader for removal of slips including cost of fuel oil lubricants, wages of operational staff any repair during operation will be carried out at his own risk, cost including carriage of machinery from one place to another at required location. Actual working hours will be accounted for payment and proper disposal of slips will be insured by the contractor and including all leads and lifts & work shall be executed as per the direction of Engineer-in-Charge.	90.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour 98550.00
<b>Total:</b>						<b>98550.00</b>
<b>Amount Quoted by the Contractor in Percentage</b>						<b>Rs.</b>

Note : (i) All the material will procured by the contractor him self.

Executive Engineer  
 Shimla Rural Division  
 HPPWD, Dhama

Schedule Of Quantity						Estimated Cost:- 98,550.00	
Name of Work :- R/R damages on Badheri Section under Jutogh sub division (SH:- Hiring of JCB for removal of snow/slip)Job No. 3						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5		6 7	8
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost .including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow/,slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	90.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	98550
<b>Total Rs.</b>							<b>98550</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
Shimla Rural Division,  
HP,PWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 98,550.00	
Name of Work :- R/R damages on Badheri Section under Jutogh sub division (SH:- Hiring of JCB for removal of snow/slip)Job No. 2						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5		6 7	8
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost .including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow/,slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	90.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	98550
<b>Total Rs.</b>							<b>98550</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

6  
 Executive Engineer,  
 Shimla Rural Division,  
 HP,PWD, Dhama

## Schedule Of Quantity

Name of Work :- R/R damages on Bangora Kalihatti Bastigunana road km. 0/00 to 11/675 (SH:- removal of slips at Various Rds) Job No.II

Estimated Cost:- 99,374.00

Earnest Money:- 2000.00


Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611. The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same	1014.02	Cum	98.00	Rupees Ninety Eight Only	Per Cubic Metre	99374
<b>Total Rs.</b>							
<b>Amount Quoted by the Contractor in Percentage</b>							<b>99374</b>
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhama

### Schedule Of Quantity

Name Of Work :- R/R damages on Various road under Sub Division Dhama (SH:- Removal of Slips at various Rds) Job No-1						Estimated Cost:- 97,709.00	
						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302 3 5 and 1611 as per the directions of Enigneer-in-Charge.	1017.80	Cum	96.00	Rupees Ninety Six Only	Per Cubic Metre	97709
<b>Total Rs.</b>							<b>97709</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

  
 Executive Engineer,  
 Shimla Rural Division,  
 HP, PWD, Dhama

**Schedule Of Quantity**

**Name Of Work :- R/R damages on Various road under Sub Division Dhami (SH:- Removal of Slips at various Rds) Job No-II**

**Estimated Cost:- 98,020.00**

**Earnest Money:- 2000.00**

**Time:- One Months.**

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount	
		3	4	In figures	In words			
1	2	3	4	5	6	7	8	
1	Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3.5 and 1611 as per the directions of Enigneer-in-Charge.	1021.04	Cum	96.00	Rupees Ninety Six Only	Per Cubic Metre	98020	
<b>Total Rs.</b>								
<b>Amount Quoted by the Contractor in Percentage</b>								<b>98020</b>
<b>Note :- All the material will pro cured by the contractor him self</b>								

Executive Engineer,  
 Shimla Rural Division,  
 HP, PWD, Dhami

### Schedule Of Quantity

**Name Of Work :- R/R damages on Various road under Sub Division Dhami (SH:-  
Removal of Slips at various Rds) Job No-III**

Estimated Cost:- 98,633.00

Earnest Money:- 2000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302 3.5 and 1611 as per the directions of Enigneer-in-Charge.	1027.43	Cum	96.00	Rupees Ninety Six Only	Per Cubic Metre	98633
<b>Total Rs.</b>							<b>98633</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhami

Schedule Of Quantity						Estimated Cost:- 98,167.00	
Name Of Work :- R/R damages on Nehra Shaltu Dargot road km. 0/00 to 5/530 (SH:- Removal of Slips at various Rds)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in lift upto all leads and lifts as technical specifications 302.3 5 and 1611 as per the directions of Enigneer-in-Charge.	1033 34	Cum	95 00	Rupees Ninety Five Only	Per Cubic Metre	98167
<b>Total Rs.</b>							<b>98167</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
Shimla Rural Division,  
HP,PWD, Dhamsi


**SCHEDULE OF QUANTITY**

Name of Work:- Restoration of rain damages on Baggipul Thachi Sarog Road Km. 0/00 to 6/00 ( Sh: Removal of slips at various RDs)

Estimated Cost: - Rs 98848 /- only  
 Earnest Money : - Rs. 2000 /-only  
 Time: - One Month

S. No	Sub head and items of work	Qty.	Rate figures	Unit	Amount	
1	2	3	4	5	6	
1	Hiring of Excavator-cum-Loader for removal of slips including cost of fuel oil lubricants wages of operational staff any repair during operation will be carried out at his risk and cost including carriage of machinery from one place to another at required location. Actual working hours will be accounted for payment and proper disposal of slips will be insured by the contractor & including all leads and lifts & work shall be executed as per the direction of Engineer -in-Charge.	1040.50	Cum	95.00	Rupees Ninety Five Per Cubic Meter	98848.00
<b>Total:</b>					<b>98848.00</b>	
<b>Amount Quoted by the Contractor in Percentage</b>					<b>Rs.</b>	

Note : (i) All the material will procured by the contractor him self.


  
 Engineer in Charge  
 Civils and Infra Division  
 Bangalore

Schedule Of Quantity						Estimated Cost:- 99,000.00		
Name Of Work :- R/R damages on Baggipul Thachi Sarog road Km. 0/00 to 6/00 (SH:- Hiring of JCB / Rock breaker for breaking / removal of rock / boulder of slips at various Rds)						Earnest Money:- 2000.00		
						Time:- One Months.		
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount	
				In figures	In words			
1	2	3	4	5	6	7	8	
1	Hiring of Excavator- cum- Loader for removal of rock /boulders including cost of fuel oil, lubricants wages of operational staff. any repair during operation will be carried out at his risk & cost, including carriage of machinery from one place to another at required location. Actual working will be accounted for payment & proper diposal of snow, slips will be insured by the contractor & including all leads & lifts & work will be executed as per directon of Engineer- in - Charge.	55.00	Hour	1800.00	Rupees One Thousand Eight Hundred Only	Per Hour	99000	
<b>Total Rs.</b>								<b>99000</b>
<b>Amount Quoted by the Contractor in Percentage</b>								
<b>Note :- All the material will procured by the contractor him self</b>								

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhamsi.

**SCHEDULE OF QUANTITY**

Name of work :- Restoraton of Rain damages on (i) Thachi Rehana Road Km. 0/00 to to 2/645 (ii) Link Road to village Basol Km. 0/00 to 1/700 (Sh:- Removal of slips at various RDs.)

Estimated Cost: - Rs 94269 /- only  
Earnest Money : - Rs. 2000 /-only  
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			4	5		
1	2	3	4	5	6	7
1	Removal of land slide slip clearance in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in lift upto all leads and lifts as per direction of Engineer-in-Charge & technical specification 302.3.5 and 1611.	992.31 Cum	95.00	Rupees Ninety Five Only	Per cubic metre	94269.00
0					<b>Total:</b>	<b>94269.00</b>

**Amount Quoted by the Contractor in Percentage**

**Rs.**

Executive Engineer  
Shimla Rural Division  
HPPWD, Dhama

**Schedule Of Quantity**

**Name Of Work :- Construction of Nehra via Keru km. 0/00 to 3/00 (SH:- C/O Retaining wall at Rd. 1/556 to 1/560)**

**Estimated Cost:- 98,542.00**


**Earnest Money:- 2,000.00**

**Time:- One Months.**

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount	
				In figures	In words			
1	2	3	4	5	6	7	8	
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings Including carriage of material within all leads and lifts.	3.83	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	894	
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts	6.12	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2182	
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 20mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.58	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	90068	
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7	6.50	Rmt.	170.00	Rupees One Hundred Seventy Only	Per running Metre	1105	
5	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD., specifications of 1990 volume-I. Including carriage of material within all leads and lifts	5.10	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	4293	
<b>Total Rs.</b>								<b>98542</b>
<b>Amount Quoted by the Contractor in Percentage</b>								
<b>Note :- All the material will procured by the contractor him self</b>								

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhamsi

Schedule Of Quantity						Estimated Cost:- 99,324.00	
Name Of Work :- Construction of Nehra via Keru km. 0/00 to 3/00 (SH:- C/O Retaining wall at Rd. 1/524 to 1/528)						Earnest Money:- 2,000.00	
						Time:- One Months.	
S.No	Description of Work s	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in earth work in hilly area in all heights and depths in all kind of soil by manual/mechanical means including saturated soil comprising of mixed soil, ordinary rock and hard rock all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side, water pollution, etcetra and to protect stability of hill side track shall be excavated with chiseling and wedging out rock (where blasting is prohibited). all earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super-elevation and level as shown on the drawings including carriage of material within all leads and lifts.	4.68	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	1092
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material up to 3m depth. Including carriage of material within all leads and lifts.	7.02	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	2503
3	Providing and laying cement concrete 1:4:8 (1 cement : 4 Sand : 8 graded stone aggregate 20mm nominal size) and curing complete excluding the cost of form work in Foundation and plinth. including carriage of material The rate including octroi, royalty, Malkana toll tax, GST or any other taxes input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	19.89	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	91494
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pie extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7	11.00	Rmt.	170.00	Rupees One Hundred Seventy Only	Per running Metre	1870
5	Back filling filling behind abutment wing wall and retaining wall, and Breast walls complete including carriage of material within all leads and lifts and as per HP.PWD, specifications of 1990 volume-I. Including carriage of material within all leads and lifts	2.81	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2365
<b>Total Rs.</b>							<b>99324</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhama. 

### Schedule Of Quantity

<b>Schedule Of Quantity</b>						Estimated Cost:- 99,645.00	
<b>Name of Work :- Restoration of Rain damage on Shoghi Salana road km. 0/00 to 8/00 (SH:- Hiring of JCB for removal of Slips at various Rds)</b>						Earnest Money:- 2000.00	
						Time:- One Months.	
S No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Hiring of JCB Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	91.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	99645
<b>Total Rs.</b>							<b>99645</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
 Shimla Rural Division,  
 HP, PWD, Dhama *Sam*

### Schedule Of Quantity

**Name of Work :- Restoration of Rain damage on Shoghi Salana road km. 0/00 to 8/00  
(SH:- Hiring of Tipper for removal of Slips at various Rds)**

Estimated Cost:- 98,600.00  
Earnest Money:- 2000.00  
Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	Hiring of JCB Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	34.00	day	2900.00	Rupees Two Thousand Nine Hundred Only	Per day	98600
<b>Total Rs.</b>							98600
<b>Amount Quoted by the Contractor in Percentage</b>							98600
<b>Note :- All the material will procured by the contractor him self</b>							


Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhamsi. *Sam*

### Schedule Of Quantity

**Name of Work :- Restoration of Rain damage on Shoghi Mehli road km. 0/00 to 12/375  
(SH:- Hiring of JCB for removal of Slips at various Rds)**

Estimated Cost:- 98,550.00  
Earnest Money:- 2000.00  
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount	
		3	4	In figures	In words			
1	2	3	4	5	6	7	8	
	Hiring of JCB Excavator cum loader for removal of Land slides /slips including the cost of fuel, oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow, slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	90.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	98550	
<b>Total Rs.</b>								
<b>Amount Quoted by the Contractor in Percentage</b>								98550
<b>Note :- All the material will procured by the contractor him self</b>								

  
 Executive Engineer,  
 Shimla Rural Division,  
 HP, PWD, Dhama.

### Schedule Of Quantity

Estimated Cost:- 98,600.00

**Name of Work :- Restoration of Rain damage on Shoghi Mehli road km. 0/00 to 12/375  
(SH:- Hiring of Tipper for removal of Slips at various Rds)**

Earnest Money:- 2000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5		6 7	8
1	Hiring of JCB Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	34.00	day	2900.00	Rupees Two Thousand Nine Hundred Only	Per day	98600
<b>Total Rs.</b>							<b>98600</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhamsi. *Sm*

Schedule Of Quantity							Estimated Cost:- 98,600.00	
Name of Work :- Restoration of Rain damage on Chauri ki Ghatti to Yaan via Bhad road km. 0/00 to 8/850 (SH:- Hiring of Tipper for removal of Slips at various Rds)							Earnest Money:- 2000.00	
							Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount	
		3	4	In figures	In words			
1	2	3	4	5	6	7	8	
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow/slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	34.00	day	2900.00	Rupees Two Thousand Nine Hundred Only	Per day	98600	
<b>Total Rs.</b>								<b>98600</b>
<b>Amount Quoted by the Contractor in Percentage</b>								
<b>Note :- All the material will procured by the contractor him self</b>								

Executive Engineer,  
Shimla Rural Division,  
HP,PWD, Dhani. *[Signature]*

**Schedule Of Quantity**


Estimated Cost:- 98,550.00

**Name of Work :- Restoration of Rain damage on Chauri ki Ghatti to Yaan via Bhad road km. 0/00 to 8/850 (SH:- Hiring of JCB for removal of Slips at various Rds)**


Earnest Money:- 2000.00

Time:- One Months.

S No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	2	3	4	5	6	7	8
	Hiring of JCB excavator cum loader for removal of landslides/slips including the cost of fuel, oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location, actual working will be accounted for payment and proper disposal of snow, slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	90.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	98550
<b>Total Rs.</b>							<b>98550</b>
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
Shimla Rural Division,  
HP, PWD, Dhami 

Schedule Of Quantity						Estimated Cost:- 92,000.00	
Name of Work :-Construction of Bag to Kayalu road km 0/00 to 10/500 & C/o link road Bathora to Panevat km 0/00 to 3/500(SH:- Providing and fixing of village board and reflectorized cautionary, mandatory and information sign board and RCC Km stone/local stone)						Earnest Money:- 2000.00	
						Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Cause 1701.2.3 fixed over MS sheeting 1.5 mm thick supported on a mild steel angle iron post 75x40 Lc firmly fixed to the ground by means of properly designed foundation with M 15 grade cement concrete 450mm x 450mm x 600mm below ground level as per drawings and Technical Specification Clause 801. (identification sign with size 1200x900 (informatory sign board)	1.00	No	7000.00	Rupees Seven Thousand Only	Each	7000
2	Providing and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Cause 1701.2.3 fixed over MS sheeting 1.5 mm thick supported on a mild steel angle iron post 75x40 Lc firmly fixed to the ground by means of properly designed foundation with M 15 grade cement concrete 450mm x 450mm x 600mm below ground level as per drawings and Technical Specification Clause 801. (identification sign with size 750x600 (Village board)	11.00	No	5000.00	Rupees Five Thousand Only	Each	55000
3	Reinforced cement concrete M15 grade KM stone/local stone and standard design as per IRC 8 fixed in position including and printing etc. (5th)	2.00	No	6000.00	Rupees Six Thousand Only	Each	12000
4	Reinforced cement concrete M15 grade KM stone/local stone and standard design as per IRC 8 fixed in position including and printing etc.	4.00	No	4500.00	Rupees Four Thousand Five Hundred Only	Each	18000
<b>Total Rs.</b>							92000
<b>Amount Quoted by the Contractor in Percentage</b>							
<b>Note :- All the material will procured by the contractor him self</b>							

Executive Engineer,  
Shimla Rural Division,  
HP,PWD, Dhamsi. 

Schedule Of Quantity							Estimated Cost:- 78,000.00	
Name of Work :- Construction of Lambidhar to Sariaya road km. 0/00 to 1/180 (SH:- Providing and Fixing of village board and reflectorized cautionary, mandatory and informatory sign board)							Earnest Money:- 2000.00	
							Time:- One Months.	
S.No	Description of Work	No.of Qty.		Rate		Unit	Amount	
				In figures	In words			
1	2	3	4	5	6	7	8	
1	Providing and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide Clause 1701.2.3 fixed over M S sheeting, 1.5 mm thick supported on a mild steel angle iron post 75x40 Le firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 450 mm X 450mm X 600mm below ground level as per drawings and Technical Specification Clause 801. i) Direction and place in nidification sign with size 1200x900 (informatory sign board)	9.00	No	7000.00	Rupees Seven Thousand Only	Each	63000	
2	Providing and fixing of retro-reflectorized cautionary, mandatory and informatory sign as per IRC:67 made of encapsulated lens type reflective sheeting vide clause 1701.2.3 fixed over aluminum sheeting, 1.5 mm thick supported on a mild steel angle iron post 75 mm X 6mm firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 450 mm X 450mm X 600mm below ground level as per drawings and Technical Specification Clause 1801(900/600 direcation and place edification)	3.00	No	5000.00	Rupees Five Thousand Only	Each	15000	
<b>Total Rs.</b>								<b>78000</b>
<b>Amount Quoted by the Contractor in Percentage</b>								
<b>Note :- All the material will procured by the contractor him self</b>								

Executive Engineer,  
Shimla Rural Division,  
HP,PWD, Dhamsi

### Schedule Of Quantity

Estimated Cost:- 99,927.00

Earnest Money:- 2,000.00

Time:- One Months.

**Name Of Work :- A/R & M/O HPPWD Rest House building at Jalog (SH:- Providing painting work and mise works etc.)**

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount	
		3	4	In figures	In words			
1	2			5	6	7	8	
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of materials within all leads and lifts and as per the direction of Engineer in Charge.	703.24	Sqm	16.00	Rupees Sixteen Only	Per Square metre	11252	
2	Providing and applying white cement based putty of average thickness 1 mm. of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. including carriage of materials within all leads and lifts and as per the direction of Engineer in Charge.	210.97	Sqm	73.65	Rupees Seventy Three and Paise Sixty Five Only	Per Square metre	15538	
3	Distemper with Oil bound washable distemper/acrylic washable distemper of approved brand and manufacture to give an even shade :New work (two or more coats) over and including water thinnable priming coat with cement primer.	703.24	Sqm	104.00	Rupees One Hundred Four Only	Per Square metre	73137	
<b>Total Rs.</b>								<b>99927</b>
<b>Amount Quoted by the Contractor in Percentage</b>								
<b>Note :- All the material will procured by the contractor him self</b>								

Executive Engineer,  
Shimla Rural Division,  
HP PWD, Dhamsi. *S.M.*

**Schedule Of Quantity**

Estimated Cost:- 99,645.00

**Name Of Work :- Restoration of Rain damage on (1)Bathora to Panewat road km 0/00 to 3/500. (2)Bag to Kayalu road km 0/00 to 10/500 (3) DGBR to Barota road km 0/00 to 1/550 (SH:- Hiring of JCB for removal of slips and debris ,cleaining of drain , dressing of berms at various Rd,s in various roads)**

Earnest Money:- 2000.00

Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount	
		3	4	In figures	In words			
1	2	3	4	5	6	7	8	
1	Hiring of JCB/Excavator cum loader for removal of Land slides /slips including the cost of fuel oil, lubricants, wages of operational staff, any repair during operation will be carried out at his risk and cost including carriage of Machinery from one place to another at required location,actual working will be accounted for payment and proper disposal of snow,slips will be ensured by the contractor and including all leads and lifts and work will be executed as per the direction of Engineer in charge	91.00	Hour	1095.00	Rupees One Thousand Ninety Five Only	Per Hour	99645	
<b>Total Rs.</b>								<b>99645</b>
<b>Amount Quoted by the Contractor in Percentage</b>								
<b>Note :- All the material will procured by the contractor him self</b>								

Executive Engineer,  
Shimla Rural Division,  
HP,PWD, Dhara