

Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2024-25/

8397-426 Dated/ 10-9-2025

To

The Executive Engineer (IT Cell),
Nirman Bhawan Nigam Vihar Shimla-2.
Himachal Pradesh Shimla -2.

Subject:- Publication of Tender Notice.

Enclosed please find herewith the Tender notice of works as given in the Notice inviting Tenders alongwith Schedule of quantities for uploading on departmental website as per Notification Secretary (PW) to the Govt. of HP letter No. PBW(B) A (3) 1/2024 dated Shimla -03.01.2025

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in public interest.

DA/ Stated as above

~~Executive Engineer~~
~~Palampur Division~~
~~HPPWD Palampur~~

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

- 1 The Superintending Engineer 5th Circle, HP.PWD Palampur.
2. The drawing branch in this office.
- 3 All Assistant Engineer working under this Division
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

CERTIFICATE

Certified that the tenders invited vide this office NIT No. PWP/ Agr. Asstt/ NIT/ 2025/- 8397-426 dated 10.09.2025 are urgent in nature and in public interest.

~~Executive Engineer~~
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'**

Sealed item rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **19.09.2025** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 18.09.2025 up to 4.00 P.M and the application for issue of tender form shall be received 17.09.2025 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	Restoration of rain damages on Tanda Pantehar to Patial Basti Km 0/010 to 0/900 (SDRF Deposit)	Rs. 98,355.00	Rs. 2,000.00	One Month
2	NH-154 to Govt. High School Tanda via S.C.V. B Degree College to connect SC Basti Km 0/00 to 5/00 (MNP) (SW:- Providing and fixing dual Directional reflective speed breakers)	Rs. 99,600.00	Rs. 2,000.00	One Month
3	Restoration of rain damages on Lambapatt to Assanpatt & Khalet to Sidhpur Sarkari road Km 0/00 to 3/00 (SH:- P/L Interlocking concrete block pavement from RD 2/860 to 2/883.50)	Rs. 99,249..00	Rs.2,000.00	Three Month
4	Restoration of rain damages on Lambapatt to Assanpatt & Khalet to Sidhpur Sarkari road Km 0/00 to 3/00 (SH:- P/L Interlocking concrete block pavement from RD 2/930 to 2/953.50)	Rs. 99,438.00	Rs. 2,000.00	Three Month
5	Minor repair & Alteration of ETT lab at Banuri JCBF Palampur , Minor repair of ETT lab O/O AD JCBF Palampur (SH:- P/F Prepainted sheet, GI Sheet gutter etc) Deposit)	Rs. 89,584.00	Rs. 1800.00	Three Month
6	Minor repair & Alteration of ETT lab at Banuri JCBF Palampur , Minor repair of ETT lab O/O AD JCBF Palampur (SH:- P/F Prepainted sheet, Painting work etc) Deposit)	Rs. 89,450.00	Rs. 1800.00	Three Month

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years

Executive Engineer
Palampur Division
HPPWD Palampur

Schedule of Quantity

Work :- Restoration of rain damages on Tanda Pantehar to Patial Basti km. 0/00 to 0/900 to (Under SDRF Deposit)
 W :- Providing and fixing Double Shank pavement marker Cat Eyes at Zebra Crossing

Estimated Cost :- Rs. 98,355/-
 Earnest Money :- Rs. 2000/-
 Time limit : One month

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing and fixing pavement marker (cat Eyes) Made out of ABS 3M/Every or equivalent plastic of size 100x90x20mm (One hundred into Ninety into twenty millimetre) having high intensity 30 degree micro cube corner spark glow reflector White/Red/ yellow double shank Heavy duty without nailshaving 50 mm stem of ABS. The pavement marker shall be installed with suitable epoxy ABS including carriage of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in -Charge.	249.00	Nos.			Each	
						Total :-	

Executive Engineer
 Palampur Division
 HP.PWD Palampur

Schedule of Quantity

of Work :- NH-154 to Govt. High School Tanda via S.C.V.B. Degree College to connect SC Basti Km. 0/00 to 0/500 (under MNP)
 Sub Work :- Providing and fixing dual directional reflective speed breaker

Estimated Cost :- Rupees 99,600/-
 Earnest Money :- Rupees 2000/-
 Time limit : One Month.

2

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and fixing dual directional reflective speed breaker/ rumble strips high impact resistant plastic body of sizes 275x150x32mm (Two hundred seventy five into one hundred fifty into thirty two millimetre) having six glass large 12mm (twelve millimetre) diameter reflector lenses to one side 12 (Twelve) number on both side provided with two steel zink plated nails of 12mm (Twelve millimetre) and of length 120mm (One hundred twenty millimetre) for fixing to road by hammering make green/greenlite etcetera as per drawing and specifications including carriage of material and equipment in all leads and lifts with all mode of transportation and as per the direction of Engineer-in-charge.	83.00 Nos.			Each	
	Total:-					

Executive Engineer
 Palampur Division
 H.P.PWD Palampur

3

Work No.

Schedule of Quantity

Name of Work :- Restoration of rain damages on Lambapatt to Assanpatt & Khalet to Sidhpur Sarkari road Km. 0/00 to 3/00
(S. W. :- P/L interlocking Concrete block Pavement from RD 2/860 to 2/883.50 (Deposit))

Estimated Cost :- Rs.99,249/-
Earnest Money :- Rs.2000/-
Time limit : Three Months.

S. No.	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In words		
1	Providing and laying of interlocking Concrete Block Pavements having thickness 80 mm. as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	70.50			Per square metre	
2	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix , P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802, 803, 1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.43			Per Cubic metre	
					Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

4

Work No.

Estimated Cost :- Rs.99,438/-
Earnest Money :- Rs.2000/-
Time limit : Three Months.

Schedule of Quantity
Name of Work :- Restoration of rain damages on Lambapatt to Assarpatt & Khalet to Sidhpur Sarkari road Km. 0/00 to 3/00
(S. W. :- P/L interlocking Concrete block Pavement from RD 2/930 to 2/953.50 (Deposit))

S. No.	Description of Item	Quantity		Rate		Unit	Amount
		In figure	In words	In figure	In words		
1	Providing and laying of interlocking Concrete Block Pavements having thickness 80 mm.as per drawing and Technical Specifications Clause 1504 as per the entire satisfaction and direction of Engineer -in -charge including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	70.50	Square Metre			Per square metre	
2	Providing Concrete for plain/reinforced cement concrete 1:2:4 (one cement:Two sand: four crushed stone aggregate) Nominal mix , P.C.C.grade M-20 (M-Twenty) in open foundations as per drawing and Technical Specifications Clause 802,803,1202 & 1203 including carriage of materials within all leads and lift and other incidentals. The rate including of octroi, royalty, malkana, tolltax, sale tax or other taxes imposed by the Government.	1.46	Cubic metre			Per Cubic metre	
						Total :-	

Executive Engineer
Palampur Division
HP.PWD Palampur

5

Work No.

Estimate Cost :-Rs. 89,584/-
Earnest Money :-Rs. 1800/-

Time Limit :- Three Months

Schedule of Quantity
Name of Work :- Minor repair & alteration of ETT lab at Banuri JCBF Palampur, Minor repair of ETT lab O/O AD

JCBF Palampur
(SH:- P/F prepainted sheet, G. I. Sheet gutter etc.

S. No	Description of Item	Quantity		Rate		Unit	Amount Rupees	
				In figure	In Words			
1	Providing and fixing 0.60 mm thick prepainted steel sheet in roofing, with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyster of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks , bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accesories as required as per direction of Engineer-in- Charge including all leads and carriage of material and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	25.92	Sqm			Per Square metre		
2	Providing and fixing 15 cm. wide 45 cm. overall semicircular plain G.I. sheet gutter with Iron brackets 40x3 mm. size bolts and nuts and washers etc. including making necessary connections with rain water pipe complete as per design. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	64.00	Metre			Per metre		
3	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110 mm diameter with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge. The rate including of octroi, royalty, malkana, tolltax, GST or other taxes imposed by the government.	60.00	Metre			Per metre		
Total :-								

Executive Engineer,
Palampur Division,
HPPWD Palampur

6

Work No.

Estimate Cost :-Rs. 89,450/-

Earnest Money :-Rs. 1800/-

Time Limit :- Three Months

Schedule of Quantity

of Work :- Minor repair & alteration of ETT lab at Banuri JCBF Palampur, Minor repair of ETT lab O/O AD
of Palampur

PH:- P/F prepainted sheet, painting work etc.

S. No	Description of Item	Quantity		Rate		Amount Rupees
				In figure	In Words	
1	Providing and fixing 0.60 mm thick prepainted steel sheet in roofing with hot dipped metallic, zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per direction of Engineer-in-Charge including all leads and carriage of material and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	21.33	Sqm			
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	99.75	Square metres			
3	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	285.00	Square metres			
4	Wall painting with apex weather proof exterior emulsion of Assian Paint/Nerolac/Surksha of Nerolac Paint / Berger/Dulex paint of approved brand and manufacture to give an even shade : exterior including carriage of materials within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	285.00	Sqm.			
5	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture including carriage of materials with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, Tol tax, GST or any other taxes imposed by the Government.	72.10	Square metres			
				Total :-		

Executive Engineer,
Palampur Division,
HPPWD Palampur