

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWP/CB/Tender Notice/2025-26- 5809-10
To

Through e-mail
eeict-pwd-shi@hp.gov.in

Dated:- 09-09-2025


✓
The Executive Engineer (IT Cell),
HPPWD, Nigam Vihar, Shimla-2.
eeict-pwd-shi@hp.gov.in

Subject :- Regarding publication of Tender Notice on departmental website to be opened on 17.09.2025.

Enclosed please find herewith the tender notice alongwith schedule of quantity for uploading on department website as per notification Pr. Secy. (PWD) to the Govt. of HP, No. PBW (B) A (3) 1/2020 dated Shimla-2 the 16th July 2021.


1. Certified that the tender mentioned in the notice is exigencies/emergency of urgent nature due to rainy season and in the public interest.

Enclosures:- Notice Inviting tender and schedule of quantity.(15 Nos.)


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

Copy forwarded along with tender notice via e mail for information to:-

1. The Superintending Engineer Nahan 12th Circle HP.PWD Nahan for information please.


Executive Engineer,
Paonta B&R Division,
HP. PWD. Paonta Sahib.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed Percentage rate tender are hereby invited by the Executive Engineer Paonta (B&R) Division HP.PWD Paonta Sahib on behalf of Governor of HP from the approved/ eligible contractor registered in HPPWD for the work, so as to reach in this office on 17.09.2025 up to 02.30 PM and shall be opened on 17.09.2025 the same day at 3.00P.M. in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (non refundable) up to 4.00 PM on 16.09.2025 for which the applications should reach in this office up to 4.00 PM on 15.09.2025. The tender form will be issued to the contractor giving proof of registration as GST.

The earnest money in the shape of NSC / Time deposit account / Saving account in any of the Post Office in HP or FDR/CDR from nationalized bank duly pledged in the name of Executive Engineer Paonta B&R Division HP.PWD Paonta Sahib must be accompanied with the application. Conditional tender and tender received without earnest money will be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject any or all tenders without assigning the reason. If there happens to be any holiday the same will be open on the next working day.

Sr. No	Name of works	Estimated Cost	Earnest Money	Time Limit	Cost of Form	Class
1	Restoration of rain damages to Kotri Bagna Swar Kolar Km. 0/00 to 8/00. (SH:- Removal of slips in Km. 0/00 to 8/00)	Rs. 99,400/-	Rs. 2000/-	Two Months.	350/-	C & D
2	Restoration of rain damages to Paonta Rampurghat road Km. 0/0 to 5/00. (SH:- Providing and laying granular Sub base in various Kms. 0/00 to 5/00)	Rs. 98,984/-	Rs. 2000/-	Two Months.	350/-	C & D
3	Restoration of rain damages to Bangran Kishankot rood km. 0/0 to 2/750 and Narayangarh Ajoli road km. 0/0 to 6/125.(SH:-Hiring of JCB and Tractor with trolley for repair of pot holes and repair of berms by filling with granular material on Bangran Kishankot road km. 1/750 to 2/750 and Narayangarh Ajoli road 2/0 to 4/0)	Rs. 99,135/-	Rs. 2000/-	Two Months.	350/-	C & D
4	Restoration of Rain damages to link road from NH-707 to Village Chhachheti km. 0/0 to 14/250. (SH:- Repair of pot holes by filling with granular material and removal of slips in km.7/0 to 10/0).	Rs. 99,520/-	Rs. 2000/-	Two Months.	350/-	C & D

5	Restoration of Rain damages to link road from NH-707 to Village Chhachheti km. 0/0 to 14/250. (SH:- Repair of pot holes by filling with granular material and removal of slips in km.10/500 to 12/500).	Rs. 99,430/-	Rs. 2000/-	Two Months.	350/-	C & D
6	Restoration of Rain damages to Rampurghat Nawada Manpur Deora Singhpura road km. 0/0 to 8/400. (SH:- Repair of pot holes and repair of berms by filling with granular material in km.2/200 to 4/200).	Rs. 99,880/-	Rs. 2000/-	Two Months.	350/-	C & D
7	Restoration of Rain damages to link road to village Manpur Deora km. 0/0 to 3/300. (SH:- Repair of pot holes and repair of berms by filling with granular material in km.0/0 to 2/0).	Rs. 98,486/-	Rs. 2000/-	Two Months.	350/-	C & D
8	Restoration of Rain damages to Paonta Bhagani Gojjar Dakpathar road km. 0/0 to 26/500 (MDR-94) (SH:- Repair of pot holes and repair of berms by filling with granular material in km.8/0 to 11/0).	Rs. 99,850/-	Rs. 2000/-	Two Months.	350/-	C & D
9	Restoration of Rain damages to Paonta Bhagani Gojjar Dakpathar road km. 0/0 to 26/500 (MDR-94) (SH:- Repair of pot holes and repair of berms by filling with granular material in km.14/0 to 17/0).	Rs. 98,580/-	Rs. 2000/-	Two Months.	350/-	C & D
10	Restoration of Rain damages to Paonta Bhagani Gojjar Dakpathar road km. 0/0 to 26/500 (MDR-94) (SH:- Repair of pot holes and repair of berms by filling with granular material in km. 21/0 to 23/0).	Rs. 98,984/-	Rs. 2000/-	Two Months.	350/-	C & D
11	Restoration of rain damages to Phandi Bodiwala road km. 0/00 to 3/600 and link road to lower Bodiwala km. 0/00 to 1/500. (SH:- Removal of slips on various RDs)	Rs. 99,805/-	Rs. 2000/-	Two Months.	350/-	C & D
12	Restoration of rain damages link road to Lohgarh km. 0/00 to 5/020 and Lohgarh to Banda Bahadur road km. 0/00 to 4/200. (SH:- Removal of slips on various RDs)	Rs. 99,755/-	Rs. 2000/-	Two Months.	350/-	C & D
13	Restoration of Rain damages to Various roads under Majra Section (SH:- Repair of pot holes and repair of berms by filling with granular material on various roads).	Rs. 98,911/-	Rs. 2000/-	Two Months.	350/-	C & D

J

14	Restoration of rain damages to various roads of Paonta local Section under Sub-Division No. I HP.PWD. Paonta Sahib.(SH:- Dressing of berms and repair of pot holes by filling with granular material on Badripur Kishanpura Bhatanwali road and Bhuppur Tibtian colony road at various RDs)	Rs. 99,863/-	Rs. 2000/-	Two Months.	350/-	C & D
15	Restoration of rain damages to Khairni Basti Palhori road km. 0/0 to 7/00. (SH:- Removal of slips in km. 0/00 to 7/00).	Rs. 99,755/-	Rs. 2000/-	Two Months.	350/-	C & D

CERTIFICATE:- Certified that the tenders mentioned above in this notice are exigencies/emergency of urgent nature due to Rainy Season and in public interest.

Conditions:-

The tender document shall be issued to only those contractors / firms:-

1. Who possess valid Contractor Registration Number.
2. Who possess valid GST Registration Number, Permanent Account Number and EPF Number.
3. Ambiguous / telegraphic / conditional tenders or tenders by FAX / E-mail shall not be entertained / considered in any case.
4. If any date mentioned above happens to be local/gazetted holiday, the same shall be processed on next days.
5. The earnest money for above cited work should be submitted with the applications for purchase of tender form, no exemption for earnest money will be allowed.
6. The contractor / Firms are requested to insert the percentage rate in words as well as in figures/failing which XEN reserves the right to accept/ reject any or all tenders.
7. List of machinery tool plants as per schedule F Sr. No. 6.19 Ref. Clause No. 18 i.e. R.C. and purchase bills along with proof of ownership of JCB/Affidavit from owner of JCB and Tractor with Trolley on hire basis.
8. GST Clearance Certificate from GST Department and up to date filling return as per instruction issued by the GST Department.

Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib.
Dated:- 09-09-2025

No.PWP/CB-Tender Notice/2025-26- 5011-5060

Copy forwarded to the following for information and necessary action please:-

1. The Engineer-in- Chief, HP. PWD Shimla-I
2. All the Superintending Engineer, in HP.PWD
3. The Sub Divisional Magistrate Paonta Sahib.
4. All the Executive Engineer in HP.PWD.
5. The Executive Engineer I&PH Division Paonta Sahib.
6. The Block Development Officer Block Paonta Sahib.
7. All the Assistant Engineer working under this Division.
8. The Executive Officer Municipal Committee Paonta Sahib.
9. All head of the Branches in this division.
10. Notice Board.

Executive Engineer,
Paonta B&R Division,
HP. PWD., Paonta Sahib

Job No. 1.

99400/-

SCHEDULE OF QUANTITY


Name of work:- Restoration of rain damages to Kotri Bagna Swar Kolar KM 0/00 to 8/00 (SH:- Removal of slips in km 0/00 to 8/00)		Job.-		Estimated Cost:- 99755/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Figures	Rate in
				142.00	Words
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a lift up to 1.5 metre and lead upto 1000 meter as per technical specification 302.3.5 and 1611 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	700.00 cubic metre	Per cubic -metre	142.00	Rupees one hundred forty two and paise zero only
Total:-					99400.00

Executive Engineer,
Paonta B&R Division
HP. PWD. Paonta Sahib

Job No. 2.

SCHEDULE OF QUANTITY

Sr. No.	Sub-Head and item of work	Quantity	Unit	Job.-		Estimated Cost:- 98984/- Only. Earnest Money:- 2000/- Only Time Limit. - Two Months.
				Figures	Words	
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	109.35 cubic metre	Per cubic metre	905.20	Rupees nine hundred five and paise twenty only	98984
Total:-						98984


Executive Engineer,
Paonta B&R Division
HP, PWD, Paonta Sahib

Job No. 3.

SCHEDULE OF QUANTITY

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
Name of work:- Restoration of rain damages to Bangran Kishankot road km 0/0 to 2/750 and Narayangarh Ajoli road km 0/0 to 6/125. (SH:- Hiring of JCB and Tractor with trolley for repair of pot holes and repair of berms by filling with granular material on Bangran Kishankot road km 1/750 to 2/750 and Narayangarh Ajoli road 2/0 to 4/0.)						
Estimated Cost:- 99135/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.						
1	Hiring of hydraulic excavator cum loader of 1 cum bucket capacity for excavation, removal of slips, removal of debris and dressing of berms including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor and shall be borne by the contractor at his own cost. The work shall be executed as per the MORT specification and as per the directions of Engineer-in Charge.	57.00 hours	Per hour	1055.00	Rupees one thousand fifty five and paise zero only	60135.00
2	Hiring of tractor with trolley i/c operating and service staff as required and including POL and including full time chowkidar for machine complete with minimum eight hours a day. Any loss or damage caused to the machinery during transit or at site of work shall be responsibility of the contractor and will be borne by the contractor at his own cost. The break down or any kind of hindrance charges of machinery or operating staff shall be met out of his own cost. Other conditions shall be subject to the various clauses of contract agreements including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	12.00 Days	Per day	3250.00	Rupees three thousand two hundred fifty and paise zero only	39000.00
G.Total						99135.00

Executive Engineer,
Paonta B&R Division
HP. PWD. Paonta Sahib

Job No - 4.

SCHEDULE OF QUANTITY

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
Name of work:- Restoration of rain damages to link road from NH 707 to village Chhachheti km 0/0 to 14/250 (SH:- Repair of pot holes by filling with granular material and removal of slips in km 7/0 to 10/0)						
		Job.-		Estimated Cost:- 99520/- Only.		
				Earnest Money:- 2000/- Only		
				Time Limit: - Two Months.		
1	Maintenance of Earthen shoulder by stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	600.00 sqm	Per square metre	17.50	Rupees seventeen and paise fifty only	10500.00
2	Maintenance of Earthen shoulder by Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	600.00 sqm	Per square metre	63.50	Rupees sixty three and paise fifty only	38100.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. By mechanical means including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	300.00 Rmt	Per running metre	23.00	Rupees twenty three and paise zero only	6900.00
4	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift up to 1.5 metre and lead upto 1000 meter as per technical specification 302.3.5 and 1611 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	310.00 cubic metre	Cubic metre	142.00	Rupees one hundred forty two and paise zero only	44020.00
Total:-						99520.00

Executive Engineer,
Paonta B&R Division
HP, PWD, Paonta Sahib

Job No - S.

SCHEDULE OF QUANTITY

Sr. No.	Sub-Head and item of work	Quantity		Unit	Rate in		Amount
		sqm	Per square metre		Figures	Words	
Name of work:- Restoration of rain damages to link road from NH 707 to village Chhachheti km 0/0 to 14/250 (SH:- Repair of pot holes by filling with granular material and removal of slips in km 10/500 to 12/500)							
		Job -		Estimated Cost:- 99430/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.			
1	Maintenance of Earthen shoulder by stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	600.00	Per square metre	17.50	Rupees seventeen and paise fifty only	10500.00	
2	Maintenance of Earthen shoulder by Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	400.00	Per square metre	63.50	Rupees sixty three and paise fifty only	25400.00	
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. By mechanical means including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	200.00	Per running metre	23.00	Rupees twenty three and paise zero only	4600.00	
4	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift up to 1.5 metre and lead upto 1000 meter as per technical specification 302.3.5 and 1611 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	415.00	Cubic metre	142.00	Rupees one hundred forty two and paise zero only	58930.00	
						Total:-	99430.00

Executive Engineer,
Paonta B&R Division
HP. PWD. Paonta Sahib

Job No. 6.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages to Rampurghat Nawada Manpur Deora Singhhpura road km 0/0 to 8/400 (SH):- Repair of pot holes and repair of berms by filling with granular material in km 2/200 to 4/200)		Job:-		Estimated Cost:- 99880/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.		
Sr. No.	Sub-Head and item of work	Quantity	Unit	Figures	Rate in Words	Amount
1	Granular sub-base/base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	110.34	Per cubic metre	905.20	Rupees nine hundred five and paise twenty only	99880.00
					Total:-	99880.00

Executive Engineer,
Paonta B&R Division
HP, PWD, Paonta Sahib

Job No. 7.

SCHEDULE OF QUANTITY

Sr. No.	Sub-Head and item of work	Quantity	Unit	Job.-		Estimated Cost:- 98486/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.
				Figures	Rate in Words	
Name of work:- Restoration of rain damages to link road to village Manpur Deora km 0/0 to 3/300 (SH:- Repair of pot holes and repair of berms by filling with granular material in km 0/0 to 2/0)						
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	108.80 cubic metre	Per cubic metre.	905.20	Rupees nine hundred five and paise twenty only	98486.00
Total:-						98486.00




Executive Engineer,
Paonta B&R Division
HP, PWD, Paonta Sahib

Job No. 8,

SCHEDULE OF QUANTITY

Sr. No.	Sub-Head and item of work	Quantity	Unit	Job.-		Estimated Cost:- 99850/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.
				Figures	Words	
1	Maintenance of Earthen shoulder by stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	750.00	Per square metre	17.50	Rupees seventeen and paise fifty only	13125.00
		sqm				
2	Maintenance of Earthen shoulder by Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	750.00	Per square metre	63.50	Rupees sixty three and paise fifty only	47625.00
		sqm				
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. By mechanical means including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	1700.00	Per running metre	23.00	Rupees twenty three and paise zero only	39100.00
		Rmt				
				Total:-		99850.00


 Executive Engineer,
 Paonta B&R Division
 HP. PWD. Paonta Sahib

Job No. 9,

SCHEDULE OF QUANTITY

Sr. No.	Sub-Head and item of work	Quantity	Unit	Job.-		Estimated Cost:- 98580/- Only. Earned Money:- 2000/- Only Time Limit: - Two Months.
				Figures	Words	
Name of work:- Restoration of rain damages to Paonta Bhagani Gojjar Dapathar road km 0/0 to 26/500 (SH:- Repair of pot holes and repair of berms by filling with granular material in km 14/0 to 17/0)						
1	Maintenance of Earthen shoulder by stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	1320.00 sqm	Per square metre	17.50	Rupees seventeen and paise fifty only	23100.00
2	Maintenance of Earthen shoulder by Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	1080.00 sqm	Per square metre	63.50	Rupees sixty three and paise fifty only	68580.00
3	Construction of unlined surface drains of average cross-sectional area 0.40 sqm in soil to specified lines, grades, levels and dimensions. Excavated material to be used in embankment with a lift upto 3m and lead of 50 m (average lead 25 m) as per Technical Specification Clause 307. By mechanical means including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	300.00 Rmt	Per running metre	23.00	Rupees twenty three and paise zero only	6900.00
Total:-						98580.00

Executive Engineer,
Paonta B&R Division
HP. PWD. Paonta Sahib

Job No. 10,


SCHEDULE OF QUANTITY

Sr. No.		Sub-Head and item of work	Quantity		Unit	Rate in		Amount
			109.35	Per cubic metre		Words	Amount	
1		Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	109.35	Per cubic metre	905.20	Rupees nine hundred five and paise twenty only	98984.00	
Total:-								98984.00

Name of work:- Restoration of rain damages to Paonta Bhagani Gojjar Dapathar road km 0/0 to 26/500 (MDR-94)
 (SH:- Repair of pot holes and repair of berms by filling with granular material in km 21/0 to 23/0)

Job:-
 (MDR-94)

Estimated Cost:- 98984/- Only.
 Earnest Money:- 2000/- Only
 Time Limit: - Two Months.


 Executive Engineer,
 Paonta B&R Division
 HP. PWD, Paonta Sahib

Job No. 11.

SCHEDULE OF QUANTITY


Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut material with in a lift up to 1.5 metre and lead upto 1000 meter as per technical specification 302.3.5 and 1611 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	702.85 cubic metre	Per cubic metre	142.00	Rupees one hundred forty two and paise zero only	99805.00
Total:-						99805.00

Name of work:- Restoration of rain damages to Phandi Bodiwala road km 0/00 to 3/600 and Link Road to Lower Bodiwala Km 0/00 to 1/500 (SH:- Removal of slips on various RDs)

Job.-

Estimated Cost:- 99755/-
Earnest Money:- 2000/- Only
Time Limit: - Two Months.


99805/-


Executive Engineer,
Paonta B&R Division
HP. PWD. Paonta Sahib

Job No. 12.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages Link road to Lohgarh km 0/00 to 5/020 and Lohgarh to Banda Bahadur Road km 0/00 to 4/200 (SH:- Removal of slips at various RDs)		Job.-		Estimated Cost:- 99755/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Figures	Rate in
				142.00	Words
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a lift up to 1.5 metre and lead upto 1000 meter as per technical specification 302.3.5 and 1611 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	702.50 cubic metre	Per cubic metre		Rupees one hundred forty two and paise zero only
					99755.00
				Total:-	99755.00


Executive Engineer,
Paonta B&R Division
HP. PWD. Paonta Sahib

Job No. 13.

SCHEDULE OF QUANTITY


98911/-

Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface; mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	109.27 cubic metre	Per cubic metre	905.20	Rupees nine hundred five and paise twenty only	98911.00
Total:-						98911.00

Job.-

Name of work:- Restoration of rain damages to various roads under Majra Section(SH:- Repair of pot holes and repair of berms by filling with granular material on various roads)

Estimated Cost:- ~~98911/-~~ Only.
Earnest Money:- 2000/- Only
Time Limit: - Two Months.


Executive Engineer,
Paonta B&R Division
HP. PWD. Paonta Sahib

Job No. 14.

SCHEDULE OF QUANTITY


Sr. No.	Sub-Head and item of work	Quantity	Unit	Rate in		Amount
				Figures	Words	
Name of work:- Restoration of rain damages to various roads of Paonta Local Section under Sub Division No.1 HPPWD Paonta Sahib(SH):- Dressing of berms and repair of pot holes by filling with granular material on Badripur Kishanpura Bhatanwari road and Bhuppur Tibbitian colony road at various RD's)						
Job.-		Estimated Cost:- 99863/- Only.		Earnest Money:- 2000/- Only		
		Time Limit: - Two Months.				
1	Maintenance of Earthen shoulder by stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	800.00 sqm	Per square metre	17.50	Rupees seventeen and paise fifty only	14000.00
2	Maintenance of Earthen shoulder by Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	700.00 sqm	Per square metre	63.50	Rupees sixty three and paise fifty only	44450.00
3	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using Gravel mix soil. including all leads, lifts and carriage as per entire satisfaction of engineer in charge.	45.75 cum	Per cubic metre	905.20	Rupees nine hundred five and paise twenty only	41413.00
Total:-						99863.00

Executive Engineer,
Paonta B&R Division
HP. PWD. Paonta Sahib

Job No. 15.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages to Kharini Basti Palhori road km 0/0 to 7/00 (SH:- Removal of slips in km 0/00 to 7/00)		Job - Removal of slips in		Estimated Cost:- 99755/- Only. Earnest Money:- 2000/- Only Time Limit: - Two Months.	
Sr. No.	Sub-Head and item of work	Quantity	Unit	Figures	Rate in
				142.00	Words
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a lift up to 1.5 metre and lead upto 1000 meter as per technical specification 302.3.5 and 1611 including allLeads, lifts and carriage as per entire satisfaction of engineer in charge.	702.50 cubic metre	Per cubic metre		Rupees one hundred forty two and paisa zero only
Total:-					99755.00


Executive Engineer,
Paonta B&R Division
HP. PWD. Paonta Sahib