

OFFICE OF
EXECUTIVE ENGINEER, SALOONI DIVISION HPPWD SALOONI
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT SALOONI
Phone No. 01899-233287 Email: ee-slo-hp@nic.in
NOTING INVITING TENDER

Sealed item rate tender on form 6&8 are hereby invited by the Executive Engineer, Salooni Division HPPWD Salooni on behalf of the Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD. So as to reach in his office on or before **18.09.2025 to 11:00 AM** and the same shall be opened on the same day at **11:30 AM**, in the presence of the intending Contractor or their authorized representatives if any. The tender form can be obtained from his office on cash payment (Non refundable) on **17.09.2025 upto 01.30 PM** and the application for issue of tender form shall be received on **17.09.2025 upto 04.30 P.M.** The earnest money in the form of FDR from nationalized bank in HP duly pledged in favour of the Executive Engineer, Salooni Division HPPWD Salooni must be accompanied with each tender. The tender form will be issued to contractor who giving proof of enlistment, GST, Conditional tenders and the tenders received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 75 days. The Executive Engineer, reserves the right to reject the tender without assigning any reason. Special care should be taken to write the rates both in figure and in words.

Sr. No.	Name of work	Estimated Cost	Earnest money	Cost of form	Time limit	Eligible Class
1.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 28/0 to 49/0 (SH: Hiring of JCB for removal of slips at K.M. 28/0 to 32/0)	99,910/-	2000/-	350/-	90 Days	D & C
2.	Restoration of rain damages on Sundla Girjindoo road K.M. 0/0 to 36/500 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 15/0)	96,820/-	2000/-	350/-	90 Days	D & C
3.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 28/0 to 93/400 (SH: Construction of crate work wing wall at R.D. 73/325 to 73/330 and 73/331 to 73/336)	99,815/-	2000/-	350/-	90 Days	D & C
4.	Restoration of rain damages on link road to village Luhani and Sundla to Salooni (SH: Hiring of JCB for removal of slips at various RD,s)	98,880/-	2000/-	350/-	90 Days	D & C
5.	Restoration of rain damages on Kuthed to Kandhwara road K.M. 0/0 to 12/100 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 6/0)	99,910/-	2000/-	350/-	90 Days	D & C
6.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 49/0 to 57/0 (SH: Hiring of JCB for removal of slips at K.M. 49/0 to 57/0)	97,850/-	2000/-	350/-	90 Days	D & C
7.	Restoration of rain damages on Sundla Girjindoo road K.M. 0/0 to 36/500 (SH: Hiring of JCB for removal of slips at K.M. 5/0 to 10/0)	98,880/-	2000/-	350/-	90 Days	D & C
8.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at K.M. 18/0 to 23/0)	94,760/-	2000/-	350/-	90 Days	D & C
9.	Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Pusta at R.D. 5/935 to 5/937)	95,649/-	2000/-	350/-	90 Days	D & C
10.	Restoration of rain damages on Samoga to Dhanwal road, link road to village Jusav and Link road to village Andressar (SH: Hiring of JCB for removal of slips at various RD,s)	99,910/-	2000/-	350/-	90 Days	D & C
11.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at K.M. 23/0 to 28/0)	96,820/-	2000/-	350/-	90 Days	D & C


12.	Restoration of rain damages on link road to village Kuthed K.M. 0/0 to 6/0 (SH: Construction of PCC and Crate work Retaining wall at R.D. 1/272.50 to 1/275)	99,582/-	2000/-	350/-	C & D	90 Days
13.	Restoration of rain damages on Kuthed to Kandhwara road K.M. 0/0 to 12/100 (SH: Hiring of JCB for removal of slips at K.M. 6/0 to 12/100)	98,880/-	2000/-	350/-	90 Days	D & C
14.	Restoration of rain damages on Bihali Bachuni Chamber Katara road K.M. 0/0 to 11/100 (SH: Hiring of JCB for removal of slips at K.M. 5/0 to 11/100)	99,910/-	2000/-	350/-	90 Days	D & C
15.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 28/0 to 49/0 (SH: Hiring of JCB for removal of slips at K.M. 46/0 to 49/0)	97,850/-	2000/-	350/-	90 Days	D & C
16.	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 6/0)	96,820/-	2000/-	350/-	90 Days	D & C
17.	Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Pusta at R.D. 5/937 to 5/939)	95,649/-	2000/-	350/-	90 Days	D & C
18.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at K.M. 13/130 to 18/0)	99,910/-	2000/-	350/-	90 Days	D & C
19.	Restoration of rain damages on Salooni to Ghal road K.M. 0/0 to 7/500 (SH: Hiring of JCB for removal of slips at various RD,s)	96,820/-	2000/-	350/-	90 Days	D & C
20.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 13/130 to 28/0 (SH: Hiring of JCB for removal of slips at K.M. 13/130 to 28/0)	98,880/-	2000/-	350/-	90 Days	D & C
21.	Restoration of rain damages on Sundla Girjindoo road K.M. 0/0 to 36/500 (SH: Hiring of JCB for removal of slips at K.M. 15/0 to 20/0)	97,850/-	2000/-	350/-	90 Days	D & C
22.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 57/0 to 93/400 (SH: Hiring of JCB for removal of slips at K.M. 57/0 to 62/0)	99,910/-	2000/-	350/-	90 Days	D & C
23.	Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Pusta at R.D. 5/939 to 5/941)	95,649/-	2000/-	350/-	90 Days	D & C
24.	Restoration of rain damages on Kund to Siula road K.M. 0/0 to 6/255 (SH: Hiring of JCB for removal of slips at various RD,s)	98,880/-	2000/-	350/-	90 Days	D & C
25.	Restoration of rain damages on Kandhwara to Bhadela road K.M. 0/0 to 4/100 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 4/100)	97,850/-	2000/-	350/-	90 Days	D & C
26.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 28/0 to 93/400 (SH: Construction of crate work wing wall at R.D. 75/090 to 75/100 (1 st and 2 nd steps)	98,879/-	2000/-	350/-	90 Days	D & C
27.	Restoration of rain damages on Bihali Bachuni Chamber Katara road K.M. 0/0 to 11/100 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 5/0)	97,850/-	2000/-	350/-	90 Days	D & C
28.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 57/0 to 93/400 (SH: Hiring of JCB for removal of slips at K.M. 73/0 to 80/0)	96,820/-	2000/-	350/-	90 Days	D & C
29.	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at K.M. 6/0 to 12/0)	99,910/-	2000/-	350/-	90 Days	D & C
30.	Restoration of rain damages on link road to village Kuthed K.M. 0/0 to 6/0 (SH: Construction of PCC and Crate work Retaining wall at R.D. 1/277.50 to 1/280)	99,566/-	2000/-	350/-	C & D	90 Days

31.	Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 3/0)	98,880/-	2000/-	350/-	90 Days	D & C
32.	Restoration of rain damages on Link road to village Bani, link road to village Chakoti via Sukreth and Dangri to Sarar (SH: Hiring of JCB for removal of slips at various RD,s)	99,910/-	2000/-	350/-	90 Days	D & C
33.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 57/0 to 93/400 (SH: Hiring of JCB for removal of slips at K.M. 63/0 to 67/0)	98,880/-	2000/-	350/-	90 Days	D & C
34.	Restoration of rain damages on link road to Bhalei Matta Mandir K.M. 0/0 to 1/500 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 1/500)	96,820/-	2000/-	350/-	90 Days	D & C
35.	Restoration of rain damages on Maira to Jakhral road K.M. 0/0 to 10/500 (SH: Hiring of JCB for removal of slips at K.M. 5/0 to 9/500)	97,850/-	2000/-	350/-	90 Days	D & C
36.	Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Pusta at R.D. 5/941 to 5/943)	95,651/-	2000/-	350/-	90 Days	D & C
37.	Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 4/0)	95,790/-	2000/-	350/-	90 Days	D & C
38.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 57/0 to 93/400 (SH: Hiring of JCB for removal of slips at K.M. 80/0 to 85/0)	99,910/-	2000/-	350/-	90 Days	D & C
39.	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at K.M. 6/0 to 12/0)	97,850/-	2000/-	350/-	90 Days	D & C
40.	Restoration of rain damages on Maira to Jakhral road K.M. 0/0 to 10/500 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 5/0)	98,880/-	2000/-	350/-	90 Days	D & C
41.	Restoration of rain damages on Lachori to Seri road K.M. 0/0 to 8/500 (SH: Hiring of JCB for removal of slips at K.M. 4/0 to 8/500)	96,820/-	2000/-	350/-	90 Days	D & C
42.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 28/0 to 93/400 (SH: Construction of crate work wing wall at R.D. 68/120 to 68/130 (1 st steps)	99,975/-	2000/-	350/-	90 Days	D & C
43.	Restoration of rain damages on Chowga to Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 6/0)	98,880/-	2000/-	350/-	90 Days	D & C
44.	Restoration of rain damages on Sundla Girjindoo road K.M. 0/0 to 36/500 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 5/0)	99,910/-	2000/-	350/-	90 Days	D & C
45.	Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Pusta at R.D. 5/943 to 5/945)	95,651/-	2000/-	350/-	90 Days	D & C
46.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 57/0 to 93/400 (SH: Hiring of JCB for removal of slips at K.M. 85/0 to 93/400)	96,820/-	2000/-	350/-	90 Days	D & C
47.	Restoration of rain damages on Kandi to Athed road K.M. 0/0 to 12/0 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 6/0)	98,880/-	2000/-	350/-	90 Days	D & C
48.	Restoration of rain damages on Chakoli to Lader road K.M. 0/0 to 20/0 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 10/0)	99,910/-	2000/-	350/-	90 Days	D & C

49.	Restoration of rain damages on Hutta Ligga Ladwah road K.M. 0/0 to 7/040 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 7/040)	97,850/-	2000/-	350/-	90 Days	D & C
50.	Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Hiring of JCB for removal of slips at K.M. 3/0 to 6/0)	95,790/-	2000/-	350/-	90 Days	D & C
51.	Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 28/0 to 93/400 (SH: Construction of crate work wing wall at R.D. 68/120 to 68/130 (1 st , 2 nd , and 3 rd steps)	98,743/-	2000/-	350/-	90 Days	D & C
52.	Restoration of rain damages on Chowga to Khal road K.M. 0/0 to 13/705 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 13/705)	99,910/-	2000/-	350/-	90 Days	D & C

TERMS AND CONDITIONS:-

1. The contractor should produce a copy of enlistment /renewal at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reasons.
3. The contractor /firm have his registration and GST No., the copy of Pan number same be attached with the application.
4. The earnest Money shall be deposited duly pledged in favour of Executive Engineer, Salooni Division HPPWD Salooni and cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
5. The contractor /firms are requested to insert the rate of each item in works as well as in figures failing which XEN reserves the right to accept/reject any tender without assigning any reasons at any stage.



Executive Engineer,
Salooni Division
HPPWD Salooni.

No. PW/SD/GA/Contract/Tender/2025-2026- 4976-5025

Dated: - 10/09/2025

Copy forwarded to:-

1. The F.C-Cum-Principal Secretary (PW) to the Govt. of Himachal Pradesh Shimla-2 for favour of information, please.
2. The Engineer-in-Chief, HPPWD, Shimla.
3. The Chief Engineer (Kangra Zone) HPPWD Dharamshala.
4. The Superintending Engineer, 7th Circle HPPWD Dalhousie.
5. The Executive Engineer (IT Cell) office of Engineer-in-Chief HPPWD Shimla for uploading the NIT on the Departmental website.
6. All the Assistant Engineers under Salooni Division.
7. All the Contractor working under this division.
8. H.D.M./Supdt./Acctt. of this office.
9. Notice Board.


Executive Engineer,
Salooni Division
HPPWD Salooni.

OFFICE OF
EXECUTIVE ENGINEER, SALOONI DIVISION HPPWD SALOONI
HIMACHAL PRADESH, PUBLIC WORKS DEPARTMENT SALOONI
Phone No. 01899-233287 Email: ee-slo-hp@nic.in

CERTIFICATE

Certified that tender of works, as called vide this office letter No. PW/SD/GA/Contract/tender/2025-2026- ~~49 76-5a25~~ Dated: 10-09-25 are emergent nature in exigency of public interest.


Executive Engineer,
Salooni Division
HPPWD Salooni.

DNIT					Estimated cost		99910.00
Name of work:- Restoration of rain damages on Bathri Sundla Langer J & K Boundary road K.M. 28/0 to 49/0 (SH: Hiring of JCB for removal of slips at K.M. 28/0 to 32/0)					Earnest money		2000.00
					Time limit		90 days
S. N.	Description of Item	Quantity	Rate	Unit	In Words		Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute resonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty	99910.00
Total							99910.00
Rupees Ninety Nine Thousand Nine Hundred Ten Only							

DNIT No. 80 For the Year 2025-26
 DNIT checked & approved for Rs. 99910/- only
 (Rs. Ninety Nine thousand Nine Hundred
 Ten only)


 Executive Engineer
 Salooni Division
 HPPWD Salooni 

2

DNIT

Name of work:- Restoration of rain damages on Sundla Girjindoo road km 0/0 to 36/500 (SH:Removal of slip at km 10/0 to 15/00

Estimated cost	96820.00		
Earnest money	2000.00		
Time limit	One month		
Quantity	Rate	Unit	Amount
94.00	1030.00	Per hours	96820.00
Total			96820.00

Sr. No	Description
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less then 17.00 cum per hour to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.

DNIT NO 81 For the year 2025-26
 DNIT Checked and approved for ₹ 96,820/only
 (Rupees Ninety Six Thousand Eight Hundred Twenty) only


 Executive Engineer
 Salooni-Division
 H.P.P.W.D Salooni 

Name of work: Restoration of rain damages on Bathri Sundia Langeria J&K boundary road Km 28/00 to 93/400 (SH. Construction of crate work W/wall at

RD 73/325 to 73/330 and 73/331 to 73/335)

DNIT

S. N.	Description of Item	Quantity	Rate	Unit	Estimated cost	Three months Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORP technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	5.60	5.9 10	Per cubic metre	3690.00	3690.00
2	Providing and laying boulder apron laid in wire crate with 4mm dia G.I wire conforming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORP technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi, royalty, maikana, toll tax sale tax or other taxes imposed by the Government.	31.25	2803.70	Cum	87772.00	87772.00
3	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals.	5.50	1518.80	Cum	8353.00	8353.00
				Total	99815.00	99815.00

DNIT NO82 For the year 2025-26
 DNIT checked and approved for ₹ 99,815/only
 Rupees Ninety Nine Thousand Eight Hundred Fifteen Only


 Executive Engineer
 Saloom Division
 HPPWD Saloom

DNIT

Name of work:- Restoration of rain damages on link road to village Luhani and Sundla to Salooni (SH: Hiring of JCB for removal of slips at various RD,s)

S. N.	Description of Item	Quantity	Rate	Unit	Estimated cost					
					Earnest money	Time limit				
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all rxcavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statisfication of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute reonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty	98880.00	90 days	2000.00	
Total							98880.00			

Rupees Ninety Eight Thousand Eight Hundred Eighty Only

DNIT No. - 83 For the Year 2025-26
DNIT Checked & approved for Rs. 98,880/only.
(Rs. Ninety Eight thousand Eight Hundred Eighty only)

✓
 Executive Engineer
 Salooni Division
 HPPWD Salooni

DNIT

Name of work:- Restoration of rain damages on Kuthed Kandhwara road km 0/0 to 12/100 (SH: Removal of slip at km 0/0 to 6/00)

Sr. No	Description	Estimated cost	Rate	Unit	Amount
		Earnest money			One month
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97 00	1030 00	Per hours	99910.00
Total					99910.00

DNIT NO 84 for the year - 2025-26
DNIT closed and approved for ₹ 99,910 only
Rupes Ninety Nine thousand Nine hundred only


 Executive Engineer
 Salogant-Division
 H.P.W.D Salogant



DNIT

Name of work:- Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. ~~49/0~~ to ~~57/0~~ (SH: Hiring of JCB for removal of slips at K.M. 49/0 to 57/0)

S. N.	Description of item	Quantity	Rate	Estimated cost		Amount
				Time limit	Earnest money	
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	95.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty
Total						97850.00

Rupees Ninety Seven Thousand Eight Hundred Fifty Only

*DNIT No. - 885 For the Year 2025-26
 DNIT Checked & approved for Rs. 97850/- only
 (Rs. Ninety Seven Thousand Eight Hundred Fifty only)*


 Executive Engineer
 Saloomi Division
 HPPWD Saloomi

97850/-

DNIT

Name of work:- Restoration of rain damages on Sundla Girjindoo road km 0/0 to 36/500 (SH:Removal of slip at km 5/0 to 10/00)

Sr. No	Description	Estimated cost		One month	
		Earnest money	2000.00	Unit	Amount
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactors of Engineer-in-Charge any loss to the public/private property or any accident etc happened during the course of hiring period;execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per hours	98830.00
Total					98830.00

DNIT No 86 For the year 2025-26
DNIT Checked and approved For ₹ 98,830/only
Crupes Ninety Eight Thousand Eight Hundred Eighty Only


 Executive Engineer
 Salooni-Divisor
 H.P. P. W. D. Salooni


DNIT

Name of work- Restoration of rain damages on BSL J&K Boundary road 13/130 to 28/00(SH:- Removal of slip at km 18/00 to 23/00)

Sr. No	Description	Estimated cost	24750.00		
		Earnest money	2500.00		
Quantity	Rate	Unit	Amount		
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	92.00	1070.00	Per hours	98750.00
Total					98750.00

DNIT No 87 For the year 2015-16
DNIT checked and approved For ₹ 94,750/only
CR Noes Ninety Four Thousand Seven Hundreded Sixty Only


 Executive Engineer
 Salooni-Division
 H.P.W.D. Salooni

DNIT

Name of work:- Restoration of rain damages on Bhalel Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Pusta at R.D. 5/935 to 5/937)

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Estimated cost
						Earnest money
						Time limit
						90 days
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface In layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	6.44	519.80	Per cubic metre	Rupees Hundred Nineteen And Paise Eighty Only	Five 3348.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royality,Malkana,Toll tax, GST or any other taxes imposed by the Government.	16.20	5697.60	Per cubic metre	Rupees Thousand Hundrad Seven And Sixty Only	Five Six Ninety Paise
Total						95649.00

Rupees Ninety Five Thousand Six Hundred Forty Nine Only

DNIT No. - 28 For the Year 2025-26
DNIT Checked & approved for Rs. 95,649/only
(Rs Ninety five thousand Six Hundred forty nine only)


 Executive Engineer
 Salooni Division
 HPPWD Salooni

DNIIT		Estimated cost				
Name of work:- Restoration of rain damages on Samoga to Dhanwal road, link road to village Jusav and Link road to village		99910.00				
Addressar (SH: Hiring of JCB for removal of slips at various RD,s)		Earnest money 2000.00				
		Time limit 90 days				
S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty 99910.00
Total						99910.00

Rupees Ninety Nine Thousand Nine Hundred Ten Only

DNIIT No. 89 For the Year 2025-26
 DNIIT checked & approved for Rs. 99,910/- only
 (Rs. Ninety Nine Thousand Nine Hundred Ten only)

Executive Engineer
 Saloomi Division
 HPPWD Saloomi

DNIT

Name of work- Restoration of rain damages on BSL J&K Boundary road 13/130 to 28/00(SH:-Removal of slip at km 23/00 to 28/00)

Sr. No	Description	Estimated cost	96820.00		
		Earliest money	2000.00		
Quantity	Rate	Unit	Amount		
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	94.00	1030.00	Per hours.	96820.00
Total				96820.00	

DNIT No 90 For the year 2025-26
DNIT Checked and approved For ₹ 96,820/only
CRUPes Ninety Six Thousand Eight Hundred Twenty) only



 Executive Engineer
 Salooni-Division
 H. P. W. D. Salooni


DNIJ

Name of work:- Restoration of rain damages on link road to village Kuhed K.M. 0/0 to 6/0 (SH: Construction of PCC and Crete work Retaining wall at R.D. 1/272.50 to 1/275)

S. N.	Description of item	Quantity	Rate	Unit	In Words	Estimated cost	
						Earnest money	90 days
1	Earth work In excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	5.83	528.68	Per Cubic Metre	Rupees Five Hundred Twenty Eight And Paise Sixty Eight Only	3082.00	
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	9.18	5660.17	Per Cubic Metre	Rupees Five Thousand Six Hundred Sixty And Paise Seventeen Only	51960.00	
3	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters) mesh(woven diagonally) including 10% for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in-Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi, royalty, malkana, toll tax sale tax or other taxes imposed by the Government.	15.63	2464.61	Per Cubic Metre	Rupees Two Thousand Four Hundred Sixty Four And Paise Sixty One Only	38522.00	
4	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	4.20	1301.64	Per Cubic Metre	Rupees One Thousand Three Hundred One And Paise Sixty Four Only	5467.00	
5	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (V): 20(H) towards drainage face complete as per drawing and MORD technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-in-Charge. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	2.00	275.30	Each	Rupees Two Hundred Seventy Five And Paise Thirty Only	551.00	
Total						99582.00	

DNIJ No. 91 - For the year 2025-26
DNIJ Cleared & approved for Rs. 99,582/- only
(Rs. Ninety nine thousand five hundred
figures two only)

EC
 Executive Engineer
 Salooni Division
 HPPWD Salooni


DNIT

Name of work:- Restoration of rain damages on Kuthed Kandhwarra road km 0/0 to 12/100 (SH: Removal of slip at km 6/0 to 12/100)

Sr. No	Description	Estimated cost	Rate	Unit	Amount
		Earnest money			One month
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	98880.00	1030.00	Per hours	98880.00
Total					98880.00

*DNIT no. 92 for the year 2015-16
 DNIT Cleared and approved for ₹ 98880/- only
 Rupees Ninety Eight Thousand Eight Hundred Eighty Only*


 Executive Engineer
 Salooni-Division
 H.P.W. D. Salooni

DNIT

Name of work- Restoration of rain damages on Bihali Bachuni Chamber Katara road 0/0 to 11/100 (Sh.-Removal of slips at 5/00 to 11/100)

Sr. No	Description	Estimated cost	One month	
		Earrest money	Quantity	Amount
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	99915.00	97.00	99915.00
Total:		2000.00		99915.00

DNIT no. 93 for the year 2015-26
 DNIT checked and approved for ₹ 99,910/only
 Responsibility mine thousand mine hundred ten only


 Executive Engineer
 Salooni Division
 H. P. W. D Salooni


DNIT

Name of work:- Restoration of rain damages on Bathri Sundla Langera J & K Boundary road K.M. 28/0 to 49/0 (SH: Hiring of JCB for removal of slips at K.M. 46/0 to 49/0)

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	Estimated cost Earnest money
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all rxcavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	95.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty	97850.00 2000.00
Total						97850.00	

Rupees Ninety Seven Thousand Eight Hundred Fifty Only

*DNIT No. - 94 - For the year 2025-26
 Audit Checked & approved for Rs. 97,850/- only
 (Rs. Ninety Seven thousand Eight hundred fifty only)*


 Executive Engineer
 Salooni Division
 HPPWD Salooni

DNIT

Name of work - Restoration of rain damages on Kandi Athed road km 0/00 to 12/00 (Sh.: Removal of slips at 0/00 to 5/00)

Sr. No	Description	Estimated cost		Unit	Amount
		Quantity	Rate		
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	94.00	1030.00	Per hour	96820/-
Total					96820/-

*DNIT NO 95 for the year 2015-16
DNIT checked and approved for ₹ 96,820/- only
Rupees Ninety Six thousand eight hundred twenty only*

Executive Engineer
Saloon-Division
H.P. W. D. Saloon

EC

B

96820/-


DNIT

Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Pusta at R.D. 5/937 to 5/939)

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Estimated cost
						Earnest money
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	6.44	519.80	Per cubic metre	Rupees Hundred Nineteen And Paise Eighty Only	95649.00 2000.00 90 days Amount
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1.5:1.0 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	16.20	5697.60	Per cubic metre	Rupees Thousand Hundred Ninety Seven And Paise Sixty Only	Five Six 92301.00
Total						95649.00

Rupees Ninety Five Thousand Six Hundred Forty Nine Only

*DNIT No. 96. For the Year 2025-26
 DNIT Checked & approved for Rs. 95,649/only
 (Rs. Ninety five thousand Six Hundred forty nine only)*


 Executive Engineer
 Salooni Division
 HPPWD Salooni

B

DNIT

Name of work- Restoration of rain damages on BSL J&K Boundary road 13/130 to 28/00(SH:- Removal of slip at km 13/130 to 18/00)

Sr. No	Description	Estimated cost		Unit	Amount
		Quantity	Rate		
1	Hiring of Excavator cum loader for removal of land slide slips/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1000.00	Per hours	99910.00
Total					99910.00

DNIT No. 97 For the year 2025-26
DNIT checked and approved for ₹ 99,910/only
Crupes Ninety Nine Thousand Nine Hundred Ten only


 Executive Engineer
 Salloom-Division
 H.P.W.D. Salloom


DNIT

Name of work:- Restoration of rain damages on Salooni to Ghal road K.M. 0/0 to 7/500 (SH: Hiring of JCB for removal of slips at various RD,s)

S. N.	Description of Item	Quantity	Rate	Estimated cost		90 days Amount
				Unit	In Words	
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	94.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty 96820.00
Total						96820.00

Rupees Ninety Six Thousand Eight Hundred Twenty Only

*DNIT No. 98 For the Year 2025-26
 DNIT Checked & approved for Rs. 96,820/- only
 (Rs. Ninety Six thousand Eight hundred
 Twenty only)*

Exec
 Executive Engineer
 Salooni Division
 HPPWD Salooni

DNIT

Name of work - Restoration of rain damages on BSL J&K Boundary road 13/130 to 28/00(SH) - Removal of slip at km 13/130 to 28/00)

Sr. No	Description	Estimated cost	18,890.00		
		Earnest money	20,000.00		
Quantity	Rate	Unit	Amount		
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per hours	98,880.00
Total					98,880.00

DNIT NO 99 for the year 2015-16
 DNIT checked and approved for ₹ 98,880/only
 Ninety eight thousand eight hundred eighty only


 Executive Engineer
 Sales and Division
 H. P. W. D. Saloon


DNIT

Name of work- Restoration of rain damages on Sundla Girjindoo road km 0/0 to 36/500 (SH:Removal of slip at km 15/0 to 20/00)

Sr. No	Description	Estimated cost		Unit	Amount
		Earnest money	Time limit		
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	95.00	1030.00	Per hour	97850.00
Total					97850.00

DNIT No 100 For the year 2025 - 26
DNIT checked and approved For E 47,850/only
(Rupees Ninety Seven Thousand Eight Hundred Fifty) only


 Executive Engineer
 Salooni-Division
 H. P. W. D. Saloon


DNIT

Name of work:- Restoration of rain damages on Bathri Sundia Langera J & K Boundary road K.M. 57/0 to 93/400 (SH: Hiring of JCB for removal of slips at K.M. 57/0 to 62/0)

S. N.	Description of Item	Quantity	Rate	Estimated cost		Time limit	Amount
				Earnest money	In Words		
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute reonsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less then 17.00 cum per hours to be lifted and snow not less then 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty	99910.00
Total							99910.00

Rupees Ninety Nine Thousand Nine Hundred Ten Only

DNIT NO 101 for the year 2025-26
 DNIT checked and approved for ₹ 99,910/only
 (Rupees Ninety Nine thousand Nine Hundred Ten) only


 Executive Engineer
 Salooni Division
 HPPWD Salooni

DNT

Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Pusta at R.D. 5/939 to 5/941)

S. N.

Description of Item

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Estimated cost
						Earnest money
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	6.44	519.80	Per cubic metre	Rupees Hundred Nineteen And Paise Eighty Only	95649.00 2000.00 90 days Amount 3348.00
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	16.20	5697.60	Per cubic metre	Rupees Thousand Six Hundred Seven And Paise Sixty Only	92301.00
Total						95649.00

Rupees Ninety Five Thousand Six Hundred Forty Nine Only

*DNT No. 102 For the year 2025-26
DNT Checked & approved for Rs. 95,649/only
(Rs. Ninety five thousand Six Hundred
forty nine only)*


 Executive Engineer
 Salooni Division
 HPPWD Salooni 

DNI

Name of work:- Restoration of rain damages on Kund to Siula road K.M. 0/0 to 6/255 (SH: Hiring of JCB for removal of slips at various RD,s)

S. N.	Description of item	Quantity	Rate	Unit	In Words	Estimated cost
						Earnest money
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall by the absolute reponsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees Thousand Only	98880.00
Total						2000.00
						90 days
						Amount
						98880.00
						98880.00

DNIIT are 103 for the year 2015-16
 DNIIT checked and approved for ₹ 98,880/only
 (Ninety eight Thousand Eight Hundred Eighty Only)


 Executive Engineer
 Salooni Division
 HPPWD Salooni

DNIT

Name of work:- Restoration of rain damages on Kandhwara Bhadela road km 0/0 to 4/100 (Slip Removal of slip at km 0/0 to 4/100)

Sr. No	Description	Estimated cost		Unit	Amount
		Quantity	Rate		
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	36.00	1030.00	Per month	97850.00
Total					97850.00

DNIT NO 104 for the year 2025-26
DNIT cleared and approved for ₹ 97850 only
Respones ninety seven thousand eight hundred fifty) only


 Executive Engineer
 Salooni-Division
 H.P.W. J. Salooni

DNIT

Name of work- Restoration of rain damages on Bihali Bachuni Chamber Katara road 0/0 to 11/100 (Sh.-: Removal of slips at 0/00 to 5/00)

Sr. No	Description	Estimated cost	Time limit		Unit	Amount
		Earnest money	Rate	Per hours		
1	Hiring of Excavator cum loader for removal of land slide slips/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 2.2 metre.	97850.00	2000.00	1030.00	Per hours	97850.00
Total						97850.00

*DNIT 200/106 for the year 2015-26
 DNIT checked and approved for ₹ 97,850/only
 (Repays Ninety Seven thousand eight hundred fifty only)*


 Executive Engineer
 Salooni-Division
 H.P.W.D. Salooni


DNT

Name of work:- Restoration of rain damages on Bathri Sundla Langer a J & K Boundary road K.M. 57/0 to 93/400 (SH: Hiring of JCB for removal of slips at K.M. 73/0 to 80/0)

Estimated cost 96820.00

Earnest money 2000.00

Time limit 90 days

S. N.	Description of item	Quantity	Rate	Unit		In Words		Amount
				Per	Hours	Rupees Thousand	Only	
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute reonsinility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	94.00	1030.00					96820.00
Total								96820.00

Rupees Ninety Six Thousand Eight Hundred Twenty Only

*DNT NO 107 for the year 2025-26
DNT checked and approved for ₹ 96,820/only
Rupees Ninety Six Thousand Eight Hundred Twenty Only*

ed
Executive Engineer
Saloomi Division
HPPWD Saloomi

DNIT

Name of work- Restoration of rain damages Kandi Athed road km 0/00 to 12/00 (Sh... Removal of slips at 6/00 to 12/00)

Sr. No	Description	Estimated cost		Unit	Amount
		Earnest money	Time limit		
1	Hiring of Excavator cum loader for removal of land slide slips/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	999,10.00	2000.00	Per hours	999,10.00
Total					99910.00

*DNIT NO 108 for the year 2025-26
 DNIT checked and approved for ₹ 99,910/- only
 (Rupees Ninety nine thousand nine hundred ninety)*

ECR
 Executive Engineer
 Saloomi-Division
 H. P. W. D. Saloomi
B

DNT
Name of work:- Restoration of rain damages on link road to village Kuthed K.M. 0/0 to 6/0 (SH: Construction of PCC and Crate work Retaining wall
at R.D. 1/277.50 to 1/280)

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Estimated cost Earnest money	90 days Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORO technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and balling out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	5.80	528.68	Per Cubic Metre	Rupees Five Hundred Twenty Eight And Paise Sixty Eight Only	3066.00	
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or balling out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi/royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	9.18	5660.17	Per Cubic Metre	Rupees Five Thousand Six Hundred Sixty Four Paise Seventeen Only	51960.00	
3	Providing and laying boulder apron laid in wire crate with 4mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10% for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORO technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads, and lifts and other incidental. The rate also includes octroi/royalty, malkana, toll tax sale tax or other taxes imposed by the Government.	15.63	2464.61	Per Cubic Metre	Rupees Two Thousand Four hundred Sixty Four And Paise Sixty One Only	38522.00	
4	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	4.20	1301.64	Per Cubic Metre	Rupees One Thousand Three Hundred One And Paise Sixty Four Only	5467.00	
5	Providing weep holes in brick masonry/stone masonry/plain or reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia P.V.C. pipe (Finolex/ Vertex) with slope of 1 (V): 20(H) towards drainage face complete as per drawing and MORO technical specification section 700 and 1200 including hauling /carriage of materials to various location through all modes of transportation in all leads, lifts and other incidental complete in all respect and as per the direction of Engineer-in-Charge. The rate is including royalty, Malkana, Toll tax, GST or other taxes imposed by the Government.	2.00	275.30	Each	Rupees Two hundred Seventy Five And Paise Thirty Only	551.00	
Total						99566.00	

DNT No. 109 for the year 2025-26

DNT Checked & approved for Rs. 99566/- only

(Rs. Ninety Nine thousand five Hundred

Sixty Six only)

Rupees Ninety Nine Thousand Five Hundred Sixty Six Only

Executive Engineer

Satoni Division

HPPWD Satoni



DNIT

Name of work- Restoration of rain damages on Bhalei mata temple to Athed road km 0/0 to 6/00(SH:-Removal of slips at 0/00 to 3/00)

Sr. No	Description	Estimated cost		Unit	Amount
		Earnest money	One month		
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	93880.00	2000.00	Per hours	93880.00
Total					93880.00

DNIT NO 110 for the year 2025-26
 DNIT checked and approved for ₹ 98,880 only
 (Repeas Ninety eight thousand Eight Hundred eighty) only


 Executive Engineer
 Salooni-Division
 H.P.W.D. Salooni

DNIIT

Name of work:- Restoration of rain damages on Link road to village Barli, link road to village Chakori via Sukreth and Dangri to Sarar
(SH: Hiring of JCB for removal of slips at various RD,s)

Estimated cost 99910.00
Earnest money 2000.00

S. N.	Description of item	Quantity	Rate	Unit	In Words		Amount
				Time limit	Per	Hours	
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer. in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per	Rupees	One	99910.00
				Hours	Thousand	Thirty	
					Only		
Total							99910.00

Rupees Ninety Nine Thousand Nine Hundred Ten Only

DNIIT No 111 for the year 2015-16
DNIIT checked and approved for ₹ 99,910/ only
(Rupees Ninety Nine thousand Nine hundred Ten only)


Executive Engineer
Salooni Division
HPPWD Salooni

DNIT

Name of work:- Restoration of rain damages on Bathri Sundla Langeri J & K Boundary road K.M. 57/0 to 93/400 (SH: Hiring of JCB for removal of slips at K.M. 63/0 to 67/0)

S. N.	Description of Item	Quantity	Rate	Estimated cost		90 days Amount
				Earnest money	In Words	
				Time limit		
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Per Hours	Rupees Thousand Only	One Thousand Thirty 98880.00
Total						98880.00

Rupees Nirety Eight Thousand Eight Hundred Eighty Only

*DNIT No 112 for the year 2025-26
 DNIT checked and approved for ₹ 98,880/only
 Rupees Ninety Eight Thousand Eight Hundred Eighty only*


 Executive Engineer
 Salooni Division
 HPPWD Salooni

DNIT

Name of work - Restoration of rain damages on link road to Bhalet Mandir km 0/0 to 1/500 (Sh.: Removal of snow/slips at 0/0 to 1/500)

Sr. No	Description	Estimated cost		Unit	Amount
		Earnest money	Time limit		
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	94 00	1030 00	Per hours	96820 00
Total					96820 00

DNIT NO 113 for the year 2015-16
 DNIT checked and approved for ₹ 96,820/only
 (Rupees ninety six thousand eight hundred twenty only)


 Executive Engineer
 Salooni-Division
 H.P.W.D. Salooni

DNIT

Name of work:- Restoration of rain damages on Maira to Jakhral road K.M. 0/0 to 10/500 (SH: Hiring of JCB for removal of slips at K.M. 5/0 to 9/500)

Estimated cost 97850.00
Earnest money 2000.00

S. N.	Description of Item	Quantity	Rate	Time limit		In Words	Amount
				Unit	Per		
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire statification of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	95.00	1030.00	Per Hours	Hours	Rupees Thousand Only	One Thirty 97850.00
Total							97850.00

Rupees Ninety Seven Thousand Eight Hundred Fifty Only

DNT No 114 For the year 2025-26
DNT Checked and approved For ₹ 97,850/only
(Rupees Ninety Seven Thousand Eight Hundred Fifty) only


Executive Engineer
 Salooni Division
 HPPWD Salooni

B

DNIT

Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Pusta at R.D. 5/941 to 5/943)

Estimated cost

95651.00

Earnest money

2000.00

S. N.	Description of Item	Quantity	Rate	Unit	in words	Amount	Time limit
							90 days
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	6.44	519.80	Per cubic metre	Rupees Five Hundred Nineteen And Paise Eighty Only	3348.00	
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, Toll tax, GST or any other taxes imposed by the Government.	16.20	5697.70	Per cubic metre	Rupees Thousand Hundred Ninety Seven And Paise Seventy Only	92303.00	
Total						95651.00	

Rupees Ninety Five Thousand Six Hundred Fifty One Only

*DNIT No. 115 For the year 2025-26
 DNIT Checked & approved for Rs. 95651/only
 (Rs. Ninety five thousand Six Hundred
 Fifty one only)*


Executive Engineer
Salooni Division
HPPWD Salooni

DNIT

Name of work - Restoration of rain damages on Lachori Seri road km 0/0 to 8/500 (Sh.: Removal of slips at 0/00 to 4/00))

Sr. No	Description	Estimated cost		Unit	Amount
		Earnest money	Time limit		
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	93 00	1030 00	Per Hours	95790 00
Total					55790.00

*DNIT NO 116 for the year 2015-16
 DNIT checked and approved for ₹ 95,790/only
 (Rupees Ninety Five thousand Seven hundred Ninety Only)*


 Executive Engineer
 Salooni-Division
 H.P.W.D. Salooni
6

Name of work:- Restoration of rain damages on Bathri Sundla Langeri J & K Boundary road K.M. 57/0 to 93/400 (SH: Hiring of JCB for removal of slips at K.M. 80/0 to 85/0)

DNT

S. N.	Description of Item	Quantity	Rate	Unit	In Words	Amount	Estimated cost	
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty	99910.00	
Total							99910.00	99910.00

Rupees Ninety Nine Thousand Nine Hundred Ten Only

DNT No 117 For the year 2025-26
 DNT Checked and approved For ₹ 99,910/only
 (Rupees Ninety Nine Thousand Nine Hundred Ten) only


 Executive Engineer
 Salooni Division
 HPPWD Salooni

DNIT

Name of work - Restoration of rain damages on Kandi Athed road km 0/0 to 12/00 (Sh.: Removal of slips at (from to 12/00))		Estimated cost	97850.00			
		Earnest money	2000.00			
		Time limit	One month			
Sr. No	Description	Quantity	Rate	Unit	Per hours	Amount
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is insured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	95.00	1030.00			97850.00
Total						97850.00

DNIT A10 118 for the year 2015-16
 DNIT checked and approved for ₹ 97,850/only
 (Rates Ninety Seven thousand eight hundred fifty) only


 Executive Engineer
 Saloom-Division
 H.P.W.D Saloom


DNIT

Name of work:- Restoration of rain damages on Maira to Jakhral road K.M. 0/0 to 10/500 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 5/0)

Estimated cost 98880.00
Earliest money 2000.00

S. N.	Description of Item	Quantity	Rate	Unit		In Words	Amount
				Per	Rupees		
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer. in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	96.00	1030.00	Hours	Thousand Only	One Thirty	98880.00
Total							98880.00

Rupees Ninety Eight Thousand Eight Hundred Eighty Only

*DNIT NO 119 For the year 2025-26
DNIT Checked and approved For ₹ 98,880/only
Rupees Ninety Eight Thousand Eight Hundred Eighty Only*

*Executive Engineer
Salooni Division
HPPWD Salooni*

B

DNIT

Name of work- Restoration of rain damage on Lachori Seri road km 0/0 to 8/500 (Sh.: Removal of slips at 4/00 to 8/500)

Sr. No	Description	Estimated cost			96820.00
		Earnest money	Time limit	Unit	Amount
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	94.00	1030.00	Per hours	96820.00
Total					96820.00

*DNIT no 120 for the year 2015-16
 DNIT checked and approved for ₹ 96,820/only
 (Rupees ninety six thousand eight hundred twenty) only*


 Executive Engineer
 Salooni-Division
 H. P. W. D. Salooni


Name of work:- Restoration of rain damages on Bathri Sundia Langeria J&K boundary road km 28/00 to 93/400 (SH:- Construction of crate work W/wall at DNIIT

RD 68/120 to 68/130 (Crate 1st step)

S. N.	Description of Item	Quantity	Rate	Estimated cost	Time limit	Three month Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all (Type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of sheeting and bracing, removal of slumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	75.60	559.10	42258.90	Per cubic metre	42258.90
2	Providing and laying boulder apron laid in wire grate with 4mm dia G.I. wire conforming to IS 280 and IS 4826 in 100 mm x 100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10% for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORD technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi royalty, maikana, toll tax sale tax or other taxes imposed by the Government.	15.625	2808.70	43886.60	Per cubic metre	43886.60
3	Backfilling behind retaining wall/breast wall complete as per drawing and technical specification clause 1204.3.8 in granular material within all leads and lift of material as per direction of Engineer-in-Charge and other incidentals.	9.10	1518.80	13821.00	Per cubic metre	13821.00
Total				99975.00		

DNIIT No 121 For the year 2025-26
 DNIIT checked and approved for ₹ 99,975 only
 Trustees Ninety Nine Thousand Nine Hundred Seventy Five Only


 Executive Engineer
 Saloni Division
 HPPWD Sakoni

DNIT

Name of work- Restoration of rain damages on Chowga Khal road km 0/0 to 13/705 (Sh.: Removal of slips at 0/0 to 6/00)

Sr. No	Description	Estimated cost	Earnest money		Unit	Amount
			Time limit	One month		
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with an lead of 200 metre.	98880.00	2000.00		Per hours	98880.00
Total						98880.00

DNIT No 122 for the year 2015-16
 DNIT checked and approved for ₹ 98,880/- only
 Rupees Ninety Eight thousand Eight Hundred Eighty only


 Executive Engineer
 Saloom-Division
 H.P.W.D Saloom


Name of work:- Restoration of rain damages on Sundla Girjindoo road km 0/0 to 36/500 (SH:Removal of slip at km 0/0 to 5/00)

DNIT

Sr. No	Description	Estimated cost		One month	
		Earnest money	99910.00	2000.00	Amount
1	Hiring of Excavator cum loader for removal of land slide slips/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per hours	99910.00
Total					99910.00

*DNIT No. 123 For the year 2025-26
 DNIT checked and approved for ₹ 99,910/only
 (Rupees Ninety Nine Thousand Nine Hundred Ten) only*

(Signature)
 Executive Engineer
 Salooni Division
 H. P. P. W. D. Salooni

DNIT

Name of work:- Restoration of rain damages on Bhalei Matta Temple to village Athed road K.M. 0/0 to 6/0 (SH: Construction of PCC Pusta at R.D. 5/943 to 5/945)

Estimated cost

95651.00

Earnest money

2000.00

Description of item

Time limit

90 days

Quantity

Rate

Unit

In Words

Amount


1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.	6.44	519.80	Per cubic metre	Rupees Hundred Nineteen And Paise Eighty Only	Five Hundred Ninety Six	3348.00	
2	Providing and laying Mechanically mixed and vibrated concrete for plain / reinforced concrete nominal mix 1:5:10 (one cement is to five sand is to ten graded crushed stone aggregate 40 millimeter (forty millimeter) nominal size in or under water and curing complete for 14 (fourteen) days, in open foundations for all type of structures and the like drain etcetera including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying under water complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification Clauses 802,803,1202 and 1203 or as directed by the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate includes octroi,royalty,Malkana,Toll tax, GST or any other taxes imposed by the Government.	16.20	5697.70	Per cubic metre	Rupees Thousand Hundred Seven And Paise Seventy Only	Five Hundred Sixty Nine	92303.00	
Total							95651.00	

Rupees Ninety Five Thousand Six Hundred Fifty One Only

DNIT No. 124 For the year 2025-26

DNIT Checked & approved for Rs. 95,651/- only

(Ninety five thousand Six Hundred fifty one only)


 Executive Engineer
 Salooni Division
 HPPWD Salooni



DNIT

Name of work:- Restoration of rain damages on Bathri Sundia Langera J & K Boundary road K.M. 57/0 to 93/400 (SH: Hiring of JCB for removal of slips at K.M. 85/0 to 93/400)

S. N.	Description of Item	Quantity	Rate	Unit	Time limit	Estimated cost Earnest money	In Words	Amount
1	Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/provate property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	94.00	1030.00	Per Hours	Thirty	96820.00	One Thousand Thirty	96820.00
Total								96820.00

Rupees Ninety Six Thousand Eight Hundred Twenty Only

*DNIT No. 125 For the year 2025-26
DNIT checked and approved for ₹ 96,820 only
Rupees . Ninety Six Thousand Eight Hundred Twenty Only*


 Executive Engineer
 Salooni Division
 HPPWD Salooni

DNIT

Sr. No	Name of work - Restoration of rain damages on Kandi Athed road km 0/0 to 12/00 (Sh.: Removal of slips at 0/00 to 6/00)	Estimated cost		One month	
		Earnest money	Time limit	Amount	Amount
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	96 00	1030 00	Par hours	98880 00
Total					98880 00

DNIT NO 126 for the year 2025-26
 DNIT checked and approved for ₹ 98,880 only
 (Paper Ninety eight thousand eight hundred eighty only)


 Executive Engineer
 Salooni-Division
 H. P. W. D. Salooni

Name of work:- Restoration of rain damages on Chakoli to Lader road K.M. 0/0 to 20/0 (SH: Hiring of JCB for removal of slips at K.M. 0/0 to 10/0)

S. N.		Description of Item	Quantity	Rate	Unit	In Words	Amount
1		Hiring of Excavator cum Loader for removal of landslide slip clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfaction of Engineer- in Charge any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall by the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer- in Charge. It is ensured that slip removal not less than 17.00 cum per hours to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per Hours	Rupees Thousand Only	One Thirty 99910.00
Total							99910.00

Rupees Ninety Nine Thousand Nine Hundred Ten Only

*DNIT No. 127 For the year 2025 - 26
 DNIT Checked and approved For ₹ 99,910/only
 CRupees Ninety Nine Thousand Nine Hundred Ten Only*

Executive Engineer
 Salooni Division
 HPPWD Salooni

DNIT

Name of work - Restoration of rain damages on Hutta Ligga Ladwah road km 0/0 to 7/040 (Sh.: Removal of slips at 0/0 to 7/040)

Sr. No	Description	Quantity	Rate	Unit	Amount
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	95.00	1030.00	Per hours	97850.00
Total					97850.00

DNIT no 128 for the year 2015-26
 DNIT checked and approved for ₹ 97,850/only
 ninety seven thousand eight hundred fifty only


 Executive Engineer
 Salooni-Division
 H.P.W.D. Salooni

DNIT

Name of work- Restoration of rain damages on Bhalei mata temple to Athed road km 0/0 to 6/00(5H.-Removal of slips at 3/00 to 6/00)

Sr. No	Description	Estimated cost	One month
		Earnest money	Amount
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	95790.00	95790.00
	Quantity	1030.00	Per hours
	Time limit		
	Rate	93.00	Amount
	Unit		
	Total		95790.00

DNIT NO 129 for the year 2015-16
DNIT checked and approved for ₹ 95,790 only
Repears Ninety five thousand seven hundred Ninety only


 Executive Engineer
 Salween Division
 H.P. & W.D. Salween


Name of work: Restoration of rain damages on BSL J&K Boundary Road km 28/00 to 93/400 (SH:- C/o Crate work wing wall at RD 68/120 to 68/130 (crate

DNIT

S. N.	Description of Item	Quantity	Rate	Estimated cost Earnest money	Time limit	Three month Amount
1	Providing and laying boulder apron laid in wire crate with 4mm dia G I wire conforming to IS 280 and IS 4826 in 100 mm x100mm (hundred millimeters into hundred millimeters) mesh(woven diagonally) including 10%for laps & joints laid with stone boulders weighing not less than 40kg (forty kilogram) each in toe walls as per drawing and MORO technical specifications clause 2503 and as per direction of the Engineer - in -Charge including carriage of materials within all leads and lifts and other incidental. The rate also includes octroi, royalty, maikana, toll tax sale tax or other taxes imposed by the Government.	35,155	2808.70		Cum	98743.00
Total						98743.00

DNIT No 130 For the year 2025-26

DNIT Checked and approved For ₹ 98,743/only

(Rupees Ninety Eight Thousand Seven Hundred Forty Three) only

EC
 Executive Engineer
 Salceni Division
 HPPWD Salceni

DNIT

Name of work- Restoration of rain damages on Chowga Khal road km 0/0 to 13/705 (Sh.:-Removal of slips at 6/0 to 13/705)

Sr. No	Description	Estimated cost		One month	
		Quantity	Rate	Unit	Amount
1	Hiring of Excavator cum loader for removal of land slide slip/snow clearance in all kind of soil and disposal of all excavated earth or un serviceable material from the road surface up to any leads and lifts and all heights and depths as per the direction and entire satisfactions of Engineer-in-Charge any loss to the public/private property or any accident etc happened during the course of hiring period/execution shall be the absolute responsibility of the owner which shall have to be fully compensated by the contractor in all cases. The fuel and operational staff for machinery will be provided by the owner. The daily log book will be maintained at site which should be duly verified by the Engineer-in-charge. It is ensured that slip removal not less than 17.00 cum per hour to be lifted and snow not less than 15.00 cum per hour to be lifted with in a lead of 200 metre.	97.00	1030.00	Per hours	99910.00
Total:					99910.00

DNIT x10.13/ for the year 2025-26
 DNIT checked and approved for ₹ 99,910/- only
 ninety nine thousand nine hundred ten only

Executive Engineer
 Salooni-Division
 H.P.W.D. Salooni

(8)